
FENWICK SOLAR FARM

**Fenwick Solar Farm
EN010152**

Statement of Need

Document Reference: EN010152/APP/7.3

Regulation 5(2)(q)

Infrastructure Planning (Applications: Prescribed Forms and Procedure)
Regulations 2009

October 2024
Revision Number: 00

Revision History

Revision Number	Date	Details
00	October 2024	DCO application

Prepared for:
Fenwick Solar Project Limited

Prepared by:
AECOM Limited

© 2024 AECOM Limited. All Rights Reserved.

This document has been prepared by AECOM Limited (“AECOM”) for sole use of our client (the “Client”) in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.

Table of Contents

Executive Summary	7
1. Overview.....	9
1.1 Document Purpose	9
1.2 Document Overview	10
1.3 Description of the Scheme.....	11
2. Legal and policy background: the need for urgent decarbonisation.....	12
2.1 Chapter summary	12
2.2 Global decarbonisation	12
2.3 Decarbonisation in the UK	15
2.4 The Government's Energy Strategy.....	17
2.5 The UK's Plan For Decarbonisation.....	18
2.6 The Energy White Paper	19
2.7 Net Zero Strategy – Build Back Greener	20
2.8 The British Energy Security Strategy	21
2.9 Mission Zero – The Skidmore Review	22
2.10 Powering Up Britain.....	24
2.11 Climate Change Committee Progress Report to Parliament, 2024.....	25
2.12 Energy Act 2023	26
2.13 Connections Action Plan.....	27
2.14 Conclusions On Decarbonisation Policy Context.....	29
3. National Policy Statements	30
3.1 Planning Policy For Nationally Significant Infrastructure Projects.....	30
3.2 A Synthesis Of National Policy Statement EN-1 (2023).....	31
3.3 A Synthesis Of National Policy Statement EN-3 (2023).....	35
3.4 A Synthesis Of National Policy Statement EN-5 (2023).....	36
3.5 Conclusions on the NPSs	37
4. Electricity demand must grow to deliver net zero	38
4.1 Chapter Summary.....	38
4.2 Introducing The FES.....	38
4.3 Trends In UK Electricity Demand	40
4.4 Transport Policies Underpin A Growth In Future Electricity Demand	43
4.5 Home Energy Policies Underpin A Growth In Future Electricity Demand	44
4.6 Peak Electricity Demand Is Also Expected To Grow	45
4.7 Conclusions on Electricity Demand	46
5. Delivering Net Zero Through Clean Electricity Supplies	48
5.1 Chapter Overview	48
5.2 Current And Future Generation Mix	48
5.3 Development Pipelines	53
5.4 Offshore Wind.....	55
5.5 Onshore Wind.....	58
5.6 Nuclear	60
5.7 Unabated Fossil Fuels And Abatement Technologies	64
5.8 Hydrogen.....	66
5.9 Biomass.....	67

5.10	Solar Power	68
5.11	Flexibility	74
5.12	Conclusions on Future Energy Supplies	85
6.	Technical Considerations For UK Solar Schemes	88
6.1	Chapter Overview	88
6.2	Large-scale and small-scale generators	88
6.3	Large-Scale, Brownfield and Rooftop Solar	90
6.4	Site selection for large-scale solar	93
6.5	Technology Selection / Orientation	98
6.6	Overplanting	100
6.7	Land use associated with large-scale solar	106
6.8	Solar cell efficiency	108
6.9	Co-Location	111
6.10	Conclusions on Technical Considerations	116
7.	Suitability Of The Proposed Location For Large-Scale Solar.....	118
7.1	Chapter Purpose.....	118
7.2	Local Demand / Decarbonisation Requirements.....	118
7.3	Local Supply	119
7.4	Grid Suitability.....	121
7.5	Connection Points / History	124
7.6	Conclusions on the Proposed Location	126
8.	The contribution of large scale solar to system security	129
8.1	Chapter overview.....	129
8.2	Power System Stability	130
8.3	Power System Adequacy	131
8.4	Curtailment	132
8.5	The System Adequacy Of Solar Generation	134
8.6	Conclusions on System Security	141
9.	The contribution of large scale solar to the affordability of electricity	143
9.1	Chapter overview.....	143
9.2	Pricing in the GB electricity market.....	143
9.3	Levelised Cost Of Solar Generation	145
9.4	Whole System Costs	148
9.5	Conclusions on Affordability.....	149
10.	Overall Conclusions.....	150
11.	Author's Qualifications And Experience	153
11.1	Qualifications And Experience	153
12.	References	154
13.	Abbreviations	159

Figures

Figure 2-1: Representation of global GHG emissions of modelled pathways [Ref. 3, Figure SPM.4]	14
Figure 2-2: UK historical emissions, the CBDP indicative pathway and the UK's targets [Ref. 8(2024), Figure 1.1]	16
Figure 2-3: National (UK) District GHG Emissions 2005 – 2022 (LULUCF net benefits small and not shown [Ref. 9, Author Analysis]	19
Figure 4-1: Evolution of UK electricity demand projections (2019,2023 & 2024) [Ref. 19, Author Analysis].....	42
Figure 4-2: Electricity average cold spell peak demand (including losses) [Ref. 19(2024), Figure ES.O3]	46
Figure 5-1: Historical Electricity generation (TWh/Yr) and carbon intensity (gCO ₂ (e)/kWh) [Ref. 19, Tables 5.6 & 5.14]	49
Figure 5-2: Projected electricity generation (TWh/Yr) and carbon intensity (gCO ₂ (e)/kWh) [Ref. 19(2024), Tables ES.08-11 & ES1 – ‘Holistic Transformation’] 50	
Figure 5-3: Projected electricity generation capacity (GW) and carbon intensity (gCO ₂ (e)/kWh) [Ref. 20(2024), Tables ES.09 & ES1 – ‘System Transformation’]....	51
Figure 5-4: Current and potential future connected capacity of offshore wind technology [Ref. 38(2024), Table ES1, Author Analysis]	56
Figure 5-5: FES future nuclear capacity pathways 2023-2050 (GW) [Ref. 19(2024), Table ES.21, Author Analysis]	63
Figure 5-6: Cumulative and annual installed solar capacity in the UK, 2010 – June 2024 [Ref. 61, Author Analysis]	69
Figure 5-7: Evolution of future solar capacity forecasts in the UK (2019, 2023 & 2024) [Ref. 19, Author Analysis]	70
Figure 5-8: Driver of Flexibility Requirements [Ref. 64]	75
Figure 5-9: Growth in Short Duration Storage capacity vs. Solar Capacity, 2024 – 2050 [Author Analysis, 20(2024), Tables ES.09 & ES1]	77
Figure 6-1: Reported and estimated small-scale and large-scale solar capital costs (£/kW) [Ref. 66, Ref. 67].....	92
Figure 6-2: United Kingdom solar irradiation [Ref. 68].....	96
Figure 6-3: Transmission system connection points and potential connection dates [Ref. 69].....	97
Figure 6-4: Illustrating clipped generation vs. optimised generation on overplanted solar schemes vs. unitary schemes [Author Analysis]	102
Figure 6-5: Grid Utilisation increases as overplanting increases, but gains are incrementally smaller above a ratio of c.1.5. [Author Analysis].....	104
Figure 6-6: GWh/Yr/MW decreases as overplanting increases, and losses are incrementally larger above a ratio of c.1.3. [Author Analysis]	105
Figure 6-7: Evolution in solar cell efficiency 1975 – 2024 [Ref. 75]	110
Figure 6-8: BESS imports solar generation at midday and exports in the evening [Author Analysis]	112
Figure 6-9: BESS imports solar generation at midday and exports in the evening – lower import / export rates [Author Analysis]	112
Figure 6-10: BESS imports solar generation at midday and exports in the evening – lower import / export rates [Author Analysis]	113
Figure 6-11: BESS imports grid generation and solar generation and exports twice in the day [Author Analysis].....	113
Figure 6-12: BESS stores clipped solar generation and exports in the evening [Author Analysis]	114
Figure 6-13: 30 mins of system frequency (Hz) and illustrative BESS operation under frequency response [Author Analysis]	115

Figure 7-1: Energy consumption in Yorkshire and the Humber (TWh/Yr) [Author Analysis, Ref. 9]	119
Figure 7-2: NGENSO Regional generation carbon intensity analysis (Left: on a higher wind day, Right: on a lower wind day) [Ref. 20(2022)]	121
Figure 7-3: B8 and B9 Boundary flows under most extreme scenarios [Ref. 76, Boundary Data workbook]	124
Figure 7-4: Transmission System within 50km of Thorpe Marsh [Ref. 76, Appendix A]	125
Figure 8-1: Illustrative Generation Dependability for a combined portfolio of solar and wind in GB [Author analysis, Ref. 81, Ref. 20(2024)]	136
Figure 8-2: Deploying 47GW of large-scale solar alongside government offshore wind ambitions (50GW) meets anticipated seasonal demand levels [Ref. 19(2024), Tables ES1 & ED1, Author analysis].....	140
Figure 9-1: Representative marginal cost stack for the GB electricity system [Author analysis]	145
Figure 9-2: Levelised cost of energy comparison [Ref. 67]	146
Figure 9-3: Cost of Electricity Generation. An evolution of Levelised Cost forecasts [Ref. 67, Author analysis]	147

Tables

Table 5-1: The potential contributions of a storage asset within the Scheme to the GB electricity market, including ancillary service provision [Author analysis]	81
Table 7-1: Generation technologies accepted to connect at Thorpe Marsh.....	126
Table 8-1: Comparison of assumed load factors with independent data sources...	138
Table 8-2: Comparison of installed capacity assumptions vs. FES 2024.....	139

Executive Summary

- ES1 This Statement of Need provides relevant legal, policy, and industry evidence in support of the urgent need for decarbonisation and action to support security of electricity supplies in the UK. It also provides evidence in support of ground mounted solar electricity generation generally, and Fenwick Solar Farm (the Scheme) specifically, in relation to the benefit brought against the UK's critical strategic needs.
- ES2 This Statement of Need concludes that the decarbonisation, security of supply and affordability benefits delivered by the Scheme to the national urgent need for low-carbon generation, should be accorded very significant weight when assessing the planning balance.
- ES3 Urgent and unprecedented actions are required on a global scale to halt climate change. A rapid increase in the supply of low carbon electricity is needed for the UK to meet its legally binding climate change targets. Solar generation is a critical part of the UK's strategy to achieve net zero by 2050, a key step towards which is the government's national mission for 'Clean Power by 2030'.
- ES4 However, the need for new clean power does not stop at 2030. The continued delivery of low-carbon generation facilities beyond 2030 is necessary to meet future electricity demand growth and achieve essential wider societal carbon savings. It is also important to continue to bring forward schemes in case 'Clean Power by 2030' is not achieved.
- ES5 The Secretary of State must have regard to the current suite of National Policy Statements (NPSs) for energy as relevant NPSs, and must decide the application in accordance with those NPSs. The NPSs confirm that large-scale ground mounted solar farms have a critical role to play in achieving the government's aims, and establish a critical national priority (CNP) for low-carbon infrastructure, including large-scale solar farms, because of the decarbonisation, energy security and affordability benefits that they deliver.
- ES6 The NPSs also confirm that assets which provide flexibility to the national electricity system, or to the energy system generally, are also needed to achieve national decarbonisation and energy security aims. The NPSs state that government is supportive of solar that is co-located with storage to maximise the efficiency of land use. The Scheme, which is a large-scale solar plus energy storage scheme, is therefore fully aligned with the government's aims.
- ES7 Decarbonisation will increase demand for electricity. Policies are already in-flight which are increasing, or are set to increase, electricity demand. Therefore, a significant number of new low-carbon electricity schemes, including this Scheme, are required to meet that demand and support the delivery of net zero.
- ES8 The NPSs explain that the availability of grid connection, suitable irradiance levels and local topography are key inputs to the selection of sites suitable for large-scale solar generation developments. The number of locations within the UK at which large-scale solar generation is suitable is therefore

- likely to be limited, and this is a material issue when considering how the UK is to meet the urgent need for low-carbon generation as is set out in the NPSs.
- ES9 Progress has been made in the development of different low-carbon electricity generation technologies. However, many of the technologies with potential to play a role in the delivery of a net zero energy system have uncertain delivery timescales. Developments with the proven ability to achieve carbon savings comfortably within the next decade are essential to keep the UK on its legally binding carbon reduction path. Large-scale solar is one of the most likely technologies to be deliverable at scale against the timeframes required to support net zero.
- ES10 Many factors are important in the design of a large-scale solar scheme within the context of a particular location, and flexibility in design is important to allow for the scheme to be designed in order to optimise its benefits. Optimising the use of existing and available grid infrastructure is necessary in the next decade to achieve the government's national mission for 'Clean Power by 2030' and to meet future electricity demand growth and achieve essential wider societal carbon savings beyond 2030.
- ES11 The proposed location of the Scheme enables the Scheme to deliver against the urgency of need, in relation to decarbonisation, security of supply and affordability, and makes use of existing and available grid infrastructure by connecting to the National Electricity Transmission System (NETS) footprint. No adverse grid operability effects are anticipated as a result of connecting the Scheme to the NETS at the proposed location.
- ES12 Solar generation contributes to security of supply. Aggregated generation output from portfolios which consist of multiple different renewable technologies, including solar, is more predictable and less variable than single-technology portfolios. Solar generation is needed to support a high level of generation adequacy and generation dependability within the Great British electricity system. Storage facilities also contribute to security of supply by storing energy when it is generated in abundance, and releasing it to the grid when it is needed. Storage facilities also provide grid balancing services which are essential for the safe and secure operation of the NETS.
- ES13 Solar facilities are already among the cheapest form of electricity generation in the UK and previous government department forecasts indicate that costs will continue to reduce in the future. By generating low carbon electricity at a low marginal cost, large-scale solar power reduces the energy generated by more expensive and more carbon intensive forms of generation. Solar therefore decarbonises the electricity system and lowers the market price of electricity.
- ES14 In summary, a significant capacity of low-carbon solar generation is urgently needed in the UK. The Scheme will, if consented, provide an essential progression to meeting the governmental objectives of delivering sustainable development to enable decarbonisation. By doing so, the Scheme will address the climate change emergency that affects everyone's lives and the environment, by ensuring our energy supply is secure, low-carbon and low-cost.

1. Overview

1.1 Document Purpose

- 1.1.1 Fenwick Solar Project Limited (the Applicant) is seeking a Development Consent Order (DCO) for a large-scale solar plus storage development, connecting to the National Electricity Transmission System (NETS) (the Scheme).
- 1.1.2 This Statement of Need for solar generation describes how and why the Scheme addresses all relevant aspects of government policy, in particular the National Policy Statements EN-1 and EN-3. These Statements were published by the previous government in November 2023 and designated on 17 January 2024 [Ref. 1, Ref. 2]. The decision to consent the Scheme must be taken in accordance with the NPSs. NPS EN-1 establishes a critical national priority for nationally significant low-carbon infrastructure, the definition of which includes solar PV.
- 1.1.3 NPS EN-1 explains that:
- “The urgent need for CNP Infrastructure to achieving our energy objectives, together with the national security, economic, commercial, and net zero benefits, will in general outweigh any other residual impacts not capable of being addressed by application of the mitigation hierarchy. Government strongly supports the delivery of CNP Infrastructure and it should be progressed as quickly as possible”* [Ref. 1, Para 3.3.63].
- 1.1.4 This Statement of Need demonstrates the important contribution the Scheme will make to the three national energy policy aims:
- Net zero and the importance of urgently deploying low-carbon generation assets at scale;
 - Security of supply (geographically and technologically diverse supplies); and
 - Affordability and reducing exposure to volatile international markets.
- 1.1.5 This Statement of Need for the development of large-scale solar generation demonstrates why the Scheme is urgently needed at the scale proposed; why the proposed location is highly suitable for such a scheme; and how the Scheme addresses all relevant aspects of established and emerging governmental energy and climate change policy and commitments.
- 1.1.6 The Government’s election manifesto includes their ambition to deliver ‘Clean Power by 2030’. This ambition brings forward the ambitions set by the previous government to decarbonise Great Britain’s (GB’s) electricity supply and support wider decarbonisation with more secure and affordable energy supplies. Further information on their manifesto pledges, which include the tripling of solar capacity by 2030, is included at **Section 2.4** of this Statement. The delivery of large capacities of low-carbon generation, including large-scale solar generation, is a critical part of the government’s plans.
- 1.1.7 Delivering ‘Clean Power by 2030’ is an important step towards delivering the UK’s legally binding target of national net zero carbon emissions by 2050.

Chapter 4 of this Statement provides evidence that delivering net zero requires electricity demand to grow as transport, heat and industrial energy demand is decarbonised with clean power.

- 1.1.8 However, the need for new clean power does not stop at 2030. The continued delivery of low-carbon generation facilities beyond 2030 is necessary to meet future electricity demand growth and achieve essential wider societal carbon savings. It is also important to continue to bring forward renewable energy schemes, in the event that ‘Clean Power by 2030’ is not achieved.
- 1.1.9 This Statement of Need therefore provides evidence that solar is a key part of the government’s strategy for low-cost decarbonisation of the energy sector. It calls on established and emerging primary analysis and opinion by qualified third parties, to support the need case for the Scheme. The Scheme is required to ensure that the UK remains on track to meet its legally binding carbon emissions reduction targets, while enhancing national security of supply, and at a cost which, in relation to other electricity generation infrastructure developments, provides value for money for end-use consumers.

1.2 Document Overview

- 1.2.1 This Statement of Need provides relevant legal, policy, and industry evidence in support of the urgent need for decarbonisation and action to support security of electricity supplies in the UK.
- 1.2.2 This Statement of Need also provides evidence in support of ground mounted solar electricity generation generally, and the Scheme specifically, in relation to the benefit brought against the UK’s critical strategic needs.
- 1.2.3 This Statement of Need should be read in conjunction with international and national policy context relevant to the need for and benefits of this Scheme.
- 1.2.4 **Chapter 2** of this Statement of Need explains that urgent and unprecedented actions are required on a global scale to halt climate change. A critical step in the strategy to fight climate change is a full decarbonisation of the GB electricity system by 2035, and it is noted that the government’s election manifesto describes its aim to bring this target forwards to 2030.
- 1.2.5 **Chapter 3** of this Statement of Need summarises those National Policy Statements (NPSs) which are important and relevant to the Scheme. The decision to consent the Scheme must be taken in accordance with the NPSs. The NPSs provide that there is a critical national priority (CNP) for nationally significant low carbon infrastructure, including solar development, for both energy security and Net Zero, and that grid connection, irradiance and site topography are key inputs to the selection of sites suitable for large-scale solar generation developments.
- 1.2.6 **Chapter 4** provides evidence that decarbonisation will increase demand for electricity and describes the policies and strategies already in-flight which are increasing, or are set to increase, electricity demand.
- 1.2.7 **Chapter 5** provides an overview of progress in the development of different technologies with potential to play a role in the delivery of a net zero energy system. It highlights the uncertainty of delivery timescales for many

technologies, and the opportunity brought forward by developments with the proven ability to achieve carbon savings comfortably within the next decade. Storage assets will support the operation of low-carbon generators to achieve carbon savings.

- 1.2.8 **Chapter 6** provides evidence on technical considerations associated with the development of solar in the UK including principles associated with the siting and location of large-scale solar schemes and describes factors which are important in the design of a scheme within the context of a particular location.
- 1.2.9 **Chapter 7** sets out the benefits of the location of the Scheme in relation to decarbonisation, security of supply and delivering against the urgency of need. The chapter also provides evidence on the suitability of the proposed location from a grid operability and connection availability perspective.
- 1.2.10 **Chapter 8** provides evidence that solar generation contributes to security of supply as part of a multi-technology aggregated generation portfolio. Whereas **Chapter 5** demonstrates the need for storage facilities to be developed as renewable generation capacity grows, **Chapter 8** describes how co-located solar plus storage schemes can deliver flexibility.
- 1.2.11 **Chapter 9** provides evidence that solar facilities are already among the cheapest form of electricity generation in the UK and the development of more solar schemes will help to reduce the cost of wholesale electricity.

Chapter 10 provides the overall conclusions of this Statement of Need which are that a significant capacity of low-carbon solar generation is urgently needed in the UK. Developing this Scheme will be an essential step in meeting the governmental objectives of delivering sustainable development to enable decarbonisation. By doing so, the Scheme will address the climate change emergency that affects everyone's lives and the environment, by ensuring our energy supply is secure, low-carbon and low-cost.

1.3 Description of the Scheme

- 1.3.1 The Scheme would comprise the construction, operation and maintenance, and decommissioning of a solar photovoltaic (PV) electricity generating facility, with a total capacity exceeding 50 megawatts (MW) together with a Battery Energy Storage System (BESS), export and import connection to the National Electricity Transmission System (NETS) via National Grid's Thorpe Marsh Substation and associated infrastructure.
- 1.3.2 A full description of the Scheme is included in **Environmental Statement (ES) Volume I, Chapter 2: The Scheme [EN010152/APP/6.1]**
- 1.3.3 A non technical summary of the Scheme and its likely environmental effects is provided in the **ES Volume IV, Non-Technical Summary [EN010152/APP/6.4]**.

2. Legal and policy background: the need for urgent decarbonisation

2.1 Chapter summary

- 2.1.1 This chapter describes the global context of international climate change aims, commitments and actions taken to date, and future actions needed to limit global temperature increase to 1.5°C above pre-industrial levels.
- 2.1.2 It is important to emphasise the urgency of the need to decarbonise UK energy generation to meet national climate change target and climate budgets.
- 2.1.3 The urgency required of actions to deliver decarbonisation globally is increasing. Carbon has a cumulative warming effect, and it is well understood that decarbonisation progress to date must accelerate in all countries to limit the temperature increase to 1.5°C above pre-industrial levels.
- 2.1.4 Actions to decarbonise the UK must also accelerate for the UK to keep on track with meeting its five-yearly carbon budgets, its 2030 Nationally Determined Contribution (NDC), and its net zero target by 2050.
- The need for and the scale of future carbon reduction actions is increasing. The only way that need and scale will decrease in the future, while still limiting global temperature increases, is by delivering actions like the Scheme without undue delay.

2.2 Global decarbonisation

- 2.2.1 The Paris Agreement is a legally binding international treaty on climate change. It was adopted by 196 Parties at the UN Climate Change Conference (COP21) in Paris, France, on 12 December 2015. It entered into force on 4 November 2016.
- 2.2.2 The overarching goal of the Paris Agreement is to hold *“the increase in the global average temperature to well below 2°C above pre-industrial levels”* and pursue efforts *“to limit the temperature increase to 1.5°C above pre-industrial levels.”*
- 2.2.3 In October 2018, following the adoption by the UN Framework Convention on Climate Change of the Paris Agreement, the Intergovernmental Panel on Climate Change (IPCC), which is the United Nations body for assessing the science related to climate change, published a Special Report on the impacts of global warming of 1.5°C above pre-industrial levels. This report concluded that human-induced warming had already reached approximately 1°C above pre-industrial levels, and that without a significant and rapid decline in emissions across all sectors, global warming would not be likely to be contained, and therefore more urgent international actions to decarbonise are required.
- 2.2.4 NDCs are at the heart of the Paris Agreement and the achievement of its long-term goals. NDCs embody efforts by each country to reduce national emissions and adapt to the impacts of climate change. The Paris Agreement (Article 4, paragraph 2) requires each Party to prepare, communicate, and

maintain successive NDCs that it intends to achieve. Parties shall pursue domestic mitigation measures, with the aim of achieving the objectives of such contributions.

- 2.2.5 The IPCC Working Group III (IPCC WG3) published its Summary of Climate Change as part of the IPCC's Sixth Assessment Report in April 2022 [Ref. 3]. The IPCC WG3 report notes that although the rate of growth of average global annual greenhouse gas (GHG) emissions was lower between 2010 and 2019 than in the previous decade, average global annual GHG emissions during the last decade were higher than in any previous decade on record.
- 2.2.6 The IPCC WG3's global GHG emissions for four modelled scenarios are included in Figure 2-1. The red band shows global annual GHG emissions considering global decarbonisation policies which at the time of writing the report had been implemented. Implemented policies are likely to slow the historical increase in annual emissions but are not yet sufficient to reduce them. That is to say, policies which have already been implemented mean that global GHG emissions will continue at their current level through to 2050.
- 2.2.7 The purple, green, and blue bands show the IPCC's conclusions on different decarbonisation pathways, which must be followed to meet three scenarios of global temperature increases.
- 2.2.8 The purple band shows the decarbonisation path achieved by NDCs to 2030 followed by the decarbonisation path required to limit temperature increase to 2°C above pre-industrial levels with a probability of at least 67%. The red band is higher than the purple band, which implies that policies implemented to date are not yet sufficient to meet 2030 NDC commitments.
- 2.2.9 The green band shows the decarbonisation path which will achieve the same outcome as the purple path, by increasing actions in the 2020s and overshooting current NDCs. By urgently increasing decarbonisation actions now, future year-on-year carbon reductions to meet the same outcome can be lower and therefore are likely to be more achievable.
- 2.2.10 The cumulative warming effect of carbon means that not delivering against plans set out for the 2020s will lead to a greater scale and urgency to future plans and their delivery in order to meet the temperature increase limit set by the Paris Agreement. Delaying decarbonisation actions increases the risk of losing the fight against climate change, whilst in the meantime ongoing climate change events and impacts are unlikely to slow or decrease, putting lives and livelihoods at risk.
- 2.2.11 The blue band shows the decarbonisation path which will meet the commitments of the Paris Agreement with a probability of 50%.
- 2.2.12 Conclusions arising from Figure 2-1 are:
- a. Global climate change commitments are not yet sufficient to meet nor sustain a (likely) successful track towards containing global temperature rise below 1.5°C;
 - b. Policies implemented to date fall short even of those commitments; and

c. The delivery of measures will be required beyond 2030 to ensure that the 2050 target is met.

2.2.13 The IPCC WG3 report findings also imply that mitigation after 2030 can no longer establish a pathway which will likely not exceed 1.5°C global temperature increase vs. 1990, during the 21st Century.




Figure 2-1: Representation of global GHG emissions of modelled pathways [Ref. 3, Figure SPM.4]

2.2.14 The compelling need for global action to decarbonise continued to be reinforced through the IPCC’s 20 March 2023 publication of its 2023 assessment of global climate change. The report concludes that the world is likely to pass a dangerous temperature threshold within the next 10 years, pushing the planet past the point of catastrophic warming — unless nations drastically transform their economies and immediately transition away from fossil fuels [Ref. 4].

2.2.15 The Synthesis Report of the IPCC’s Seventh Assessment Report will be produced after the completion of the Working Group reports and released by late 2029.

2.2.16 In a June 2024 news report which accompanied the publication of its Global Annual to Decadal Climate Update (2024 – 2028) report, the World Meteorological Organisation (WMO) stated that “There is a 47% likelihood

that the global temperature averaged over the entire five-year 2024-2028 period will exceed 1.5°C above the pre-industrial era [Ref. 5]. This implies that sufficient progress on fighting climate change has not yet been made and more needs to be done in both mitigation and adaptation.

- 2.2.17 The 28th Conference of the Parties to the United Nations Framework Convention on Climate Change (COP28) was held in Dubai in December 2023. COP28 achieved agreement among the parties, to *“tripling renewables and doubling energy efficiency”*. On a global basis, COP28 concluded the requirement for action to abolish carbon emissions is more urgent now than ever it has been.
- 2.2.18 The same is true for the UK [Ref. 6], and in July 2024, the Secretary of State for Energy Security and Net Zero met with past and future COP Presidents to discuss the need for greater urgency in tackling the climate crisis while underlining *“the UK’s determination to act as a global leader and reliable partner on climate action”* and *“the importance of the UK’s renewed domestic leadership in encouraging ambitious action abroad. Climate and clean energy are at the heart of the new government’s agenda. The UK is taking immediate action to unlock investment in onshore wind, [and] begin a solar revolution”* [Ref. 87].

2.3 Decarbonisation in the UK

- 2.3.1 As a result of its commitments to the Paris Agreement, in June 2019 the UK became the first major economy to legislate for a 2050 net zero GHG emissions target through the Climate Change Act 2008 (2050 Target Amendment) Order 2019 [Ref. 7].
- 2.3.2 Decarbonisation is therefore a UK legal requirement.
- 2.3.3 In December 2020, the UK communicated its NDCs under the Paris Agreement to reduce GHG emissions by at least 68 per cent from 1990 levels by 2030. In April 2021, the then government legislated for the Sixth Carbon Budget (CB6), which requires the UK to reduce GHG emissions by 78 per cent by 2035 compared to 1990 levels.
- 2.3.4 UK governmental objectives are to ensure the supply of energy to the national energy system always remains secure, reliable, affordable, and consistent with meeting legally binding GHG emissions including the NDC. NPS EN-1 states that government has identified that this will require a step change in the decarbonisation of the UK’s energy system [Ref. 1, Para 2.3.3], and large-scale ground mounted solar has an important role to play in the UK.
- 2.3.5 The Climate Change Committee (CCC), a national independent advisory committee, made clear in its Progress Report to Parliament in 2019 [Ref. 8(2019)], that the UK is not on track to meet its fourth (2023-2027) or fifth (2028-2032) carbon budget.
- 2.3.6 This position was reinforced in the latest 2024 report which states that:
“Urgent action is needed to get on track for the UK’s 2030 target ... only a third of the emissions reductions required to achieve the 2030 target are currently covered by credible plans. Action is needed across all sectors of

the economy, with low-carbon technologies becoming the norm.” [Ref. 8(2024), p8]

And

“The UK should now be in a phase of rapid investment and delivery ... Annual offshore wind installations must increase by at least three times, onshore wind installations will need to double and solar installations must increase by five times.” [Ref. 8(2024), p9]




Figure 2-2: UK historical emissions, the CBDP indicative pathway and the UK’s targets [Ref. 8(2024), Figure 1.1]

- 2.3.7 Emissions in the UK have steadily fallen over the last three decades and the UK met its first three carbon budgets covering the period 2008 - 2022 [Ref. 8(2024), p18]. In 2023 emissions were 49.5% below 1990 levels according to provisional estimates [Ref. 8(2024), p19].
- 2.3.8 Figure 2-2 shows historical emissions and performance against historical Carbon Budgets. The CCC’s Carbon Budget Delivery Plan (CBDP, yellow) for Carbon Budgets CB4, CB5 and CB6 are also shown, as is the UK’s NDC in 2030.
- 2.3.9 The reduction in carbon emissions required from CB5 to achieve CB6 is significant. The delivery of new low-carbon electricity generation beyond 2030 is essential for progress towards the UK’s 2050 net zero legally binding target to continue to be made. The Scheme will meet the need for new low-carbon generation to be brought online beyond 2030.
- 2.3.10 The CCC concluded that the main driver of carbon emission reductions in 2023 was from electricity supply, largely due to increased electricity imports and reduced electricity exports, as *“the UK returned to its normal status as a net importer of electricity, after one year as a net exporter of electricity in 2022”* [Ref. 8(2024), p19], suggesting that there is still work to do to

decarbonise electricity generation in the UK. The annual pace of change required to meet the UK's 2030 NDCs is 18.8 MtCO_{2e} per year from 2023 to 2030, however the average annual rate over the previous seven years was only 13.8 MtCO_{2e} per year. The CCC report that outside the electricity supply sector, the average annual rate of reduction over the previous seven years was only 6.3 MtCO_{2e} per year, but will need to more than double to 14.3 MtCO_{2e} per year over the next seven years to meet the 2030 NDC.

- 2.3.11 The CCC conclude that *“This will require substantial increases in the rates of reduction in most sectors outside of electricity supply”* [Ref. 8(2024, p17)]. **Chapter 4** shows that decarbonisation of other sectors is largely dependent on the availability of sufficient quantities of low-carbon electricity as a substitute for carbon-emitting fuels. It therefore follows that the development of new low-carbon electricity generation infrastructure also needs to accelerate.
- 2.3.12 Progress in decarbonising electricity supply has been delivered by phasing out coal-generated electricity and increasing the share of renewable generation. The CCC conclude that to maintain progress, *“We now need to rapidly reduce oil and gas use as well.”* [Ref. 8(2024), p8].
- 2.3.13 Without adequate supply of low-carbon electricity, the urgent requirement for a rapid decarbonisation of other sectors (as will be required to meet future Carbon Budgets) is unlikely to be achieved.

2.4 The Government's Energy Strategy

- 2.4.1 The UK's general election in July 2024 saw a change of government. However, the UK's 2030 NDC remains unchanged at 68 per cent reduction in territorial emissions by 2030 on 1990 levels. The Sixth Carbon Budget (2033-2037) also remains unchanged, requiring the UK to reduce GHG emissions by 78 per cent by 2035 compared to 1990 levels.
- 2.4.2 The government made major commitments to the delivery of clean energy in its election manifesto [Ref. 31], including to achieve 'Clean Power by 2030'. The government's commitments include to:
- a. Double onshore wind, triple solar power, and quadruple offshore wind by 2030;
 - b. Invest in carbon capture and storage, hydrogen and marine energy;
 - c. Take decisions on existing and new nuclear power;
 - d. Embrace the future of energy production and storage; and
 - e. Through a new publicly-owned company, Great British Energy, partner with energy companies, local authorities, and co-operatives to install thousands of clean power projects, through a combination of onshore wind, solar, and hydropower projects.
- 2.4.3 While further detail on how the government's manifesto pledges will be delivered is not currently available, it is important to note that:
- a. The government's strategy to deliver societal decarbonisation through decarbonisation of the electricity sector and electrification of other sectors is consistent with the previous government's strategy;

- b. The government's decarbonisation and energy security strategy pledges are more ambitious than those of the previous government at the time of the general election;
 - c. The delivery of large capacities of low-carbon generation, including large-scale solar generation, is a critical part of the government's plans; and
 - d. Delivery of 'Clean Power by 2030', if achieved, must be followed by further measures to ensure that energy stays green beyond 2030. This is also true if 'Clean Power by 2030' is not achieved.
- 2.4.4 In March 2020, the Energy System Catapult's Innovating to Net Zero report observed that:
- "Net Zero narrows the set of viable pathways for the future energy system. Where an 80% target allowed considerable variation in relative effort across the economy, with some fossil fuels still permissible in most sectors, Net Zero leaves little slack."* [Ref. 25, p5]
- 2.4.5 It therefore follows that the government's proposed approach to achieve net zero shares many similarities with the approach taken by the previous government, and indeed there is nothing inconsistent between the government's approach and the approach taken by the previous government which would mean a move away from existing policies in support of renewable electricity supplies.
- 2.4.6 That said, one key aspect of difference is that the urgency of the need to implement measures which deliver decarbonisation is now greater because of the reasons described in **Section 2.2** of this Statement. The government's support for renewable generation going forwards is therefore highly likely to be no lower than the support set out in existing publications and strategies and, if anything, may be more supportive, as evidenced by the approval of four large-scale solar DCOs (Sunnica Energy Farm, Mallard Pass Solar Project, Gate Burton Energy Park and Cottam Solar Project) in the first months of the government's term in office, the first three of which were overdue decisions.
- 2.4.7 The need for new clean power does not stop at 2030. The continued delivery of low-carbon generation facilities beyond 2030 is necessary to meet future electricity demand growth and achieve essential wider societal carbon savings. It is also important to continue to bring forward schemes in case 'Clean Power by 2030' is not achieved.
- 2.4.8 This chapter therefore calls on existing publications, including those published under previous governments, to support the evidence base for the need for large-scale solar in the UK to deliver energy security, decarbonisation and affordability benefits, and notes that the urgency to deliver these benefits has increased under this government.

2.5 The UK's Plan For Decarbonisation

- 2.5.1 The UK chose to largely decarbonise its power sector by adopting low carbon sources quickly, and invited industry to bring forward new low carbon developments to meet the twin challenge of energy security and climate change [Ref. 1, Para 4.2.2].

- 2.5.2 Implementing this strategy by closing generation capacity with high carbon emissions and replacing it with low-carbon renewable energy has delivered significant decarbonisation benefits in the UK to date.
- 2.5.3 Figure 2-3 shows that carbon emissions associated with the UK’s electricity system (green dashed line) have reduced by approximately 70% between 2005 and 2022 (the most recent year for which data is available from this source). Non-electrical emissions have also reduced but by a lower percentage.
- 2.5.4 The domestic and transport sectors had the highest carbon emissions in 2022. Fossil fuels remain a major source of energy to these sectors. Critically the percentage reductions of emissions in those sectors between 2005 and 2022 were significantly lower than national average emission reductions, at 42% and 21% respectively. Emissions from the domestic sector had also reduced by just 21% when measured excluding reductions in emissions from electricity.
- 2.5.5 Figure 2-3 suggests that the transport, domestic and industrial sectors require a significant intervention to reduce carbon emissions, and that the reduction of emissions from those sectors will be critical if net zero 2050 is to be reached. The continued delivery of low-carbon generation facilities beyond 2030 is necessary to reduce emissions from those sectors.




Figure 2-3: National (UK) District GHG Emissions 2005 – 2022 (LULUCF net benefits small and not shown [Ref. 9, Author Analysis])

2.6 The Energy White Paper

- 2.6.1 The Energy White Paper [Ref. 10], published in December 2020, outlined a strategy to transform the energy system, tackling emissions while continuing to ensure secure and reliable supply, and affordable bills for households and businesses.
- 2.6.2 Solar has helped increase UK renewable generation capacity five-fold between 2010 and 2020 [Ref. 10, p40].

- 2.6.3 A low-cost, net zero consistent system is likely to be composed predominantly of wind and solar [Ref. 10, p43].
- 2.6.4 Onshore wind and solar will be key building blocks of the future generation mix, along with offshore wind. We will need sustained growth in the capacity of these sectors in the next decade to ensure that we are on a pathway that allows us to meet net zero emissions in all demand scenarios [Ref. 10, p45].
- 2.6.5 Solar plays an increasingly important role in supporting an affordable and fair energy system by displacing price-setting gas from the electricity system [Ref. 10, p30].
- 2.6.6 The second mission of the government's election manifesto, 'Clean Power by 2030', shows consistency with the themes and measures recommended in the Energy White Paper, albeit the target quanta are higher.
"To deliver our clean power mission, Labour will work with the private sector to double onshore wind, triple solar power, and quadruple offshore wind by 2030." [Ref. 31, p51]
- 2.6.7 It is clear that the government's strategy also requires a significant increase in the deployment of solar power as part of a clean national electricity system by 2030.

2.7 Net Zero Strategy – Build Back Greener

- 2.7.1 The Net Zero Strategy (NZS) [Ref. 11], published in October 2021, set out a long-term plan for the economy-wide transition to net zero that will take place over the next three decades.
- 2.7.2 The NZS's key policy is for the UK to be powered entirely by clean electricity by 2035, subject to security of supply [Ref. 11, p20].
- 2.7.3 The previous government committed to accelerate deployment of low-cost renewable generation, such as wind and solar, to meet their key policy aim [Ref. 11, p94], and the government's election manifesto contains similar pledges in support of their mission to deliver 'Clean Power by 2030'.
- 2.7.4 A sustained increase to the deployment of land-based renewables such as locally supported onshore wind and solar in the 2020s and beyond is required to meet CB6 [Ref. 11, p103 and [Ref. 8(2024, p9].
- 2.7.5 The NZS includes up-to-date evidence of the low cost of large-scale solar globally, which is supporting the necessary increase in capacity of large-scale solar builds in the UK [Ref. 11, p312].
"Gas will continue to play a role in setting the electricity price for some years to come but, over time, will do so less frequently, as more and more low carbon generation (such as wind and solar) connect to the electricity system ... This will help put downward pressure on wholesale electricity prices" [Ref. 11, p337].
- 2.7.6 The government's election manifesto states that they will go beyond the previous government's ambition and will deliver 'Clean Power by 2030' by *"creat[ing] a new publicly-owned company, Great British Energy ... [to] ... partner with industry and trade unions to deliver clean power by co-investing in leading technologies to install thousands of clean power projects, through*

a combination of onshore wind, solar, and hydropower projects” [Ref. 31, pp53-54].

- 2.7.7 By doing so, Great British Energy will help make Britain a clean energy superpower, *“cut bills, create jobs and deliver security with cheaper, zero carbon electricity by 2030, accelerating to net zero.” [Ref. 31, p11].*

2.8 The British Energy Security Strategy

- 2.8.1 The British Energy Security Strategy, published in April 2022, set out the immediate need to manage the financial implications of soaring commodity prices in the near term and also the long-term goal of *“address[ing] our underlying vulnerability to international oil and gas prices by reducing our dependence on imported oil and gas” [Ref. 12, p6].*
- 2.8.2 The British Energy Security Strategy recognises the critical role of renewables in accelerating the transition away from fossil fuels [Ref. 12, p16].
- 2.8.3 The British Energy Security Strategy introduced the then government’s increased ambition for solar generation, supporting a five-fold increase in deployment of solar technology by 2035, recognising the abundant source of solar energy in the UK and an 85% reduction in cost of solar power over the last ten years. [Ref. 12, p19]. The online British Energy Security Strategy includes an explicit ambition for up to 70GW of British solar on roofs and on the ground by 2035.
- 2.8.4 For ground-mounted solar, the strategy indicates a future consultation on planning rules to strengthen policy in favour of development on non-protected land, while ensuring communities continue to have a say and environmental protections remain in place. [Ref. 12, p19].
- 2.8.5 Critically, the British Energy Security Strategy includes actions such as the bringing forward electricity into home heating and supporting the rollout of electric vehicles (EVs) as part of the Electric Vehicle Infrastructure Strategy, which will increase demand for electricity in future years, from potentially as early as the mid-2020s.
- 2.8.6 The second mission of the government’s election manifesto, ‘Clean Power by 2030’ has been chosen:
“not because it is easy, but because working people can never again be left vulnerable to dictators like Putin.
To deliver our clean power mission, Labour will work with the private sector to double onshore wind, triple solar power, and quadruple offshore wind by 2030.” [Ref. 31, p51]
- 2.8.7 The government’s mission shows consistency with the themes and measures recommended in the British Energy Security Strategy, albeit the target quanta differ in that the government’s ambitions with regard to the scale and pace of delivery of low-carbon electricity generation, are larger, and quicker, than those of the previous government.

2.9 Mission Zero – The Skidmore Review

- 2.9.1 Mission Zero was published in January 2023 by Rt Hon Chris Skidmore MP, Chair of the then government's Independent Review of Net Zero. The report was commissioned to ask how the UK might deliver its own net zero targets in a manner that was more affordable, more efficient, and in a pro-business and pro-enterprise way. Mission Zero recognises the importance of taking action on net zero. It also recognises the fact that the energy transition is a new economic reality, particularly amid the global reality of the energy security crisis and rising gas and fossil fuel prices in 2022.
- 2.9.2 Mission Zero reconfirms the global importance of the UK's commitment to achieve net zero and makes recommendations which should be taken forwards, alongside other wider recommendations. It states that the UK should be proud of the steps it has taken so far to achieve net zero, and that climate change and the economy are intertwined. The UK must however move quickly, not only to protect and secure delivery of our national climate commitments but also deliver the economic benefits of moving away from a carbon economy. The review finds that *"The benefits of net zero will outweigh the costs"* and believes that *"This is too important to get wrong"* [Ref. 13, p8].
- 2.9.3 The government's election manifesto shows consistency with these themes, through the inclusion of a quote from Sir Patrick Vallance, a former Chief Scientific Advisor and recently appointed Minister of State for Science in the Department for Science, Innovation and Technology (July 2024). Sir Patrick explains, in regard to a national mission for 'Clean Power by 2030', that *"We can be the innovators and the implementers, helping ourselves and exporting our solutions worldwide. But if we choose to go slowly, others will provide the answers, and ultimately we'll end up buying these solutions rather than selling them"* [Ref. 31, p48] thereby supporting the commercial imperative to proceed with decarbonisation at pace, as previously described in Mission Zero.
- 2.9.4 Mission Zero makes the following recommendations which are relevant to the growing need for large-scale ground mount solar to be deployed in the UK:
- a. Priority Mission no. 2: *"Full-scale deployment of solar including a rooftop revolution to harness one of the cheapest forms of energy, increase our energy independence and deliver up to 70GW of British solar generation by 2035"*. The government's election manifesto calls for solar power to triple (to approximately 45GW) by 2030 [Ref. 31, p51];
 - b. Priority Mission no. 8: *"Working towards gas free homes by 2035 [or earlier]"* and Recommendation 1 is to set a legislative target for gas-free homes and appliances. The government's Warm Homes Plan *"will offer grants and low interest loans to support investment in insulation and other improvements such as solar panels, batteries and low carbon heating to cut bills."* [Ref. 31, p56] which when delivered will reduce domestic reliance on natural gas;
 - c. Recommendation 15 is the swift delivery of Zero Emissions Vehicles (ZEVs) and the ZEV mandate to apply from 2024. Powering Up Britain (see following) remains ambitious and forward-thinking in its targets for

the decarbonization of light road transport, but is less explicit in regard to associated timelines – noting the practical requirement to remain compatible (from a supply chain / industry change perspective) with the wider European position: *“Between 2030 and 2035, new cars and vans will only be able to be sold if they offer significant zero emission capability”* [Ref. 14, p27]. The government’s election manifesto sets out their support for *“the transition to electric vehicles by accelerating the roll out of charge points, [and] giving certainty to manufacturers by restoring the phase-out date of 2030 for new cars with internal combustion engines”* [Ref. 31, p31];

- d. Priority Mission 8 and Recommendations 1 and 15 add weight to the argument for rollout of solar and other renewable generation to meet the growing demand which will arise from their delivery, consistent with the government’s mission to deliver ‘Clean Power by 2030’;
- e. Priority Mission no. 9 is to *“Embed nature and habitat restoration ... maximising co-benefits for climate and nature wherever possible.”* Ground mount solar can deliver on this Priority Mission through delivering biodiversity net gain because of development;
- f. Recommendation 11 is to *“Set up taskforce and deployment roadmaps in 2023 for solar to reach up to 70GW by 2035.”* This Recommendation recognises that the current pipeline for solar projects in the UK, and the most ambitious industry projections for solar deployment, are not yet of sufficient scale to meet the then government’s ambition without undue levels of risk associated with the deployment of other technologies. A change in government does not materially change the risk to delivery of projects in the near term, and on 9 July 2024, Ed Miliband, the new Secretary of State for Energy Security and Net Zero appointed Chris Stark, the former chief executive of the CCC, to *“head new Mission Control, tasked with turbocharging UK to clean power by 2030”* [Ref. 88]; and
- g. Mission Zero recognises the importance of local action and local plans to the achievement of net zero. People and places must be empowered to deliver net zero through a full alignment on a local level with a net zero future through the introduction of a ‘net zero test’. All local authorities will be required to play their part in achieving carbon neutrality in the future. Ground-mounted solar (at both Nationally Significant infrastructure and local planning authority scale) is a leading deliverable low-carbon generation technology which will enable local authorities to deliver against plans to decarbonize on a local level.

2.9.5 The government’s mission to deliver ‘Clean Power by 2030’ is consistent with many of the findings of Mission Zero. For example:

- a. The ambitious targets to *“double onshore wind, triple solar power, and quadruple offshore wind by 2030”* [Ref. 31, p51];
- b. The establishment of Great British Energy to *“drive forward investment in clean, home-grown energy production”* [Ref. 31, p53]; and
- c. Establishing the Mission Control for Clean Power, with four strands of activity including: setting and tracking the overall approach to delivering

2030 across the energy system; real time monitoring of progress on UK infrastructure projects critical to 2030; acting as an innovation centre by encouraging discussion among experts; and serving as a convener for the Mission Control approach across government and with industry [Ref. 88].

2.10 Powering Up Britain

- 2.10.1 The previous government's Powering Up Britain Strategy, Powering Up Britain: Energy Security Plan and Powering Up Britain: Net Zero Growth Plan all set out how the UK will achieve energy security, promote green growth and meet its net zero targets.
- 2.10.2 Powering Up Britain was published in March 2023 to present the most up to date information on the previous government's energy strategy, explaining *"how the Government will enhance our country's energy security, seize the economic opportunities of the transition [to renewables], and deliver on our net zero commitments"* [Ref. 14(1), p6], and observes that *"The [Mission Zero] Review was unequivocal in its assessment that the plan set out in the Net Zero Strategy was the right one, whilst providing recommendations to strengthen delivery."* [Ref. 14(1), p16]
- 2.10.3 Powering Up Britain concludes that *"We need investment at scale ... to rapidly rollout existing technologies ... at pace to meet our ambitions for decarbonising power and [lower] wholesale UK electricity prices."* [Ref. 14(1), p9] and observes that *"a significant proportion of technologies we will need for 2050 are currently at the demonstration or prototype phase"* [Ref. 14(1), p9]. This implies that while we should continue to strive for innovation, waiting for novel technologies to deliver comes with risk (as some technologies may not deliver) and therefore the government's strategy to deliver a rapid rollout of existing technologies while continuing to invest in new technologies is of critical importance in the fight against climate change. Ground-mounted large-scale solar is a mature technology which is capable of delivering a reliable and rapid rollout once projects are consented.
- 2.10.4 The government's election manifesto includes ambitions to *"triple solar power"* by 2030 [Ref. 31, p51] as well as continue to *"invest in carbon capture and storage, hydrogen and marine energy... the long-term energy storage our country needs ... and new nuclear power stations, such as Sizewell C, and Small Modular Reactors ... to ensure the long-term security of the [nuclear] sector"* [Ref. 31, pp51-52].
- 2.10.5 Powering Up Britain recognises the huge potential solar generation can have in decarbonisation. Large-scale ground-mounted solar is a mature technology, capable of delivering a reliable and rapid rollout once projects are consented, and is one of the cheapest forms of electricity generation that is readily deployable at scale.
- 2.10.6 Powering Up Britain therefore includes the acceleration of renewables deployment as critical to support the delivery of the then government's plans: *"Our goal is to develop up to 50GW of offshore wind by 2030 and to quintuple our solar power by 2035"* [Ref. 14(1), p7], noting that 14GW of solar is already installed in the UK [Ref. 14, p19].

- 2.10.7 Powering Up Britain's Energy Security Plan confirms that the then government was *"aiming for 70GW of ground and rooftop capacity together by 2035 ... We need to maximise deployment of both types of solar to achieve our overall target"* [Ref. 14(5), p37].
- 2.10.8 In support of the emphasis Powering Up Britain places on the need to maximise the deployment of ground-mounted solar, the strategy states that the *"Government seeks large scale solar deployment across the UK, looking for development mainly on brownfield, industrial and low/medium grade agricultural land. The government will therefore not be making changes to categories of agricultural land in ways that might constrain solar deployment"* [Ref. 14(1), p20].
- 2.10.9 Powering Up Britain makes it clear that the then government expected the operational capacity of both large-scale and rooftop solar to grow in pursuit of net zero. In other words, that development on agricultural land is also anticipated.
- 2.10.10 Through the establishment of Great British Energy and Mission Control for 'Clean Power by 2030', the government has already set in place organisations to speed the transition towards UK energy security and net zero. The government's election manifesto recognises that *"Local power generation is an essential part of the energy mix and reduces pressures on the transmission grid"* [Ref. 31, p54] and their action to consent four large-scale transmission connected ground mount solar schemes in their first month in office, makes it clear that large-scale solar has a role to play in their plan for a secure and low-carbon energy future.

2.11 Climate Change Committee Progress Report to Parliament, 2024

- 2.11.1 The CCC published the 2024 edition of their annual Progress Report to Parliament in July 2024. The report leads with the Committee's view that *"the new government will have to act fast to hit the country's [climate] commitments"* [Ref. 8(2024), p8].
- 2.11.2 The Committee summarised that *"the cost of key low-carbon technologies is falling, creating an opportunity for the UK to boost investment, reclaim global climate leadership and enhance energy security by accelerating take-up. British-based renewable energy is the cheapest and fastest way to reduce vulnerability to volatile global fossil fuel markets. The faster we get off fossil fuels, the more secure we become"* [Ref. 8(2024), p8].
- 2.11.3 Further, the Committee assessed that *"only a third of the emissions reductions required to achieve the 2030 target are currently covered by credible plans. Action is needed across all sectors of the economy, with low-carbon technologies becoming the norm,"* and that rapid reductions in the use of oil and gas must also be secured [Ref. 8(2024), p8].
- 2.11.4 The Committee's assessment also implies that plans to achieve emissions reductions beyond 2030 are not yet credible and therefore that schemes which come forwards which will help deliver those reductions in that timeframe are also needed.
- 2.11.5 To deliver this, the Committee recommend that:

- a. Annual offshore wind installations must increase by at least three times, onshore wind installations will need to double and solar installations must increase by five times;
 - b. Approximately 10% of existing homes in the UK will need to be heated by a heat pump, compared to only approximately 1% today; and
 - c. The market share of new electric cars needs to increase from 16.5% today to nearly 100%.
- 2.11.6 These recommendations are consistent with a continuing move away from the use of fossil fuels and towards an energy system with electricity at its centre, either directly or through the use of hydrogen, produced at least in part, by the electrolysis of water.
- 2.11.7 The CCC report that *“indicators for low-carbon technology roll-out are off track, with rates needing to significantly ramp up”* to achieve 2030 targets [Ref. 8(2024), p9], including on engineered removals. While technologies with substantial lead-times continue to be progressed, delivery of essential nearer-term carbon emission reductions will need to come from increasing renewable electricity generation capacity.

2.12 Energy Act 2023

- 2.12.1 In October 2023, the Energy Act 2023 (EA 2023) came into law. The EA 2023 aims to strengthen energy security and support the delivery of net zero and affordable energy bills for households in the long term.
- 2.12.2 Government’s press release at the time of Royal Assent [Ref. 15] describes the key elements of the EA 2023.
- 2.12.3 The EA 2023 brings heat networks into the remit of the Office for Gas and Electricity Markets (Ofgem), further supporting the UK’s whole-system approach to energy, and updates their remit further so that the Office considers net zero targets as part of its everyday decisions.
- 2.12.4 New measures will also support consumers in their transition to ‘smart products’ which will pave the way to the automatic response of UK electricity demand at times of abundance or potential scarcity – a key measure if households are to deliver flexibility to the UK’s energy system.
- 2.12.5 On the energy supply side, the EA 2023 legislates for the regulation of nuclear fusion, an important enabler of the UK’s prototype fusion ambitions for 2040.
- 2.12.6 The EA 2023 also introduces a new licensing framework for CO₂ and hydrogen transport and storage to help deliver the UK’s first carbon capture and hydrogen production sites.
- 2.12.7 Further provision is made within the EA 2023 to support the growth of offshore wind while ensuring that compensation for any adverse environmental effects is delivered strategically as opposed to being delivered on a scheme-by-scheme basis.
- 2.12.8 The EA 2023 should therefore be seen as enabling legislation which will support the UK to deliver on technology development to achieve net zero by

2050. Further discussion on those technologies is included in **Chapter 5** of this Statement.

- 2.12.9 A forthcoming Energy Independence Act will establish the framework for the government's energy and climate policies.

2.13 Connections Action Plan

- 2.13.1 Securing a timely grid connection is a critical enabler for low carbon infrastructure to contribute towards a zero-carbon electricity system in the 2030s, but grid connection availability is currently constrained.
- 2.13.2 The government's election manifesto states that *"The national grid has become the single biggest obstacle to the deployment of cheap, clean power generation and the electrification of industry. With grid connection dates not being offered until the late 2030s, important business and infrastructure investment is being stalled or lost overseas. Labour will work with industry to upgrade our national transmission infrastructure and rewire Britain."* [Ref. 31, p55]
- 2.13.3 In November 2023, DESNZ and Ofgem jointly published a Connections Action Plan which states:
- "Nearly half of transmission generation projects have a connection date at least five years from now, with some scheduled to wait ten years or more. This is simply too slow and remains the biggest risk to our ability to decarbonise our power system by 2035 ...*
- The Plan is aimed at getting a significant majority of projects connected by their requested connection date, up from 14 per cent today, and to reduce the average delay a project faces in connecting to the transmission network from five years to six months"* [Ref. 16, p7]
- 2.13.4 The Connections Action Plan includes reforms to the connections process which have been designed to enable viable projects to connect in a timely and cost-effective manner. The reforms are:
- a. Raising entry requirements, including evidence of landowner permission, to deter speculative connection applications;
 - b. Removing stalled projects to release capacity for more viable projects;
 - c. Better utilising existing network capacity to reduce connection timelines; and
 - d. Allocating available network capacity to connect projects that are readier to progress and are able to quickly make use of capacity.
- 2.13.5 The Connections Action Plan explains that the efficient utilisation of existing networks can defer or negate the need for expensive new infrastructure, which takes time to deliver [Ref. 16, pp26&27] and that ensuring that existing and future capacity is allocated efficiently will allow timely connection offers, aligned with net zero objectives.
- 2.13.6 In relation to increasing network capacity, the Connections Action Plan describes that there are two approaches. The first is to increase network build and the second, which is described as *"more efficient"* and *"typically*

lower cost”, is to “*maximise the use of the currently available and planned network capacity*” [Ref. 16, pp40&41].

- 2.13.7 Capacity allocation is defined in the Plan as an approach to “*maximise the benefits of available capacity such that projects that are more ready and able to connect can do so ahead of those which are stalled, while maintaining appropriate opportunities for technologies with varying lead times, in line with net zero pathways*” [Ref. 16, p44]
- 2.13.8 Schemes which propose to develop technology which will support the move to net zero (such as solar and storage schemes) are therefore aligned with the government’s aims and strategy. Schemes which propose to connect to existing and available connection infrastructure are aligned with the Connections Action Plan reforms.
- 2.13.9 Ensuring assets can connect to the electricity network where and when they need to is crucial to achieving net zero, as well as to delivering affordability for consumers and maintaining security of supply.
- 2.13.10 However, there are currently insufficient existing National Grid or distribution network substations suitably located with the capacity available to connect new solar, onshore wind and offshore wind assets required to meet the government’s low-carbon aims.
- 2.13.11 New substations will need to be proposed, designed and constructed to deliver the government’s ambition and other substations will need to be expanded to connect new schemes. This programme of work will need to occur at the same time as other schemes are connected to existing substations which have available capacity.
- 2.13.12 All schemes with grid connection dates in or before 2030 are valuable to deliver the government’s ambition to deliver ‘Clean Power by 2030’, and it is important to continue to bring forward schemes with connection dates in the 2030s in the event that ‘Clean Power by 2030’ is not achieved.
- 2.13.13 Any positive interventions made by a government or other statutory bodies, such as those set out in the Connections Action Plan and in the government’s election manifesto, provide for the possibility that earlier connection dates may be achievable for schemes which meet National Grid’s queue entry and prioritisation requirements as they evolve.
- 2.13.14 The Scheme proposes to connect a large-scale solar plus storage asset to an existing part of the National Electricity Transmission System via an existing point of connection. Through the design of the Scheme, the Applicant seeks to maximise use of the connection capacity which is to be made available to it. The Scheme is therefore fully aligned with the direction of travel of relevant policy and action plans in support of achieving the government’s ambition of delivering ‘Clean Power by 2030’.

2.14 Conclusions On Decarbonisation Policy Context

- 2.14.1 Urgent and unprecedented action is needed on an international scale to meet the commitments established through the Paris Agreement for urgent actions to decarbonise society and stop global warming.
- 2.14.2 The UK has legally binding targets to decarbonise and is developing new, and enhancing existing, policies to ensure that those targets are met in a secure and affordable fashion.
- 2.14.3 However, policies are not yet sufficient to deliver to those national commitments, and delivery against those UK policies is further behind.
- 2.14.4 Without a rapid increase in the supply of low-carbon electricity, the urgent requirement to decarbonise other sectors (as will be required to meet future Carbon Budgets) is unlikely to be achieved.
- 2.14.5 Solar generation is increasing in both scale and importance within emerging government policy. Not only for the benefits it delivers to decarbonisation, but also because of the need for secure and affordable energy supplies.
- 2.14.6 The government's ambition is to triple solar capacity by 2030, alongside doubling onshore wind and quadrupling offshore wind.
- 2.14.7 To deliver the government ambition, the equivalent of approximately one large-scale solar scheme would need to be switched on each and every month between August 2024 and 2030.
- 2.14.8 Schemes which make use of existing grid infrastructure are valuable to deliver the government's ambition to deliver 'Clean Power by 2030'. It is important to continue to bring forward schemes with connection dates in the 2030s to meet future growth in electricity demand and also in the event that 'Clean Power by 2030' is not achieved.
- 2.14.9 The Scheme will, if consented, make an important and significant contribution towards achieving critical progress towards the government's legally binding net zero target by 2050.

3. National Policy Statements

3.1 Planning Policy For Nationally Significant Infrastructure Projects

- 3.1.1 The legal requirement to achieve net zero underpins the urgent need for the delivery of large capacities of consentable and affordable electricity generation schemes which make best use of GB's natural low-carbon energy resources and available grid connection points.
- 3.1.2 The NPSs were established against obligations made as part of the Climate Change Act 2008 (CCA2008) and were first designated in June 2011. Following a period of revision and consultation, a revised suite of NPSs were designated by the previous government on 17 January 2024.
- 3.1.3 The NPSs include the then government's conclusion that there is a critical national priority (CNP) for the provision of nationally significant low-carbon infrastructure, which includes large-scale solar farms, because a combination of many or all types of such infrastructure is urgently required for both energy security and Net Zero.
- 3.1.4 The overarching National Policy Statement for Energy (NPS) EN-1 [Ref. 1] sets out national policy for energy infrastructure in England and Wales. It has effect, in combination with NPS EN-3 (for renewable energy infrastructure) [Ref. 2] and NPS EN-5 (for electricity networks) [Ref. 17], on recommendations made by the appointed Examining Authority (ExA) to the relevant Secretary of State (at the time of submission, the Secretary of State for Energy Security and Net Zero) on applications for energy developments that fall within the scope of the NPSs.
- 3.1.5 NPS EN-1, when combined with the relevant technology-specific energy NPS, provides the primary basis for decisions by the Secretary of State for developments that fall within the scope of the NPSs [Ref. 1, Paras 1.1.1, 1.1.2].
- 3.1.6 NPS EN-3 covers those technologies which, at the time of publication, were technically viable at generation capacities of over 50MW onshore and 100MW offshore. Critically, this includes solar generation, and as such the need for this technology is fully covered by the NPSs.
- 3.1.7 By virtue of intended generating capacity of the Scheme, the NPSs are relevant and applicable to the Scheme.
- 3.1.8 This Statement of Need for the development of large-scale solar generation reflects the national policy position, that there is a critical national priority for nationally significant low-carbon infrastructure, including solar generation, and that solar is a key part of the national strategy for low-cost decarbonisation of the energy sector. It builds upon the arguments made in the NPSs to demonstrate why the Scheme is urgently needed at the scale proposed; why the proposed location is highly suitable for such a scheme; and how the Scheme also addresses all relevant aspects of established and emerging government energy and climate change policy and commitments.
- 3.1.9 Section 104 of the Planning Act 2008 (PA2008) makes clear that where an NPS exists relating to the type of development applied for, the Secretary of

State must have regard to it as a relevant NPS, and must decide the application in accordance with that NPS. The NPSs provide specific policy in relation to solar development, and the policies set out in NPS EN-1, 3 and 5 therefore apply as ‘relevant’ NPSs under s104.

- 3.1.10 The urgent national need for energy generating stations set out in both NPS EN-1 and EN-3 is of great significance to the determination of the Scheme. The NPSs establish that:

“Subject to any legal requirements, the urgent need for CNP Infrastructure to achieving our energy objectives, together with the national security, economic, commercial, and net zero benefits, will in general outweigh any other residual impacts not capable of being addressed by application of the mitigation hierarchy” [Ref. 1, Para 3.3.63].

- 3.1.11 There is a presumption under the NPSs that the urgent need for CNP infrastructure will outweigh any residual effects in all but the most exceptional cases. This presumption does not apply to residual impacts which present an unacceptable risk to, or interference with, human health and public safety, defence, irreplaceable habitats or unacceptable risk to the achievement of net zero. Where no such residual impacts exist, the presumption weighs in favour of the need for CNP infrastructure.

- 3.1.12 Policies within NPSs EN-1, EN-3 and EN-5 are relevant to the Scheme and those in accordance with which this Application must be decided are set out in **Sections 3.2 to 3.4** of this Statement.

- 3.1.13 The urgency of the need for nationally significant low carbon infrastructure established in the NPSs requires actions to be taken in the near-term for that need to be met and therefore the urgent need for the Scheme is demonstrated by the urgent need for new energy infrastructure as set out in NPS EN-1: *“Government strongly supports the delivery of CNP infrastructure and it should be progressed as quickly as possible”* [Ref. 1, Para 3.3.63].

- 3.1.14 The government’s action to consent four large-scale transmission connected ground mount solar schemes in their first months of office, makes it clear that large-scale solar has a role to play in their view of a secure and low-carbon energy future.

- 3.1.15 The urgent national need for energy generating stations means that significant weight should be attributed to the Scheme’s ability to contribute to meeting that need.

3.2 A Synthesis Of National Policy Statement EN-1 (2023)

- 3.2.1 The fundamental need for the large-scale infrastructure, which NPS EN-1 considers, recognises the UK’s legal commitment to decarbonise to net zero by 2050 and so contribute to holding the increase in global average temperature due to climate change, to well below 2 degrees above pre-industrial levels. The NPS states that:

“Using electrification to reduce emissions in large parts of transport, heating and industry could lead to more than half of final energy demand being met by electricity in 2050, up from 17 per cent in 2019, representing a doubling in demand for electricity. Low carbon hydrogen is also likely to play an increasingly significant role” [Ref. 1, Para 2.3.7].

- 3.2.2 The national policy direction established by the previous government is to develop an integrated energy system which relies on low-carbon electricity generation for a significant proportion of its supply. The government's election manifesto supports the continuation of this policy direction albeit with greater speed. As a consequence:
- “Demand for electricity is likely to increase significantly over the coming years and could more than double by 2050 as large parts of transport, heating and industry decarbonise by switching from fossil fuels to low carbon electricity. The Impact Assessment for CB6 shows an illustrative range of 465-515TWh in 2035 and 610-800TWh in 2050”* [Ref. 1, Para 3.3.3].
- 3.2.3 The stated policy objectives for the energy system are *“to ensure our supply of energy always remains secure, reliable, affordable, and consistent with meeting our target to cut GHG emissions to net zero by 2050”* [Ref. 1, Para 2.3.3].
- 3.2.4 Meeting this objective will require a step change in the decarbonisation of our energy system, in particular to deliver a dramatic increase in the volume of energy supplied from low carbon sources [Ref. 1, Para 2.3.5].
- 3.2.5 The security, reliability and affordability of energy supplies is also of critical importance because of the role energy plays in delivering economic prosperity and social well-being [Ref. 1, Para 2.5.1].
- 3.2.6 Accelerating deployment of renewables, nuclear, hydrogen, CCUS and network infrastructure will help address the UK's current vulnerability to international energy prices through the supply of clean, secure and affordable UK-sourced power on a route to achieving net zero [Ref. 1, Para 2.5.6].
- 3.2.7 There is a need for significant amounts of new large-scale infrastructure to meet national energy objectives and the NPS establishes that the need for such infrastructure is urgent [Ref. 1, Para 3.1.1].
- 3.2.8 There must always be sufficient electricity to meet demand, with margin to accommodate unexpectedly high demand, unexpected plant closures or extreme weather events and NPS EN-1 explains that the larger the margin, the more resilient the system will be with dealing with those types of events [Ref. 1, Para 3.3.1 & 3.3.2].
- 3.2.9 No single type of electricity infrastructure will be able to meet any UK government objectives in isolation, so new generators of varied technology, assets that provide flexibility and new networks will all be needed [Ref. 1, Para 3.3.4]. However, the previous government concluded from its analysis that *“a secure, reliable, affordable, net zero consistent system in 2050 is likely to be composed predominantly of wind and solar”* [Ref. 1, Para 3.3.20]. The government's election manifesto also calls for significant increases in deployed capacities of wind and solar [Ref. 31, p51].
- 3.2.10 The NPS states that decentralised and community energy systems, which by definition would include rooftop solar installations, could lead to some reduction in demand on the main transmission system, but *“the government does not believe they will replace the need for new large-scale electricity infrastructure to meet our energy objectives.”* NPS EN-1 goes on to explain that the connection of large-scale generation facilities via high voltage

- transmission systems enables the pooling of generation and demand and enables the efficient bulk transfer of power between areas with surplus and areas in deficit [Ref. 1, Para 3.3.12].
- 3.2.11 The government's election manifesto sets out that Great British Energy "*will deploy local energy production to benefit communities across the country*" and that "*Local power generation is an essential part of the energy mix and reduces pressures on the transmission grid*" [Ref. 31, pp53-54]
- 3.2.12 The government's election manifesto also sets out their ambition to "*upgrade our national transmission infrastructure and rewire Britain*" [Ref. 31, p55]. Alongside this pledge, the consent of four large-scale ground mount solar schemes in the first months of their term in office, has confirmed that new large-scale solar assets are also a part of their plan to deliver 'Clean Power by 2030'.
- 3.2.13 NPS EN-1 also states that "*it is prudent to plan on a conservative basis to ensure that there is sufficient supply of electricity to meet demand across a wide range of future scenarios*" [Ref. 1, Para 3.3.10].
- 3.2.14 To hit the target of UK commitments to decarbonise the power sector by 2035 [Ref. 18], the NPSs conclude that it is necessary to bring forward new renewable electricity generating projects as soon as possible. The need for new renewable electricity generation projects is therefore urgent.
- 3.2.15 To achieve the government's ambition of delivering 'Clean Power by 2030', the need for new renewable generation projects becomes more urgent still.
- 3.2.16 The NPS establishes that substantial weight should be given to this need when considering applications for development consent under the PA2008, and the Secretary of State is not required to consider separately the specific contribution of any individual project to satisfying the need established in the NPS [Ref. 1, Paras 3.2.7 & 3.2.8].
- 3.2.17 NPS EN-1 explains that large capacities of low-carbon generation will be required to:
- a. Ensure that there is sufficient electricity to meet increased demand;
 - b. Replace output from retiring plants;
 - c. Ensure there is sufficient margin in our supply to accommodate unexpectedly high demand; and
 - d. Mitigate risks such as unexpected plant closures and extreme weather events [Ref. 1, Section 3.3].
- 3.2.18 The NPSs conclude that national energy security and net zero ambitions will only be delivered through the development of new low carbon sources of energy at speed and scale [Ref. 1, Para 4.2.2] and therefore that there is a critical national priority (CNP) for the provision of nationally significant low carbon infrastructure [Ref. 1, Para 4.2.4]. Low carbon electricity generation infrastructure is described as "*all onshore and offshore generation that does not involve fossil fuel combustion*" [Ref. 1, Para 4.2.5] and as such large-scale solar generation is classified as CNP infrastructure under NPS EN-1.

- 3.2.19 The NPS sets the expectation that *“For projects which qualify as CNP Infrastructure, it is likely that the need case will outweigh the residual effects in all but the most exceptional cases”* [Ref. 1, Para 4.1.7].
- 3.2.20 The Scheme meets the definition of CNP Infrastructure because it is for the development of greater than 50MW capacity of a low carbon source of energy. As CNP infrastructure, the urgent need for the Scheme to achieving the UK’s energy objectives, together with the national security, economic, commercial and net zero benefits, will in general outweigh any other residual impacts not capable of being addressed by application of the mitigation hierarchy [Ref. 1, Para 3.3.63].
- 3.2.21 In noting the crucial national benefits of increased system robustness through new electricity network infrastructure projects, NPS EN-1 also recognises the particular strategic importance in the next decade of the role of solar generation in the UK’s generation mix.
- “As part of delivering [a secure, reliable, affordable, net zero consistent system in 2050], government announced in the British Energy Security Strategy an ambition to deliver up to 50GW of offshore wind by 2030 ... and the requirement in the Energy White Paper for sustained growth in the capacity of onshore wind and solar in the next decade”* [Ref. 1, Para 3.3.21].
- 3.2.22 The siting of new solar capacity is therefore important and the location of points of connection to existing networks to enable that capacity to come forwards, are an important consideration.
- 3.2.23 In relation to integration technologies, NPS EN-1 states that:
- “New generating plants can deliver a low carbon and reliable system, but we need the increased flexibility provided by new storage and interconnectors (as well as demand side response ...) to reduce costs in support of an affordable supply. Storage and interconnection can provide flexibility, meaning that less of the output of plant is wasted as it can either be stored or exported when there is excess production.”* [Ref. 1, Paras 3.3.5 & 6].
- 3.2.24 NPS EN-1 goes on to explain that storage is needed to reduce the costs of the electricity system and increase reliability by storing surplus electricity in times of over-supply, to provide electricity when demand is higher. **Section 5.11** of this Statement explains that storage can achieve the benefits set out in the NPS from stand-alone facilities or facilities co-located with renewable generation facilities.
- 3.2.25 The local and national benefits which storage assets can provide are also referenced in NPS EN-1 [Ref. 1, Para 3.3.6], being:
- a. Maximising the usable output from intermittent low carbon generation;
 - b. Reducing the total amount of generating capacity required to meet peak demand;
 - c. Reducing the need for new network infrastructure;
 - d. Providing a range of balancing services to help operate the electricity system; and
 - e. Reducing constraints on the electricity network.

3.2.26 The role of ‘low-carbon hydrogen’ is also signalled as likely growing in significance in the UK’s future energy system, and therefore supports the need for infrastructure which can generate low-carbon electricity to produce low-carbon hydrogen [Ref. 1, Paras 2.3.5 - 2.3.7].

3.3 A Synthesis Of National Policy Statement EN-3 (2023)

3.3.1 NPS EN-3 [Ref. 2] covers nationally significant renewable energy infrastructure which includes solar photovoltaic (PV) at more than 50MW in England and more than 350MW in Wales [Ref. 2, Para 1.6.1].

3.3.2 NPS EN-3 bolsters the support for solar development in the UK that was previously provided in the draft 2021 versions, now stating that it has *“committed to sustained growth in solar capacity to ensure that we are on a pathway that allows us to meet net zero emissions. As such solar is a key part of the government’s strategy for low-cost decarbonisation of the energy sector”* [Ref. 2, Para 2.10.9].

3.3.3 The statement goes on to re-iterate the contribution that solar generation is expected to make to achieving net zero targets and the energy security goals set out in the British Energy Security Strategy, of *“a five-fold increase in combined ground and rooftop solar deployment by 2035 (up to 70GW)”* [Ref. 2, Para 2.10.10].

3.3.4 The government has set out its ambition to triple solar capacity by 2030, implying the need for a higher rate of deployment than required to meet the previous government’s goals.

3.3.5 Because *“Solar farms are one of the most established renewable electricity technologies in the UK and the cheapest form of electricity generation”* [Ref. 2, Para 2.10.13], solar is also expected to bring forwards affordability benefits for consumers.

“Solar farms can be built quickly and, coupled with consistent reductions in the cost of materials and improvements in the efficiency of panels, large-scale solar is now viable in some cases to deploy subsidy-free.” [Ref. 2, Para 2.10.14]

3.3.6 NPS EN-3 also describes that:

“Government is supportive of solar that is co-located with other functions (for example, agriculture, onshore wind generation, or storage) to maximise the efficiency of land use”. [Ref. 2, Para 2.10.10]

3.3.7 NPS EN-3 establishes that energy storage, if proposed as part of a solar farm proposal, may be treated as associated development to that proposal [Ref. 2, Para 2.10.16].

3.3.8 Grid connection, and in particular the likely proximity of schemes to suitable connection points on the transmission network, is also addressed:

“The connection voltage, availability of network capacity, and the distance from the solar farm to the existing network can have a significant effect on the commercial feasibility of a development proposal.”

“To maximise existing grid infrastructure, minimise disruption to existing local community infrastructure or biodiversity and reduce overall costs applicants

may choose a site based on nearby available grid export capacity.” [Ref. 2, Paras 2.10.24&25]

- 3.3.9 NPS EN-3 also lists irradiance and site topography as key inputs to site selection [Ref. 2, Paras 2.10.19 & 20].
- 3.3.10 NPS EN-3 suggests anticipated levels of land efficiency for solar generation, recognising both the land take which schemes such as this one requires, but also that evolution in the technology is anticipated and this may bring about efficiency benefits through the life of the Scheme:
- “Along with associated infrastructure, a solar farm requires between 2 to 4 acres for each MW of output. A typical 50MW solar farm will consist of around 100,000 to 150,000 panels and cover between 125 to 200 acres. However, this will vary significantly depending on the site, with some being larger and some being smaller. This is also expected to change over time as the technology continues to evolve to become more efficient.” [Ref. 2, Para 2.10.17]*
- 3.3.11 The degradation of solar efficiency over time is addressed in NPS EN-3 [Ref. 2, Para 2.10.55], suggesting that developers may need to account for the light-induced degradation effects on solar panels by overplanting solar panel arrays.
- 3.3.12 The design life of solar panels should also be considered *“when determining the period for which consent is required. An upper limit of 40 years is typical, although applicants may seek consent without a time-period or for differing time-periods of operation.”* [Ref. 2, Para 2.10.65].

3.4 A Synthesis Of National Policy Statement EN-5 (2023)

- 3.4.1 NPS EN-5 covers new, non-exempt above ground electricity lines over 2km in length whose nominal voltage is expected to be 132kV or above and other kind of electricity infrastructure in England which is constituted as associated development for which consent is sought along with an NSIP [Ref. 17, Para 1.6.2].
- 3.4.2 NPS EN-5 explains that *“significant amounts of new electricity networks infrastructure is required”* [Ref. 17, Para 2.2.3], something with which the government agrees [Ref. 31, p55].
- 3.4.3 NPS EN-5 acknowledges that the siting of new electricity transmission infrastructure is determined by *“the location of new generating stations or other infrastructure requiring connection to the network, and/or system capacity and resilience requirements determined by the Electricity System Operator”* [Ref. 17, Para 2.2.2].
- 3.4.4 If the UK’s Centralised Strategic Network Planning process identifies strategic investments intended to facilitate achieving net zero and decarbonisation targets, *“the Secretary of State should have regard to the need case for new electricity networks infrastructure set out in Section 3.3 of NPS EN-1”* [Ref. 17, Paras 2.8.2&3].
- 3.4.5 The Scheme proposes to connect to an existing substation, to which other low-carbon generation schemes are also proposing to connect. That substation connects to an existing part of the national grid with available

transmission capacity, bringing the potential for large quantities of low-carbon energy to be transmitted to the National Electricity Transmission System and on to consumers nationally. This is a benefit of the Scheme within the context of the significant need for new electricity networks infrastructure.

3.5 Conclusions on the NPSs

- 3.5.1 Per paragraph 3.1.9 above, section 104 of the PA2008 makes clear that where an NPS (e.g. NPSs EN-1, EN-3 and EN-5) exists relating to the type of development applied for (e.g. the Scheme), the Secretary of State must have regard to it as a relevant NPS, and must decide the application in accordance with that NPS.
- 3.5.2 Solar generation is expected to make an important contribution to the UK's renewable energy generating capacity towards 2050.
- 3.5.3 The NPSs demonstrate that:
- a. The need for solar technology (as a renewable source) in GB is urgent and significant and has increased, with nationally significant solar technology now defined as CNP infrastructure;
 - b. Large-scale solar is technically and economically feasible;
 - c. Large-scale solar can and will bring benefits for the UK; and
 - d. Flexibility is also needed.
- 3.5.4 Integration technologies which provide flexibility will play an essential role in achieving the full decarbonisation of the whole GB energy system, by enhancing the benefits brought by low-carbon generation. NPS EN-1 supports the need for integration technologies, and BESS is a suitable and beneficial integration technology.
- 3.5.5 NPS EN-3 provides policy support for schemes, such as this scheme, which include co-located solar and storage technologies because both technologies are needed and co-location maximises the efficiency of land use. Co-location also maximises utilisation of the grid connection.
- 3.5.6 These factors manifest in the material contribution brought by solar and storage schemes to the UK's legal decarbonisation targets; the enhancement of security of supply; and the affordability of electricity for GB consumers.
- 3.5.7 NPS EN-3 provides that grid connection, irradiance and site topography are key inputs to the selection of sites suitable for large-scale solar generation developments.
- 3.5.8 Therefore, the number of locations at which large-scale solar generation is suitable is likely to be limited, and the number of locations at which co-located large-scale solar plus storage generation is suitable is likely to be limited even further.
- 3.5.9 This is a material issue when considering how the UK is to meet the urgent need for low-carbon generation as is established in the current NPSs.

4. Electricity demand must grow to deliver net zero

4.1 Chapter Summary

4.1.1 This chapter provides information to support and quantify the policy position that future electricity demand will need to grow to a very significant degree in order to achieve net zero. As set out in NPS EN-1:

“[Government] analysis suggests that even with major improvements in overall energy efficiency, and increased flexibility in the energy system, demand for electricity is likely to increase significantly over the coming years and could more than double by 2050 as large parts of transport, heating and industry decarbonise by switching from fossil fuels to low carbon electricity ” [Ref. 1, Para 3.3.3].

4.1.2 Energy final consumption in the UK in 2023 was 1,506TWh, with 18% (269TWh) in the form of electricity [Ref. 19, Table 1.1au]. Electricity demand is expected to grow significantly in the future as carbon-intensive sources of energy are displaced by electrification of other industry sectors, or production of non-carbon energy vectors, such as hydrogen, by use of electricity. Energy efficiency measures may mean that total UK energy consumption decreases in the future, but an increasing share of that consumption will come from electricity generated by low-carbon sources.

4.1.3 The annual National Grid ESO (NGESO) Future Energy Scenarios (FES) documents provide important and relevant information on these points. The FES are discussed in more detail in the following sections. Note that on 1 October 2024, NGESO became the National Energy System Operator (NESO). This Statement references reports and data published before the organisation’s name change and therefore refers to the organisation as NGESO throughout.

4.2 Introducing The FES

4.2.1 NGESO’s FES [Ref. 19] are annual publications which explore strategic, credible choices to propel GB on the route to decarbonisation.

4.2.2 The FES are an important point of view, which contributes to an objective assessment of the need for, and scale of, how much energy GB might need and where it could come from, to build a picture of the ways in which net zero could be reached.

4.2.3 The 2024 FES includes pathways which outline a narrower range of outcomes than the scenarios included in previous FES publications, to help *“drive forward Great Britain’s strategic investment needs and to support the rapid and fundamental change that is required.”*

4.2.4 Three of the 2024 FES pathways meet net zero in 2050. A counterfactual that does not meet net zero is presented alongside the pathways that do.

4.2.5 NGESO recommend that direct comparisons should not be made between previous year’s scenarios and the 2024 pathways due to the change in framework. In particular:

- a. NGESO have included economic modelling where previously their scenarios were cost agnostic. The FES therefore now assesses all three national policy aims of decarbonisation, security of supply and affordability; and
 - b. Efficiency of location and network infrastructure is also considered through the impact of network constraints in the analysis.
- 4.2.6 The net zero commitment underpins the urgency for new low carbon generation infrastructure to be built and commissioned, and government support for such developments is critical.
- 4.2.7 The key observation is that in all lower-carbon futures, the electricity sector will not operate in isolation from other energy sectors. Rapid decarbonisation is required across all areas of demand – including residential, transport, industrial and commercial. Deep electrification of all those areas is required in order to meet net zero, and until widespread electrification is achieved, the need for urgent electrification will increase year-on-year.
- 4.2.8 The 2023 FES includes an Energy Background Document in which it is stated that:
- “A range of technologies with different characteristics can, in combination, help deliver secure, affordable low carbon electricity supplies and harness the potential of domestic renewable resources. More electricity from wind and solar is vital to help UK meet its target for net zero by 2050”* [Ref. 21, p15].
- 4.2.9 The Energy Background Document also provides an example of how strategic coordination and whole system thinking can deliver a secure and affordable energy system built largely on renewables and hydrogen, although in reality, the need for low carbon electricity generation capacity is, based on currently known and deliverable technologies, independent of the scale of adoption of hydrogen in the UK.
- “Producing hydrogen via electrolysis can create additional demand when needed to avoid curtailing wind and solar generation and this hydrogen can then be used to generate power at times of peak demand or low renewable output”* [Ref. 21, p18].
- 4.2.10 Consumer engagement in demand side flexibility and demand reduction measures across the pathways is a key component of what makes the pathways differ from each other. All net zero pathways follow the ZEV mandate for car sales while different take-up rates for hydrogen use in home heating drives differences between the scenarios.
- 4.2.11 From their look-back at previous years, NGESO has found *that “a high usage of renewables is enabling the carbon intensity of electricity generation to continue to fall,”* [Ref. 19(2024), p15]. NGESO also conclude from their analysis that *“Solar power generation remains one of the lowest cost options to meet our energy needs and, if efficiently integrated, can minimise the total system cost”* [Ref. 19(2024), p115].
- 4.2.12 **Chapter 9** of this Statement provides additional evidence that, based on current economics, solar generation is likely to be one of the cheapest sources of electricity in both the 2020s and 2050 energy mix. A diverse mix

of low-carbon generation will be required to meet national decarbonisation targets.

- 4.2.13 The pathways analysis was completed prior to 2024's general election, but the government's ambitions to deliver 'Clean Power by 2030' are at least as ambitious as the previous government's ambitions over the next important years. The 2024 FES therefore remains relevant and useful to support the need for the Scheme.

4.3 Trends In UK Electricity Demand

- 4.3.1 In the 1990s and early 2000s, GB electricity demand grew only slowly, but from 2005 electricity demand has fallen year-on-year due to:

- a. A decline in economic growth rate (particularly with the recession of 2009);
- b. A reduction in the level of electricity intensity as the economy has shifted to less energy-intensive activities;
- c. The introduction of energy efficiency measures including more efficient lighting and technology development more generally [Ref. 22, p28 & Ref. 23, p48]; and
- d. The COVID-19 pandemic (2020-2021) and cost of living crisis (2022-2023).

- 4.3.2 Today's view of future GB electricity demand is, however, one of returning growth through:

- a. The switching of sources of final-use power for heating and transport from carbon-intensive sources to electricity, the generation of which can be decarbonised using technologies already available today, will put upward pressure on demand;
- b. The least-cost energy efficiency measures, such as introduction of low-voltage LEDs for lighting, have now been implemented across business and domestic sectors; and
- c. Economic restructuring in GB away from manufacturing to a service-based economy has largely occurred, however the growth of new high-technology and highly skilled manufacturing, both contributing to national economic growth and prosperity, is likely to place additional pressures on the electricity sector.

- 4.3.3 The FES shows that achieving net zero requires electricity demand to grow. Consequentially, low-carbon electricity supply will need to increase further to meet that demand, including the potential for increased anticipated demand for green hydrogen, which could be produced using renewable electricity to electrolyse water with zero carbon emissions.

- 4.3.4 The majority of industry projections of GB electricity demand to 2050 are for a significant increase from today's level of circa 300TWh. The amount by which forecasts increase varies according to the level of decarbonisation of non-energy sector demand, and the source of that decarbonisation. For example, hydrogen is an important energy vector which may be able to help decarbonise hard to reach sectors of transport, space heating and heavy

industry. Off-grid hydrogen production would require the generation of low-carbon power, but this would be counted outside of the transmission system demand projections for 2050 (i.e. in addition to the views included in the following list):

- a. The NPSs foresaw a doubling of current demand [Ref. 1, Para 2.3.37], i.e. to circa 600TWh;
- b. NGENSO present a range from 533TWh for their counterfactual pathway to between 667 and 700TWh for the three net zero pathways [Ref. 19(2024), p26];
- c. The National Infrastructure Commission (NIC) forecasts 465 – 595TWh [Ref. 24, p35];
- d. The Energy Systems Catapult forecasts 525 – 700TWh [Ref. 25, pp23&27];
- e. The CCC's sixth carbon budget presents a range from 550 – 680TWh [Ref. 26, Table 3.4.a];
- f. The government impact assessment for Carbon Budget 6 (CB6) presents a range from 610 – 800TWh [Ref. 1, 3.3.3 and 27, p29];
- g. The 2020 Energy White Paper presents a range from 575 – 665TWh [Ref. 10, p42];
- h. Mission Zero suggests that *“electricity demand by 2050 could be roughly double today's level of total electricity demand”* [Ref. 13, Paras 287 & 299]; and
- i. The Connections Action Plan projects electricity demand of between 570-770 TWh by 2050 depending on how net zero is met [Ref. 16, pp68-70].

4.3.5 The increasing level of future demand is relevant to the need for low carbon generation capacity because sufficient capacity must be developed to meet that demand. Further, as indicated in Mission Zero and borne out historically by industry data, in the future, demand on winter days *“could be double that of milder days”* [Ref. 13, Para 299]. Therefore, timing demand to periods of high supply, or with supply, will be important, as will building sufficient generation capacity to meet demand under a variety of weather conditions. NPS EN-1 states that *“it is prudent to plan on a conservative basis to ensure that there is sufficient supply of electricity to meet demand across a wide range of future scenarios”* [Ref. 1, Para 3.3.10].

4.3.6 Figure 4-1 shows how NGENSO's forecasts for electricity demand in Great Britain developed from 2019 (prior to the UK's 2019 commitment to net zero), through 2023 to 2024. Each annual forecast is represented as a shaded area ranging from the lowest forecast demand scenario to the highest scenario per delivery year, for those scenarios which met the 2050 climate targets of the time.

4.3.7 Without the drive to electrify traditionally non-electric sectors such as heat and transport, GB electricity demand reduced year-on-year.

4.3.8 Current forecasts for future GB electricity demand have increased significantly. Increased electrification of transport, heat, and industrial

demand is essential for the achievement of net zero and is a key driver for the increase in future electricity demand.

- 4.3.9 The range of demand provided by recent sources shows a shallow increase in forecast GB electricity demand over the coming five years as the aforementioned policies start to take hold. The forecasts then ramp up significantly around the end of the 2020s and thereafter. For the avoidance of doubt, the UK electricity demand forecasts shown include the use of electricity in the production of hydrogen.
- 4.3.10 The 2024 FES system demand forecasts include electric vehicle (EV) electricity demand which follows the ZEV mandate, removing some uncertainty from previous forecasts, but the use of hydrogen across multiple sectors is included only in later years because progress in developing hydrogen production in the UK has been slower than planned.
- 4.3.11 Since the UK made its 2019 commitment to net zero, forecast GB electricity demand in 2050 has converged towards a range from 650 – 700TWh. Achieving net zero in the UK will require a significant increase in electricity demand in all scenarios.
- 4.3.12 It is implicit that the trajectories shown in Figure 4-1 can only be met (and therefore net zero achieved) if there is sufficient operational low-carbon electricity generation capacity to generate the low-carbon energy demanded by consumers.
- 4.3.13 In 2023, 285TWh of consumer demand was met by 166TWh of low-carbon generation (58%) and 119TWh of carbon intensive generation. Consumer demand across the three net zero FES pathways in 2030 averages 330TWh. Therefore, low-carbon generation will need to increase by approximately 164TWh between 2024 and 2029 to deliver ‘Clean Power by 2030’.
- 4.3.14 Consumer demand across the three net zero FES pathways in 2040 averages 530TWh. Therefore low-carbon generation will need to increase by approximately a further 200TWh between 2030 and 2039 to keep power clean through the 2030s.




Figure 4-1: Evolution of UK electricity demand projections (2019, 2023 & 2024) [Ref. 19, Author Analysis]

- 4.3.15 The capacity of new low-carbon schemes which will need to come on-line prior to 2030 to achieve ‘Clean Power by 2030’ is unprecedented. However,

an even greater capacity of new low-carbon schemes will need to come on-line in the 2030s to keep power clean through to 2040 as other sectors also decarbonise.

- 4.3.16 This provides evidence for the need for new low-carbon generation facilities to continue to come on-line into the 2030s, to meet that anticipated growth in demand.

4.4 Transport Policies Underpin A Growth In Future Electricity Demand

- 4.4.1 Surface transport is currently the largest source of UK GHG emissions. Surface transport accounted for just under one quarter of the UK's 2023 emissions, [Ref. 82024], Figure 1.3, Charts and Data]. Continuing the shift to low emission vehicles will give a significant boost to UK decarbonisation.
- 4.4.2 Growth in the use of EVs is expected to create significant new demands on the electricity network. Having proposed a ban on the sale of all new petrol and diesel vehicles to be effective from 2030 [Ref. 28] alongside a ban on sales of new hybrid vehicles by 2035, the previous government, in September 2023, announced that the UK's ban on the sale of new petrol and diesel cars would be pushed back to 2035, allowing petrol and diesel cars to be purchased new up to that date, and permitting second hand trades thereafter.
- 4.4.3 The ZEV mandate was introduced by the previous government on 1st January 2024. It demands that at least 22% of all cars and 10% of all vans sold in Britain in 2024 are pure electric, rising to 80% of cars and 70% of vans by 2030, and 100% of each by 2035.
- 4.4.4 The government's election manifesto includes an intent to restore the phase-out date of 2030 for new cars with internal combustion engines, bringing forward the additional future electricity demand versus the ZEV mandate trajectory [Ref. 31, p31].
- 4.4.5 Although this policy reversion has not been formally announced, the government has signalled that the majority of new cars sold in the UK will have to be fully electric by 2030, suggesting a market and manufacturer, rather than regulation, led approach to electrification [Ref. 29].
- 4.4.6 The Society of Motor Manufacturers and Traders reported a 17.8% increase in Battery Electric Vehicle (BEV) sales in the UK in 2023 versus 2022, and 16.5% of all new vehicle purchases in the UK in 2023 were BEV [Ref. 30]. In the period January to August 2024, BEV sales are up 10.5% year-on-year, to 17.2% of all new vehicle purchases in the UK so far this year.
- 4.4.7 Reducing costs, improvements in the range of EVs, inter-brand competition encouraged by the ZEV mandate and improving charging infrastructure are expected to encourage consumers to choose EVs over petrol and diesel cars.
- 4.4.8 The eventual and necessary transition of all cars from fossil fuels to support net zero will continue due to their lower run costs, improving performance, increasing model choices, and zero emission capability.

- 4.4.9 The net zero FES pathways include an increase in annual electricity demand in the UK due to electric vehicles of ~27TWh in 2030 and 101 – 127TWh by 2050. [Ref. 19(2024), Chart EC.07]. A growing penetration of hydrogen into the surface transport sector could further increase electricity demand through the need to produce hydrogen via electrolysis.
- 4.4.10 The Electric Vehicle Infrastructure Strategy (March 2022) [Ref. 33] facilitates the adoption of electricity into transport and sets the expectation, by 2030, of there being around 300,000 public charge points as a minimum in the UK, up from just 64,643 on 1st July 2024 [Ref. 34]. The government's election manifesto describes that they will “*support the transition to electric vehicles by accelerating the roll out of charge points*” [Ref. 31, p31].
- 4.4.11 The UK has put leadership of a low-carbon transport revolution at the heart of its Industrial and Clean Growth strategies and regards EVs as a critical new technology which will be vital in the fight against climate change. Commitments by governments to invest in ‘gigafactories’ for the mass production of batteries and EV supply chain, [Ref. 35, Ref. 36, Ref. 37 and Ref. 31, p30] provide evidence that there is strong political support for the rapid development and rollout of EVs, with which will come significant additional electricity demand. Indeed, as the SMMT data shows, the rollout of EVs has already begun.
- 4.4.12 To support efforts in the decarbonisation of heavier transport (e.g. road freight, rail and air), the previous government pledged to invest £140 million in 2021/22 across hydrogen-powered freight trials and the delivery of 4,000 zero emission buses [Ref. 10, p94]. The application of hydrogen as a fuel for flight and rail, and in industrial energy-intensive processes, is also progressing.

4.5 Home Energy Policies Underpin A Growth In Future Electricity Demand

- 4.5.1 In 2023, the domestic sector accounted for approximately 36% of the UK's electricity demand and 44% of the UK's demand for natural gas [Ref. 19(2024), Tables ED1 & ED3].
- 4.5.2 Government-backed energy efficiency schemes seek to improve the insulation of the UK's homes as well as reduce demand from lights, appliances and services.
- 4.5.3 Reducing UK domestic electricity demand will support the move to a zero-emissions electricity system. Flexibility in consumption, either through variable ‘time of use’ tariffs or demand flexibility schemes may allow consumers to support the flexibility needs of a low-carbon electricity system.
- 4.5.4 Improved insulation and improved boiler efficiency may help reduce domestic demand for gas and thereby reduce carbon emissions associated with the use of gas in the home. However, the domestic use of gas must be substituted out for either electricity or hydrogen for domestic carbon emissions to fall to zero or very close to zero. The CCC state that, by 2030, “*approximately 10% of existing homes in the UK will need to be heated by a heat pump, compared to only approximately 1% today,*” for the UK to reach its 2030 climate targets [Ref. 8(2024), p9].

- 4.5.5 The Energy White Paper sets out an aim to increase the rate of installation of home electric heat pumps from 30,000 per year to 600,000 per year by 2028. The British Energy Security Strategy aims to ensure that by 2050 all UK buildings will have low-carbon heating, and reconfirmed [Ref. 12, p12] the then government's intent to phase out the sale of new and replacement gas boilers by 2035 – an intent which was replicated in Powering Up Britain and confirmed by the then government in September 2023. Beyond 2035, certain gas boiler replacements will no longer be permitted.
- 4.5.6 The government's election manifesto includes many aims to reduce home energy demand, including:
- a. A Warm Homes Plan to offer grants and low interest loans to support investment in insulation and other improvements such as solar panels, batteries and low carbon heating;
 - b. work with the private sector to provide further private finance to accelerate home upgrades and low carbon heating; and
 - c. Ensuring that homes in the private rented sector meet minimum energy efficiency standards by 2030.
- 4.5.7 FES 2024 pathways show flat residential demand against 2023 levels, however in the 2030s residential demand is shown to increase as the domestic use of gas is systematically reduced and replaced by electricity. Net zero pathways in 2050 show increases in residential electricity demand of between 68% and 79% vs. 2023 levels, primarily due to the electrification of home heat and cooking.

4.6 Peak Electricity Demand Is Also Expected To Grow

- 4.6.1 The daily profile of electricity demand is less easy to forecast into the future, but estimated peak (the highest instantaneous) demand remains a key determinant of required installed generation capacity.
- 4.6.2 Figure 4-2 illustrates National Grid ESO's forecast of peak GB power demand (using NGENSO's Average Cold Spell methodology) out to 2050. In the three net zero pathways, peak demand is anticipated to range between 62GW and 65GW by 2030 (2023, for comparison, was 58GW); between 89GW and 103GW in 2040, and between 104GW and 119GW in 2050 [Ref. 19(2024), Figure ES.03].
- 4.6.3 All net zero pathways show an increase in peak demand from as early as 2025, driven by underlying industrial and commercial demand growth (through substitution of other energy sources) and the electrification of heating and transport.
- 4.6.4 Historically, electricity peak demand has tended to occur on winter weekday evenings, when industrial and commercial demand overlaps with residential. However, NGENSO state that "*as the share of renewable electricity supply increases, electricity peaks could occur at other times*" [Ref. 19(2024), p101], an important point relating to security of supply, which is discussed in **Chapter 8** of this Statement.
- 4.6.5 EVs and hydrogen vehicles will require the deployment of additional electricity generation capacity and may also act as integration measures for

renewable and baseload generation, capable of shifting load from when demand is high, to periods where supply is higher.

- 4.6.6 Sufficient electricity generation capacity will need to be deployed to be able to meet instantaneous demand, as well as forecast annual demand, under normal and unfavourable weather conditions, supporting the need for significant growth in UK low-carbon electricity generation capacity.




Figure 4-2: Electricity average cold spell peak demand (including losses) [Ref. 19(2024), Figure ES.03]

4.7 Conclusions on Electricity Demand

- 4.7.1 Policies are already in place to substitute electricity for fossil fuel as a source of energy in non-traditional sectors in the UK, and many of those policies have started to deliver both on a national and local basis.
- 4.7.2 GB electricity demand will increase during the 2020s as a result of this substitution, supporting the urgent need for new low-carbon electricity generation facilities to come forward to meet demand.
- 4.7.3 Peak electricity demand is uncertain but is likely to grow. Significant capacity of new, low-carbon generation will be required to meet both peak demand and electricity needs across a wide range of weather conditions, which may increasingly occur outside of the traditional winter peak periods due to the anticipated increase in electricity consumption through electrification of non-traditional sectors and the increased share of electricity supplies from a range of renewable generation technologies.
- 4.7.4 The capacity of new low-carbon schemes which will need to come on-line prior to 2030 to achieve 'Clean Power by 2030' is unprecedented. However, an even greater capacity of new low-carbon schemes will need to come on-line in the 2030s to keep power clean through to 2040 as other sectors also decarbonise.
- 4.7.5 Rapidly increasing low-carbon supplies will reduce the cost and carbon content of produced electricity in the UK as is explained in **Chapter 9** of this Statement. Lower cost and lower carbon energy supplies will incentivise other sectors to move away from fossil fuels to electricity.

- 4.7.6 Increasing UK-located low-carbon generation capacity will also prevent an increase in UK electricity demand from increasing GB consumers' exposure to volatile energy prices and reducing GB security of supply.
- 4.7.7 Without a rapid increase in low-carbon supply, the decarbonisation of other sectors is less likely to occur due to potentially unfavourable commercial factors, and potentially heightened supply risk amid growing demand. This could place at risk progress which needs to be made on decarbonising other sectors to achieve national carbon reduction targets in 2030 and beyond.
- 4.7.8 The Scheme will contribute to meeting GB's growing electricity demand and will therefore be a critical enabler of achieving the UK's decarbonisation and energy security aims.

5. Delivering Net Zero Through Clean Electricity Supplies

5.1 Chapter Overview

5.1.1 This chapter reviews selected current policy support and development / delivery in technologies which are being tasked to support the delivery of net zero.

5.2 Current And Future Generation Mix

5.2.1 The Net Zero Strategy's key policy is for the UK to be powered entirely by clean electricity by 2035, subject to security of supply [Ref. 11, p20].

5.2.2 Electrification is a key strategy to deliver decarbonisation in the UK and the previous government targetted a zero-carbon electricity system by 2035 [Ref. 18]. The government have signalled an increase in that ambition by establishing a mission to deliver 'Clean Power by 2030' [Ref. 31, p51]. By growing the UK's low-carbon electricity generation capacity, the carbon emissions associated with the electricity we use to light our homes and power our appliances will decrease.

5.2.3 By growing the UK's low-carbon electricity generation capacity further, electricity can be used instead of carbon emitting fuels in other non-traditional sectors (e.g. petrol in transport) and further decarbonisation can be achieved. The decarbonisation of all sectors is essential for the UK to meet net zero [Ref. 8(2024), p8].

5.2.4 To decarbonise the UK's electricity system, less electricity must be sourced from carbon emitting generation capacity. Low-carbon generation capacity must therefore be developed both as a substitute for carbon emitting capacity, and to increase the amount of electricity generated to meet additional, non-traditional demand.

5.2.5 It is important to clarify that this Statement of Need does not seek to justify, or promote, the exclusion of any other generation technologies from the future GB generation mix.

5.2.6 Figure 5-1 below shows historical electricity generation in the UK from 1996 to 2022 by fuel source, measured in terawatt hours (TWh, 1 TWh = 1,000,000 MWh), and the resulting average grid carbon intensity, measured in gCO₂(e)/kWh.

5.2.7 Figure 5-1 shows that Coal + Oil generation reduced from approximately a one-half share of UK generation in 1996 to nearly zero by 2023. The last UK coal fired power station closed in September 2024 and Coal + Oil generation will therefore be zero from 2025 onwards.




Figure 5-1: Historical Electricity generation (TWh/Yr) and carbon intensity (gCO2(e)/kWh) [Ref. 19, Tables 5.6 & 5.14]

- 5.2.8 Low-carbon generation, including renewable wind and solar, increased from near zero in 1996 to over 40% of UK generation in 2022.
- 5.2.9 Nuclear has reduced from generating over one quarter of the UK’s electricity needs in 1996, to just 14% in 2023. Gas has contributed approximately 40% of UK generation each year throughout much of the period shown.
- 5.2.10 GB Grid carbon intensity reduced from over 500 gCO2(e)/kWh in 1996 to 171 gCO2(e)/kWh in 2023, a reduction of 67%, while electricity generation has reduced by only 17% over that period.
- 5.2.11 The carbon intensity of the GB Grid has reduced since 1996 due to a regulatory increase in the cost of emissions from high-carbon intensity generation assets, the subsequent closure of coal plants in the UK, and a significant increase in low-carbon, low-marginal cost generation (predominantly wind and solar) since 2010. **Section 9.2** of this Statement explains how GB electricity market arrangements support this essential shift.
- 5.2.12 As well as providing views on future national electricity demand, the FES pathways provide projections for how that demand will be met. Figure 5-2 below shows projected electricity generation in the UK from 2023 to 2050 by fuel source, measured in terawatt hours under NGESO’s ‘Holistic Transformation’ pathway, and the resulting average grid carbon intensity, measured in gCO2(e)/kWh.
- 5.2.13 The ‘Holistic Transformation’ pathway shown in Figure 5-2 shows that wind generation will increase from 96TWh in 2023 to 467TWh in 2050. Nuclear generation more than doubles from 42TWh to 97TWh over the same timeframe. Solar generation increases approximately seven-fold, from 16TWh to 115TWh. Under a ‘Hydrogen Evolution’ pathway, where solar capacity deployment is the lowest of NGESO’s net zero pathways, solar generation increases approximately five-fold, to 76TWh in 2050.

5.2.14 These low-carbon generation sources, if delivered, will provide the much-needed electricity required to reduce grid carbon intensity from current levels to zero or lower in 2035, aligned with previous government’s decarbonisation targets. To achieve the government’s mission to deliver ‘Clean Power by 2030’, the rollout of low-carbon and negative carbon emissions generation would have to be faster than in NGESO’s current net zero pathways.




Figure 5-2: Projected electricity generation (TWh/Yr) and carbon intensity (gCO2(e)/kWh) [Ref. 19(2024), Tables ES.08-11 & ES1 – ‘Holistic Transformation’]

5.2.15 Critically, grid carbon intensity reaches zero at the same time as unabated gas generation ceases. Carbon Capture, Usage and Storage (CCUS) technology must be deployed at scale and integrated into the existing gas generation network, for gas technology to have a role in the future electricity system. Abated gas generation (i.e. gas plus CCUS) is included in the purple ‘Other’ category in Figure 5-2. Figure 5-2 also shows only the generation and not the power consumption of storage assets (e.g. Pumped Storage (Hydro) or batteries).

5.2.16 The UK is also pursuing a strategy of interconnection with other markets. Interconnectors are physical cables through which energy can flow in either direction. Market forces determine which direction the energy flows, from low price to high price markets.

5.2.17 Interconnectors can support energy security but, as the British Energy Security Strategy states, “*If we’re going to get prices down and keep them there for the long term, we need a flow of energy that is affordable, clean and above all, secure. We need a power supply that’s made in Britain, for Britain*” [Ref. 12, p3].

5.2.18 The UK has traditionally been an importer of energy from European markets, of National Grid scenarios project that the UK will be a net exporter of energy from the 2030s, however interconnectors may play an important role in meeting UK electricity demand at certain times of the day or year. For simplicity, interconnector flows have been excluded from Figure 5-2.

5.2.19 The share of UK electricity generation which is to be met by onshore and offshore wind power is projected to increase from 34% in 2023 to

approximately 60% by 2050 under all net zero pathways. However, the UK’s approach to electricity supply will be more resilient to and secure against variations in the weather, technical failures and market forces through being the multi-technology approach proposed by the government (and the previous government) and incorporated in NGESO’s FES pathways.

- 5.2.20 NPS EN-1 states that “We need to ensure that there is sufficient electricity to always meet demand; with a margin to accommodate unexpectedly high demand and to mitigate risks such as unexpected plant closures and extreme weather events” [Ref. 1, Para 3.3.1].
- 5.2.21 The expected growth in electricity demand leads to a need for increased capacities of electricity generation. The national shift from dispatchable carbon-emitting generation to low-carbon renewable generation also implies a growth in electricity generation capacity.
- 5.2.22 **Section 4.3** of this Statement describes the scale of generation required from new facilities to achieve ‘Clean Power by 2030’ and then maintain clean power through to 2050.
- 5.2.23 To improve the likelihood of being able to ensure system adequacy from renewable generators in all but the most unlikely of meteorological situations, a large capacity of interconnected assets from as broad as possible a range of technologies and geography may be beneficial.
- 5.2.24 Figure 5-3 shows, for the same ‘Holistic Transformation’ pathway, the significant increase in installed capacity of each technology required to meet the output projections shown in Figure 5-2 above.




Figure 5-3: Projected electricity generation capacity (GW) and carbon intensity (gCO2(e)/kWh) [Ref. 20(2024), Tables ES.09 & ES1 – ‘System Transformation’]

- 5.2.25 Figure 5-3 shows that electricity generation capacity must increase to three-fold current installed capacity in order to generate sufficient output to meet demand in 2050.
- 5.2.26 To provide some points of comparison, the NIC anticipate that 129 – 237GW of renewable capacity must be in operation by 2050, including 56 – 121GW of solar, 18 – 27GW of onshore wind, and 54 – 86GW of offshore wind [Ref. 24, p19].

- 5.2.27 Energy Systems Catapult (ESC) projections are comparable capacities. 165 – 285GW of capacity will be required in 2050, including 18 – 80GW of solar [Ref. 25, pp23&27]. The ESC includes higher expectations of future nuclear capacity than other analyses, anticipating 20 – 38GW of nuclear versus 11 – 22GW (NGESO) and just 5GW (NIC).
- 5.2.28 Approximately ten percent of NGESO’s ‘Holistic Transition’ capacity pathway in 2050, or 44GW, is expected to be short duration storage, shown in pink in Figure 5-3. Long Duration Storage, including Pumped Hydro and hydrogen, is included within the purple ‘Other’ data series. Further information on electricity storage is included in **Section 5.3** of this Statement.
- 5.2.29 The quantity of new generation capacity required in the UK to meet its net zero targets is enormous, and unprecedented in relation to capacity growth seen at any previous time. Yet such projections have been broadly consistent between different expert bodies and between years, since the net zero target was written into law in 2019.
- 5.2.30 NPS EN-1 also articulates the view that it is prudent to plan infrastructure development on a conservative basis *“to ensure that there is sufficient supply of electricity to meet demand across a wide range of future scenarios”* [Ref. 1, Para 3.3.10]. Prudence would imply not over-relying on technologies which are yet to be proven, have long development lead-times, or which have historically experienced funding difficulties. For this reason, NGESO’s pathways include major contributions from wind and solar generation rather than CCUS, hydrogen or nuclear generators.
- 5.2.31 Such an expansion of capacity, across many technologies, does not come without risk. It is very possible, if not probable, that one or more technologies will miss their targets. This would increase the need for technologies which are successfully being deployed to accelerate their deployment further, in compensation.
- 5.2.32 Challenges will come through international competition in supply chains, technology and labour markets, and also in grid connection. FES 2023 reiterated the obvious point that *“sufficient electricity connection capacity is vital”* to support capacity projections [Ref. 19(2023), p132].
- 5.2.33 Grid is a finite but critical enabler to decarbonisation both in terms of absolute scale and timing to connect. NPS EN-3 recognises the benefit to decarbonisation and consumers of using already available grid infrastructure:
“To maximise existing grid infrastructure, minimise disruption to existing local community infrastructure or biodiversity and reduce overall costs applicants may choose a site based on nearby available grid export capacity” [Ref. 2, Para 2.10.25]
- 5.2.34 The CCC also continue to identify grid connection as a potential brake to beating climate change and delivering energy security. They recommend that the government ensures that *“electricity networks have the capacity to meet growing need due to changes to sources of electricity and increased demand across sectors”* [Ref. 8(2024), p95]. The implication of this recommendation is that, in their view, network capacity and connections are not currently adequate to meet UK needs.

5.2.35 Put simply, to fight climate change, we need to make the most of the infrastructure we have available, and we will need to build more. This context provides further support for the Applicant's proposal to develop a large-scale solar facility with co-located storage as associated development at an existing point of connection, which connects into existing and available section of the transmission system. **Chapter 7** provides more information on this point.

5.3 Development Pipelines

5.3.1 The following sections in this chapter provide additional evidence in relation to the main categories of renewable generation technologies tasked to support the delivery of a low-carbon and secure electricity system by 2035, and their contribution to decarbonisation, security of supply and affordability.

5.3.2 New energy projects follow a uniform high-level development process.

- a. The first step is to secure a grid connection offer and define the project cognisant of technical, environmental, land and planning constraints. Data on current and potential future connections for large-scale projects is available on National Grid's Transmission Entry Capacity (TEC) Register [Ref. 38];
- b. The second step is to apply for and obtain planning consent. The government's Renewable Energy Planning Database (REPD) [Ref. 39] provides insight into determined and yet to be determined renewable energy projects at all scales nationally; and
- c. The third step is to secure revenues for the project. System adequacy is primarily managed through GB's Capacity Market in which eligible assets compete at annual auctions for capacity payments in return for providing an equivalent firm supply of capacity to the electricity system.

5.3.3 Wind and solar technology were first included as eligible technologies in the Capacity Market in 2019, however the Capacity Market is not open to assets which already hold Contracts for Difference (CfD) contracts (and vice versa). The inclusion of renewable generation technologies in the Capacity Market underlines the contribution renewable energy can make to system adequacy and system security:

"The system is typically better off with intermittent capacity than without it – wind farms, for example, can contribute to overall security of supply" [Ref. 40, p114].

5.3.4 The CfD scheme is the government's main mechanism for supporting low carbon electricity generation.

5.3.5 The CfD scheme was introduced under the Energy Act 2013 to incentivise investment in renewable energy by providing developers of projects with high upfront costs and long lifetimes with direct protection from volatile wholesale prices. CfDs also protect consumers from paying increased support costs when electricity prices are high.

5.3.6 Renewable generators located in Great Britain that meet the eligibility requirements can apply for a CfD by submitting bids into CfD Allocation

- Rounds, in which a range of different renewable technologies compete directly against each other for a contract.
- 5.3.7 The Low Carbon Contract Company's CfD Register [Ref. 41] and the EMR Delivery Body's Capacity Market Registers [Ref. 42] hold data on contract award.
- 5.3.8 Although lists and registers provide important evidence towards current and future generation capacities, the listing of a scheme on any grid connection register, a planning database or a commercial contract register, does not guarantee that the scheme will come forwards.
- 5.3.9 For example, in February 2023 National Grid ESO shared their analysis that "*only 30-40% of projects [schemes] in the [connections] queue make it to fruition*" [Ref. 43]. **Section 2.13** of this Statement describes reforms being taken under the Connections Action Plan to deter speculative connection applications and remove stalled schemes from the connections queue.
- 5.3.10 Of the 243GW of projects of all technologies listed on the REPD, just 51.3GW are operational and 39.3GW will not move forwards due to having been refused planning consent, being abandoned (by the developer), or planning permission having expired.
- 5.3.11 Analysis of the CfD Register [Ref. 41] shows that even schemes which have achieved consent, and a revenue contract are not guaranteed to deliver. 81 schemes with CfDs have registered a reduction to the capacity of the CfD Unit or have had their CfD terminated:
- Offshore wind: four schemes (1,408MW) terminated, 1,494MW reduction on 21 schemes still going forwards;
 - Onshore wind, including Remote Island Wind: five schemes (341MW) terminated, 81MW reduction on 14 schemes still going forwards;
 - Biomass / Waste / CHP / Advanced Conversion schemes: thirteen schemes (292MW) terminated, 25MW reduction on two schemes still going forwards; and
 - Solar PV: ten schemes (288MW) terminated, 77MW reduction across 12 schemes still going forwards.
- 5.3.12 Developers may elect to terminate CfD contracts for a variety of reasons, including change of ownership or commercial opportunities outside of the CfD framework. Reducing the capacity allocated to a CfD contract may also improve the commercial performance of a scheme under certain market conditions. However, the risk of non-delivery rises on capacity which has not yet commenced its CfD contract and which has dropped out, of or been terminated from, its CfD contract.
- 5.3.13 However, NPS EN-1 states that it is the government's view that infrastructure development should be planned on a conservative basis [Ref. 1, Para 3.3.10] without over-relying on technologies which are yet to be proven, have long development lead-times, or which have historically experienced funding difficulties.
- 5.3.14 This data and corresponding analysis suggests that it is not prudent to assume the full delivery of pipeline projects listed on various registers,

because it is highly unlikely that a significant proportion of that capacity will be commissioned.

5.4 Offshore Wind

- 5.4.1 The UK is a world-leader in offshore wind technology with ambition to deliver 50GW of operational capacity by 2030, up from 14.7GW operational in 2023 [Ref. 19(2024), Table ES1]. The government's election manifesto calls for a quadrupling of offshore, i.e. to over 55GW, by 2030 [Ref. 31, p51].
- 5.4.2 None of National Grid's 2024 FES pathways meet the government's 2030 target, and only one meets the previous 50GW target, highlighting the massive scale of renewable infrastructure required to meet net zero. Of the three net zero pathways, offshore wind capacity in 2030 ranges between 43.4GW and 53.6GW, generating between 165TWh and 192TWh of low-carbon energy each year.
- 5.4.3 Offshore wind is expected to produce a significant proportion of the UK's future low-carbon electricity needs, however the government's proposals (and those of the previous government) take a multi-technology approach to the future electricity system, in part to provide security of supply through variable weather conditions.
- 5.4.4 Offshore wind is not tasked with meeting, and cannot be expected to meet, future UK electricity needs on its own.
- 5.4.5 National Grid's TEC Register [Ref. 38] lists projects which have accepted a connection offer.
- 5.4.6 Figure 5-4 shows, in blue columns, the grid connection capacity of potential future Offshore Wind projects by their *contracted* year of connection.
- 5.4.7 The red line shows the capacity projection for offshore wind from NGENSO's 'Electric Engagement' pathway, which is the median capacity projection of the three net zero pathways in FES 2024.
- 5.4.8 The red triangle marks the government's approximate level of ambition as described in their election manifesto, to 'quadruple offshore wind' [Ref. 31, p51].
- 5.4.9 Of the total offshore wind (including floating wind) pipeline shown, which amounts to 125GW of capacity, 9GW, connecting between 2026 and 2036, proposes a mix of technologies while 116GW is proposed to be stand-alone offshore wind. The TEC Register records the connection capacity for the development and does not identify the proposed capacity for each of the constituent technologies proposed to be installed. However, it may be a reasonable assumption that, because offshore wind assets tend to be large, their grid connection agreement has been sized with the intended capacity of offshore wind in mind, and co-located assets have been included in the Figure.




Figure 5-4: Current and potential future connected capacity of offshore wind technology [Ref. 38(2024), Table ES1, Author Analysis]

- 5.4.10 Figure 5-4 should therefore be interpreted as an approximation rather than a precise view of the offshore wind development pipeline, but as described previously, not all of that capacity can be assumed to deliver.
- 5.4.11 At the time of writing this Statement, the TEC register lists a total of 34.1GW of capacity which has not yet connected but is scheduled to connect before 2030 bringing the UK's total operational offshore wind capacity to 49.5GW in 2030, if all of the pipeline delivers. This is broadly in line with both the most ambitious FES pathways and the current target of 50GW in 2030, but does not deliver sufficient capacity to meet the government's increased ambition. This will increase the need for capacity to deliver beyond 2030 to keep on track for net zero 2050.
- 5.4.12 The connection of many schemes with connection agreements in the late 2020s and beyond will be dependent on a significant number of onshore and offshore transmission network reinforcement works. The Connections Action Plan makes clear the level of network development required to facilitate the connection of up to 50GW of offshore wind to the UK electricity network by 2030 and the risks associated with the delivery of these pipelines should not be understated.
- 5.4.13 While it is not a given, there is potential for any network development delays to affect multiple offshore wind schemes. This is important because National Grid's approach to offshore transmission development is currently favouring a network of connections with transmission assets being shared by multiple schemes. Previously offshore transmission assets have been developed for individual schemes [Ref. 16, p62]. The impact of a delay on the delivery of an offshore transmission development may therefore be felt across more than one scheme.
- 5.4.14 When a grid connection has been secured, schemes are prepared for planning consent submission and appear on the government's Renewable Energy Planning Database [Ref. 39]. The relationship between projects listed on the TEC Register and projects listed on the REPD is not one-to-one

- because developers may take different approaches to planning and delivery for example in the phasing of schemes for consent and delivery.
- 5.4.15 The TEC Register lists 22 offshore wind schemes comprising 24.4GW proposing to connect in the period 2024 – 2028. In order to meet these dates, it is likely that planning consent must have already been secured. The REPD lists 21 offshore wind schemes comprising 21.1GW in ‘awaiting construction’ or ‘under construction’ status. It is therefore possible that offshore wind delivery is already set to be at least 3.3GW lower than the pipeline shown in Figure 5-4 by 2027.
- 5.4.16 Data from the REPD [Ref. 39] shows that 46 offshore wind farms took on average over 6 years from submitting their planning applications, to achieving commercial operation. Achieving planning consent took approximately two years, leaving on average nearly 4.5 years to construct and commission each scheme.
- 5.4.17 On receipt of planning consent, offshore wind developers are then eligible to compete with other projects for CfDs.
- 5.4.18 10.2GW of offshore wind schemes have secured but not yet commenced their CfDs. Many of these projects are still in construction, but approximately 1.4GW are already operating, suggesting that their contracts will soon commence.
- 5.4.19 The data therefore suggests that of the 24.4GW of offshore wind which is not yet operational but has an agreement with National Grid to connect in 2028 or earlier, approximately 21GW has secured planning consent, and only approximately 50% of that capacity (10GW) has secured a CfD.
- 5.4.20 However, the number of schemes which have secured funding and commenced construction still does not indicate a commitment by or obligation on the promoter to deliver that project at all or, if it does, at a particular generation capacity.
- 5.4.21 In July 2023, for example, the previous developer of Norfolk Boreas wind farm (1.8GW) announced that it was halting development of its because it *“no longer made financial sense to continue”* [Ref. 44]. Norfolk Boreas, Norfolk Vanguard West and Norfolk Vanguard East, with a combined planned capacity of 4.2GW, were purchased by another developer in December 2023. Development of the schemes has resumed.
- 5.4.22 In summer 2023, the then government held CfD Allocation Round 5 (AR5). The Allocation Rounds follow a competitive process, so information on project prequalification for the allocation round is not published. When AR5 results were published in September 2023, however, no contracts had been awarded to offshore wind projects.
- 5.4.23 The Allocation Round Price Cap for AR5 was £44/MWh in 2012 money (equivalent to approximately £61.40/MWh in 2024). One possible conclusion of the AR5 result, is that developers require a strike price of more than £61.40/MWh to make their projects economically viable, yet could not be awarded a contract at a higher value than the Price Cap and therefore no contracts were awarded to offshore wind projects in AR5.
- 5.4.24 The long-term effect of the AR5 outcome on the future development of offshore wind remains to be seen. In November 2023 the then government

- increased the Administrative Price Cap for offshore wind in advance of CfD AR6 which opened in March 2024.
- 5.4.25 AR6 results were published in September 2024. 3.4GW of new offshore wind secured contracts for delivery in 2028/29 at a strike price of £58.87/MWh (2012 money, equivalent to approximately £82.10/MWh in 2024) [Ref. 41].
- 5.4.26 Another possible knock-on effect on offshore wind delivery of the AR5 result is an over-subscription in future Allocation Rounds from schemes unsuccessful in previous rounds and schemes which have recently secured planning competing for contracts. Greater competition in future rounds may drive price down, but only to a level of commercial acceptability.
- 5.4.27 As offshore wind capacity grows, schemes may be located further from shore, or in deeper water, or incorporate new technology – for example floating platforms – which may all increase future development costs over those achieved within the technology class to date.
- 5.4.28 The UK’s current offshore wind pipeline shows great potential to deliver significant decarbonisation and energy security benefits. However, it is clear from recent scheme and contracting progress that delivery of the pipeline should not be taken for granted.
- 5.4.29 With some schemes under construction currently paused and a temporary hiatus in securing revenue contracts for schemes which have already secured planning consent and overcome significant complexity in associated grid connection works, the risk of non-delivery of offshore wind capacity has increased over the last two years.
- 5.4.30 The next Contracts for Difference Allocation Round, AR7, is currently scheduled to be held in 2025 and may represent the last opportunity to contract new UK offshore wind capacity to deliver before 2030.
- 5.4.31 It is therefore not a given that the government’s ambition to quadruple offshore wind by 2030 will be met, or even that National Grid’s FES pathways for the technology class will be achieved by 2030.
- 5.4.32 Any shortfall in the delivery of offshore wind projects against National Grid’s scenarios will need to be made up for instead by other technologies prior to 2030 and / or adds to the need to develop schemes which will deliver in the 2030s to make up for any shortfalls prior to 2030 as well as continued to keep power clean beyond 2030.

5.5 Onshore Wind

- 5.5.1 FES reports that 13.7GW of onshore wind capacity was operational in 2023 [Ref. 19(2024), Table ES.07].
- 5.5.2 In 2015 the then government placed an effective moratorium on further onshore wind development in England. According to the REPD, operational onshore wind capacity in England increased by just 0.7GW between the end of 2015 and January 2024.
- 5.5.3 FES net zero consistent pathways cover a range of 23 – 27GW of onshore wind operational by 2030, which increases to 32 – 42GW by 2050 [Ref. 19(2024), Table ES.07].

- 5.5.4 In September 2023, the previous government announced a proposed lift on the ban on onshore wind in England, by introducing changes to the National Planning Policy Framework (NPPF).
- 5.5.5 The government reversed the moratorium in July 2024 by revising planning policy to place onshore wind on the same footing as other energy development in the National Planning Policy Framework (NPPF). This is to assist in achieving their election manifesto aim of doubling onshore wind capacity in the UK by 2030 [Ref. 31, p51].
- 5.5.6 With the moratorium having been in place for such a long time, onshore wind development pipelines in England are currently thin. Re-establishing a pipeline of onshore wind schemes in England may take some time.
- 5.5.7 National Grid's TEC Register [Ref. 38] shows that no new onshore wind schemes in England and Wales have agreements to connect to the Transmission system before 2025, and only 4GW hold agreements to connect before 2030. Other schemes totalling approximately 2.9GW have been accepted to connect to the English and Welsh electricity distribution networks, however the REPD shows that just 33 applications for a total of 700MW of onshore wind have been made but are not yet determined in England and Wales. 37 schemes for a total of 290MW are awaiting construction. Just one 35MW development in Wales secured a CfD as part of AR5, and a total of 73MW of capacity in AR6, mainly for delivery in 2027/28.
- 5.5.8 Data from the REPD also shows that onshore wind schemes that achieve planning consent in Great Britain take between five and seven years to pass through the planning system (average duration between commercial operations date and planning application submission date, for successful onshore wind schemes listed on the REPD). Pre-application development may last for two or more years beforehand although this will be highly scheme specific.
- 5.5.9 It is therefore not a given that the changes to the NPPF will deliver the required generation capacity to meet even its share of National Grid's least optimistic projections for the technology class, or the government's ambition to double onshore wind capacity by 2030.
- 5.5.10 The UK will therefore need to look to Scotland to support an increase in onshore wind capacity through the next circa five years.
- 5.5.11 The REPD pipeline for Scotland shows 7GW of consented schemes which are not yet operational (just 1.9GW of these are listed as under construction) as well as 7.4GW of applications in Scotland which have not yet been determined.
- 5.5.12 The REPD also shows that of the total capacity of Scottish onshore wind schemes listed in the REPD as having been determined, only 55% has been consented (15.8GW consented of 28.8GW determined). If historical consent rates continue into the future with a pace consistent of that of the past, the Scottish pipeline of onshore wind schemes is not of a sufficient scale to deliver the range of onshore wind required by 2030 in National Grid's net zero compatible scenarios.

- 5.5.13 Therefore, relying solely on Scottish onshore wind to deliver against the National Grid's projections is also not a prudent approach to delivering progress against the UK's decarbonisation and energy security targets.
- 5.5.14 The UK's Contracts for Difference Allocation Round 6, results of which were published in September 2024, allocated contracts to 1GW of onshore wind, predominantly in Scotland and predominantly in 2027/28.
- 5.5.15 Any shortfall in the delivery of onshore wind schemes against National Grid's scenarios will need to be made up for instead by other technologies.

5.6 Nuclear

- 5.6.1 GB operational nuclear capacity is, at the time of submission of this report, at 6GW, down from over 9GW in 2020. Two stations (2.4GW) are due to close in March 2026 [Ref. 46] and a further two stations (also 2.4GW) are due to close in 2028. Operator EDF is investigating the possibility of extending operation of the existing stations for as long as possible but as with all nuclear facilities, continued operation is dependent on stringent operational inspections continuing to yield satisfactory results [Ref. 47].
- 5.6.2 The government has committed to "*extending the lifetime of existing plants*" [Ref. 31, p52], but operational lifetime is limited at these four stations by irreversible engineering processes deep inside the reactor cores.
- 5.6.3 It therefore remains highly unlikely that any significant lifetime extension commitments will be made by the operator in these station's final years of operation. An ongoing programme of inspection and testing will continue to inform the operator, with oversight from the UK's independent nuclear regulator, on the ability of these stations to operate safely until their next programmed inspections.
- 5.6.4 Therefore, by as early as 2029, only one currently operational nuclear power station, Sizewell B (1.2GW) will continue to operate in the UK. Operator EDF is seeking permission to extend the life of this reactor by 20 years to 2055. A 60-year operational lifetime is commonplace for the nuclear technology in use at Sizewell B.
- 5.6.5 Nuclear power is a low-carbon power source, therefore the likely closure within the next five years of 4.8GW of capacity, which has historically generated c.30TWh/year of low-carbon electricity, will need to be made up by other low-carbon sources of electricity, just to prevent an increase in grid carbon intensity over the next five years.
- 5.6.6 New nuclear has been a part of every UK government energy strategy since the mid-2000s and many barriers to nuclear development have been removed over the last decade. For example, site selection (the National Policy Statement for Nuclear Power Generation, although this now is due to be replaced), early regulatory approval of reactor designs (the Generic Design Assessment (GDA) process) and revenue and back-end cost certainty through the CfD, a key element of the 2013 Electricity Market Reform, and the Funded Decommissioning and Waste Management Plan. The Energy Act 2013 also created a body corporate, the Office for Nuclear Regulation (ONR) to regulate, in Great Britain, all nuclear licensed sites.

- 5.6.7 The nuclear development process is neither easy, nor short. Nuclear projects have long development and construction lead times with many regulatory and commercial approvals and decision points along the way. Hinkley Point C development started in earnest in the late 2000s and civil site construction commenced in 2016. Hinkley Point C is still under construction.
- 5.6.8 The government has committed to *“get Hinkley Point C over the line”* [Ref. 31, p52] but it was announced in January 2024 that the plan to start commercial operations has already been further delayed to between 2029 and 2031 [Ref. 48], due to construction delays.
- 5.6.9 In the 2020 Energy White Paper, the then government stated its aim *“To bring at least one large scale nuclear project to the point of Final Investment Decision by the end of this Parliament [i.e. in 2024], subject to clear value for money and all relevant approvals.”* [Ref. 10, p16]. Sizewell C, which is proposed to be a replica of Hinkley Point C, received a Development Consent Order in July 2022 but remains uncommitted, although non-nuclear construction ground and associated development works have commenced.
- 5.6.10 In November 2022, the then government took a £700 million stake in Sizewell C and became a 50% shareholder in the project’s development with EDF. A further £511 million was made available *“to continue project development and prepare the Suffolk site for construction”* [Ref. 49]. Since September 2023, the government has been working together with EDF to raise private capital investment for the project. In December 2023, the then government invested an additional £1.3 billion in the project, consolidating its position as the majority shareholder [Ref. 50].
- 5.6.11 In August 2024 the government announced the Sizewell C Development Expenditure (Devex) Subsidy Scheme of up to £5.5 billion to *“enable continued support to the development of the proposed new nuclear power plant Sizewell C (SZC) to the point of a Final Investment Decision (FID)”* [Ref. 89].
- 5.6.12 If a Final Investment Decision is taken early in the government’s term of office, and formal construction commences soon afterwards, overlaying Hinkley Point C’s construction programme would see first commercial operation at Sizewell C well into the second half of the 2030s. Construction efficiencies may be secured through replication of construction methods from Hinkley Point C to Sizewell C, but are not guaranteed.
- 5.6.13 Great British Nuclear (GBN) was launched by the then government in 2023, as an ‘arms-length body’ with its first priority being to *“administer a competitive process to select the best small modular reactor (SMR) technologies from around the world. This SMR technology selection process will underpin government’s commitment to two nuclear Project Final Investment Decisions during the next Parliament, with at least one of these being into an SMR project”* [Ref. 51].
- 5.6.14 SMRs are nuclear facilities which are proposed to achieve economies of scale through multiples of projects, rather than the size of a single project. Modular construction of nuclear facilities is largely anticipated to be factory based, requiring only the installation of prefabricated components in situ. In this way, learning can be applied during subsequent manufacturing in a

- controlled environment, delivering anticipated rewards in terms of construction duration, cost and quality.
- 5.6.15 The first three SMR designs are now being assessed under GDA by the ONR, a process which has previously taken three or more years. SMRs will require the construction of approved manufacturing facilities prior to delivery of the first unit. Although SMRs may bring decarbonisation and energy security benefits to the UK, the first SMR unit is very unlikely to be operational in the UK within this decade.
- 5.6.16 In October 2023, GBN down-selected six companies through the initial stage of a nuclear technology competition, successful companies were considered to “*offer the greatest confidence in being able to make a final investment decision in 2029*” and be “*most able to deliver cutting-edge technology by [the] mid-2030s*” [Ref. 52]. GBN are currently assessing four bids made for government development support contracts, two companies are now no longer part of the competition.
- 5.6.17 Any reactor which succeeds in becoming commercially operational, whether large or small, will need to pass through GDA, be allocated an approved site, secure grid connection and secure a Development Consent Order. Manufacturing facilities may also require nuclear-level consenting and approval. Reactor operating companies will need to secure a Nuclear Site Licence and become both intelligent customer and controlling mind of the end-to-end design, operation and decommissioning of the site.
- 5.6.18 Revenue mechanisms will also need to be developed, funding secured, and then the process of construction and installation commenced, and facilities commissioned.
- 5.6.19 In the FES 2024 net zero pathways, NGENSO assumes the closure of two existing nuclear stations prior to 2030 and the commissioning of Hinkley Point C reactor between 2029 and 2031, in line with developer announcements. SMRs appear from 2034 at the earliest, and Sizewell C commissions in the second half of the 2030s.
- 5.6.20 It is clear that nuclear development does not come without risk. In the 2010s, three mature GW-scale reactor projects progressed towards Financial Investment Decision, but only one, Hinkley Point C (EDF, 3.2GW) has been taken forwards to construction. The other two (Wylfa and Moorside) were discontinued in 2019 and 2017 respectively, due primarily to commercial matters.
- 5.6.21 It is therefore not yet the case that the existence of a governmental plan for nuclear, and companies currently participating in that plan, can be relied upon to deliver the potential benefits of such a plan.
- 5.6.22 This analysis suggests, firstly, that no nuclear facility other than Hinkley Point C is able to join the existing Sizewell B reactor on the grid before 2035, the previous government’s target date for full decarbonisation of the electricity system. And secondly, that the closure of 4.8GW of existing nuclear power before 2030, the year by which the government aim to have delivered clean power, may be inevitable.

5.6.23 Achieving even the minimum of the four FES pathways require that Sizewell C will go ahead, but operation is not forecast to be until 2036 in the most optimistic net zero FES pathway and 2039 in the other two. Figure 5-5 shows the average and the range of the annual nuclear capacity projections for National Grid’s net zero compatible FES projections.




Figure 5-5: FES future nuclear capacity pathways 2023-2050 (GW) [Ref. 19(2024), Table ES.21, Author Analysis]

- 5.6.24 In October 2023, the then government also published ‘Towards Fusion Energy 2023’, the next stage of the UK’s nuclear fusion energy strategy [Ref. 53].
- 5.6.25 The UK’s nuclear fusion strategy sets out two objectives. Firstly, a UK demonstration of commercial viability of fusion from a UK prototype plant which delivers net energy, and secondly the development of a world-leading fusion industry.
- 5.6.26 Not detracting from the important activity of fusion research and development, it is relevant for the purpose of examination of this scheme to place this exciting prospect in the UK into context. In support of the first objective:

“the STEP Programme will design, develop and build, by 2040, a prototype fusion power plant capable of delivering net energy” [Ref. 53, p20].
- 5.6.27 EA 2023 legislates for fusion regulation, an essential pre-requisite for developers to plan prototype projects.
- 5.6.28 Any possible decarbonisation contribution from nuclear fusion will therefore not materialise in time to support the then government’s target to decarbonise the electricity system by 2035, and it is not yet clear that achieving the government’s current fusion targets, including a successful demonstration STEP project, will enable nuclear fusion to make a net contribution to decarbonisation from any facilities following STEP, prior to 2050.

5.7 Unabated Fossil Fuels And Abatement Technologies

- 5.7.1 National Grid's FES shows that 29.4GW of CCGT (Combined Cycle Gas Turbine) generation capacity was operational in the UK in 2023, and in 2023 this capacity contributed nearly one quarter of the UK's total annual generation output. 6.5GW of other gas-fired generation capacity, including Open Cycle Gas Turbines, smaller gas reciprocating engines and gas-fired combined heat and power was also operational in 2023 [Ref. 19(2024), Table ES1].
- 5.7.2 Currently all UK CCGT (and other gas-fired) capacity is fully unabated, meaning that the CO₂ emitted as a by-product of generating electricity is released to the atmosphere and contributes to global warming. Progressing towards a zero-carbon electricity system requires the decarbonisation of these assets, or the replacement of their generation capacity with alternative low-carbon sources. The most significant decarbonisation requirement is on the CCGT fleet.
- 5.7.3 Decarbonisation of the fuel used to generate electricity in the CCGT fleet can be achieved by burning hydrogen. Capturing carbon emissions and storing them away from the atmosphere would also decarbonise the assets and is dependent upon the deployment at scale of Carbon Capture Usage and Storage (CCUS).
- 5.7.4 FES 2024 net zero pathways include gas schemes with carbon capture operating from 2033 at the earliest. Deploying CCUS more quickly will provide a greater capacity of low-carbon dispatchable generation to the market to complement renewable generation assets in meeting demand. Deploying CCUS more quickly than the FES 2024 pathways is necessary for CCGT to be part of the government's ambition to deliver 'Clean Power by 2030'.
- 5.7.5 The net zero FES pathways include 18.8 – 34.7GW of dispatchable low-carbon generation in operation in 2040, from a base of 0 – 1.3GW in 2030.
- 5.7.6 CCUS is also required to facilitate Bioenergy with Carbon Capture and Storage (BECCS), as described in **Section 5.9**.
- 5.7.7 Powering Up Britain aimed to deliver four operational CCUS clusters to capture and store 20-30 million tonnes of carbon dioxide (MtCO₂) by 2030 [Ref. 14(1), p21]. This was confirmed by the previous Prime Minister in September 2023 [Ref. 32].
- 5.7.8 CCUS has a key role in the UK's Net Zero Strategy. It is a prominent feature of the National Infrastructure Strategy [Ref. 54], Energy White Paper [Ref. 10] and Industrial Decarbonisation Strategy [Ref. 55]. Previous governments have recognised that *"the technology has not been delivered at scale and significant risks remain"* [Ref. 54, p53] but recent progress has been made in developing and consenting projects as well as developing a commercial framework to support the technology. The government's current CCUS Deployment Pathway seeks to secure an option to deploy CCUS at scale during the 2030s, subject to costs coming down sufficiently.
- 5.7.9 However, the CCC note in their 2024 Progress Report to Parliament, that *"progress on developing engineered removals is behind schedule and*

achieving the Government's ambition to remove at least 5 MtCO₂ per year by 2030 is increasingly challenging" [Ref. 8(2024), p81]

- 5.7.10 CCUS deployment is currently progressing under a cluster approach with Track 1 and Track 2 projects now identified and under development.
- 5.7.11 Eight projects were selected from the Track 1 cluster sequencing process for CCUS to proceed to negotiations for government support. Three are part of the East Coast Cluster and five are part of the HyNet Cluster. Both clusters have previously been identified as funding recipients.
- 5.7.12 HyNet report the potential to reduce CO₂ emissions by 10 million tonnes every year by 2030 by producing and transporting hydrogen to end users through a network of dedicated pipes, while also capturing the associated CO₂ emissions and piping them in a separate pipe to an undersea storage facility. The HyNet Carbon Dioxide Pipeline was granted a Development Consent Order in March 2024. The Hynet North West Hydrogen Pipeline planning application, is now expected to be submitted to the Planning Inspectorate in 2025, delayed from early 2024.
- 5.7.13 The East Coast Cluster aims to capture and store an average of around 23 MtCO₂ per year by 2035, with three selected Track 1 projects aiming to connect to the cluster by 2027.
- 5.7.14 The Net Zero Teesside project, a Track 1 CCGT + CCUS project with associated CO₂ transportation infrastructure, which is part of the East Coast Cluster, was granted a Development Consent Order in February 2024. In the Decision Letter, the then Secretary of State recognised the urgent need for gas-fired electricity generation with CCS infrastructure as set out in EN-1 and determined that the project would help deliver the UK's net zero commitment by 2050. Therefore, the project would be in line with the then government's wider policy statements on energy and climate change.
- 5.7.15 A planning application for a second part of the East Coast Cluster, the Humber Low Carbon Pipelines project, was withdrawn by previous developer National Grid Carbon Limited in January 2024. The project was to construct CO₂ and hydrogen transportation pipelines to connect various emitters and generators in the Humber region and is now being taken forward under a separate DCO application by new owner, Northern Endurance Partnership.
- 5.7.16 Both HyNet and East Coast Clusters provide the possibility of directly capturing and storing emissions from CCGT and Biomass electricity generation facilities located close to the clusters as well as the opportunity to decarbonise heavy industry in the areas local to the proposed pipelines.
- 5.7.17 Progress has been made on project definition, design and consenting in recent years. EA 2023 provides a licensing framework for CO₂ transport and storage, but business models to secure future revenues are still in development. These will be a critical input to future Final Investment Decisions both at the cluster level, and at the level of the projects of which they are comprised.
- 5.7.18 In October 2024, government confirmed funding to launch the UK's first carbon capture sites, with an aim to make the UK *"among the first to deploy this game-changing technology at scale in Teesside and Merseyside"* [Ref. 86].

- 5.7.19 The Cluster approach, when it is delivered, will provide abatement for a significant proportion of the UK's operational CCGT fleet and other industrial carbon emissions. However, an extension of the UK's CCUS or hydrogen pipelines will be required to take emissions out of the many CCGT facilities which are not near to an existing or proposed cluster.
- 5.7.20 A prudent approach to future energy supply would suggest that the full decarbonisation of the existing UK CCGT fleet should not be assumed by 2030.
- 5.7.21 Therefore, other low-carbon supplies may be required to make up for facilities which have by 2030 not yet been abated in order to secure the government aims to deliver 'Clean Power by 2030', and maintain its cleanliness thereafter.

5.8 Hydrogen

- 5.8.1 The previous government's 2021 UK Hydrogen Strategy [Ref. 56, p2] explains that hydrogen has *"the potential to overcome some of the trickiest decarbonisation challenges facing our economy"*, especially in enabling the decarbonisation of industry and land transport, and as a potential substitute for current carbon-intensive marine and aviation fuels.
- 5.8.2 Currently most hydrogen is produced by converting methane to hydrogen and carbon dioxide (this is known as 'blue hydrogen'). As blue hydrogen production emits carbon as a by-product, the development of blue hydrogen facilities will require CCUS capability to achieve net zero carbon. CCUS clusters with hydrogen and carbon dioxide pipelines are hoped to become operational in the second half of the 2020s.
- 5.8.3 Hydrogen can also be produced through the electrolysis of water (this is known as 'green hydrogen'). The 'green' label for electrolysed hydrogen presumes that the input electricity used in the hydrogen production process is itself low-carbon, therefore, there are no carbon emissions associated with the process.
- 5.8.4 Green hydrogen production relies on considerable amounts of renewable energy to electrolyse water. Electrolysis currently accounts for approximately 1% of global hydrogen production. However, a growth in electrolysis capability and capacity opens out the prospect of using renewable generation to produce hydrogen, in potentially significant quantities.
- 5.8.5 Powering Up Britain confirms the then government's ambition for up to 1 GW of electrolytic hydrogen and up to 1GW of CCUS-enabled hydrogen in operation or construction by the end of 2025, subject to affordability and value for money. [Ref. 14(1), p22]. Progress in the governmental Hydrogen Allocation Rounds (HARs) for electrolytic hydrogen [Ref. 57] implies that this ambition is unlikely to be met. Government expected to *"award contracts totalling up to 250MW of capacity from HAR1, subject to affordability and value for money. We aim for contracts to be awarded in Q4 2023, with first projects becoming operational in 2025."* Eleven schemes totalling 125MW of capacity were awarded contracts under HAR1 in December 2023 and are currently at various stages of development.

- 5.8.6 The second HAR closed for applications in April 2024 and intends to award up to 875MW of capacity, taking the combined capacity of the first two allocation rounds to 1GW if fully subscribed.
- 5.8.7 The consultation document related to market engagement for HAR 2 [Ref. 58] describes that, despite the previous government's aim to deliver 1GW by 2025, projects will be able *"to select a delivery year between March 2026 until March 2029"* [Ref. 58, p8]. This suggests that the government's initial Hydrogen capacity aims will not be met, and the potential for demonstration Hydrogen projects to be delayed.
- 5.8.8 Delaying the bulk production of hydrogen will also delay the benefits arising from its use. The development of fully commercial, at-scale schemes will encourage further development and rollout, but secure supplies will be needed to entice early adopters to showcase this new technology.
- 5.8.9 Industry is more optimistic of progress, and the Hydrogen Energy Association reports that *"The first wave of large-scale electrolytic hydrogen projects will be in operation in 2025"*, including pioneering projects located in Wales, Scotland and East Anglia totalling over 1GW of hydrogen electrolysis capacity [Ref. 59].
- 5.8.10 NGENSO's FES 2024 estimates that between 110 and 186TWh of electrical energy will be required annually in the UK by 2050 to produce hydrogen through electrolysis to meet its many potential end-uses [Ref. 19(2024), Table ES.K]. The wide range of future demand estimates is due to different net zero compatible scenarios producing hydrogen in different ways. The Energy System Catapult foresees the need for *"a new low carbon hydrogen economy ... delivering up to 300TWh per annum, roughly equivalent to electricity generation today"* and concluding that *"electricity generation itself may have to double, or even treble if most hydrogen is to be produced by electrolysis"* [Ref. 25, pp6 & Ref. 36].
- 5.8.11 Hydrogen remains an interesting and valuable technology to support net zero. Once hydrogen has been produced, it can be stored, transported, and used in a range of applications as a substitute for natural gas or other carbon intensive fuels. EA 2023 lays the foundations for a future which includes hydrogen technology by creating provisions for business modes for hydrogen production, transport and storage.
- 5.8.12 The Government plans to allocate £500 million to support the manufacturing of green hydrogen [Ref. 31, p27].

5.9 Biomass

- 5.9.1 FES 2024 stated that 4.3GW of Biomass generation was operational in the UK in 2023, producing approximately 30TWh of low-carbon electricity [Ref. 19(2024) Table ES1].
- 5.9.2 The previous government's Biomass Strategy, published in 2023 reaffirmed that *"Only biomass use that complies with strict criteria is considered to be low carbon and to deliver genuine CO2 emissions savings"* [Ref. 60, p6].
- 5.9.3 Building on the already green credentials of the technology, the Biomass Strategy sets a vision to continue to use sustainable biomass in power generation in the 2020s. The Biomass Strategy aimed to transition away

- from unabated uses of biomass by 2035 by incorporating, where possible and with priority, BECCS to make biomass use net negative carbon emissions.
- 5.9.4 Recognising that “*Biomass can play a significant role in decarbonising nearly all sectors of the economy*” the previous government also stated that “*Biomass is not a silver bullet, and neither is carbon capture. We will rely on a range of solutions to achieve net zero*” [Ref. 60, p4].
- 5.9.5 BECCS is not currently operating at scale in the UK, however demonstration and commercial scale plants are operational in other countries. Active work is therefore being undertaken in government and industry to develop business models which support biomass and the delivery of low-carbon electricity as well as negative emissions through the deployment of CCUS to deliver BECCS in the UK.
- 5.9.6 Consideration is being made within government, as to whether new or refurbished biomass plants must, on commissioning, be fit to deploy carbon capture in the future.
- 5.9.7 Against the backdrop of national biomass capacity reducing as existing plant reach the end of their commercial life, FES net zero pathways include BECCS capacities coming on line progressively from 2030 towards an operational capacity of approximately 2GW by 2035 and 3.4 – 4.7GW by 2050 [Ref. 19(2024), Table ES1]. In January 2024, the then Secretary of State approved plans to convert two existing biomass units at Drax Power Station to BECCS.
- 5.9.8 BECCS will be dependent upon the delivery of CCS infrastructure to support the capture of emissions, and any shortfall in the delivery of BECCS schemes against the FES pathway projections will need to be made up for instead by other technologies.

5.10 Solar Power

- 5.10.1 The government’s solar photovoltaics deployment information resource [Ref. 61] records installed and operational solar capacity in the UK. The government’s data shows that at the end of June 2024, the UK had 16.9GW of operational capacity, of which 0.4GW was located in Northern Ireland.
- 5.10.2 UK Solar has generated over 10TWh annually since 2017, rising to 13.9TWh in 2023 [Ref. 19, Table 5.6]. UK solar generation makes an important and reliable annual contribution to meeting national demand. Solar is well placed to play the role it has been ascribed in recent government publications, including those summarised in **Chapter 2** of this Statement.
- 5.10.3 Figure 5-6 following shows how solar capacity has grown in the UK each year since the records began in 2010.
- 5.10.4 Growth in UK solar capacity has been characterised by two phases, the first was supported by the Feed in Tariff (FiT) scheme, that entered into law by the Energy Act 2008 and took effect from April 2010. This phase is denoted by the yellow columns in Figure 5-6. The FiT scheme paid a revenue to owners of solar installations (and other renewable generation assets) with a capacity lower than 5MW.




Figure 5-6: Cumulative and annual installed solar capacity in the UK, 2010 – June 2024 [Ref. 61, Author Analysis]

- 5.10.5 Figure 5-6 shows that the scheme was effective in increasing solar capacity over the period 2010 to 2015. A tariff reduction was announced in December 2015, reflecting reducing installation costs and therefore less of a requirement to incentivise new installations. Annual installations reduced over 2017 and 2018 (light brown columns) as capacity accredited by the scheme before the 2015 tariff announcement continued to be constructed.
- 5.10.6 The FiT scheme closed to new applicants in 2019, and solar capacity growth since 2019 has been supported by market revenues only (dark brown columns).
- 5.10.7 Annual installations are shown by the red line. Additions in the first half of June 2024 have been doubled to provide a comparative annual run rate from the first half-year actuals. Annual installations peaked at 4.3GW in 2015 and averaged 1.2GW over the period 2010 to 2024.
- 5.10.8 Solar has undergone significant technological advances in scale and commercial efficiency, and the UK has many areas of commercially viable solar irradiation. It is therefore important to make best use of this natural, renewable energy resource to meet the UK's legal carbon emission reduction obligations.
- 5.10.9 The previous government stated that it expected a 5-fold increase in the deployment of solar by 2035 [Ref. 12, p19] equivalent to 70GW of operational capacity by the same date. In its election manifesto, the government set out its ambition to triple solar power by 2030 [Ref. 31, p51], requiring a higher annual rate of installations in the period to 2030 as was set by the 2035 target.
- 5.10.10 Importantly, to achieve either of these aims, solar capacity will have to increase by over 4GW each year starting from 2024, i.e. new installations in every year of the government's current term in office, will have to be higher than the UK's previous single highest record of annual installations.

5.10.11 The FES 2024 net zero pathways for solar consider 28 – 40GW installed capacity in 2030, 50 – 85GW in 2040, and 72 – 108GW in 2050 [Ref. 19(2024), Table ES.14]. In every scenario, a pathway to net zero includes a significant future increase in solar capacity beyond that which is installed or in development today, as shown in Figure 5-7.

5.10.12 Figure 5-7 superimposes FES forecast ranges for solar capacity from 2019, 2023 and 2024, with each range shown as a shaded area covering the pathway with the lowest forecast capacity to the highest capacity in each year. Historic installed capacity is shown by the yellow line in 2020-2023.




Figure 5-7: Evolution of future solar capacity forecasts in the UK (2019, 2023 & 2024) [Ref. 19, Author Analysis]

- 5.10.13 Figure 5-7 shows that the range of future solar capacity forecasts for different FES pathways increased from FES 2019 to FES 2023, and again to the most recent publication.
- 5.10.14 The UK's net zero commitment in 2019 manifested in FES pathways as a further increase in solar capacity, shown by the dark grey range in Figure 5-7 (the 2023 forecast) being higher than the light grey 2019 forecast.
- 5.10.15 The blue triangle shows the previous government's aim for solar capacity to reach 70GW by 2035. The red diamond shows the government's ambition to triple solar capacity by 2030. Both are higher than the maximum of the FES 2024 net zero pathways.
- 5.10.16 To achieve the previous government's target of 70GW of solar operational by 2035, installations would need to track the most aggressive FES 2024 pathway for the next ten years.
- 5.10.17 To achieve the government's aim to triple solar by 2030, an even more aggressive deployment rate is needed over the next five years.
- 5.10.18 This underscores the need for solar schemes to come forwards for delivery in the 2020s as well as to continue to come forwards beyond 2030 to deliver the ongoing need for the technology in the UK.

- 5.10.19 Year-on-year cost reductions have made solar technology progressively more attractive (and now preferential) compared to many other forms of electricity generation, promoting the commercial rationality for the UK to prioritise the development of solar capacity. The incorporation of a cost perspective in the 2024 FES is therefore likely to be one reason why capacity installation pathways have increased from the 2023 forecast to the 2024 forecast. Solar capacity helps to address energy affordability challenges (see **Chapter 9**) as well as meet the already urgent need for schemes to come forwards to support decarbonisation and energy security aims.
- 5.10.20 Each of the annual ranges of future installed solar capacity in Figure 5-7 may be explained by the extent to which other low carbon technologies including onshore and offshore wind, nuclear, CCUS and BECCS, are deployed in the UK. Delays or shortfalls in the deployment of any technologies versus their FES pathways will require a compensatory acceleration or expansion in the deployment of other technologies for the UK to remain on track to achieve net zero.
- 5.10.21 In this context, the urgent development of large capacities of technologies which are proven in development and operation is clearly a prudent approach and is consistent with the conservative approach to infrastructure development described in NPS EN-1 [Ref. 1, Para 3.3.10].
- 5.10.22 The solar sector is proven in operation with over 16GW of installed capacity already reliably delivering zero-carbon electricity to the UK's electricity system. The solar sector is also proven in delivery because of its short development duration and is therefore well placed to deliver to the urgent need for low-carbon generation.
- 5.10.23 Data from the REPD [Ref. 39] quantifies the average duration from planning submission to operation of a solar farm in the UK is 1.4 years (over an average of 1,213 projects) with a 1-year construction timeframe post consent.
- 5.10.24 Larger projects may take longer to consent and construct. 13 solar projects with capacity over 40MW are listed as operation on the REPD. These projects took on average 2 years from planning submission to operation, of which construction lasted on average 1.4 years.
- 5.10.25 This data is in stark contrast to historical development timescales in the UK for onshore wind (see **Section 5.5**), offshore wind (see **Section 5.4**) and nuclear power (see **Section 5.6**)
- 5.10.26 However, many large-scale schemes have target operational dates which are determined by available grid connection dates. Large-scale schemes may therefore follow a development plan to coordinate with those dates. Larger schemes of over 50MW capacity are also required to apply for development consent under the PA2008, with different statutory timelines to smaller schemes, which may affect the time elapsed from planning submission to operation as NSIP schemes start to deliver.
- 5.10.27 At first view, solar pipelines look healthy but must be viewed with caution, particularly in relation to the analysis included at **Section 5.3** of this

Statement regarding the attrition of projects and capacity from pipelines and registers prior to commercial operation.

- 5.10.28 Solar schemes can be developed stand-alone or co-located with storage or other generation technologies. Both stand-alone and co-located schemes play essential roles in contributing to the three pillars of energy policy: decarbonisation, security of supply and affordability.
- 5.10.29 **Section 5.11** of this Statement explains that storage is an essential part of the future energy system. **Section 6.9** explains that the co-location of storage with renewable generation has benefits, however it is not necessary (and nor is it a policy requirement) that all renewable energy schemes are co-located with storage.
- 5.10.30 Stand-alone solar schemes (and schemes using other renewable generation technologies) are already prevalent and will likely continue to be prevalent in the UK's future electricity system.
- 5.10.31 Figure 5-9 shows that in each of the three FES pathways which are compatible with net zero, the capacity of solar generation always outstrips that of storage. It is therefore anticipated by the Electricity System Operator, that the future electricity system will consist of both stand-alone solar (and other renewable) projects, as well as co-located projects.
- 5.10.32 Stand-alone renewable schemes generate, from a renewable source, zero-marginal carbon electricity. Therefore, stand-alone schemes also provide an essential contribution to reaching net zero.
- 5.10.33 The TEC Register [Ref. 38] lists 3.6GW of stand-alone solar and 33.9GW of co-located solar projects with connection dates prior to 2030. The TEC register does not record the capacity of individual technology types within an application. Therefore, it is more precise to state that solar technology is proposed to be installed at projects which comprise a total of 37.5GW of connection capacity to the NETS prior to 2030.
- 5.10.34 Embedded Capacity Registers [Ref. 61] list a total of 51GW of solar projects in 'Accepted to connect' status. The data does not indicate when connections will be available.
- 5.10.35 A point of connection is absolutely necessary for a developer to secure for a development to be viable to take forwards and in many cases grid connection can be secured prior even to engaging local landowners. The current scarce nature of grid connections in GB, coupled with expectations of large capacities of connections being required in the future, prioritises the procurement of grid entry connection capacity as a critical project development activity.
- 5.10.36 The cost of securing and holding a grid connection for a potential scheme is also not prohibitive in relation to development costs as a whole. It is therefore understandable that the current 'connection queue' capacity is very high. This does not necessarily mean that all of that capacity will make it to commercial operation, and the Connections Action Plan resolves to remove less viable schemes from the connections queue, and prioritise those which are more advanced in their development.
- 5.10.37 Planning consent is required for all schemes greater than micro-scale. The REPD lists 12.5GW of consented projects awaiting construction but only

2GW is currently under construction. Of the total 14.5GW with planning consent, 1GW of these schemes are of a Nationally Significant scale. Four schemes (1.9GW) have secured consent from the new Secretary of State but consent is not yet reflected for all in the REPD.

- 5.10.38 Applications totalling a further 7.7GW of solar capacity have been submitted to planning authorities other than the Planning Inspectorate, with an average submission date of May 2023. None have yet been determined. Given average development durations, it is possible for successful schemes to deliver in 2025 or 2026, subject to their grid connection dates (which are not listed on the REPD).
- 5.10.39 A further 3GW of capacity in England, across 7 schemes, has been submitted to the Planning Inspectorate but has not yet been determined. Grid connection dates for these schemes range from late 2027 to 2031. One scheme, submitted to the Planning Inspectorate in early 2024, if consented, is likely to delay its grid connection date from 2025 to allow adequate time for its planning application to be consented and then construction to complete.
- 5.10.40 A further 18 schemes, totalling approximately 9GW, are at the pre-application stage with the Planning Inspectorate, including the Scheme, with application submission dates estimated from late 2024 (up to 6 schemes) through 2025 (up to 9 schemes) and 2026 (three schemes). Grid connection dates for these schemes range from 2025 to 2033.
- 5.10.41 At best, therefore, approximately one third of the capacity of solar schemes with agreements to connect to the NETS prior to 2030 have so far engaged with the Planning Inspectorate and it is not a given that all capacity which comes forward proceeds to the development consent / planning stage, or is successful in its planning application and on through construction to operation.
- 5.10.42 In relation to revenue contracting, the pipeline is even further constrained although results of the government's CfD allocation rounds supports solar's ability to deliver to shorter timeframes than other renewable generation technologies. Solar secured contracts to deliver the majority of contracted capacity in CfD Allocation Rounds AR4 and AR5 delivering in 2025 (1.6GW) and 2028 (1.1GW) [Ref. 41].
- 5.10.43 A further 3.3GW of solar was awarded a CfD in AR6, delivering in 2026/27 (1.1GW) and 2027/28 (2.2GW).
- 5.10.44 However, data also suggests that an attrition or stall rate could be significant. Under 5% of potential pre-2030 connected capacity has yet passed through planning and secured a revenue contract for the electricity generated.
- 5.10.45 It is the view of this author, that if a significant capacity of solar generation is not built out to a scale comparable with the projections provided by NGESO and others, then the UK will be highly unlikely to continue to reduce its carbon emissions over the coming decade, and ultimately meet its legally binding net zero target.
- 5.10.46 The size of the pipelines for solar schemes is encouraging across all scales of development, but the data shows that the attrition of schemes through the development process is a real risk to the delivery of that capacity.

A significant proportion of low-carbon schemes currently listed on registers will not become operational, and with that as context, bringing this Scheme forwards will be a critical step in the development and delivery of large-scale solar capacity in the UK.

5.11 Flexibility

5.11.1 The NIC describe the need for flexibility in the UK's future energy system, stating that:

“It is key that, alongside deploying renewables, the UK continues to drive innovation in the power sector to effectively build a flexible electricity system. Storage technologies, flexible demand, efficient interconnectors, and other innovations are also needed to support renewables and maintain the security of the electricity system.” [Ref. 63, p6]

5.11.2 Flexibility is delivered through interactions between both supply (generation) and demand (consumption) to help the national energy system function safely and efficiently. The full operation of flexible assets within that system requires them to both store energy from (or save) and release energy to (or use more) the energy system in response to market drivers, as will subsequently be explained.

5.11.3 The overriding themes for the GB electricity market in the coming decade are those of decarbonisation through an increase in deployment of renewable generation, and higher demand due to the electrification of heat, transport, and industrial demand, while meeting Security of Supply standards and affordability aims.

5.11.4 This means a move away from dispatchable fossil-driven assets and towards renewable plant: a theme which will alter the needs of the GB electricity system. System security of supply will need to address:

- a. Changing patterns of, and variability in, residual demand (demand net of renewable output);
- b. A reduction in the proportion of synchronous plant connected and available to support system frequency; and
- c. A shift in the location of generation reflecting resource (wind and solar) distribution.

5.11.5 Figure 5-8 illustrates the events, consequences and value drivers over different timeframes for flexibility in the GB electricity market. Greater variability in residual demand (i.e. demand net of renewable generation supplied) will increase the need for flexibility solutions across multiple timeframes.

5.11.6 Flexibility is needed to maximise the use of renewables when there is an abundance of generation, and to fill the supply gaps in periods of shortfall.

5.11.7 Storage provides flexibility. Flexibility is the ability to shift in time or location the consumption or generation of energy. Flexibility is also the ability to shift energy from one medium (vector) to another, e.g. electrical energy to gravitational potential energy through Pumped Storage schemes, and back again.




Figure 5-8: Driver of Flexibility Requirements [Ref. 64]

5.11.8 NPS EN-1 sets out the policy position in favour of electricity storage:

“Storage has a key role to play in achieving net zero and providing flexibility to the energy system, so that high volumes of low carbon power, heat and transport can be integrated.” [Ref. 1, Para 3.3.25]

5.11.9 Storage facilities need to be able to import energy and export energy. Sources of energy import are discussed later in this section.

Types of Flexibility

5.11.10 Storage has the capability to deliver flexibility over different timeframes and can be categorised as:

- a. Short Duration Storage (SDS) with durations of four hours or lower, suited to addressing short duration balancing needs;
- b. Medium Duration Storage (MDS) with durations of over four hours, up to 12 hours, suited to addressing within day balancing; and
- c. Long Duration Storage (LDS) with durations of over 12 hours, required for multi-day and seasonal balancing needs.

5.11.11 Here, ‘duration’ refers to the amount of energy a storage facility can hold, rather than the time for which energy can be efficiently stored between import (charge) and export (discharge).

5.11.12 Short Duration Storage addresses the increasing need for flexibility in matching supply with demand within-day, i.e. balancing increasing levels of renewable electricity supply with demand and providing system services to support the operation of a high-renewable electricity system.

5.11.13 Long Duration Storage addresses the view that, in the future, the electricity system is expected to exhibit greater seasonal variability and provide for the potential of periods of days or weeks where there may prolonged excesses, or shortfalls, of renewable output.

5.11.14 Extreme but rare extended periods of low renewable generation (sometimes referred to as ‘*Dunkelflaute*’ events) possibly lasting up to several weeks have the potential to pose a security of supply risk. There is still considerable uncertainty around forecasting when these events will occur and how long

they will last, so there is a need for both sufficient storage capacity and generation capacity to manage security of supply through these periods while also supporting decarbonisation targets.

- 5.11.15 Conversely, enduring periods of high renewable generation can better contribute to overall electricity system decarbonisation if abundant generation can be stored rather than curtailed.
- 5.11.16 Long Duration Storage assets are an important part of the anticipated solution to help manage both types of events, but these are not the events which Short Duration Storage assets, such as those which form part of the Scheme, are designed to address.
- 5.11.17 There are many technologies which have potential to provide grid scale electricity storage functions, ranging from pumped storage hydro schemes, BESS or more novel technologies such as liquid air storage, compressed air storage for SDS or hydrogen with potential for LDS application. Pumped storage hydro schemes have been in existence for over 50 years. BESS are becoming increasingly commonplace in the UK. Other novel technologies are now being designed and developed with varying timescales for deployment.
- 5.11.18 Key differentiators between storage technologies are not only how energy is stored but is also how much energy can be stored, and for how long it can be stored, from both a technical and commercial basis.
- 5.11.19 NPS EN-3 also describes the government's support for solar which is co-located with storage [Ref. 2, Para 2.10.32].
- 5.11.20 Storage systems which are co-located with solar in the UK have so far tended to be SDS systems because SDS systems complement the generation profile of solar facilities and provide system functions which support the operation of the solar facility by (among other functions) balancing supply with demand.
- 5.11.21 The co-location of MDS or LDS systems with solar has not yet been proposed in the UK but future advances in technology may make this a viable possibility.
- 5.11.22 BESS are short duration electricity storage systems.

Quantifying future flexibility needs

- 5.11.23 FES 2024 net zero pathways indicates that storage and interconnection (flexibility) capacity will need to increase (from 15.8GW in 2023) to 38.8 – 45.7GW in 2030 and 56.9 – 76GW by 2050 to balance supply and demand both within the GB system and across borders. Net zero pathways show Short Duration Storage system capacity increasing from 4.7GW in 2023 to 22.8 – 27.8GW by 2030, 31.1 – 38.6GW by 2040 and 36 – 44GW by 2050 [Ref. 19(2024), Table ES1].
- 5.11.24 As renewable generation capacity increases on the GB electricity system, so too will the total capacity of operational storage systems to balance an increasingly variable supply portfolio with demand across timeframes ranging from milliseconds to seasons.

“Storage and interconnection can provide flexibility, meaning that less of the output of plant is wasted as it can either be stored or exported when there is

excess production. They can also supply electricity when domestic demand is higher than generation, supporting security of supply. This means that the total amount of generating plant capacity required to meet peak demand is reduced” [Ref. 1, Para 3.3.6].

5.11.25 Figure 5-9 shows solar and Short Duration Storage capacity projections from 2024 to 2050. The annual projections for SDS capacity (y-axis) are plotted against the annual projections for solar capacity (x-axis) for each of the three FES net zero pathways. The data has been re-cast to show increases versus a 2023 baseline. Figure 5-9 shows anticipated growth in SDS capacity as a function of increasing solar capacity.

5.11.26 Each pathway follows a similar trend. An increase of 10GW of solar (i.e. increasing GB installed solar capacity from c.16GW as at the time of submission to c.26GW) corresponds to a projected increase of c.15GW of Short Duration Storage (i.e. increasing GB installed storage capacity to c.20GW). An increase of 40GW of solar capacity corresponds to an increase of c.25GW of Short Duration Storage.

5.11.27 The data shows that Short Duration Storage capacity initially needs to increase by c.1500MW per 1000MW of solar capacity growth, but NGENSO’s current pathways show that growth can then settle to c.250MW per 1000MW of solar capacity growth thereafter.

5.11.28 This analysis provides an indication of the scale of the need for SDS in the UK electricity system, however, it will not be solely a growth in solar capacity, but more likely a growth in the capacity of all renewable generation, which drives the requirement to increase capacity of many types of storage technology.




Figure 5-9: Growth in Short Duration Storage capacity vs. Solar Capacity, 2024 – 2050 [Author Analysis, 20(2024), Tables ES.09 & ES1]

Co-location and stand-alone schemes

5.11.29 As both renewable generation capacity and storage capacity are expected to increase, projects which seek to connect to grid connection points which can accommodate storage facilities may propose to bring forwards co-located storage facilities as Associated Development to the main (renewable generation) development, as envisaged by NPS EN-3 [Ref. 2, Para 2.10.16].

5.11.30 As described previously, storage facilities may also be developed as stand-alone from any renewable generation schemes.

- 5.11.31 Developments may identify location-specific reasons why storage schemes will not be co-located with renewable generation schemes, but it is important to recognise that stand-alone storage schemes are already commonplace in GB. Such schemes have already and are likely to continue to come forwards, delivering decarbonisation and energy security benefits as part of the UK's electricity system through their own grid connections. It is not necessary (nor is it a policy requirement) that all storage is co-located with a renewable energy scheme but as NPS EN-1 makes clear, co-location is an approach which is supported because it can help to maximise the efficiency of land used by a scheme. Co-location also helps to maximise utilisation of a scheme's grid connection capacity, if that connection has both import and export capability.
- 5.11.32 Figure 5-9 shows that in each of the three FES pathways which deliver net zero, the capacity of solar generation outstrips that of storage capacity at all times. It is therefore anticipated by the Electricity System Operator, that the future electricity system will consist of both stand alone solar schemes (and by extension other renewable schemes), as well as co-located schemes.
- 5.11.33 However, where grid connections offers enable the co-location of renewable generation with storage, a scheme which includes both may be proposed and by doing so would – among other reasons – ensure that the greatest use can be made of the scheme's grid connection infrastructure.
- 5.11.34 Projects which are being brought forwards as stand-alone generation schemes still play an essential role in contributing to the three pillars of energy policy: decarbonisation, security of supply and affordability, because of their critical ability to generate, from a renewable source, zero-marginal carbon electricity – which is something that storage, on its own, cannot do.
- 5.11.35 The size of the import connection secured by connection agreement with National Grid at the point of connection is an important input into the maximum power capacity of the BESS proposed at a facility. Other physical parameters may limit specific elements of the scheme, including parameters which will have the effect of capping the energy capacity of the proposed BESS.
- 5.11.36 Given the need for flexible sources of generation to support the rollout of renewable generation capacities onto the NETS, it follows that where the deployment of storage facilities is acceptable in a planning sense, that the consent process does not impart any conflicting or arbitrary caps on either energy or power capacity of an installed storage facility. Developers may therefore approach consent in such a way that secures flexibility in design (by way of a 'Rochdale envelope' approach) to allow provision in the DCO for technological innovation and improvements that may be realised at the time of procurement and construction.
- 5.11.37 This will ensure that a scheme may be constructed to incorporate future and as yet unknown innovation, safety improvements and cost-efficiencies.

BESS provide Flexibility

- 5.11.38 BESS provides flexibility to the electricity systems because they are able to import power when national supply outstrips demand, and export power

when demand outstrips supply. BESS are also able to provide Ancillary (Balancing) Services.

- 5.11.39 Typically, BESS (as opposed to other forms of storage, e.g. pumped hydro, or in the future hydrogen) are used to balance supply and demand over short time periods (e.g. milliseconds to days). BESS may import energy at times of low demand (e.g. overnight) or high supply (e.g. the middle of a sunny day, or when wind generation is high) and release that energy when demand is high.
- 5.11.40 In the UK, demand currently tends to be higher in the morning (e.g. 07:00 to 09:00) and in the early evening e.g. 17:00 to 19:00) than it is at other times of the day, although it is conceivable that the daily shape of national demand will trend towards the daily shape of national supply through the implementation of smart meters, time of use tariffs, electric heating and transport needs in domestic and commercial properties.
- 5.11.41 Ancillary (Balancing) Services are procured by NGESO and under these contracts, operators respond to NGESO'S requests to import or export power. Ancillary (Balancing) services are important because supply of and demand for electricity must be matched at all times, and the electricity system needs to be kept in balance and within statutory control parameters. Ancillary (Balancing) Services are used by NGESO to do this.
- 5.11.42 Table 5-1 describes the potential contributions made by a storage asset as part of the Scheme to the GB electricity market. This includes the role of the storage asset in supporting the operation of the solar asset by directing energy from times when generation is in abundance to times when it is needed, and its ability to provide ancillary services which support the operation of the solar asset as part of a decarbonised GB electricity system. Further explanation of the associated nature of the storage development is included in the **Planning Statement [EN010152/APP/7.1]**.
- 5.11.43 Table 5-1 describes on each row, the different types of service, or commercial application, available to BESS. The second column provides an explanation of the service. The third column addresses the applicability of each service to either solar, storage or both (whether co-located or not).
- 5.11.44 The fourth column describes whether the service is an Ancillary Service, procured by NGESO for the proper functioning of the electricity system or has other purposes which help 'keep the lights on' but are not those services specifically described by the NIC as those which "*support renewables and maintain the security of the electricity system*" [Ref. 63, p6].
- 5.11.45 The fifth column describes whether in providing each Ancillary Service (as categorised in the fourth column), a co-located solar + BESS would import, export or both, power from/to the NETS.
- 5.11.46 BESS are needed to provide these services, because the assets which currently provide these services, being thermal (coal or CCGT plant), are either closing to reduce emissions associated with electricity generation to achieve net zero, or are expected to run less and less in the future as renewable energy grows, and the majority of these services can only be delivered by plant which are already operating.

- 5.11.47 Under an Ancillary (Balancing) Services contract, thermal plant would provide positive regulation (i.e. are ready to increase their output) by operating at a low level of power which can then be increased in very short order following instruction from National Grid ESO. Thermal assets which are already operating at higher levels of power are able to provide negative regulation (i.e. are ready to decrease their output) in a similar way by turning their output down following instruction from National Grid ESO.
- 5.11.48 BESS will be able to provide both upward and downward regulation by ensuring that they are entering their contracted period with a 50% State of Charge. This allows the BESS to import energy under instruction and store it until it is full (i.e. SoC reaches 100%), or export energy until it is empty (i.e. SoC reaches 0%).

Table 5-1: The potential contributions of a storage asset within the Scheme to the GB electricity market, including ancillary service provision [Author analysis]

Service	Explanation	Applicability	Service Type	Connection
Trading	Forward balancing of anticipated energy supply with energy demand	Solar assets generate energy. Storage helps by directing energy from when it is produced to when it is needed. Storage can be co-located with solar assets, or developed independently.	Other	
Balancing Mechanism	Being available to NGESO to balance supply and demand at delivery	Solar will provide downward flexibility, if needed, but at the 'cost' of low-carbon energy unless that energy is instead stored. Co-located RES and storage can provide both upward and downward flexibility, and operating storage in support of a RES asset avoids the loss of any low-carbon energy generated by that asset. Stored energy can be dispatched over milliseconds to days, depending on technology and need.	Other	
Frequency Response / Dynamic Services	Changing output over seconds / minutes to help maintain national system frequency at the statutory level of 50Hz		Ancillary	Both
Reserve Operation	Changing output over minutes / hours to re-balance supply and demand following a fault or other event on the electricity system			
Reactive Power	Locational service which supports the 'flow' of power from source to destination	A mandatory service for all transmission-connected assets, delivered by solar, other RES and storage assets	Ancillary	Export
Inertia	Helps to slow the rate of change of the electricity system in response to an unforeseen event, stopping faults from escalating	Solar inverters are able to provide synthetic inertia. Storage also provides synthetic inertia	Ancillary	Both
Black Start	A locational service which would help 'turn back on	Solar is unlikely to provide Black Start on a stand-alone basis. Stand-	Ancillary	Both

Service	Explanation	Applicability	Service Type	Connection
	the lights' if the national electricity system failed	alone storage may be capable of providing limited Black Start support. A co-located asset is likely to be able to be more useful.		
Constraint Management	Changing output in response to local energy supply, demand and transmission conditions, to ensure locational adequacy at all timescales	Solar can provide downward constraint management services. Co-locating solar and storage can allow for the provision of upward and downward constraint services	Ancillary	Both
Infrastructure	By connecting generation assets where they are needed and where infrastructure already exists, less new electricity transmission and distribution infrastructure needs to be delivered	RES and storage can help with reducing new infrastructure requirements, and sharing connection points by co-locating assets means that, ultimately, less connection points will be needed	Other	

5.11.49 Table 5-1 shows how the provision of many services requires both an import and an export connection, which allows for the upward and downward regulation as previously described.

5.11.50 Not all grid connections have available import capacity, so it follows that where export and import capacity is available at a particular grid connection point, BESS should be considered and assessed. If those available connections are not used, it is possible that storage will not be able to come forward to the capacity and timings required to support the full integration of low carbon power into the UK electricity system because new connection points will be needed to connect the scale of storage foreseen as necessary by NGENSO.

5.11.51 A co-located BESS is foreseen to undertake the following five types of operation during its operational life:

- a. Importing from the co-located solar facility when local solar generation is high but national generation is higher than national demand;
- b. Exporting to the grid when co-located solar generation is low but national demand is higher than national generation;
- c. Importing from the grid when national demand is low but national generation is high;
- d. Exporting to the grid when national generation is low but national demand is high; and
- e. Importing or exporting from the grid under an Ancillary (Balancing) Service contract instruction from NGENSO.

5.11.52 BESS will operate in the electricity market in response to a market need. Market need manifests as a differential in market price at different times, driving the BESS to import or export accordingly. A greater market need will drive a greater price differential. Electricity is bought and sold ahead of time (based on operational forecasts of supply and demand, see following) and also by NGENSO much closer to (or at) delivery. Buying or selling ahead of time is called trading and commitments are then delivered through BESS operations, as is illustrated in the following. Any other operation at delivery will be under an Ancillary (Balancing) Services contract arrangement.

BESS Operational Parameters

5.11.53 Two important operational parameters which describe the size of a BESS are its power capacity and its energy capacity. It has already been stated that the size of the import connection secured by connection agreement with National Grid at the point of connection is an important input into the maximum power capacity of the BESS proposed at a facility.

5.11.54 The following examples describe how the operational parameters for the size of the BESS are related to each other, using as an illustration, a 100MW, 200MWh lithium ion system.

5.11.55 Power capacity is measured in megawatts (MW) and describes the maximum instantaneous level of power export or import achievable by the BESS. This is analogous to the power capacity of a conventional generator.

- 5.11.56 Energy capacity describes how much energy the BESS can store. Energy equals power multiplied by time. Energy capacity is measured in megawatt hours (MWh) and can be described as MWh, simply hours, or by a C-rate.
- 5.11.57 For clarity, energy capacity does not relate to how long energy can be stored for (elapsed time between charge and discharge) although different technologies may have different technical or commercial factors which provide a practical limit to that elapsed time.
- 5.11.58 A BESS with 100MW power capacity would, at any specific moment, be able to import, or export (not both at the same time) up to 100MW of electrical power.
- 5.11.59 If that BESS was able to store enough energy to export at full capacity for one hour, it would have an energy capacity of 100MWh (100MW x 1h).
- 5.11.60 A BESS with two hours of energy capacity would be able to store 200MWh (100MW x 2h). This energy could be exported to grid at its maximum power rate (100MW) for two hours.
- 5.11.61 Once fully depleted (i.e. all stored energy has been exported from the BESS), the BESS would take two hours at full import power rate (also 100MW) to reach a full state of charge. The state of charge (SoC) can be measured as an absolute number (e.g. when full, the state of charge in this example would be 200MWh) or as a percentage of the energy capacity of the BESS (e.g. when full, the state of charge would be 100%).
- 5.11.62 The battery C-rate describes the ratio of the power capacity and energy capacity, and the C-rate is the inverse of the number of hours required fully to charge the BESS from empty to full. This example describes a 0.5C BESS which takes at least two hours to discharge all of its energy from full (100% SoC) to empty (0% SoC).
- 5.11.63 In reality, BESS are not normally operated across the full 0% - 100% range of state of charge, instead cycling across 80% to 90% of that range (i.e. from c.10% SoC to c.90% SoC) to preserve battery cell life. Neither are BESS 100% efficient, and a Round Trip Efficiency (RTE) measure describes the percentage of energy which has been imported to the BESS is then available for export. A current typical RTE value is 88%.
- 5.11.64 **Section 6.9** of this Statement shows how a co-located Solar and BESS scheme may operate and how the BESS may support the solar facility as well as fulfil additional functions to support high-RES electricity system operation in the UK energy market. In the examples given in that section, to simplify the explanation given on how BESS may operate, both round trip efficiency and the operational range of state of charge have been ignored.
- 5.11.65 **Section 9.2** of this Statement describes the commercial operation of the UK's electricity market and how changing levels of forecast supply and demand may affect electricity price. In summary, if over some future period of time, the national supply of electricity is expected to be higher than the national demand for electricity, then market price will be low. If national demand is forecast to be higher than supply over a different period of time, then market price will be higher.

- 5.11.66 A BESS which imports during lower price periods and exports that power during higher price periods will therefore help balance supply and demand in both periods.
- 5.11.67 Once charged, a lithium-ion BESS is able to hold its charge without significant depletion (charge leakage) for a period of at least days, meaning that BESS are able to import energy one day and export it the next.
- 5.11.68 In practice, however, lithium-ion BESS are anticipated to provide short term balancing and electricity market operations and the long-term storage of imported energy in the BESS is not currently foreseen as a normal mode of operation for any lithium-ion BESS co-located with a solar facility.
- 5.11.69 Evidence on possible modes of operation of a co-located solar and BESS scheme are included at **Section 6.9**.

5.12 Conclusions on Future Energy Supplies

- 5.12.1 This Statement of Need aligns with NPS EN-1 and concludes that many low-carbon generating technologies are urgently needed to meet the government's energy objectives by:
- Providing security of supply;
 - Providing an affordable, reliable system (through the deployment of technologies with complementary characteristics); and
 - Ensuring the system is net zero consistent.
- 5.12.2 This Statement of Need describes progress made in the development of as yet unproven, unconsented or unfunded schemes or schemes with long or as yet unproven development timelines.
- 5.12.3 Yet, to address the ongoing climate emergency, it is critical that the UK urgently develops a large capacity of low carbon generation.
- 5.12.4 The evidence shows that there are many significant uncertainties associated with the development of such schemes, particularly in relation to the timeframes in which material contributions to decarbonisation and security of supply must be made. Put plainly, such schemes cannot yet be relied upon to contribute to the delivery of net zero and many simply will not be ready to contribute in a meaningful way to decarbonisation before the 2030s. The importance of achieving meaningful progress in decarbonisation during the 2020s is described in **Section 5.3**.
- 5.12.5 The evidence therefore points to the development of proven technologies such as large scale solar as necessary to mitigate against the potential for non-delivery of other technologies. Such schemes should be brought forwards with urgency to make tangible and essential advances in decarbonisation in the near term.
- 5.12.6 The government's current policy of developing market-led frameworks to support the development of low-carbon generation from diverse sources of energy remains important. Such schemes have the potential to complement the UK's growing renewable generation capacity to bring decarbonisation and security of supply benefits forwards before 2030 and beyond into the next decade.

- 5.12.7 Solar power generation has global momentum, and large-scale schemes are already being developed in GB. Solar is a proven technology. It is already delivering as part of the UK's electricity system and will continue to deliver further critical benefits to consumers through the urgent and continued decarbonisation, security of supply and affordability.
- 5.12.8 The IPCC has stressed the importance of urgent action to decarbonise electricity generation, and the CCC have reported that the UK needs to commission more low-carbon generation, and more quickly, to meet its net zero obligations.
- 5.12.9 The prompt development and deployment of proven technologies, such as solar, is a lower-risk pathway for delivering low-carbon generation both now and for the longer term, than waiting for technologies which may not deliver.
- 5.12.10 This is consistent with the approach described in NPS EN-1 which articulates the prudence of planning infrastructure development on a conservative basis, including for scenarios in which the future use of hydrogen is limited. [Ref. 1, Para 3.3.10]
- 5.12.11 Solar generation is needed in the UK to keep the country on course in its fight against climate change because it is a beneficial, fundable and deliverable technology.
- 5.12.12 Flexibility of supply is also necessary to maximise the use of renewables when there is an abundance of generation, and to fill the supply gaps in periods of shortfall. Storage capacity is needed to increase to support renewable electricity generation capacity growth. The Scheme seeks to bring forwards co-located storage facilities as Associated Development to the main (renewable generation) development.
- 5.12.13 The Scheme should therefore be recognised for the critical contribution it will make to the UK's journey to a net zero and secure energy system.
- 5.12.14 Consenting the Scheme, such that it will be able to be constructed and operated as intended, will bring the UK closer to its required track through to meet its legally binding carbon emissions reduction targets. The delivery timing associated with current forward nuclear and CCUS projections strengthen this conclusion.
- 5.12.15 It is vital that the development of low-carbon generation capacity occurs urgently in the near-term and also on an ongoing basis to facilitate wider necessary decarbonisation actions. It is important that schemes with long development timescales continue progressing their plans to achieve or sustain carbon reductions in decades to come.
- 5.12.16 Developments with the proven ability to achieve carbon savings comfortably within the next decade are essential to keep the UK on its legally binding carbon reduction path.
- 5.12.17 An actual, potential or aspirational pipeline for longer term low-carbon generation schemes presents additional opportunity for future decarbonisation. However, the presence of such a pipeline cannot legitimately be used as an argument against the consent and development of a scheme proposing to use proven technology and short development timescales, thereby delivering dependable decarbonisation benefits.

5.12.18 The Scheme is a viable proposal, which currently is planned to deliver in the early 2030s. It will achieve significant carbon reduction benefits through the deployment of a proven, low-cost technology at a very suitable grid connection. As such, the Scheme possesses exactly those attributes identified as being required both in the near-term and in the future in order to continue to make material carbon reductions in the UK electricity sector.

6. Technical Considerations For UK Solar Schemes

6.1 Chapter Overview

6.1.1 This chapter provides an overview of the characteristics of solar power and the delivery of large-scale projects.

6.2 Large-scale and small-scale generators

6.2.1 Generation assets can be 'centralised' (connecting to the NETS) or 'decentralised' (connecting to the distribution networks or 'behind the meter' in consumer premises).

6.2.2 Electricity transmission networks operate at high voltages. High voltage operation reduces transmission losses and makes the bulk flow of energy over longer distances more efficient. Distribution networks operate at a lower voltage than the transmission networks, and are located closer to points of final demand. A lower voltage connection means that Generators which connect to distribution systems must be of a smaller capacity than those which connect to the NETS. Therefore, to connect the same total capacity of generators, more connections would be required at the distribution network level (at a potentially greater overall cost to consumers) than would be required directly into the NETS.

6.2.3 The NETS was designed to allow for the connection of large generating assets, but distribution networks were originally designed to transmit power to consumers. Distribution networks were not designed to connect significant capacities of electricity generation. Connecting generation assets of any meaningful size to distribution systems is becoming more difficult and more expensive (ultimately to the bill-payer). The Connections Action Plan includes an example of how distribution network constraints cause a significant delay to the installation of rooftop solar for an industrial consumer [Ref. 16, p79]. It is therefore not the case that the connection of renewable generation to the distribution networks is either quick, or cheap.

6.2.4 By virtue of their role in transferring power from the bulk NETS to businesses, built facilities and houses, many distribution networks are in built up areas, away from areas of large natural resource potential. Geographical and technical constraints may therefore arise as generators continue to be connected to these networks, applying upward pressure to the costs and durations required to grant a connection agreement. This may materialise as significant cost, timing, and complexity considerations both for asset developers as well as for consumers who ultimately pay for the developments and the operation of the complex distribution systems which result.

6.2.5 However, in 2023 31% of all generation capacity was connected to the distribution networks. FES net zero pathways project that the proportion may decrease up to 2030, but may increase in some net zero pathways by 2050, up to 35% [Ref. 19(2024), Figure ES.07].

- 6.2.6 The proportion of generation capacity in 2050 connected to the distribution networks in the 2020s has decreased year-on-year in NGENSO's analyses since the net zero by 2050 commitment was made.
- 6.2.7 This reflects the increased and urgent need for renewable generation capacity to come forwards, but with increasing complexity associated with connecting generation to distribution networks. An ongoing programme of work is seeking to increase the capacity of the NETS in as affordable a way as possible [Ref. 65].
- 6.2.8 In their election manifesto, the government stated that *"Local power generation is an essential part of the energy mix and reduces pressures on the transmission grid"* [Ref. 31, p54]. Although the total capacity of generators connected to distribution systems is expected to grow, the total capacity of generators connected to transmission systems is also expected to grow.
- 6.2.9 FES 2024 net zero pathways triple the capacity of generation connected to the transmission network (2050 vs. 2023 capacity) to a total of 238.5 – 247.5GW. The capacity of generation connected to distribution networks is projected to increase by a factor of approximately 3.3 (2050 vs. 2023 capacity) but to a smaller total of 95.1 – 131.4GW [Ref. 19(2024), Figure ES.07].
- 6.2.10 A wholesale decentralisation of the UK's electricity system is not expected to occur in the next 30+ years, if at all, and even in the most consumer-led scenario, the share of generation capacity connected to distribution networks is anticipated to rise to only 35%.
- 6.2.11 Decentralisation is not in itself a strategy or a requirement of the energy system but is a trend which will go some way to delivering a flexible, low-carbon and affordable energy system. Distributed generation will contribute to meeting carbon emissions targets and improving energy security.
- 6.2.12 While it is right to encourage local generation capacity growth, local generation alone will not replace the need for new large-scale electricity infrastructure to meet UK energy objectives (see **Section 3.3** of this Statement).
- 6.2.13 Operating a mainly national electricity system (as current) will likely be more affordable than operating multiple distribution systems, connected by a 'light' transmission system.
- 6.2.14 By connecting more decentralised assets to distribution networks, less power will flow on the NETS and its unit cost of operation, which must be passed to consumers, will increase.
- 6.2.15 However, to ensure local as well as national adequacy of supply, the connection of more assets to distribution systems would also require either investment power transfer capability between each separate distribution system and the NETS, or a greater capacity of local low-carbon generation on each distribution system to manage local peak power security of supply.
- 6.2.16 In contrast, a system with a high proportion of transmission-connected assets would offer *"a number of economic and other benefits, such as more efficient bulk transfer of power and enabling surplus generation capacity in one area to be used to cover shortfalls elsewhere."* [Ref. 1, Para 3.3.12].

- 6.2.17 Further, to accommodate more decentralised generation capacity, more investment will be required to reinforce distribution networks and provide more connection capacity.
- 6.2.18 Operating a primarily decentralised electricity system in the UK would also likely be significantly more complex than operating today's primarily centralised system.
- 6.2.19 Electricity consumers, either directly or indirectly, through their energy bills, pay for all costs related to both transmission and distribution systems, including market inefficiencies, economic decision making, asset investments, balancing actions and transmission and distribution system enhancements. Energy bills will rise if existing assets are underutilised and/or reinforcements are required on other systems.
- 6.2.20 The NETS remains an important measure to maintain interregional connectedness, support the meeting of national peak demand "*reliably in all areas*" from geographically disparate sources whatever the weather [Ref. 23, p182] and keep power flowing to consumers with the high levels of reliability consumers have come to expect.
- 6.2.21 The Applicant has accepted a Connection Offer from National Grid to connect the Scheme to the NETS at an existing National Grid substation at Thorpe Marsh. The Connection Offer provides for the import and export of up to 237.5MW of power, connecting in 2032. Further information on grid connection for the Scheme can be found in the **Grid Connection Statement [EN010152/APP/7.5]**.

6.3 Large-Scale, Brownfield and Rooftop Solar

- 6.3.1 Decentralised solar may be installed on domestic or commercial rooftops or on brownfield land. In relation to brownfield locations, some may be suitable for solar deployment, but others will not.
- 6.3.2 Many decentralised sites may be unable to source a cost-effective and timely grid connection to support a stand-alone solar site. Distribution networks, which by 2023 were already straining with 36GW of distributed generation [Ref. 19(2024), Table ES.07], may also not be able to distribute the energy generated from new generators, even if connection points are found close to potential sites.
- 6.3.3 Many sites may simply not be suitable. They may be in areas of low solar irradiation, have unfavourable topography or be too small to develop in a cost-effective manner. Others may have remediation issues which render sites unavailable for solar development given potential costs or liabilities associated with cleaning up after prior activities.
- 6.3.4 In relation to roof space, larger commercial structures or buildings with shared roof space may have contractual issues relating to ownership, occupation and upkeep which must be resolved prior to any solar development, or may not be resolvable in a timely and efficient way. Any roof space sloping to the north will be unsuitable for solar panels. Smaller buildings, listed buildings or those with period features are also unlikely to be suitable.

- 6.3.5 Other locations may be suitable from an engineering perspective but may be overshadowed by nearby taller structures or natural features which could significantly impact irradiation and output, and therefore yield and benefit. Shaded homes in built up areas may be a prime example.
- 6.3.6 Other roof space may need to be reinforced to accommodate the additional loading associated with solar infrastructure, all of which will add to installation costs for homes and businesses.
- 6.3.7 **Section 9.3** provides more information on the economics of solar power, and demonstrates that it is already among the cheapest forms of generation over its lifetime. However, the installation costs of small scale solar are significantly higher than that of large-scale solar on a £/kW (installed capacity) basis.
- 6.3.8 Very small installations, such as those on domestic roof spaces, may not be large enough to make solar installation viable once the ‘fixed’ costs of installation (e.g. design, scaffolding, cabling and commissioning) have been accounted for. This is important because it is for bill payers to pay for the installation of small-scale generation at their properties, and installation costs for small-scale solar have increased both on an absolute scale and in relation to governmental estimates for the installation costs of large scale solar.
- 6.3.9 Figure 6-1 following shows cost information relating to the installation of domestic solar panels from the government’s Microgeneration Certification Scheme (MCS) [Ref. 66], benchmarked against the capital cost range for small scale (domestic) solar PV and large-sale solar from the government’s Cost of Electricity Generation report [Ref. 67(2023)]. Capital cost includes development, construction and infrastructure costs where appropriate.
- 6.3.10 The data shows that small scale solar (red area) to be two to four times more expensive to install than large scale solar (green area). During the period 2019 to 2021 inclusive, MCS data shows that actual installation costs were comfortably within the governmental estimated range, however in mid-2022, installation costs rose to above the top of that range.
- 6.3.11 The reported installation cost for small schemes started to reduce again from a high in early 2023, back towards government’s range, but it remains significantly higher than the governmental range for large-scale solar.
- 6.3.12 Many home or business owners may not have the capital reserves to pay for the installation of solar panels on their roof areas and others may not want them. Since the wind-down of the Feed in Tariff scheme, which was introduced on 1st April 2010 but closed to new applicants from 1st April 2019, previous governments have been silent on measures to support domestic and small commercial solar installations, other than the removal of VAT from installation costs.
- 6.3.13 The implication of these factors is that the real potential for decentralised solar in the UK is likely to be much lower than any gross potential identified when the suitability, availability, practicality and economics of such developments are taken into account.




Figure 6-1: Reported and estimated small-scale and large-scale solar capital costs (£/kW) [Ref. 66, Ref. 67]

- 6.3.14 Further, the installation of many thousands of separate systems is likely to take longer than the installation of a smaller number of ground-mount systems to achieve the same capacity. This is an important point in relation to the required urgency for solar generation.
- 6.3.15 Data from the government’s MCS scheme shows that the rate of small-scale installations increased near the end of 2022. The average installation rate from October 2022 to July 2024 inclusive, was 75MW per month. The average installation rate from January 2019 to September 2022 was just 23MW per month [Ref. 66, Author Analysis].
- 6.3.16 For the previous government’s target of 70GW of operational solar by 2035 to be achieved by microgeneration schemes alone, installation rates would need to increase by a factor of more than six, from the already record current installation rates. This increase would need to start immediately and be maintained throughout the next 11 years.
- 6.3.17 To meet the government’s ambition of a tripling of solar by 2030, from microgeneration alone, installation rates would need to reach and sustain an even higher level.
- 6.3.18 It is the Applicant’s view that this is not a credible projection and therefore large-scale solar schemes are also required in the fight against net zero.
- 6.3.19 Decentralised generation has an important role to play in decarbonisation, however on its own, smaller scale solar, including rooftop solar, is not likely to deliver a sufficient total capacity at the required pace and at an affordable cost to meet the government’s targets.
- 6.3.20 This information shows that smaller scale solar, including rooftop solar, must be considered as additional to, as opposed to instead of, the need for large-scale solar.

6.4 Site selection for large-scale solar

- 6.4.1 Site selection is a critical step in the delivery of projects with aims of meeting the UK national need for sufficient low-carbon, low-cost energy supplies to support legal decarbonisation targets and national energy security requirements. This section sets out, in generic terms, the assessment process for sites for large-scale solar generation in the UK.
- 6.4.2 Suitable sites will be:
- a. Capable of delivering to the required scale (in relation to the need for the scheme);
 - b. Technically and environmentally feasible within the stated timeframes; and
 - c. Commercially attractive to the developer.
- 6.4.3 Site selection utilises a screening approach which considers possible alternative sites, taking into account the three requirements listed above. In addition, the screening approach recognises the required urgency of low-carbon development in the UK and therefore, is an approach which is consistent with guidance contained in NPS EN-1, applies a principle of proportionality to options which are vague or immature, [Ref. 1, Paras 4.3.28], especially where those considerations are critical for the viability of the project, on the grounds that they are not important and relevant to the Secretary of State's decision. The screening process will prioritise options which are more likely to be able to meet the intended aims of the project, over options which are less likely to proceed due to technical, commercial or other reasons.
- 6.4.4 Solar developments require three fundamental technical attributes, and these therefore drive the initial screening process. These attributes (which are consistent with NPS EN-3 [Ref. 2, Paras 2.10.18-48]) are:
- a. The existence and availability of sufficient land to deliver to the project to meet the scale set out in the scheme's aims;
 - b. The availability of a suitably placed point of connection to the NETS and/or local Distribution Network; and
 - c. Solar irradiation levels which support the potential for the development to produce an energy yield which is both useful and economic.
- 6.4.5 Other attributes will also apply later into the screening process, for example those environmental attributes described in NPS EN-3 Paras 2.10.27 to 2.10.48 and the potential for environmental impacts as described in NPS EN-3 Paras 2.10.73 to 1.10.126. However, a site which does not possess all three fundamental attributes is less likely to be a suitable location for large-scale solar generation than a site which does possess these attributes.
- 6.4.6 Further information on site selection for the Scheme can be found in **ES Volume I, Chapter 3 Alternatives and Design evolution [EN010152/APP/6.1]**.
- 6.4.7 The UK's approach to the energy sector provides that *"It is for industry to propose new energy infrastructure projects that they assess to be viable within the strategic framework set by government"* [Ref. 1, Para 3.2.3]. It is

- important therefore to acknowledge that an individual developer's approach to screening may not be rigid and inflexible but instead may be sensitive to local variability and indeed developer approach. Developers may therefore weigh the importance of one or more criteria in their screening approach differently for different schemes to accommodate and incorporate the needs and benefits of different geographies and local characteristics.
- 6.4.8 The site selection process also considers other factors which will not be a simple pass/fail for taking forward a site for development, but sites which are environmentally, technically, operationally and commercially suitable will likely score favourably on a majority of important characteristics.
- 6.4.9 For example, adjoining land parcels may be both suitable and available for development, resulting in an increased density of solar deployment and an environmental footprint over a more focussed area of the countryside. Other proposals may consider separate land parcels which do not border each other but instead combine to an integrated scheme which is more dispersed within a countryside setting.
- 6.4.10 Further, the connection of separate parcels of suitable land together into a single scheme may, subject to analysis, enable those parcels of land to connect economically to the electricity system, whereas if developed as stand-alone schemes they may not be able to carry the associated costs of connection and therefore may never be developed.
- 6.4.11 Large-scale solar schemes, because of their scale and the area of land required for their development, are more likely to be sited in more rural areas of the country. In order to enhance the energy delivered from the installed capacity, schemes are also more likely to be sited in areas of higher solar irradiation levels.
- 6.4.12 Figure 6-2 is a map of PV power potential in the UK. Areas of higher irradiance are identified by colours towards the red end of the spectrum, while areas of lower irradiance are towards the blue end of the colour spectrum.
- 6.4.13 The government's Digest of UK Energy Statistics (DUKES) [Ref. 19, Table 6.2] shows that the installed capacity of solar generation in the UK rose above 10GW in 2016. Further, the average load factor of UK solar generation since that time has been 10.4% (min 9.9% in 2021, max 11.1% in 2018). A 10.4% load factor is equivalent to 910 kWh/Yr/kW(p), a value which corresponds to the boundary between the yellow to the right of 876kWh/Yr/kWp, and the darker yellow to the left of 949kWh/Yr/kWp on the scale shown in Figure 6-2.
- 6.4.14 Early experience in panel efficiency, system efficiency, site layout and scale effects may mean that the load factor of existing solar in the UK is not as high as it would be if all existing solar facilities were re-powered with panels of a current specification and technical performance. However, from Figure 6-2 it can be seen that any solar facility developed to the east of a line between Aberdeen to Manchester, and south of Manchester, could be expected to experience a higher load factor than the current UK average.
- 6.4.15 However, there may be reasons that developers bring forward schemes for consent which lie to the north and the west of those lines as they may also be beneficial to decarbonisation and energy security aims.

- 6.4.16 Large-scale solar schemes are expected to connect to the NETS. The NETS is an existing national infrastructure asset which is designed specifically for the bulk transmission of energy from its point of generation to nationwide consumers.
- 6.4.17 NPS EN-3 states that:
- “The capacity of the local grid network to accept the likely output from a proposed solar farm is critical to the technical and commercial feasibility of a development proposal.”* [Ref. 2, Para 2.10.22].
- “Larger developments may seek connection to the transmission network if there is available network capacity and/or supportive infrastructure”* [Ref. 2, Para 2.10.23].
- “To maximise existing grid infrastructure, minimise disruption to existing local community infrastructure or biodiversity and reduce overall costs applicants may choose a site based on nearby available grid export capacity.”* [Ref. 2, Para 2.10.25]
- 6.4.18 To enhance the overall benefit of the scheme in terms of environmental impact, efficiency and timeframes for connection, schemes may elect to make use of existing and available points of connection to the NETS insofar as such connection points exist, in preference to building new connections or increasing the available connection capacity at existing locations.
- 6.4.19 However, this is not always possible and new substations will be needed to facilitate the connection of schemes which are not located near existing substations. This is a similar development to that which has already occurred for offshore wind.
- 6.4.20 The Applicant has accepted a Connection Offer from National Grid to connect the Scheme to the NETS at the existing National Grid 400kV substation at Thorpe Marsh. The Connection Offer provides for the export of up to 237.5MW of power, connecting in 2032.
- 6.4.21 Further information on grid connection for the Scheme can be found in the **Grid Connection Statement [EN010152/APP/7.5]**.
- 6.4.22 Figure 6-3 following shows data from NGET’s online ‘ConnectNow Research Assistant’ [Ref. 69]. The tool is a useful but sombre reflection of the challenge faced by the UK to bring new large-scale generation developments online in timelines which will support the urgent need for decarbonisation and energy security in the UK.
- 6.4.23 Each numbered circle on the map shows the number of connection points in that broad geography, and the colour represents NGET’s view (current at the time of download of the map) of when a new connection might be achieved at each of those locations. The map shows that connecting any new assets (i.e. those which have not already secured a connection agreement with NGESO) to the National Electricity Transmission System before 2032, is not currently possible.
- 6.4.24 The UK will therefore need largely to look to those schemes which already have connection agreements to deliver the low-carbon capacity required to support the delivery of net zero and energy security aims until the mid-2030s.

6.4.25 It is important to recognise therefore, and as evidenced by the data shown in Figure 6-3, that connection to the electricity network, which is an essential element of project development, is currently a constraint to many schemes which are coming forwards.




Figure 6-2: United Kingdom solar irradiation [Ref. 68]

6.4.26 This issue has also been acknowledged by Ofgem who in May 2023 issued an open letter launching a policy review on reforming the electricity connections system [Ref. 70], by NGENSO who are now working with the industry to undertake a review of the connections queue [Ref. 71], and by the then government which published, in November 2023, a Connections

Action Plan which explains these sets of actions and how together they will work towards delivering quicker connections for low-carbon generation assets [Ref. 16].

- 6.4.27 The importance of utilising existing and available infrastructure to meet the urgent need for new large-scale solar generation is starkly clear.
- 6.4.28 Further, in light of the urgent need to decarbonise the electricity system and the current lack of available connection points for low-carbon generation assets, developers may make use of different ways of maximising the generation potential from available and accessible land resource through any limited yet available grid connection capacity the project has secured.
- 6.4.29 Great Britain's energy transition to date has been characterised by the decommissioning of (primarily) coal fired power stations and the development of new renewable power plants. When power stations decommission, they leave behind the infrastructure used to connect them to the grid.
- 6.4.30 In light of the grid connection constraints identified above, the re-purposing of existing but unused infrastructure is an incredibly important strategy to help bring renewable power online in the timeframes required to support decarbonisation and security of supply.




Figure 6-3: Transmission system connection points and potential connection dates [Ref. 69]

- 6.4.31 Existing substations and existing transmission cables with spare transmission capacity, are therefore incredibly important because they

provide the opportunity to repurpose existing, therefore largely sunk-cost, infrastructure to connect new schemes to the NETS earlier than would be possible at entirely new connections.

- 6.4.32 Large scale solar schemes must connect to the grid via high voltage electrical cables. Locating solar schemes close to grid connection points will reduce electrical losses (which rise in proportion to cable length) and may also result in a scheme with a lower environmental footprint than a scheme located further away from the point of connection, which would have longer cable routes.
- 6.4.33 The location and capacity of an available point of grid connection is therefore a firm guide for selecting sites for large-scale solar schemes. However, due to the finite number of existing substations – and the smaller number of those substations with available capacity, it is also anticipated that:
- a. New grid substations may be needed to connect the anticipated capacity of solar required to meet net zero; and
 - b. Sites may be located at greater distances from existing grid substations than previous developments.
- 6.4.34 The number of locations in the UK which satisfy all three core site selection requirements (land availability and suitability, feasible irradiation levels and grid connection availability) is limited. For example, high population density and a large extent of designated land limits opportunities for large-scale solar development in the south east of England (where Figure 6-2 shows that irradiation is highest), and the need for proximity to existing and available grid connection capacity limits opportunities in the South West and East Anglia (where Figure 6-2 shows that irradiation is also high).
- 6.4.35 It should therefore not be expected that large-scale solar is located only where irradiation is highest in GB; nor only where suitable land is available; nor only in close proximity to existing grid substations with available capacity. Developments will be proposed in locations with the blend of characteristics which is assessed as suitable for each scheme, and each scheme may have unique features which are particular to its proposed location.
- 6.4.36 Further evidence supporting the suitability of the Scheme is included in **Chapter 7**.

6.5 Technology Selection / Orientation

- 6.5.1 NPS EN-3 provides guidance that, along with associated infrastructure, a solar farm requires between 2 to 4 acres for each MW of output [Ref. 2, Paragraph 2.10.17].
- 6.5.2 There are currently three main configurations of solar panel used in the UK, each has different physical and operational characteristics:
- 6.5.3 Fixed South Facing (FSF) panels are installed in rows stretching from east to west, with the receiver side of the panel facing south. The panels will be fixed on frames at an angle to the ground (dependent on latitude and ground slope) which will have been optimised prior to installation.
- 6.5.4 Single Axis Trackers (SAT) are installed in rows stretching from north to south. A single table of panels rotates about the north-south axis so that the

- panel is perpendicular to the incident irradiation from the sun for as long as possible.
- 6.5.5 East-West (E-W) panels are installed in rows stretching from north to south, with panels facing both east and west and an apex between them. As with FSF, the panels will be fixed on frames at a set (immovable) angle to the ground.
- 6.5.6 Panels may be orientated vertically (portrait) or horizontally (landscape) and may be mounted with one or more above (or next to) the first.
- 6.5.7 Different configurations have different benefits and disbenefits, and some configurations may be better suited to some locations than others.
- 6.5.8 As the sun tracks in the sky, both throughout each day and throughout the year, the inbound irradiation on the panels will vary and frames, axes and panels will be oriented to best optimise irradiation at that location, for that configuration, across the year.
- 6.5.9 A characteristic which is common to all three configurations is the potential for there to be a shadowing effect of one panel on another panel from time to time. Site designers will seek to optimise output given the specific location, the available land, and a known grid connection capacity and this will include reducing panel-on-panel shadowing effects where possible.
- 6.5.10 Latitude will impact on the effects of shadowing and site-specific mitigations for all layouts, but especially so for FSF schemes. At higher latitudes, rows of FSF panels may be spaced further apart to reduce shadowing effects, while at lower latitudes spacing may not be as large. This is because the sun tracks lower in the sky when seen from higher latitude locations, casting longer shadows.
- 6.5.11 Spacing FSF panels further apart increases the ratio of acres / MW for the installation, but also increases the expected generation from each of the panels and therefore increases the ratio of energy generated over capacity installed (MWh / MW(p) / Year) for the scheme.
- 6.5.12 A similar analysis can be carried out for SAT and E-W configurations, however it should be noted that generally:
- a. SAT requires more land per MW(p) but has the potential to generate more MWh/MW(p) than FSF; and
 - b. FSF requires more land per MW(p) but has the potential to generation more MWh/MW(p) than E-W.
- 6.5.13 Other local characteristics such as location and land topography may determine which configuration or combination of configurations delivers the greatest benefit in terms of annual MWh generation from a Scheme while considering the land area used, cost of installation and ongoing cost of operation and maintenance of specific developments.
- 6.5.14 **ES, Volume I, Chapter 3 Alternatives and Design Evolution [EN010152/APP/6.1]** describes that the Applicant is bringing forward a scheme which uses FSF orientation, because FSF is more space-efficient at this Solar PV Site than E-W or SAT, thereby enabling the Scheme to make the best use of the grid connection. The Applicant is also seeking to maintain flexibility at the detailed design stage, to design a scheme which delivers the

greatest possible benefit over its operational lifetime, while respecting any local and environmental constraints.

6.6 Overplanting

What is overplanting?

6.6.1 NPS EN-3 describes 'Overplanting' as

"The situation in which the installed generating capacity or nameplate capacity of the facility is larger than the generator's grid connection" [Ref. 2, Para 2.10.55, Footnote 92].

6.6.2 NPS EN-3 also sets out that reasonable overplanting at a scheme should be considered as acceptable in a planning context as long as it can be justified and its impacts have been assessed through the planning process on the basis of the full extent of the scheme including any overplanting [Ref. 2, Para 2.10.55, Footnote 92].

6.6.3 By selecting sites with the right blend of characteristics, developers will bring to commercial operation, solar schemes which deliver decarbonisation, security of supply and affordability benefits.

6.6.4 An important consideration for developers is maximising the utilisation of the available grid connection capacity through the life of the scheme because schemes with greater lifetime outputs deliver greater decarbonisation and security of supply benefits and should also be more affordable. Location-specific commercial and environmental constraints also need to be respected in order for schemes to be consentable and financially rational.

6.6.5 Solar panels degrade as they age, and as they do they may produce less energy year-on-year for the same irradiation levels. Degradation is caused by physical processes relating to weather effects including the effects of light on the panels over time. Overplanting provides an opportunity to increase the quantity of valuable low-carbon, zero-marginal cost MWh of electricity transmitted from a solar scheme to the grid over its lifetime.

6.6.6 Overplanting is dependent on sufficient suitable land area to be available to the scheme for installing solar panels. Overplanting is commercially rational on all types of schemes subject to the availability and suitability of a sufficient area of land at the scheme to accommodate the overplanting.

6.6.7 Similarly, locations with sufficient local, available and suitable land but a capped grid connection capacity may seek to use that land by overplanting the scheme, thereby exporting more MWh to the grid over the life of the scheme.

6.6.8 However, there may be legitimate reasons why a particular developer, at a particular location, does not pursue an overplanting strategy for that scheme.

6.6.9 Further, overplanting is also commercially rational for both stand-alone schemes and schemes which include co-located storage facilities, although the optimum extent of overplanting at each type of scheme (i.e. with or without co-located storage) is likely to be different.

6.6.10 Indeed (and further subject to the availability of land and co-located storage technology chosen), different schemes may have different optimum overplanting strategies.

6.6.11 It is possible that, at the application stage, applicants may not be sufficiently informed to be able to lock in an *optimum* overplanting strategy. In these circumstances, at the detailed design phase (i.e. post consent) the developer must judge the appropriate trade-offs to make to deliver the optimum deliverable scheme at a specific location, subject to any conditions set out in the DCO. Some constraints may require judgement rather than pure quantitative analysis to resolve in an optimal way, and for that reason flexibility is often sought in DCO applications.

The benefits of overplanting

6.6.12 Overplanting increases the generation potential of a scheme through a fixed capacity network connection, especially when the effects of panel degradation are considered. But a balance is necessary. Overplanting implies that when irradiation is high and panels have not yet degraded, sites may be forced to self-curtail because, at those times, they will be generating more power than they are able to export. At these times, inverters will limit the amount of energy exported to the grid, and excess energy is lost. This is sometimes called *clipping*.

6.6.13 However, when irradiation is lower, such that panels are not generating to their maximum potential, it is clear that an overplanted scheme will generate more than a scheme which is not overplanted. This is because at those times output will not be limited by the grid connection capacity. This is illustrated in Figure 6-4 below.

6.6.14 The royal blue line in Figure 6-4 shows output (against the dark blue connection capacity line) of a unitary solar scheme on an average irradiation day (left hand graph) and a high irradiation day (right hand graph). Note that the term 'unitary' is here intended to describe any scheme where the total capacity of the panels installed (MW(p), in DC) equals the export capacity of the scheme (MW, in AC). The grey line on each graph shows the output of a solar scheme which is identical to the representative scheme, except that it has been overplanted (i.e. it has more panels, but no more grid capacity, than the unitary scheme).

6.6.15 On an average irradiation day, more energy is exported from the overplanted scheme than the unitary scheme and no energy is clipped.

6.6.16 However, on a high-irradiation day, more energy is exported each hour from the overplanted scheme until the grid capacity limit is reached. At this time, the overplanted scheme experiences clipping. The output from the overplanted scheme therefore 'flatlines' until lower incident irradiation causes the overall output of the scheme to reduce below the grid export limit again, and more energy is exported each hour from the overplanted scheme until the sun sets.

6.6.17 As solar panels degrade, clipped energy volumes will reduce. This is because the peak output from a degraded scheme is lower than the peak output from a scheme which has not yet degraded. Therefore, under the same irradiation conditions, the maximum generation from the degraded scheme would be lower than the maximum generation from the scheme before degradation occurred.

6.6.18 In time, the maximum achievable generation from the scheme may fall below the grid export limit. This case is illustrated by the light blue lines in Figure

6-4 which show overplanted schemes exporting more energy than unitary schemes and not incurring any clipping.

- 6.6.19 Schemes which are overplanted therefore generate more low-carbon electricity than unitary schemes. Overplanted schemes increase the utilisation of the available grid connection capacity throughout a scheme’s operational life. This is a key driver of enabling the transmission of as many MWh of energy onto the grid through the (limited) available grid connection resource as is possible, noting that, nationally, grid connection capacity is currently constrained and is projected to remain constrained over the coming decade.
- 6.6.20 Degradation of solar panels may mean that panels need to be replaced through the operational life of the scheme. Other than in instances of the premature failure of individual panels (which would likely be replaced under a warranted maintenance arrangement) panel replacement is likely to be guided by data gathered through monitoring panel performance throughout the life of the project. This may be carried out on a rolling or programmed basis subject to any parameters which defined the assessment of the scheme’s impacts on the environment.
- 6.6.21 The opportunity to overplant is driven by scheme-specific characteristics, such as available land area, cable access routes, grid connection capacity, panel orientation and local irradiation levels. Overplanting (or the level to which overplanting is proposed) also has commercial drivers and these may differ from scheme to scheme and between developers.
- 6.6.22 It is therefore expected that solar schemes will overplant where possible while balancing commercial, geographical and environmental considerations.
- 6.6.23 Developments which seek to make best use of available grid connection capacity will present as highly viable schemes and therefore will help to ensure that the need for large-scale solar generation can be fulfilled. This is an important and relevant factor in the decision-making process.




Figure 6-4: Illustrating clipped generation vs. optimised generation on overplanted solar schemes vs. unitary schemes [Author Analysis]

- 6.6.24 Given the constrained nature of available connections to the NETS, developers of solar schemes typically look for suitable locations close to existing and available grid connection points.
- 6.6.25 Further, schemes which maximise the generation and transmission of energy through the available connection will deliver a greater quantum of national climate change and energy security benefit through their operation, than schemes which deliver less energy to the grid.

- 6.6.26 Developers are therefore likely to aim to make greatest use of the existing and available grid connection at their contracted substation, by which it is meant to design a scheme which will export to the grid, the greatest volume of low-carbon energy over the lifetime of the scheme.
- 6.6.27 Overplanting supports developers in achieving this aim, but there are limits to the benefits of overplanting.

Limits to the net benefits of overplanting

- 6.6.28 Figure 6-5 and Figure 6-6 below show the results of an analysis of the average annual output of a solar scheme per MW installed (y-axis) as a function of the overplanting ratio (x-axis), for a Fixed South Facing (FSF – blue) scheme and a Single Axis Tracker (SAT – orange) layout.
- 6.6.29 These figures have been derived from inputs which are appropriate for UK-based solar schemes generally and therefore the conclusions following are also applicable across all schemes, excluding the impacts of location-specific parameters.
- 6.6.30 As the overplanting ratio of a scheme increases, clipped solar generation at times of high irradiation and early in the scheme's operational life increases. Those losses may be compensated for by greater output in times of lower irradiation and more generally later in operational life, as illustrated previously. The level of overplanting determines the overall balance between clipped generation during times of high irradiation, and incremental generation at times of lower irradiation.
- 6.6.31 Figure 6-5 below illustrates the average annual output of a scheme in terms of a Grid Utilisation metric (%) over the first 40 years of its operation.
- 6.6.32 Grid Utilisation is calculated as the total MWh exported through the grid connection during the life of the project, divided by the maximum MWh export possible through the connection during the life of the project, i.e. $[\text{grid connection capacity (MW)}] \times [\text{project life (years)}] \times 8760 \text{ (hours/year)}$.
- 6.6.33 The points on Figure 6-5 show the lifetime Grid Utilisation for schemes with an overplanting ratio of between 1.0 and 2.2, at regular increments under either an FSF (blue) or a SAT (orange) layout. Clearly an underplanted scheme (i.e. one in which the MW peak installed solar generation capacity is lower than the grid connection capacity), would deliver a lower 40-year average grid utilisation factor than that of a scheme which is planted at unity, or overplanted. Underplanted schemes therefore do not make the greatest use of the available connection capacity. Because connection capacity is nationally constrained, it is of vital importance that schemes which come forwards make the most of that contracted capacity.
- 6.6.34 The orange and blue dotted lines are straight lines of best fit through each 'curve' of points. These are for visual aid only, as they help the reader to assess the gradient of the curve which passes through each point, and where that gradient changes.
- 6.6.35 As the overplanting ratio increases, so too does Grid Utilisation. However, beyond an overplanting ratio of approximately 1.5 (where the coloured points are furthest above the same colour straight trend lines), the incremental benefit of overplanting on grid utilisation reduces (the points start to return back towards the straight line, and ultimately fall below it).

6.6.36 Figure 6-6 following shows that the average annual output of a scheme over the first 40 years of its operation on a MW(p) basis (installed panel capacity) decreases only when the overplanting ratio increases above a certain level.




Figure 6-5: Grid Utilisation increases as overplanting increases, but gains are incrementally smaller above a ratio of c.1.5. [Author Analysis]

- 6.6.37 Any scheme which has an installed capacity which is lower than its grid connection capacity would generate less energy than a scheme which is overplanted, and would therefore deliver a lower quantum of overall benefit to energy security and decarbonisation than that delivered by the overplanted scheme. Scale is therefore important.
- 6.6.38 Beyond an overplanting ratio of c.1.3, the curve between the points starts to turn downwards more steeply than it did for a lower overplanting ratio, implying an increasing inefficiency as overplanting ratio increases beyond c.1.3.
- 6.6.39 This analysis does not seek to establish ‘hard and fast’ rules around overplanting, but together Figure 6-5 and Figure 6-6 do provide quantifiable evidence which suggests that the *optimum* overplanting ratio for a solar scheme, may lie between 1.3 and 1.5, depending on the local characteristics of the site in question, such as topography, archaeology, land and other environmental factors which may reduce the scope for overplanting.
- 6.6.40 The Scheme’s indicative design (see **ES Volume II Figure 2-3 Indicative Site Layout Plan [EN010152/APP/6.2]**) illustrates at a commercially rational overplanting ratio can be delivered at the proposed location in a FSF orientation.
- 6.6.41 The extent to which a proposed location can be overplanted cannot be determined in isolation, however. There is an intrinsic relationship between orientation, overplanting and land take which must be considered in the design of all developments in relation to optimising the benefits of the scheme, while respecting the planning balance.

- 6.6.42 The output from any illustrative design may be based on different ways in which the site may be laid out within the parameters which define the extent of the scheme, and which make use of an effective overplanting ratio. The final design and layout will reflect the available technology (and overplanting ratio) arranged in accordance with the assessed parameters.
- 6.6.43 The co-location of storage facilities with certain connection characteristics at solar schemes (such as those proposed at the Scheme) provides an opportunity for generation to be stored and released when generation levels are lower.
- 6.6.44 Generally, storage facilities may be connected to generators through Alternating Current (AC) or Direct Current (DC) coupling. These different solutions provide different benefits but also can lead to different effects and there is no 'one size fits all' approach to optimising co-located facilities.




Figure 6-6: GWh/Yr/MW decreases as overplanting increases, and losses are incrementally larger above a ratio of c.1.3. [Author Analysis]

- 6.6.45 AC-coupled BESS can be placed in one single location which may be in close proximity to the substation or may have very low LVIA impacts. DC coupled systems are placed in small groups which are dispersed among the solar arrays. Access must be available to all BESS groups and some locations may render this unachievable for operational or commercial reasons. Schemes may therefore be better suited to one technology over the other from an environmental impact perspective.
- 6.6.46 Being located close to the grid substation means that line losses associated with power flows between the BESS and the grid are lower for AC-coupled BESS, while line-losses between the panels and the BESS are lower for DC-coupled BESS. These considerations may be significant when assessed over the anticipated operational life of the scheme.
- 6.6.47 AC-coupled BESS require a greater capacity of inverters to store clipped generation, increasing the cost and embedded carbon associated with the scheme when compared to a DC-coupled system.

- 6.6.48 AC-coupled systems are more established in the UK market and developer strategies may not include the development of DC-coupled systems at the time a DCO application is made.
- 6.6.49 Schemes which provide for the storage of what would otherwise be clipped generation in co-located BESS will not be limited in their overplanting ratios by the analysis presented here. Rather, the power and energy capacity of the co-located BESS facility will be important factors in determining the economically rational limit for overplanting at a scheme.
- 6.6.50 **Section 6.9** of this Statement provides further detail on the benefits of co-location, including factors which affect a developer's choice of AC or DC coupling of the BESS with the main solar facility.

6.7 Land use associated with large-scale solar

- 6.7.1 As noted above, NPS EN-3 indicates that along with associated infrastructure, a solar farm typically requires between 2 to 4 acres for each MW output [Ref. 2, Para 2.10.17]. Different configurations have different performance characteristics in terms of acres/MW(p), but MW(p) is not the only metric for the decarbonisation benefit brought forwards by solar schemes.
- 6.7.2 Lifetime average annual generation is the key metric which, if maximised for a scheme, provides the greatest decarbonisation and energy security benefit from the scheme. For a given scheme, lifetime average annual generation depends upon the overplanting ratio while taking into account the potential shading effects of panels on each other.
- 6.7.3 *In extremis*, it is possible for two panels to be located sufficiently far away from each other for neither to ever be in the shade of the other. In contrast, moving one of those panels to be directly in front of the other, would not change the total installed capacity (two panels) but would halve the annual output because the second panel would always be shaded by the first. The *in-extremis* example would however use significantly more land area than the contrasting example.
- 6.7.4 In reality, optimising lifetime average annual output across a large array of solar panels while respecting a finite land area and a finite grid connection capacity requires iteration and judgement and is a non-trivial task.
- 6.7.5 It is therefore possible that a scheme which appears to lie out with the NPS EN-3 guidance in terms of the ratio of acres used per MW installed [Ref. 2, Para 2.10.17] may deliver a higher lifetime average annual generation per acre than a scheme which lies within that guidance, and may therefore deliver greater lifetime benefits than a scheme which falls within the range set out in the NPS.
- 6.7.6 The inclusion of co-located storage as part of a scheme may also change the scheme's land take ratios, particularly as different coupling technologies are laid out in different ways.
- 6.7.7 Large-scale solar schemes are also efficient in comparison to other technologies in terms of the energy they generate over their lifetime on a per unit area basis.

- 6.7.8 Solar technology can also generate more energy per hectare of land than other electricity generation technologies, for example by growing crops for energy. By following good design principles, solar schemes can generate a similar amount of energy per hectare of land as onshore wind.
- 6.7.9 For example, a Guardian article [Ref. 72] reported that 450Ha of crop is required to provide fuel for a 1MW biogas plant, implying that a biogas plant may generate 20 MWh per year per hectare of land used. A biogas plant which is fully available may therefore produce 2 GWh/Yr/km² of clean energy.
- 6.7.10 An academic study published in 2020 [Ref. 73] indicates that the installed capacity density of onshore wind farms in Europe is 19.8 (6.2–46.9) MW/km², which is equivalent to 0.2 (0.06–0.47) MW/ha.
- 6.7.11 Guidance on industry norms for onshore wind farm developments in the UK suggests that turbine towers should be placed between six and ten rotor diameters apart from each other in order to optimise the output of each turbine. This separation is sufficient to ensure that no turbine lies within the ‘wind shadow’ of any other turbine. It is the Author’s experience however that in practice turbine towers on UK wind farms tend to be spaced between three and five rotor diameters apart, consistent with the findings of the academic study [Ref. 73].
- 6.7.12 By assuming an annual load factor of 35% for onshore wind it is possible to calculate that onshore wind may generate 61 (18–144) GWh/Yr/km², a factor of thirty more useful low-carbon energy than from biofuels.
- 6.7.13 NPS EN-3 states that UK solar typically uses between 0.8 (High density) and 1.6Ha (Low density) of land per MW of installed capacity [Ref. 2, Para 2.10.17] which is equivalent to 62.5–125 MW/km² and the illustrative design for this Scheme lies within that range.
- 6.7.14 By assuming a conservative annual load factor of 10% for solar [Author research, see also Table 8-1], solar may generate 54–108 GWh/Yr/km². At the midpoint of EN-3’s typical capacity range, large-scale solar may generate 72 GWh/Yr/km² which is higher than the average reported in the academic study [Ref. 73].
- 6.7.15 Biogas will generate just a small percentage of the levels of the two renewable technologies from the same area of land, while for efficient designs, the expected annual generation output per hectare of land for solar and onshore wind will be of a similar magnitude.
- 6.7.16 This analysis demonstrates that large-scale ground-mount solar schemes, including those that are developed with a configuration which maximises annual output, are likely to produce a greater quantity of low-carbon electricity per acre than the output from a crop-to-biogas application.
- 6.7.17 When compared to onshore wind, the energy production from land under solar is of a similar order of magnitude while the environmental effects of solar schemes may be significantly lower.

6.8 Solar cell efficiency

- 6.8.1 It is important to differentiate between the efficiency of solar technology (which is a measure of how much of the energy contained in the sunlight incident on the panel is converted into electrical energy) and the load factor, as described previously. Both influence the output of a scheme.
- 6.8.2 The load factor of a scheme is influenced by the proposed location, the installed capacity of panels and their orientation and layout. The efficiency of a scheme is influenced by panel selection, the physical properties of those panels, the properties of other electrical components which make up a scheme, and the electrical design of that scheme. In summary, the efficiency of a scheme is intrinsic to its design, whereas the load factor is dependent on location, incident sunlight and panel orientation as well as the efficiency of the scheme.
- 6.8.3 Solar panels and electrical infrastructure have become larger and more efficient, as shown in Figure 6-7, meaning that more electricity can now be generated from the same area of panel, and the same area of land than was previously possible. As a consequence, solar is now, and is expected to remain, a leading low-cost generation technology.
- 6.8.4 While they do not represent an independently sourced update to Figure 6-7, panel supplier product specification sheets can be used to assess the efficiency of currently available solar panels.
- 6.8.5 Figure 6-7 shows that the efficiency of solar cell technology has increased over the last 40 years and that Crystalline-Si, Multi-Function and Thin-Film technology cell efficiencies have increased broadly linearly.
- 6.8.6 A review by the author of 500W + solar panels commonly available on the open market in September 2024 found that they were advertised as being between 1% and 23% efficient and converted incident irradiation at a rate of 210 – 220W/m² [Author Research].
- 6.8.7 For context only, over the period 2019 to 2022, coal generation in the UK achieved an average efficiency of 35.1% and the UK's CCGT achieved 48.6%. Both technologies emit CO₂ as a by-product of electricity generation [Author Research, Ref. 74].
- 6.8.8 The same data reports nuclear efficiency of 39.9%, Hinkley Point C is expected to achieve 36-37%. Smaller gas-fired reciprocating engines achieve similar levels, but they too emit CO₂ when they generate. Wind turbines are 20 – 40% efficient at converting wind energy into electricity [Author Research].
- 6.8.9 The efficiency of solar generation is towards the lower end of the scale of efficiencies for technologies commonly used to generate electricity in the UK, but solar cell efficiency continues to improve.
- 6.8.10 It is important to recognise however that sunlight, the input energy source for solar generation, is abundant, predictable, zero-carbon and free. Wind is similar but can be more difficult to predict. Solar generation produces no marginal carbon emissions and no long-term radioactive waste. Therefore, the lower efficiency exhibited by solar technology versus other generation sources should not be considered as a material objection to its future use. Solar generation also benefits from free input fuel (sunlight), no moving

parts, low height in comparison to other technologies and zero-carbon operation.

- 6.8.11 Solar panel output increases as a product of panel size (area) and panel efficiency. Panel size has been and remains the key driver of panel power in newly released products, although efficiency increases have been achieved as a result of ongoing research and development.
- 6.8.12 Any increase in panel output due to increasing the size of each panel will not materially affect their coverage across a proposed parcel of land because the total area of panels which can be placed in the parcel will be broadly the same.
- 6.8.13 It is difficult to predict what the future capacity of a PV module will be, but manufacturers are constantly improving the technology. For example, one panel which became available in Q4 2020 was advertised at 21.3% efficiency, while a panel from a different manufacturer, which became available in Q1 2023, was advertised at 23% efficiency [Author Research].
- 6.8.14 It seems reasonable therefore to anticipate that panel efficiency will continue to increase at best linearly over the 2020s.
- 6.8.15 By installing more efficient panels, a facility may install less panels but the total coverage across a site is not expected to change significantly, and it is not a given that the installation of higher efficiency panels will result in reduced land take. Opportunities to enhance the overall efficiency of the scheme may materialise at the detailed design stage, for example by procuring more advanced (efficient) panels and spacing them out more (increasing the pitch) within land parcels to reduce shadowing effects or removing inefficient corners of fields that reduce infrastructure requirements.
- 6.8.16 Proposed designs can only incorporate products which are already available in the market. Similarly, detailed designs, which will be carried out post consent for a scheme, will only incorporate those panels which are available at the time.
- 6.8.17 At the detailed design stage, opportunities will be investigated to increase the lifetime generation output of the scheme and the benefits arising from its development, within the envelope of development secured at consent.




Figure 6-7: Evolution in solar cell efficiency 1975 – 2024 [Ref. 75]

6.9 Co-Location

6.9.1 NPS EN-3 states that:

“Government is supportive of solar that is co-located with other functions (for example, agriculture, onshore wind generation, or storage) to maximise the efficiency of land use”. [Ref. 2, Para 2.10.10]

- 6.9.2 **Section 5.11** describes the role of BESS within a net zero energy system. BESS provide services which support the operation of renewable energy generation schemes and the efficient and secure operation of the UK’s electricity system provided that they are able to both import energy from and export energy to the electricity system.
- 6.9.3 BESS may be proposed as part of solar projects as a resource to hold energy generated by the solar farm during times of low demand and release it to the national grid through the scheme’s grid connection at times of high demand. If a scheme is to connect to the electricity system at a location where the scheme is also able to import electricity from the grid, a co-located BESS could allow energy to be imported from the grid at times of low demand and exported back to the grid at times of high demand.
- 6.9.4 At some locations, the former can be achieved without upgrades being required to existing grid connection substations, but at other locations, significant upgrades to transmission system infrastructure may be required to allow BESS to contribute fully to the electricity system.
- 6.9.5 Such upgrades may be time consuming and/or expensive. Waiting for grid upgrades to deliver before developing a scheme may delay the scheme’s commissioning date, thus delaying the delivery of much needed renewable energy as a critical and urgent contribution to meeting net zero. Delays and increased costs may also increase the commercial risk associated with the scheme above the level at which investment may be secured, risking the deliverability of the scheme as a whole.
- 6.9.6 Developers may propose to install storage at sites which do not have a grid import connection, however current commercial, technical and system operation considerations would suggest that storage is more beneficial to the electricity system, and more likely therefore to be developed, if it is able to both import energy from and export energy to the NETS, as well as store energy generated from the co-located solar panels.
- 6.9.7 The following Figures illustrate how co-located solar and BESS may work together under a number of different well-defined and distinct market scenarios. The reality of electricity market operation is that BESS and solar operations are unlikely to be so clearly defined and actual operations may vary significantly on a day-to-day basis.
- 6.9.8 For simplicity, Figure 6-8 to Figure 6-12 illustrate a 500MW solar array co-located with a 500MW, 1 hour (therefore 500MWh energy storage capacity) BESS, but the illustrations are applicable to larger arrays and co-located schemes with different energy storage capacity.
- 6.9.9 In each of Figure 6-8 to Figure 6-12, the yellow bell-shape areas in sub-figures (a) and (b) represent solar generation which is transmitted to the grid through the day. The green areas represent energy imports to the BESS,

and the red areas represent energy exports from the BESS through the day. In sub-figures (c) the blue area represents the energy stored in the BESS through the day.

6.9.10 The import of energy from the co-located solar facility is illustrated by a green area overlapping a yellow area. The import of energy from the electricity network is illustrated by a green area which does not overlap a yellow area.

6.9.11 For example, in Figure 6-8 to Figure 6-12 following, the BESS is shown moving from 0% to 100% State of Charge and back again on each operation. In reality this may not be the case, and the BESS may instead undertake many more partial, rather than full, import/export operations.




Figure 6-8: BESS imports solar generation at midday and exports in the evening [Author Analysis]

6.9.12 Local solar generation is usually highest in the middle of the day, and national demand is usually highest in the evening (around approximately 17:00 in winters, 19:00 in summers).

6.9.13 Figure 6-8(a) represents solar generation at the facility over the course of one sunny day. If the asset operator’s forward view was that energy may be in surplus in the middle of the day but would be needed in the evening, the operator could schedule the BESS to import from the solar generation during the middle of the day (Figure 6-8(b), green area) and to export that energy later when it was needed more (Figure 6-8(b), red area). Figure 6-8(c) shows the State of Charge of the BESS on that day.




Figure 6-9: BESS imports solar generation at midday and exports in the evening – lower import / export rates [Author Analysis]

6.9.14 The BESS may be configured to import and export at a lower rate than its maximum power output, this will allow it to import over a longer period and export as shown in Figure 6-9. Critically, the amount of energy the BESS can store is the same as in Figure 6-8. Operators would determine their rate of import and export according to market needs.

6.9.15 National UK electricity demand varies through the day, and can also be different from day to day, for example weekdays versus weekends, or

summer versus winter days. Additionally, solar is not the only variable renewable generation on the UK electricity system.




Figure 6-10: BESS imports solar generation at midday and exports in the evening – lower import / export rates [Author Analysis]

6.9.16 This means that at times when the BESS is not supporting the operation of the principal solar site, it may be useful for the BESS to support the national supply and demand balance by importing directly from the grid rather than from the co-located solar, as was shown in Figure 6-8 and Figure 6-9 previously. A good example of when the BESS might import from the grid in response to national supply / demand balance, might be when wind generation is high.

6.9.17 Figure 6-10 shows how the BESS may import overnight, store its charge through the day, and export in the evening peak. Figure 6-10 uses a solar output profile which may be more typical of a winter’s day, but the type of operation shown is not foreseen to be restricted only to the winter.

6.9.18 On some days, operators may foresee the market need for the BESS to operate more than one import/export cycle over a 24-hour period, and Figure 6-11 shows how this might work. In practice, the BESS operational parameters will limit how the BESS is able to respond to market need.




Figure 6-11: BESS imports grid generation and solar generation and exports twice in the day [Author Analysis]

6.9.19 Ancillary (Balancing) Services are contracted at relatively short notice (e.g. contracted ‘today’ for delivery ‘tomorrow’) and service time windows tend to be contracted in multiples of 4 hours, commencing 23:00, 03:00, 07:00, 11:00, 15:00 and 19:00 daily.

6.9.20 Subject to certain technical characteristics, BESS are also able to store clipped generation and export it to the grid when solar irradiation falls such

that generation from the scheme is lower than the grid export capacity.
 Figure 6-12 shows how this might work in practice.




Figure 6-12: BESS stores clipped solar generation and exports in the evening [Author Analysis]

- 6.9.21 Figure 6-12 assumes an overplanted scheme (e.g. 600MW) connected to a capped (e.g. 500MW) grid connection. Figure 6-12(a) shows generation on a sunny day might exceed the grid connection cap for multiple hours. A co-located BESS may be able to store this energy, shown by the green area in Figure 6-12(b), so that it can be exported when grid capacity is available as indicated by the red area in Figure 6-12(b).
- 6.9.22 Abundant generation can be stored in either AC- or DC- coupled energy storage facilities. However, storage facilities which are DC-coupled to solar facilities use less equipment and provide a more efficient solution for storing abundant co-located generation without losing functionality to store energy imported from the grid, as is illustrated in Figure 6-12.
- 6.9.23 However, despite DC-coupled batteries bringing operational efficiencies, they require different physical layouts and therefore may not be appropriate for all schemes. Some schemes are therefore anticipated to come forward as co-located schemes with AC-coupled batteries, or as stand-alone solar schemes.
- 6.9.24 The Scheme is for co-located solar and storage, with AC-coupled batteries.
- 6.9.25 Ancillary (Balancing) Services help to keep the UK electricity system operating safely and securely. Many Ancillary (Balancing) Service contracts require BESS to provide both upward (export) and downward (import) regulation to the national grid, and that to do this BESS would be likely to seek to commence their period of contracted operation with a State of Charge at or close to 50%. This may mean therefore that immediately prior to a contracted period for Ancillary (Balancing) Service provision, a BESS may elect to import or export to achieve a State of Charge of 50% at the start of its contracted window.
- 6.9.26 The UK's electricity system operates at a nominal frequency of 50Hz and National Grid procure services over very short timescales (sub-second response services) out to minutes or hours for reserve services to keep frequency always at or close to 50Hz.
- 6.9.27 BESS operation under reserve service contracts will be similar to the BESS operation shown in Figure 6-8 to Figure 6-12 above, i.e. consistent importing or exporting over periods of minutes or hours at pre-agreed levels. BESS operation under response service contracts will however be different.

- 6.9.28 Response contracts require the immediate import or export of energy to the grid based on whether the instantaneous frequency of the national grid is higher or lower than the statutory 50Hz. Importing energy into the BESS has the effect of reducing grid frequency (so import actions are instructed when frequency is high). Exporting energy from the BESS has the effect of increasing grid frequency (so export actions are instructed when frequency is low).
- 6.9.29 Under normal operating conditions, the frequency of the national grid varies by small amounts from the statutory 50Hz level. Short duration injections (or exports) of energy to the grid nudge frequency back to the statutory level. Figure 6-13 following shows how grid frequency changed second-by-second over a 30 minute period of operation in July 2023, and how a BESS operating under a Frequency Response contract may respond to those normal changes in grid frequency.




Figure 6-13: 30 mins of system frequency (Hz) and illustrative BESS operation under frequency response [Author Analysis]

- 6.9.30 Figure 6-13 seeks to illustrate that if frequency is moving away from the nominal 50Hz line, BESS will respond to bring frequency back towards 50Hz. The height of the green (import) and red (export) columns is intended to signify the magnitude of the BESS response, which would be driven by a combination of the rate of change of frequency (quicker changes require a larger response) and the magnitude of the variation of grid frequency from its nominal 50Hz at the time of the instruction.
- 6.9.31 In reality BESS imports/exports may be much more frequent than those illustrated in Figure 6-13. In normal operational conditions, under Frequency Response, a BESS could be expected to import roughly the same amount of energy as it exports, leaving its State of Charge broadly unchanged over the contracted period. However it is important that the contracted State of Charge is known before the contracted period starts such that in fault conditions, the BESS can be relied upon to deliver the extent of the services it has contracted with NGEN.
- 6.9.32 Co-located BESS with both an import and export capability will allow the BESS to charge from the co-located solar and from the grid whenever UK system supply was greater than UK system demand. This type of operation

provides much needed flexibility to the UK power system and therefore will provide benefits to the UK system and decarbonisation generally.

- 6.9.33 Being able to regulate power flows both to and from the grid would allow the BESS to provide many kinds of system-wide ancillary services which will support a further reduction in the UK's reliance on fossil fuels; Table 5-1 provides more information.

6.10 Conclusions on Technical Considerations

- 6.10.1 Large-scale solar is a highly beneficial technology within the UK's electricity system.
- 6.10.2 Solar developments require locations to possess three fundamental attributes of sufficient available land, a point of connection to the electricity system and sufficient solar irradiation levels.
- 6.10.3 Large-scale schemes which connect to the NETS allow for a "*more efficient bulk transfer of power*" for national consumption [Ref. 1, Para 3.3.12] than smaller schemes which connect to distribution systems.
- 6.10.4 Connections to both transmission and distribution systems in the UK are in short supply. The use of existing and available connections is therefore necessary to support the delivery of low-carbon generation in the next decade to meet the previous government's aims for a zero-carbon electricity system by 2035, and the government's aim to deliver 'Clean Power by 2030'.
- 6.10.5 The development of new points of connection are also foreseen as necessary but are likely to have longer development timeframes than connection points which already exist, therefore the prioritisation of existing and available connections goes towards meeting the urgent need to decarbonise the electricity system.
- 6.10.6 Solar schemes represent an efficient use of land for energy generation purposes.
- 6.10.7 The efficiency of solar generation is towards the lower end of the scale of efficiencies for technologies commonly used to generate electricity in the UK, but solar cell efficiency continues to improve. Sunlight, the input energy source is abundant, predictable, renewable and free. Solar's lower efficiency than other generation sources should not therefore be considered as detrimental to its future use.
- 6.10.8 Overplanting and panel layout optimisation can both increase the likely annual generation of schemes through their grid connection points. This goes towards best meeting the urgent need for solar generation within the context of a constrained grid connection queue.
- 6.10.9 The connection of thousands of small-scale (including rooftop) systems to the aggregate capacity targeted by the government under its mission to deliver 'Clean Power by 2030' is unlikely in isolation to meet the urgent need for solar. The installation cost of small-scale schemes, which would be met by individual households, is much higher than the cost of large-scale schemes on a per unit basis.
- 6.10.10 The inclusion of a BESS as Associated Development to the main solar scheme will support the operation of the main solar scheme and will be able

to store energy generated by the main solar scheme and export it to the NETS when it is needed.

6.10.11 The Scheme considers an appropriate level of overplanting given the land area, grid connection capacity and preferred FSF panel orientation. The characteristics of the Scheme, including its AC-coupled BESS, seek to optimise the annual average generation from the Scheme over its operational life at its specified location.

7. Suitability Of The Proposed Location For Large-Scale Solar

7.1 Chapter Purpose

7.1.1 This chapter provides an overview of the evidence provided to support the suitability of the proposed location of the Scheme for large-scale solar plus storage.

7.2 Local Demand / Decarbonisation Requirements

7.2.1 The Applicant has accepted a Connection Offer from National Grid to connect the Scheme to the NETS at the existing National Grid 400kV Thorpe Marsh substation. The Connection Offer provides for the export of up to 237.5MW of power, connecting in 2032.

7.2.2 Further information on the grid connection for the Scheme can be found in the **Grid Connection Statement [EN010152/APP/7.5]**.

7.2.3 Thorpe Marsh connects directly to the NETS between Drax and Eggborough to the north and Sheffield, Manchester and Liverpool to the south west, see Figure 7-4. The NETS is well-connected and resilient in this part of the country.

7.2.4 The Scheme is located near to National Grid's Thorpe Marsh substation.

7.2.5 National Grid's TEC Register lists six schemes, including this Scheme, comprising 3.6GW of capacity with agreement to connect at Thorpe Marsh.

7.2.6 Although the Scheme proposes to connect to the NETS, it is located in the area covered by Northern Power Grid's Yorkshire distribution network.

7.2.7 Grid substations and Grid Supply Points (GSPs) are where the generators connect to the NETS and/or the NETS connects to local distribution systems. At these points, voltage is reduced from the NETS high-voltage cables to lower voltages for more local transmission via Bulk and Primary substations, then on to consumers.

7.2.8 The Yorkshire distribution area contains GSPs and Bulk and Primary substations. These substations and the distribution cables between them, are not of a sufficient capacity to facilitate connection of the Scheme.

7.2.9 However, these substations ensure that although the energy generated at the Scheme may be transmitted to consumers nationally without constraint, there is a network pathway from the Scheme to the local substations which service local consumers.

7.2.10 This does not mean that the energy generated at the Scheme will necessarily or solely service either local or national consumption, but it does mean that connecting the Scheme at Thorpe Marsh will enable the unconstrained flow of energy to either local or national consumers, whenever it is needed.

7.2.11 Figure 7-1 shows that Yorkshire and the Humber has a significant annual energy demand [Ref. 9]. In 2021 (2022 data is not yet available), this amounted to 14.1TWh of electricity (around 8.5% of national electricity consumption). Transport needs in the region consumed 36.4TWh, and a

further 78.9TWh (non-electricity demand) was sourced from other fuels such as coal, gas, oils and biomass.

- 7.2.12 Total energy consumption in Yorkshire and the Humber reduced by 22% over the period 2005 to 2021. Electricity consumption decreased by 17% and non-electricity consumption including transport decreased by 28%.
- 7.2.13 Regional energy consumption reduced in aggregate from 2005 to 2021 across both the domestic and non-domestic sectors, by 22% and 28% respectively. Domestic energy consumption not sourced from electricity has not materially reduced since 2011.
- 7.2.14 Transport consumption decreased by only 6% over the period 2005-2021.




Figure 7-1: Energy consumption in Yorkshire and the Humber (TWh/Yr) [Author Analysis, Ref. 9]

- 7.2.15 The data shows that non-electricity consumption (including transport) in Yorkshire and the Humber, is approximately five times that of electricity consumption. A significant increase in electricity as a share of total energy consumption will be required in the future to meet net zero locally. These trends are broadly consistent with the national trend as described in **Chapter 4** of this report.

7.3 Local Supply

- 7.3.1 As part of its 2022 FES, National Grid published a map of regional generation carbon intensity on two types of day (a higher wind day and a lower wind day) [Ref. 19(2022), p32]. The map is reproduced in Figure 7-2.
- 7.3.2 In 2023, the average national carbon intensity of generation was reported as 171 g/kWh [Ref. 19, Table 5.14], i.e. at the 'high' end of the 'low' range shown in Figure 7-2.
- 7.3.3 The map on the left of Figure 7-2 shows the carbon intensity of generation by region during a higher wind day, and the map on the right shows the same but for a lower wind day. The values indicate the installed wind capacity in each region at the time of publishing the map (therefore current capacities may be higher).

- 7.3.4 As expected, during windy days, the carbon intensity of generation is on average lower than the annual average figure. On days with lower wind, carbon emissions from electricity supply in Scotland and the north of England remains below the annual average, but from Yorkshire and North Wales and further south, the carbon intensity of generation is at best moderate, and may approach double the annual average figure.
- 7.3.5 Measures must be implemented to reduce the carbon intensity of generation outside of Scotland and the north of England during low-wind days. Solar generation is well suited to support a such a reduction.
- 7.3.6 Further, Figure 7-2 suggests that there is carbon emitting plant located in the south of the country which currently generates when wind output is low. This can be inferred because at times of low wind, the carbon intensity of generation in the south of the country is high. During periods of low wind, National Grid's analysis shows that the Yorkshire and the Humber area has a moderate carbon intensity of generation. The Scheme will, if consented, reduce the carbon intensity of generation in the Yorkshire and the Humber area in both 'low' and 'normal' wind conditions. The inclusion of BESS as part of the Scheme means that it will be able to store low-carbon energy when generation is in abundance and release it when demand for energy is higher.
- 7.3.7 As **Section 5.2** describes, solar and other renewable generation displaces carbon emitting generation from the grid and therefore has a decarbonising effect on the electricity system. The placement of any solar farms in these areas means that when the sun is shining their generation will be flowing through parts of the transmission system where otherwise the energy generated by carbon emitting plant would flow. It is unlikely therefore that the installation of solar schemes would cause any significant network constraints by connecting in these areas. Further information on the benefits of a multi-technology energy system can be found in **Chapter 8**.
- 7.3.8 Figure 6-2 shows that the Scheme is located in an area with solar irradiation levels above average for the UK, and initial studies suggest that an average annual load factor before degradation at the site is sufficiently high to support the development of a large-scale ground mounted solar facility at the proposed location. The region is well positioned to use its natural resources and existing infrastructure to support the UK's energy needs through the development of the proposed large-scale solar scheme to generate clean electricity to power homes, locally and nationally, cars, offices, shops and factories.




Figure 7-2: NGESO Regional generation carbon intensity analysis (Left: on a higher wind day, Right: on a lower wind day) [Ref. 20(2022)]

7.4 Grid Suitability

- 7.4.1 Annually, NGESO perform an analysis of the NETS from a security and quality of supply (SQSS) and power flow capability perspective. Their analysis is published as part of their Electricity Ten Year Statements (ETYS) [Ref. 76]. Options to improve power flow capability can be found in their Network Options Assessment (NOA) [Ref. 77].
- 7.4.2 NGESO subdivides its network into operational areas by means of system boundaries. These boundaries are not hard, nor physical, but differentiate areas within which NGESO characterise power flows.
- 7.4.3 The ETYS looks at whether the current network allows GB national demand to be met through two lenses.
- 7.4.4 The first is the Security Criteria. This validates that the capability of each boundary is sufficient to allow the expected maximum flow across that boundary required to ensure security of supplies across the network. In other words, the maximum boundary transfer capability must be greater than that required to maintain, under reasonable ‘worst case’ conditions, security of supply at all locations on one side of the boundary with supplies from the other side.
- “The boundary transfer requirements needed to satisfy demand without relying on intermittent generators or imports from interconnectors.” [Ref. 76]*
- 7.4.5 The second is the Economy Criteria. This validates that the capability of each boundary is sufficient to allow the expected flow of power across the network such that a national merit order of operation is maintained. In other

words, this criteria balances the need for cheap power to flow unconstrained across the network (therefore lowering prices and costs for consumers) against the enabling cost of upgrading the network:

“The boundary transfer requirements when demand is met with high output from intermittent and low carbon generators and imports from interconnectors. This ensures capacity is adequate to transmit power from highly variable generation without any network constraint.” [Ref. 76]

- 7.4.6 The NOA then identifies, assesses, and recommends (where appropriate) specific upgrade projects which meet the future needs as anticipated in the ETYS.
- 7.4.7 The Scheme proposes to connect to a major existing 400kV transmission circuit which provides a connection through Keadby to demand centres in the south and London.
- 7.4.8 The main transmission circuits to the south and west are double transmission circuits, providing defence in depth. In the event that one circuit faults, power can still flow on the other circuit. Double circuits also deliver high-power flow capability [Ref. 76, Appendix A].
- 7.4.9 The Yorkshire and the Humber area, the East Midlands area to the south of the Scheme and Norweb to the west, are home to critical infrastructure connecting generators and consumers across the country. The strength and capacity of connections within these areas contribute to the transfer capacities available across nearby system boundaries.
- 7.4.10 Thorpe Marsh is located in NGENSO's Transmission Zone 16: North Midlands and North Wales. This zone is connected to the surrounding NETS as shown in Figure 7-4. It is located south of National Grid's B7a boundary but north of the B8 boundary.
- 7.4.11 Boundary B7a bisects England south of Teesside. With large capacities of wind generation connecting into circuits in Scotland and northern England, Boundary B7a is anticipated to become a constraint to the economy criteria relatively soon (i.e. transfer capacity may be insufficient to allow the free flow of wind power to southern demand centres). National Grid's analysis suggests a strong need to develop the network sufficiently to allow for anticipated flows.
- 7.4.12 Critically, the Scheme lies to the south of that boundary, so does not contribute to the identified constraint.
- 7.4.13 Boundary B8 is one of the wider boundaries that crosses the centre of GB from east to west, separating the northern generation zones (Scotland, Northern England and North Wales) from the Midlands and southern demand centres.
- 7.4.14 Figure 7-3 shows the current and projected level of boundary transfer capacity (thick solid red line) across the B7a (left) and B8 (right) boundaries. The fine solid red line shows the Economy Criteria and the dashed red line shows the Security Criteria for each year to 2042.
- 7.4.15 Boundary B8 transfer capability is currently 2.5GW higher than the transfer capability of Boundary B7a. Boundary B8 transfer capability is expected to increase to 21.5GW over the coming twenty years, while B7a is expected to increase to 18GW. Power flows generally from the north to the south,

therefore connecting a large-scale renewable generator between the boundaries is not likely to cause any incremental constraints under either the economy or security criteria.

- 7.4.16 The dip in boundary transfer capacity in 2030 is inferred to indicate a period of outage and/or upgrade of existing infrastructure to facilitate the higher boundary transfer capacities from 2031 onwards.
- 7.4.17 The flow of energy from the Scheme will therefore be capable of displacing more expensive and more carbon intensive power generated south of the B7a boundary, and south of the B8 boundary. The displacement of carbon intensive power generation will be to the benefit of electricity system decarbonisation and consumer cost nationally.
- 7.4.18 The current capability of the B7a boundary is not sufficient to meet all of the P25 to P75 confidence range during high wind periods. This means that there may be curtailment down to the boundary transfer capability level, of northern wind which is unable to flow south beyond the B7a boundary when wind generation is too high. In scenarios which meet net zero 2050, curtailment of flows south over the B7a boundary may increase as a result of large capacities of offshore wind connecting in Scotland and northern England.
- 7.4.19 Until (and unless) boundaries are expanded to their Economy Criteria levels, the development of renewable generation facilities south of those boundaries allows for more low-cost, low-carbon electricity to power demand centres nationally, supporting security of supply, decarbonisation and affordability metrics.
- 7.4.20 Cross-boundary flows will be highest during periods of high wind. Periods of high wind do not usually coincide with periods of high solar irradiation, highlighting a beneficial natural 'fit' between the Scheme (and other large solar facilities in the East Midlands and Yorkshire area) with flows of wind-generated electricity from northern wind farms through this area.
- 7.4.21 Further, decarbonisation of industry and demand located between the boundaries will increase electricity demand in the area, and the location of low-carbon generation schemes between the boundaries will mean that energy can be supplied to those consumers without constraint, even if there are constraints in other areas of the network.
- 7.4.22 The inclusion of BESS as part of the Scheme provides opportunities for NGENSO to manage any potential power flow constraints on the NETS in the vicinity of the Scheme over its operational life. This may for example include any constraints which occur as a result of high wind or other causes, and minimising these in a cost effective way would be to the commercial benefit of consumers.




Figure 7-3: B8 and B9 Boundary flows under most extreme scenarios [Ref. 76, Boundary Data workbook]

7.5 Connection Points / History

- 7.5.1 Figure 7-4 shows a map of the NETS, with a 50km radius drawn in red and centred at Thorpe Marsh. Figure 7-4 shows that there are only three other 400kV substations in close proximity to the Scheme, being Eggborough, Drax and Keadby. Figure 6-3 confirms that no new schemes are able to connect to any of those substations before 2032.
- 7.5.2 Of the other eleven National Grid substations located within 50km of Thorpe Marsh, four are already connection points for operational thermal generators and three, like Thorpe Marsh, were connection points for now closed coal generators.
- 7.5.3 Table 7-1 lists the connection capacity and connection dates for each technology type which holds a connection offer from National Grid to connect at Thorpe Marsh. The table confirms that the Scheme is the only large-scale renewable generation scheme currently proposed to connect at Thorpe Marsh, the other schemes listed being predominantly storage schemes.
- 7.5.4 The Scheme is also an important part of the future generation mix connecting to Thorpe Marsh, because no other schemes are likely to be able to connect before 2032. Existing grid connection infrastructure, such as Thorpe Marsh, must be used to the greatest possible extent, to connect new low-carbon generation in timescales which meet the government’s plans (and those of the previous government) to reduce national carbon emissions.
- 7.5.5 **ES Volume I, Chapter 3 Alternatives and Design Evolution [EN010152/APP/6.1]** provides additional information on the Applicant’s site selection process.




Figure 7-4: Transmission System within 50km of Thorpe Marsh [Ref. 76, Appendix A]

Table 7-1: Generation technologies accepted to connect at Thorpe Marsh

[Ref. 38, 38a, 38b, Author Analysis]

Technology	Connection Year	Capacity (MW)	Cumulative Total (MW)	Cumulative Solar (MW)
Solar & BESS	2024-26	57.0MW incl. up to 26.0MW solar	57.0	26.0
BESS	2026	1,400.0	1,457.0	26.0
BESS & Solar	2030-32	1,025.0 MW incl. 50.0MW Solar	1,082.0	76.0
The Scheme	2032	237.5	1,319.5	313.5
BESS	2033	750.0	3,469.5	313.5
BESS	2035	180.0	3,649.5	313.5

7.6 Conclusions on the Proposed Location

- 7.6.1 Yorkshire and the Humber has a history of using its available natural resources to power the UK, firstly through coal and then through natural gas, piped from the UK Continental Shelf for local industrial and power generation use. This analysis, when considered in combination with Figure 6-2 and shows that the region is well positioned to use its natural resources and existing infrastructure to support the UK’s energy needs for a third time, through the development of the proposed large-scale solar and storage scheme to generate, store and release clean electricity to power homes, locally and nationally, as well as cars, offices, shops and factories.
- 7.6.2 This Statement of Need demonstrates that the proposed connection point is suitable and no adverse operability effects are anticipated as a result of connecting at this location.
- 7.6.3 The Scheme has a Grid Connection Agreement with National Grid. As part of National Grid’s connection reforms, *“Energy generators that are not progressing [with project development] and will not meet their connection date will either be able to choose to move backwards or leave the [connection] queue, in order to make way for projects that want to connect and are delivering on their milestones”* [Ref. 71].
- 7.6.4 If development consent is obtained for the Scheme, the Applicant would request National Grid to bring the connection date forward, should there be scope to do so.

- 7.6.5 In any event, and subject to obtaining the necessary consents, the Applicant aims to construct the Scheme ready for connection to the NETS in line with the timeframes set out in the Scheme's Grid Connection Agreement.
- 7.6.6 Therefore, if consented, the Scheme would contribute to continuing the UK's decarbonisation and security of supply efforts as electricity demand from non-traditional sectors increases in the 2030s.
- 7.6.7 If the DCO is not granted, then a critical opportunity will be missed to deliver a significant capacity of low-carbon solar generation capacity onto the NETS in the timeframes indicated. This would increase the risk of non-delivery of the UK's legal obligations because:
- a. The benefits which would have been brought forward by the scheme would need to be delivered by as yet undefined, unconsented schemes;
 - b. The criticality and scale of schemes required to deliver in later timeframes to make up for those benefits would both increase; and
 - c. The pace and cost of delivery of such schemes would also likely be higher than in the case that the Scheme was consented.
- 7.6.8 NPS EN-1 is clear on the point of need:
"The Secretary of State should assess all applications for development consent for the types of infrastructure covered by this NPS on the basis that the government has demonstrated that there is a need for those types of infrastructure which is urgent [Ref. 1, Para 3.2.6]."
- 7.6.9 NPS EN-1 further states that *"the Secretary of State has determined that substantial weight should be given to this need when considering applications for development consent under the Planning Act 2008"* [Ref. 1, Para 3.2.7] and that the *"Secretary of State is not required to consider the specific contribution of any individual project to satisfying the need established within the NPS"* [Ref. 1, Para 3.2.8].
- 7.6.10 The need for the Scheme is urgent and substantial weight should be given to that need. The proposed location is a highly suitable location for large-scale solar because of the existence of a grid connection with the capacity available to connect the Scheme in the timeframes indicated, sufficient solar irradiation and suitable land at the site.
- 7.6.11 Further, the development of a large-scale solar development connecting at Thorpe Marsh provides the potential to help decarbonise locally generated electricity to the benefit of consumers both locally and nationally.
- 7.6.12 The Applicant's grid connection at Thorpe Marsh is suitable and available for the Scheme to commission in the 2030s thereby permitting the Scheme to contribute to achieving the UK's Sixth Carbon Budget. Connection to the transmission system is of significant importance, enabling an unencumbered and efficient transfer of bulk power across the country, in order to provide electricity wherever it is needed.
- 7.6.13 The Scheme aims to optimise use of the grid connection at Thorpe Marsh from the available land through a proposed FSF layout and BESS configuration, while being sympathetic to planning issues and respecting identified constraints.

- 7.6.14 FSF is preferred at the Scheme because it is more space-efficient at this Solar PV Site than E-W or SAT, thereby enabling the Scheme to make the best use of the grid connection given appropriate layout parameters and local constraints, including the availability of suitable land. The illustrative layouts would deliver a commercially rational overplanting ratio, and the inclusion of BESS as Associated Development to the Scheme will support the main solar site during its operational period.
- 7.6.15 Any optimisation of layout at a detailed design stage would be unlikely to identify any useful areas of land because any such areas identified would be likely to be around the edges of field margins and disconnected from other useful areas and therefore would have little or no agricultural value.
- 7.6.16 Lastly, the electricity network local to the Scheme has sufficient capacity to accommodate the anticipated generation from the Scheme without constraint. By connecting between the B7a and B8 boundary, the anticipated generation is not expected to exacerbate existing network constraints often associated with periods of high generation in northern wind farms.

8. The contribution of large scale solar to system security

8.1 Chapter overview

8.1.1 This chapter provides an overview of the system security benefits of large-scale solar in the UK.

8.1.2 Decarbonisation is just one of the three pillars of GB energy policy. Low carbon generation of all forms, solar, wind and nuclear included, brings with it new challenges. Current and future energy policy and related actions must ensure that security of supply is maintained, and that electricity is affordable for all. This chapter demonstrates how solar has contributed, and will continue to contribute, to security of supply in Great Britain. As set out in NPS EN-1:

“[The government] need[s] to ensure that there is sufficient electricity to always meet demand; with a margin to accommodate unexpectedly high demand and to mitigate risks such as unexpected plant closures and extreme weather events” [Ref. 1, Para 3.3.1].

“The larger the margin, the more resilient the system will be in dealing with unexpected events, and consequently the lower the risk of a supply interruption” [Ref. 1, Para 3.3.2].

“We need a diverse mix of electricity infrastructure to come forward, so that we can deliver a secure, reliable, affordable and net zero consistent system during the transition to 2050 for a wide range of demand, decarbonisation, and technology sources” [Ref. 1, Para 3.3.19].

“A secure, reliable, affordable, net zero consistent system in 2050 is likely to be composed predominantly of wind and solar” [Ref. 1, Para 3.3.20].

8.1.3 ‘Security of supply’ means, essentially, keeping the lights on in people’s homes, and has two main components:

- a. Ensuring that there is enough electricity generation capacity available and operational to meet demand (adequacy); and
- b. Ensuring that the quality of electricity supplied to customers falls within a narrow ‘quality’ band during all reasonably foreseeable operational circumstances and is resilient during rare excursions from this band.

8.1.4 This definition of adequacy includes not only the capacity of generation assets but also the availability of source fuel to those assets so that they are able to generate electricity.

8.2 Power System Stability

- 8.2.1 Power systems connect supply (sources of power, largely generators) to assets which demand power (industrial, commercial or domestic customers). Power systems are complex; yet they must be designed and operated safely, securely, and economically.
- 8.2.2 Governments define policy to ensure that adequacy requirements are met, i.e. that there is sufficient generating capacity (i.e. the maximum achievable level of power generation which may be connected to the NETS) available to meet maximum expected demand, with secure and economic supply chains for the fuel they use to generate electricity.
- 8.2.3 Key power quality characteristics (including frequency, voltage, and power shape) must also be controlled for the electricity system to operate without fault. NGENSO define this topic area as system operability, specifically: *“the ability to maintain system stability and all of the asset ratings and operational parameters within pre-defined limits safely, economically and sustainably”* [Ref. 78, p5].
- 8.2.4 Keeping an electricity system from entering fault conditions during operation or returning an electricity system to normal operational conditions post fault, is also important. All large-scale generators must be capable of maintaining their own synchronicity with the system to a high level of reliability.
- 8.2.5 NGENSO also ensure that power demand, or load, and power supply, always remain balanced. Balancing requires the right generating assets to be connected and disconnected to/from the right power levels, and at the right time. This can sometimes be at short notice, in response to emergent (fault) conditions. NGENSO call those services which support NETS stability and operability are called Ancillary Services and examples have been listed previously in Figure 5-8 and Table 5-1.
- 8.2.6 The NIC addressed the topic of system stability by stating that it is *“Important that generators are responsible for costs and benefits they impose on the system, such as those related to where they situate”* [Ref. 79, p40].
- 8.2.7 It is well understood that the activities associated with integrating renewables into the GB electricity system will increase with their penetration. Energy balance must be managed at all times; and as renewable capacity increases, a greater volume and range of Ancillary Services may be required to maintain or regain supply / demand balance and retain system control, particularly when demand is either very high or very low. Balancing actions may also increase.
- 8.2.8 Technological advances, in particular in the introduction of power electronics into generating assets, is increasing the ancillary services and system stability services available from users of the electricity system, for example, by improving an asset’s response speed and capability to system faults, and their ability to withstand periods of system instability without disconnecting.
- 8.2.9 The installation of power electronics at low-carbon generation assets is an exciting development which will enable them to provide important system stability services as part of their normal daily operational routine. By reprogramming the digital power inverters attached to solar panels, services required by the ESO can be delivered from solar generation facilities. Some

solar farms already operating have incorporated state-of-the-art power electronics into their designs and are providing important stability services to the ESO.

8.3 Power System Adequacy

- 8.3.1 Solar plays an important role in diversifying renewable generation sources to maintain adequacy and minimise curtailment.
- 8.3.2 The uncontrollable nature of the weather raises a potential challenge to the ability of solar generation to play a significant role in electricity supply. However, the variability of solar generation can be mitigated by:
- a. Developing larger generation capacities (to maximise output during periods of low irradiation, for example through overplanting);
 - b. Connecting assets to different parts of the NETS; and
 - c. Developing projects with generation profiles which are complementary to solar (for example wind: see **Section 8.5**).
- 8.3.3 'Integration technologies' may also be used to respond to the intermittency of renewable generation, including electricity storage, interconnection, hydrogen and demand side response [Ref. 1, Para 3.3.6]. 'Integration technologies' will help balance supply and demand, improving the efficiency of the electricity system as a whole and potentially reducing the installed generation capacity required to meet peak demand.
- 8.3.4 National Grid state that security of supply *"refers to meeting all electricity demand at any given time"* and that *"Traditionally, risks to meeting electricity security of supply, have been at times of high demand."* However, *"as we move to higher volumes of weather-dependent renewable energy, we will also face additional challenges around both the oversupply and undersupply of renewable generation"* [Ref. 19(2024), p99].
- 8.3.5 The Capacity Market, which is one of the UK's primary measures for delivering security of supply, applies a de-rating factor to contracts on a technology-by-technology basis. All technologies attract a de-rating factor, and all de-rating factors are below 1. This highlights that no single technology can be relied upon to deliver security of supply at all times (else it would have a de-rating factor of precisely 1).
- 8.3.6 Critically, the de-rating factor for solar in the Capacity Market has nearly tripled for projects contracting capacity over the period 2021/22 to 2027/28 [Ref. 80] from 2.34% to 6.35%, demonstrating how quickly the market is moving away from traditional norms of supply risk at winter evening peak times only, and how important a multi-technology mix is to the achievement of security of supply for consumers at all times of the day and year.
- 8.3.7 The then government's Energy White Paper describes that meeting a possible doubling of electricity demand by 2050 *"would require a four-fold increase in clean electricity generation with the decarbonisation of electricity increasingly underpinning the delivery of our Net Zero target"* [Ref. 10, p42].
- 8.3.8 A significant increase in UK electricity generation capacity is required to meet growing demand and deliver security of supply under different weather conditions. Because the weather is uncontrollable, more capacity is needed

to ensure that demand can be met even when renewable output is low. The implication is that when renewable output is high, there is a risk of oversupply. The laws of supply and demand in liquid markets such as electricity, imply that at times of oversupply, the price of the traded commodity – i.e. electricity – will decrease.

- 8.3.9 NGENSO state that *“There is day-to-day uncertainty due to weather but in general, solar generation is quite predictable over the course of a year and the position of the sun and its expected radiation levels over the year are well known. This means it can be a great asset for meeting annual demand levels, especially [and therefore by extension, not exclusively] when coupled with suitable storage”* [Ref. 19(2023), p132]. Figure 5-6 of this Statement provides further information on the growth of storage facilities in GB.
- 8.3.10 Solar generation, and its potential abundance at foreseeable times of the day and year, will provide regular market signals which support the growth in demand-side flexibility (shifting demand to times of abundant renewable generation) and storage. As well as providing essential support to the security of supply during daylight hours, growth in solar generation will also encourage a shift in demand away from times of traditional peak needs, and/or store abundant energy which can then be dispatched when it is needed.
- 8.3.11 The inclusion of a storage facility as Associated Development to the main solar scheme allows the scheme to support the transition to net zero by providing flexibility to a fully low-carbon electricity system.

8.4 Curtailment

- 8.4.1 National Grid’s Future Energy Scenarios also describes and evaluates the potential for curtailment to occur in the UK’s future electricity system.
- 8.4.2 It is important therefore to explain why curtailment currently occurs in the UK electricity system, and the level of the prices currently paid to generators for some curtailment actions.
- 8.4.3 Currently, the majority of curtailment in the UK occurs on the large-scale wind fleet and mainly due to transmission constraints. Transmission constraints occur when the electricity network linking the point of generation to the major points of consumption, does not have the capacity to transmit all of the generation at certain times, but in particular when generation output is high.
- 8.4.4 In the 12 months starting 1 July 2023 and ending 30 June 2024, National Grid data records that wind generated 67.1TWh of energy. Transmission constraints amounted to 5.6TWh (c.8% of net generation) and constraints due simply to there being ‘too much wind energy on the system’ totalled c.0.6TWh, or less than 1% of net generation.
- 8.4.5 Curtailment in the UK is therefore currently more to do with *where* electricity is generated, than *how much* electricity is generated, and curtailment in the UK is anticipated to be associated more with wind generation than with solar generation [Ref. 19(2024), Table ES1].
- 8.4.6 Curtailment for network constraints currently results in a compensation to the asset operator for the electricity which would have been generated and sold

- but for the fact that that energy was not accepted onto the transmission system.
- 8.4.7 An asset located on a transmission network which is well connected to demand centres, is unlikely to be curtailed for the same reasons as the majority of current curtailment in the UK, however the possibility of curtailment for non-locational reasons remains.
- 8.4.8 In such circumstances, curtailment would occur because more energy was being generated than that which could be consumed or stored at that time. Figure 9-1 of this Statement shows that an excess of supply reduces market price, incentivising price-sensitive demand to increase, or in extremis, incentivising supply to shut down so as to avoid having to pay (rather than be paid) to generate. Critically, neither of these outcomes results in a compensation payment from consumers to the asset operator for the electricity they have not generated.
- 8.4.9 NGESO's analysis shows that average solar curtailment in the years 2031 – 2040 is anticipated to be 1.5 – 4.2TWh [Ref. 19(2024) Table ES1], or 3.6 – 6.4% of generation. NGESO anticipate curtailment to get worse before it gets better, as network investment, more storage and higher demand reduce solar curtailment by approximately 50% over the period 2041 – 2050.
- 8.4.10 **Chapter 7** of this Statement describes that the Scheme proposes to connect to a well-connected section of the NETS which has available transmission capacity. As such, transmission constraints are unlikely to cause curtailment at the Scheme and during its operational life, the Scheme is unlikely to receive compensatory payments for curtailments which would ultimately be funded by consumers.
- 8.4.11 Further, with energy storage assets proposed as Associated Development to the main solar scheme, the Scheme will be able to provide its own operational flexibility to the electricity system without relying on flexibility provision from other electricity system users. Such flexibility could include storing solar energy in the co-located batteries during periods of abundant solar supply until it is needed.
- 8.4.12 More generally, a growth in the capacity of flexible assets (including demand-side response, storage, interconnection and hydrogen) will help to minimise the curtailment of assets in the future UK electricity system arising from the build out of large capacities of renewable generation. But because renewable electricity is variable, the UK may not be able to meet demand at times of low renewable output without the build out of large capacities of renewable generation.
- 8.4.13 Having insufficient renewable generation capacity operational in the UK may cause:
- a. Power cuts (contrary to the government's aim to ensure security of supply);
 - b. Price spikes (contrary to the government's aim to shield consumers from volatile energy markets); and/or
 - c. Stand-by fossil fuel assets to generate (contrary to the government's aim to decarbonise the electricity system by 2030).

- 8.4.14 The alternative approach, which is the government's approach, is the build-out of large capacities of renewable generation. This approach meets the government's aims and provides opportunities for market approaches to manage curtailment through flexibility, by:
- a. Using curtailed energy to support security of supply when demand is high;
 - b. Keeping consumer costs down by capturing and storing energy when it is abundant (therefore cheap) and releasing it when it is needed; and/or
 - c. Displacing stand-by fossil assets by using stored energy as a low-carbon 'peaking' energy resource, further supporting the government's ambition to deliver 'Clean Power by 2030'.
- 8.4.15 One such flexibility measure, which has already gained traction in the UK and has been enabled by the introduction of smart meters into domestic homes, is the introduction of 'time of use tariffs' (ToUTs). ToUTs apply different prices to consumption metered at different times of the day or year. ToUTs provide customers with the opportunity to schedule their electricity consumption towards times of low prices and away from times of high prices. Consumers would benefit from their actions through their normal utility bills.
- 8.4.16 In summary, future curtailment, if/when it occurs, could be interpreted as a 'good' problem for the UK power sector to have when compared to the alternate of under-delivering on the UK's current decarbonisation and energy security aims. This is because if curtailment occurs, it would be because large capacities of renewable generation have already been built out to deliver low-carbon supplies to meet demand, deliver security of supply, meet carbon reduction targets and reduce wholesale costs of energy.
- 8.4.17 Further, the market signals associated with curtailment, will drive the development of consumer and/or supply side flexibility to make efficient use of abundant resources and drive further security of supply, decarbonisation and affordability benefits for consumers across the whole energy system.

8.5 The System Adequacy Of Solar Generation

- 8.5.1 System adequacy is primarily managed through the GB Capacity Market. On an asset-by-asset basis, intermittent generation capacity, such as wind or solar, can be variable, which means that individual assets are de-rated in the Capacity Market. However, the output from portfolios of intermittent capacity, especially those that consist of different technologies, can be relied upon more fully and are easier to forecast more accurately. This supports the efficient provision of system adequacy and security of supply.
- 8.5.2 The following analysis demonstrates this by showing that the average aggregate monthly output per unit installed capacity of a multi-technology portfolio of wind and solar assets is less variable than the average monthly output per unit installed capacity of each of the single technology portions of that portfolio.
- 8.5.3 The data for Figure 8-1 is sourced from National Grid's Demand Data and Actual Metered Generation data. These are operational data files, available to download from National Grid's data portal, and are updated on a regular basis. These files are large and as such have not been submitted as a

- reference to this document, but extracts can be provided to the Examining Authority if required or requested.
- 8.5.4 The Demand Data files include National Grid's estimated output, and capacity, for unmetered wind and unmetered solar generation.
- 8.5.5 The Actual Generation file includes metered wind generation (but not installed capacity). The workbooks accompanying regular FES publications also include historic installed wind capacity by type (onshore and offshore), connection type (distribution and transmission) and year [Ref. 19(2024)].
- 8.5.6 Data from 1st January 2022 to 31st December 2023 has been used by the author to derive a series of historical metered wind capacity of onshore and offshore wind.
- 8.5.7 Using two recent years of data provides a credible representation of national generation and capacity including all micro wind, onshore wind and offshore wind as well as rooftop, commercial and larger scale ground mounted solar to a total combined portfolio of approximately 30GW of wind and 15GW of solar (estimated at year end 2023). The solar and wind generation facilities included in this portfolio are located throughout the UK.
- 8.5.8 Figure 8-1 displays the resulting output per unit of installed capacity at a monthly level for GB wind (green columns) and solar generation (yellow columns). It shows the seasonality of wind load in GB: low in the summer months but higher in the Autumn through Spring. It also shows the seasonality of solar generation in GB: high in the spring and summer months and lower in autumn and winter. The output associated with an illustrative combined portfolio is shown by the red line.
- 8.5.9 The red line in Figure 8-1 is the weighted average load factor for the combined national portfolio of wind and solar i.e., $(\text{wind generation} + \text{solar generation}) / (\text{wind capacity} + \text{solar capacity})$. The red line always lies between the extent of the green and yellow columns and is flatter across the timeframe analysed than either of the columns, showing a lower variation from month-to-month through the year.
- 8.5.10 Taking a multi-technology approach to electricity supply can reduce the effects of weather variability on output. By combining two generation portfolios which are largely independent of each other (meaning, the level of solar generation in the UK at any time is not mathematically dependent on the level of wind generation in the UK at that time, and vice-versa) the variation of the combined portfolio of (solar + wind), when averaged over a period of time, is lower than the variation of each of the portfolios separately.
- 8.5.11 Clearly, the identification of a general trend does not imply conformance to that trend on all days and at all times. Future 'actuals' will be dependent on prevailing weather conditions as well as levels of installed wind and solar generation capacity at delivery.




Figure 8-1: Illustrative Generation Dependability for a combined portfolio of solar and wind in GB [Author analysis, Ref. 81, Ref. 20(2024)]

- 8.5.12 Running the analysis over different time periods by using a different range of historical data derives similar results. The level of certainty which may be ascribed to the general conclusions of the analysis is therefore high, based on historical information. Insofar as solar and wind capacity both increase in the future in broadly similar proportion to each other as has been experienced historically, then it is reasonable to assume that the conclusions reached will remain valid in the future.
- 8.5.13 Forecastable and stable generation output per unit of installed capacity is important because it relates to the reliability of, and therefore NGESO’s ability to depend on, forward forecasts of generation outturn. At the macro level, a greater reliability of generation outturn allows for a more efficient and targeted asset development program to be developed; and a lower requirement for (currently fossil fuelled) backup plant, without creating an excess of generation capacity.
- 8.5.14 A growing portfolio of solar generation would therefore complement the existing and growing GB wind portfolio to deliver a combination of low-carbon generation with improved reliability and predictability than associated with the separate technologies.
- 8.5.15 A second analytical model has been developed to illustrate the collective capability of solar and wind generation in meeting seasonal demand for electricity in the UK.
- 8.5.16 The model evaluates the contribution made by different generation classes to overall national demand throughout a year on a month average basis but does not take into account the requirement to balance supply and demand on a short-term basis.
- 8.5.17 The data sets model underlying demand, heat demand, transport demand and different sources of low-carbon supply including solar generation and wind generation and how each of these change through the year.

- 8.5.18 The analysis is based on the average within-year shape of demand from 2015 to 2019.
- 8.5.19 Each data set therefore comprises a month-to-month shape and a future level. The methodology used to derive the shape for each series is as follows:
- a. 2015 – 2019 national demand data is used to derive a month-average demand expressed as a ratio of annual average demand. The data therefore avoids any one-off within-year impacts associated with outlier weather patterns (because the base data covers multiple years) or due to the COVID-19 pandemic and subsequent cost of living crisis (because data including and after 2020 has not been used);
 - b. The heating demand shape has been derived from the industry rule of thumb that in the UK, gas demand in the winter is up to five times higher than in the summer, and therefore electricity demand for heating (when it displaces gas heating) will follow a similar shape;
 - c. The transport demand shape has been estimated as flat through the year; and
 - d. Demand for electrolysis of water to produce hydrogen has been included in monthly demand estimates for completeness but at only small capacities in the 2030 timeframe, in line with National Grid's projections.
- 8.5.20 Total demand is the sum of underlying demand, heat demand, transport demand and electrolysis demand.
- 8.5.21 Supply has been modelled with only zero-carbon technology types, consistent with NGENSO's FES (2024) Electric Engagement (EE) pathway. However, it should be noted that this pathway does not meet the government's ambition to deliver 'Clean Power by 2030'. The results are shown in Figure 8-2. The technology types are: zero carbon baseload (grey), onshore wind (green), offshore wind (blue) and solar (yellow).
- 8.5.22 The methodology used to derive the shape for each series is set out below.
- a. Zero carbon baseload generation represents nuclear energy from the remaining existing UK nuclear fleet (Hinkley Point C is not assumed to have been commissioned by 2030 in the EE pathway), alongside existing biomass, energy from waste and hydro generation. All assets are assumed to have an Unplanned Capability Loss Factor (breakdown rate) of 10% and planned outages are assumed to take place on the nuclear plant in rather than winters, leading to a summer baseload low carbon technology monthly availability of 50.6% and a winter month availability rate of 54.1%;
 - b. The average monthly load factor for onshore and offshore wind and solar generation has been derived from National Grid market data for the entire UK operational wind and solar portfolio for the period 2016 to 2023. The data sources are the same as those used to derive Figure 8-1 previously but over a wider historical dataset. Historically, both onshore and offshore wind generation in winter months (October through March) has been just below twice the level seen in the low months of the year (June and July), which is almost the inverse solar generation levels; and

- c. The data derives a within-year shape (at monthly granularity) which is consistent with National Grid Operational Data for the entire UK operational solar estate over the period 2016 – 2020.

8.5.23 Table 8-1 below shows the load factors assumed in the analysis alongside National Grid assumptions [Ref. 19(2024), Data worksheet ES1] and other relevant sources, such as Department for Energy Security and Net Zero (DESNZ) Regional Renewable Electricity Report [Ref. 9(2023)] and DESNZ Electricity Generation Cost Report [Ref. 67(2023)].

8.5.24 New offshore wind farms have significantly higher load factors than early farms, and the technology is projected to see significant growth from today through to 2030 and beyond. This is predominantly due to:

- a. Developments being located in areas with higher average wind resource, and larger more efficient turbines now being available on the market. The model assumption (derived from author analysis) matches the FES 2024 assumption; and
- b. New onshore wind farms are likely to be more constrained in location and turbine size than new offshore wind farms and growth in load factor is less certain. The model assumption therefore adopts a lower load factor, also derived from Author Analysis, for onshore wind than for offshore wind which also matches the FES 2024 assumptions.

Table 8-1: Comparison of assumed load factors with independent data sources
[Ref. 19(2024), Table ES1, Ref. 9(2023), Ref. 67(2023)]

Load Factor (%)	Model Assumption	FES Average	DESNZ Regional Data	DESNZ Cost Assumption
Offshore Wind	45%	45%	37%	65%
Onshore Wind	29%	29%	27%	41%
Solar	10%	12%	10%	11%

8.5.25 The FES [Ref. 19(2024), Table ED1] provides projections for the average levels of demand associated with underlying electricity use, heat, transport and electrolysis capacities of each technology which may be in operation in 2030.

8.5.26 The analysis assumes annual average load levels for underlying demand of 29.4GW, for heat demand of 3.5GW, for transport demand of 3.1GW and for Electrolysis of 1.59W.

8.5.27 The model assumes future levels of supply capacity which are consistent with the FES Electric Evolution net zero pathway and are listed in Table 8-2, alongside the projections of capacity in FES 2024 (average; minimum and maximum installed capacity in 2030 for each technology in the three net zero compliant scenarios.

8.5.28 The model is an illustration based on projections of capacity roll out, electrification of demand and efficiency / load factor. Table 8-2 shows the

output of just one projection of a multitude of possible projections. Other outcomes are therefore possible, including those associated with rapid expansions of other zero-carbon generation technologies, should they materialise.

Table 8-2: Comparison of installed capacity assumptions vs. FES 2024 [Ref. 19(2024), Table ES1, Author Analysis]

Assumed Capacity (GW)	Model Assumption	FES 2024 Average	FES 2024 Min	FES 2024 Max
Offshore Wind	46	43	29	54
Onshore Wind	26	24	20	27
Solar	34	31	22	40
Zero-carbon baseload	13	14	13	15

8.5.29 However, considering the contribution only of proven low-carbon generation technologies to meeting future demand is a prudent approach because:

- a. **Section 2.11** of this report describes the urgency for action to reduce carbon emissions from the UK’s electricity system in the critical 2020s, and **Sections 5.6 - 5.8** of this report describe that there are as yet no fully funded and consented CCUS, nuclear or hydrogen projects set to deliver in the 2020s beyond the projections already included in the analysis; and
- b. **Paragraph 3.2.13** articulates the prudent view that infrastructure development should be planned on a conservative basis, without over-relying on yet-to-be-proven technologies, technologies with long development lead-times, or technologies which have historically experienced funding difficulties.

8.5.30 Figure 8-2 should not be inferred to advocate either for a specific renewables mix, nor for a system without adequate backup or flexible generation, both of which may be required to support decarbonisation of the NETS by managing day-to-day swings in both demand and supply.

8.5.31 The government’s mission is to deliver ‘Clean Power by 2030’ by rapidly expanding the capacity of renewable generation installed in the UK. **Chapter 5** of this report describes that although the current pipelines for low-carbon generation are full, it cannot be relied upon that the delivery of those pipelines will be achieved, or that achieving any one of the targets set by the government (to triple solar capacity by 2030, alongside doubling onshore wind and quadrupling offshore wind) will also be achieved.

8.5.32 However, Figure 8-2 shows that a portfolio of low-carbon generation which includes solar, onshore and offshore wind and a low-carbon base, if delivered, is capable of closely matching a future projection of national electricity demand on a month-average level.

8.5.33 Figure 8-2 uses average load factor data therefore, for renewable technologies, load in some months may be higher than the data presented, and in other months load may be lower.

- 8.5.34 Figure 8-2 shows that if the capacity projections included in the FES Electric Engagement pathway are delivered across offshore wind, onshore wind and low-carbon baseload technologies, it would be likely that sufficient energy would be generated to meet estimated demand in some winter (October to March) months. The tops of the blue stacked columns (total generation) are near to the red line (total demand) in October, November and December and are within reach of the red line in January, February and March.
- 8.5.35 However, because of the seasonality of wind generation in UK territory, the projected capacities of low-carbon generation would likely be insufficient to meet summer (April to September) demand. The top of the blue stacked column is below the red line in the majority of these months.
- 8.5.36 Approximately 34GW of solar (an increase of 17GW on mid-2024 levels, consistent with the Electric Engagement pathway) would provide additional low-carbon energy to help meet the UK’s electricity needs throughout the year, and specifically in the summer months when wind energy yields are lower.




Figure 8-2: Deploying 47GW of large-scale solar alongside government offshore wind ambitions (50GW) meets anticipated seasonal demand levels [Ref. 19(2024), Tables ES1 & ED1, Author analysis]

- 8.5.37 The EE pathway does not meet the government’s ambition to triple solar capacity by 2030. However, demand must be met under a wide range of supply scenarios, including when renewable supplies are low. This analysis should not therefore draw the reader to the conclusion, that the government has over-estimated the level of future capacities needed to achieve their aims of delivering ‘Clean Power by 2030’.
- 8.5.38 To meet 2030 summer levels with a similar level of reliability as shown in the EE pathway without solar generation, a further c.14GW of offshore wind generation (i.e. a total installed capacity of ~60GW), or an additional c.10GW of low-carbon baseload generation (two new Hinkley Point C equivalent power plants), would be required to be built in the next 10 years.
- 8.5.39 However, by building out either additional low-carbon baseload or offshore wind generation capacity of the levels indicated to meet summer demand

levels without solar, there would be significant over-generation of power in the winter periods of between 7% and 12%. Over-generation may be curtailed (either at a cost to the consumer or by reducing available revenues to asset operators) or stored. If revenues are reduced for asset operators, in some cases assets may not be commercially attractive and therefore may not get built out.

- 8.5.40 The model supports the conclusion that the deployment of large-scale solar alongside offshore wind, onshore wind and low-carbon baseload assets provides the opportunity for a lower capital, lower curtailment (therefore lower cost) energy system through diversity of asset type than that provided by scenarios which do not include solar generation.
- 8.5.41 A high degree of certainty may be attached to this conclusion because of the horizon of data used to inform variable inputs to the model, and consistency of these and other assumptions with those made in National Grid ESO's FES 2024 pathways.
- 8.5.42 As the technical and economic viability of inter-seasonal storage advances, more options will become available for optimising GB's generation mix in relation to balancing capital deployment, development risk, the availability of suitable locations and ongoing system operations (e.g. curtailment). However, based on current assessments, it is clear that the deployment of large-scale solar alongside that of offshore wind, onshore wind and low-carbon baseload assets, provides the opportunity for a lower capital, lower curtailment (therefore lower cost) energy system through diversity of asset type than that provided by scenarios which do not include solar generation.

8.6 Conclusions on System Security

- 8.6.1 This Statement of Need sets out the case for the urgent development of low carbon sources of electricity in the UK. The British Energy Security Strategy provides additional focus on both the scale and the urgency to deliver new low carbon generation capacity, and the Scheme is ideally suited to play an essential role in meeting that urgent need.
- 8.6.2 Although individual renewable assets are variable generators, aggregated generation output from portfolios which consist of different renewable technologies is more stable. The generation profiles of diverse ranges of low-carbon generators combine to meet seasonal average demand levels without requiring significant and unproductive capital investment, seasonal excess generation, or inefficient network / system operating costs.
- 8.6.3 Many integration measures are already available, or are already in development, which, over short periods, help balance electricity generation from variable generators to meet demand, and to ensure that the best use is made of low-carbon electricity when it is being generated in oversupply. For example, BESS, pumped hydro or interconnectors (see **Section 5.11**).
- 8.6.4 The contribution made by flexible assets to the short-term balancing of supply and demand are described in **Section 6.9** and **Chapter 7**. However, until inter-seasonal storage is brought forwards at scale and at grid parity costs, the most efficient measures for seasonal balancing of renewable generation include increasing the capacity and geographic diversity of renewable generators, including portfolios of assets with complementary

- seasonal generation profiles; and managing shorter term intermittency through storage or other measures.
- 8.6.5 Solar is an asset class which is needed to support a high level of generation adequacy and generation dependability within the GB electricity system.
- 8.6.6 The Scheme, if consented, will deliver c. 1% of the new solar generation capacity required in the FES net zero pathways from 2023 to 2040, [Ref. 19(2024)]. In this context, the Scheme and many others like it are essential to move the UK towards the future of efficient decarbonisation through the deployment of large-scale, technologically and geographically diverse low-carbon generation assets.
- 8.6.7 Global expertise in the operation of electricity systems with high proportions of RES is growing. Technologies which help the integration of renewable assets to the grid are already in operation in the UK. However, solar assets are increasingly able to provide important system services themselves, and flexible integration assets are being deployed on a stand-alone and co-located basis to do the same, as well as to manage short-term supply / demand volatility.
- 8.6.8 Growth in solar capacity, alongside other renewable technologies, is expected to improve the dependability of those assets as a combined portfolio, and this is expected to reduce further any integration costs associated with such growth.
- 8.6.9 The Scheme, if approved, would contribute to an adequate and dependable GB generation mix, through enabling the generation of more low-carbon power from indigenous and renewable resources. Therefore, the approval, construction and operation of the Scheme will make a significant contribution to GB's energy security needs, and the decarbonisation needs of the UK.

9. The contribution of large scale solar to the affordability of electricity

9.1 Chapter overview

- 9.1.1 This chapter provides an overview of the affordability benefits of large-scale solar in the UK.

“Analysis [commissioned by the NIC] suggests that there is no material cost impact, either over the short or long term, of deploying renewables faster. Renewables are now the cheapest form of electricity generation due to dramatic cost reductions in recent years. Cost reductions have been greater than was predicted in 2018 when the Commission made its recommendation on what level of renewable generation the government should be targeting” [Ref. 63, p9].

9.2 Pricing in the GB electricity market

- 9.2.1 In the GB power market, generators schedule themselves to generate in response to whether a market price signal for a specific period is above or below their marginal cost of generation. Marginal cost of generation is defined as the cost of generating an additional 1MWh, usually including variable fuel, emissions and transmission costs.
- 9.2.2 Each day is subdivided into 48 half-hour Settlement Periods (SPs) and power is traded ahead of delivery for these periods, or continuous groups thereof, from just 90 minutes ahead, up to months or even seasons ahead.
- 9.2.3 Solar generation has very low or zero marginal costs and therefore solar assets generate as much power as they are able to, when they are available (i.e. whenever there is light) and whenever power prices are positive. Because of the variable, but forecastable, nature of solar irradiation, they also tend to trade on near-term power markets, therefore much of the impact of sunny (or overcast) weather on power price is felt in the few days close to delivery.
- 9.2.4 Thermal and hydro plants have higher marginal costs, relating to the cost of the fuel they are converting into that additional MWh, and any emissions costs associated with the use of that fuel. Thermal and hydro plants will therefore only generate when the market is providing a higher price signal, i.e. when demand is expected to be higher than the supply of low-marginal cost supplies at the time of dispatch. Thermal and hydro plants may also trade power, fuel and emissions costs into the future to fix their income.
- 9.2.5 Increases in the cost of source fuels and emissions increase the cost of generation from these assets, therefore when they are required to generate electricity, they will do so at a high cost which increases the price of electricity for all market consumers for that period.
- 9.2.6 All generators produce active power (MWs), and at all times, the total national active power generated must meet the total national system load. If solar farms are generating electricity during a settlement period, then less electricity is required from plants with more expensive marginal costs, therefore the price of electricity for that settlement period reduces.

- 9.2.7 Emissions pricing ensures that carbon-emitting generation is more expensive to dispatch than zero-carbon generation. Therefore, by undercutting carbon emitting assets on marginal cost, zero-carbon assets will displace carbon intensive assets, providing both a carbon emission saving and a cost benefit to consumers.
- 9.2.8 This market mechanism is illustrated in Figure 9-1. The blue line, increasing from left to right along the x-axis, represents the marginal cost of generation in GB at each level of demand. As demand increases, more expensive supply must be scheduled into the market to meet that demand.
- 9.2.9 The three red vertical lines represent different levels of demand. At a mid-level of demand, the solid vertical red line crosses the blue line (in this illustration: at about £45/MWh) and is the price of electricity for that period.
- 9.2.10 If demand reduces (e.g. to the left-hand dashed vertical red line), less plant is required to run to meet demand, therefore the marginal cost of the most expensive asset required to run to meet demand is lower and the price of electricity for that period would also reduce vs. the previous case.
- 9.2.11 Conversely, if demand increases, (e.g. to the right-hand dashed vertical red line) assets with higher marginal costs of production are required to run and they set a higher price of power.
- 9.2.12 The blue line in Figure 9-1 will be different for each half hour settlement period because generators may become available or unavailable through the day due to outages or breakdowns. The level of renewable generation will also change through the day. More renewable generation will stretch the blue line within the red ellipse (around a zero marginal cost of power), lowering the price of electricity for that period (the point of intersection between a vertical red line point with any fixed red line) and as a result, the blue line slides to the right for all higher levels of demand.
- 9.2.13 The marginal cost of production to meet demand over these periods will therefore be lower and as a result, the traded price of power will be lower.
- 9.2.14 By running this type of analysis over every settlement period over the future trading horizon, it is possible to derive a view of the price of power for the next week, month, quarter or season.
- 9.2.15 The conclusions are the same, however: increasing the capacity of renewable assets in GB reduces the traded price of power.
- 9.2.16 The GB power pricing mechanism also provides the explanation as to why the British Energy Security Strategy increases the UK's ambition for renewable generation to reduce our dependency on volatile international energy markets.




Figure 9-1: Representative marginal cost stack for the GB electricity system [Author analysis]

9.3 Levelised Cost Of Solar Generation

“The International Renewable Energy Agency (IRENA) found that between 2010 and 2019, the cost of solar PV globally dropped by 82% ... In 2019 alone, the cost of electricity from solar fell by 13% to just over five pence per kilowatt-hour. This means that by ... [2020] globally, there will be up to 1,200GW of existing coal capacity that will cost more to operate than it would to install new solar PV capacity”. [Ref. 82].

- 9.3.1 The market mechanisms described in **Section 9.1** only reduce the price of power if solar projects come to market, or if developers believe they are able to make reasonable returns on their investments. The cost of solar generation is an important enabler of its development. Solar panels and electrical infrastructure have become larger and more efficient, as described in **Section 6.7**, meaning that more electricity can be generated from the same area of land as was previously possible. As a consequence, solar is now a leading low-cost generation technology (see Figure 9-2).
- 9.3.2 Levelised Cost of Energy (LCOE) is an important metric allowing all forms of generation to be compared with each other on a consistent basis. LCOE is calculated using a discounting methodology and is a measure of the lifetime unit cost of generation from an asset, including capital and operating costs. In-life cap capital and operating expenses, for example the re-powering of sites to manage anticipated degradation, are also anticipated.
- 9.3.3 Figure 9-2 shows the results of an analysis of the government’s Electricity Generation Costs report [Ref. 67(2023)] with the range of values representative of different complexities of technical solution.
- 9.3.4 Figure 9-2 shows a ‘triple’ of columns for each of five generation technologies. Each column within each triple shows the technology’s anticipated LCOE for assets commissioning in 2025 (left hand column), 2030 (middle column) and 2035 (right hand column).
- 9.3.5 Governmental modelling anticipates different projected operational lifetime, load factors (a measure of the output of the plant per year versus its

theoretical maximum if availability is unconstrained), capital and operational costs and development duration to derive a range of cost projections. The blue bars show that range while the red columns represent the LCOE range under different projections for input fuel costs for those technologies which require a non-zero cost input fuel.




Figure 9-2: Levelised cost of energy comparison [Ref. 67]

- 9.3.6 The levelised cost ranges of large-scale solar (governmental analysis assumes a capacity of 16MW) are highlighted in yellow. Figure 9-2 shows that renewable generation technologies hold a significant levelised cost benefit when compared to technologies which are reliant on fossil fuels, even when fuel input costs are included at a low level.
- 9.3.7 The analysis illustrates that the LCOE of solar delivered in 2025 is lower than the LCOE of offshore wind delivered at a similar timeframe, and is comparable to the LCOE of onshore wind. However, predictions are that solar generation delivered in future years is likely to be cheaper than both onshore and offshore wind on an LCOE basis.
- 9.3.8 A project with a lower LCOE is more likely to be developed because of its greater resilience to low market prices, versus a project with a higher LCOE. Consumers will benefit from such a scheme through the market mechanisms described in **Section 9.2**. A lower LCOE project would also be able to bid into a future CfD Allocation Round at a lower strike price than a project with a higher LCOE, and if such a project secured an agreement, consumers would also benefit versus the case that it did not.
- 9.3.9 The government's Cost of Electricity Generation report series [Ref. 67] also shows that solar LCOE has reduced significantly in the last decade. Solar, already being highly competitive against current conventional and renewable generation costs, is predicted to retain a cost advantage for the decades ahead.
- 9.3.10 Solar costs have been driven down through the realisation of efficiencies in capital infrastructure, development and integration costs, and lifetime O&M. This includes working to reduce the effects of degradation of solar panels and inverters. Improvements in lifetime cost are likely to continue to be delivered.




Figure 9-3: Cost of Electricity Generation. An evolution of Levelised Cost forecasts [Ref. 67, Author analysis]

- 9.3.11 Technological advances have also increased the efficiency of solar panels (see **Section 6.8** of this Statement) and extended their useable lifetimes. At the same time, economies of scale through the global supply chain have reduced the cost of panels. Development costs have also reduced as efficiencies in the build process have been captured through prior experience.
- 9.3.12 Figure 9-3 shows the results of previous and current governmental analysis. The mid grey lines show the 2016 projections of the LCOE of solar commissioning in 2020, 2025 and 2030. The solid line shows the central case projection, and the dotted line shows the low case projection.
- 9.3.13 The 2013 projections (not shown in Figure 9-3) were approximately 70% higher on a consistent 2023 real price basis. Just four years later, the government's 2020 solar LCOE projection (shown in dark grey) was over 30% lower for sites commissioning in 2025 and 2030.
- 9.3.14 The projections made in 2023 are shown by the yellow solid line (central cost) and are bounded by the high and low cases shown by the dotted lines. The 2023 solar LCOE estimate is a further 10% lower than the 2020 estimate on a consistent 2023 real price basis.
- 9.3.15 Industry-sourced data and opinion concurs with the direction of the findings of these governmental reports. For example, a CCC illustration of data from IRENA analysis (2020) shows cost reductions in and the competitiveness of renewable generation technologies against fossil fuel generation [Ref. 8(2020), Figure 2.2].
- 9.3.16 Figure 9-3 should not however be taken as a justification for delaying the development of renewable projects, in order to capture a lower future installed price. **Section 2.2** explains the rationale for urgent action to develop significant capacities of low-carbon generation. Time is a precious commodity.
- 9.3.17 Further, it is the continuous development of projects which allows learnings to be implemented, technology to advance through practical application, and markets and supply chains to evolve and improve efficiency, to achieve the future cost reductions which have been forecast by previous governments and others.

- 9.3.18 Solar was included in the 2021/22 CfD Allocation Round (AR4) to help *"deliver a diverse generation mix at low cost"* and to realise *"the rate and scale of new projects needed in the near-term to support decarbonisation of the power sector and meet the net zero commitment"* while providing other benefits such as diversity of supply through different resource requirements and a geographical separation from other significant renewable energy sources [Ref. 83, pp16, 20].
- 9.3.19 Many solar projects were successful in CfD AR4, AR5 and AR6 (2024). Auction results indicate that solar is an important technology within the evolving GB electricity system its costs are competitive [Ref. 84].
- In AR4, over 2.2GW of solar capacity across 66 projects (commencing in 2023/24 or 2024/25) secured CfDs at an initial strike price of £45.99 (2012 indexation, estimated to be equivalent to £64.18 in 2024 money);
 - In AR5, over 1.9GW of solar capacity across 56 projects (commencing between 2025 and 2028) secured CfDs at an initial strike price of £47.00 (2012 indexation, estimated to be equivalent to £65.58 in 2024 money); and
 - In AR6, nearly 3.3GW of solar capacity across 93 projects (commencing in 2026/27 or 2027/28) secured CfDs at an initial strike price of £50.07 (2012 indexation, estimated to be equivalent to £69.87 in 2024 money).

9.4 Whole System Costs

- 9.4.1 The NIC's current view is that RES represent a most likely low-cost solution for GB electricity generation, over large-scale conventional investments:
- "More renewables do lead to more money being spent to match supply and demand: a system with 90 per cent renewables is estimated to cost up to £4.5 billion more per year to balance. But cheaper capital costs are estimated to offset this within the costs for the overall system" ...* [Ref. 79, p39].
- 9.4.2 Both Figure 8-1 and Figure 8-2 provide evidence that the deployment at scale of more than one renewable generation technology will help reduce the capacity of integration technologies needed to manage generation variability across many timeframes, including potentially the long-term storage of excess generation, although it is unlikely to fully remove the need.
- 9.4.3 An Imperial College expert economic analysis of whole system costs of renewables agrees; they show that the integration costs of RES fall on an absolute basis, as capacity increases from 10GW up to 50GW [Ref. 85].
- 9.4.4 The NIC published the results of a whole system cost analysis in 2020. NIC's analysis complements that of the Imperial College team, suggesting that *"there is no material cost impact, either over the short or long term, of deploying renewables faster. Renewables are now the cheapest form of electricity generation due to dramatic cost reductions in recent years."* [Ref. 63].
- 9.4.5 With the development of new schemes, solar technology is proven to be commercially rational over a growing geography. Developing technology, construction risk mitigation, efficient grid connection and efficient financing have all helped keep solar costs down. As a consequence, utility-scale

project costs projected to fall. The global solar market is growing; and the GB solar market is growing as well.

9.5 Conclusions on Affordability

- 9.5.1 Large-scale solar power decarbonises the electricity system and lowers the market price of electricity by generating power so that expensive and more carbon intensive forms of generation do not need to generate as much.
- 9.5.2 In doing so, solar power delivers national decarbonisation benefits and supports consumer affordability aims, to the benefit of electricity consumers.
- 9.5.3 Due to technological advances, solar facilities are already among the cheapest form of electricity generation in the UK and government-produced forecasts indicate that costs will continue to reduce in the future.
- 9.5.4 Scale remains important, and maximising the generating capacity of schemes improves their economic efficiency, and so brings electricity generation to the market at the lowest cost possible.
- 9.5.5 Larger solar schemes deliver more quickly and at a lower unit cost than multiple independent schemes which make up the same total capacity, bringing forward carbon reduction and energy security benefits as well as helping to keep consumer costs in check, in line with government policy (including that of the previous government).
- 9.5.6 The Scheme will be a substantial infrastructure asset, which if consented will deliver large amounts of cheap, secure and low-carbon electricity which will help the UK achieve its Sixth Carbon Budget commitments and stay on track to achieve net zero by 2050. Maximising the capacity of generation in the proposed location for the Scheme represents a significant and commercially rational step forward in the fight against the global climate emergency.

10. Overall Conclusions

- 10.1.1 Decarbonisation is a legally-binding climate change target for the UK and is of global significance. It cannot be allowed to fail, and urgent actions are required in the UK and abroad to keep decarbonisation on track to limit global warming.
- 10.1.2 The NPSs establish a critical national priority for the provision of nationally significant low-carbon infrastructure, which includes large-scale solar farms, because a combination of many or all types of such infrastructure is urgently required for both energy security and Net Zero.
- 10.1.3 NPS EN-1 states that *“For projects which qualify as CNP Infrastructure, it is likely that the need case will outweigh the residual effects in all but the most exceptional cases”* [Ref. 1, Para 4.1.7]. The Scheme is CNP Infrastructure; therefore, it follows that the urgent need for the Scheme to achieving the UK’s energy objectives, together with the national security, economic, commercial and net zero benefits, will outweigh any other residual impacts not capable of being addressed by application of the mitigation hierarchy [Ref. 1, Para 3.3.63].
- 10.1.4 The Scheme is required to ensure that the UK remains on track to meet its legally binding carbon emissions reduction targets, including the Sixth Carbon Budget, while enhancing national security of supply, and at a cost which, in relation to other electricity generation infrastructure developments, provides value for money for end-use consumers.
- 10.1.5 This Statement has shown that large-scale solar generation is economically and technically viable in the UK, and that it is an economically and technically preferable source of low-carbon energy for the GB electricity consumer.
- 10.1.6 The UK has substantial renewable energy resources, including solar, and large areas of the country receive high levels of solar irradiation. These resources must be harnessed to decarbonise our economy.
- 10.1.7 The UK policy view is that a low-cost, net zero consistent system is likely to be composed predominantly of wind and solar [Ref. 10, p43]. Flexible assets are also needed to balance supply with demand. National policy is supportive of solar that is co-located with storage to maximise the efficiency of land use. Co-location also helps to maximise utilisation of a scheme’s grid connection capacity, if that connection has both import and export capability.
- 10.1.8 The Scheme will, if consented, bring forwards large-scale ground-mount solar with co-located storage facilities. The Scheme therefore goes towards meeting the government’s aims.
- 10.1.9 **Chapter 5** of this report describes the government’s aims for many renewable technologies and describes the real risks associated with their delivery. If solar generation does not meet the decarbonisation and energy security contributions ascribed to it, the challenge faced by the UK in meeting its decarbonisation targets from other technologies will be significantly harder.
- 10.1.10 Conversely, the continued development of proven low-carbon technologies like large-scale solar is important to protect against the possibility that

- technologies which are currently in 'prototype' stage do not deliver operational capacity at the pace or scale required.
- 10.1.11 Other conventional low-carbon generation (e.g. nuclear or conventional generation with CCUS) and new low-carbon dispatchable generation (e.g. hydrogen) will be important contributors to achieving the 2050 net zero obligation, but their contributions in the timeframe in which the Scheme will deliver are uncertain.
 - 10.1.12 The Scheme would generate power ahead of other potential technologies (which may have longer construction timeframes or have potentially not yet been proven at scale) which will support decarbonisation only in future years and only if they are brought forwards.
 - 10.1.13 The need for solar is especially important given the context of the CCC's identification of the need for urgent action to increase the pace of decarbonisation in the GB electricity sector, and the then government's adoption of their recommendations for the Sixth Carbon Budget (2033 – 2037).
 - 10.1.14 The Scheme will, if consented, be capable of supporting the delivery of the Sixth Carbon Budget. Large-scale solar is needed alongside rooftop solar because without increasing capacities of both types of solar generation, the UK will likely fall short of its solar capacity aims and therefore its climate change targets.
 - 10.1.15 Large-scale solar delivery beyond 2030 remains important not only to reduce power-related carbon emissions, but also to provide a timely next step contribution to a future generation portfolio which will support the electrification and therefore decarbonisation of transport, heat and industrial demand.
 - 10.1.16 As part of a diverse generation mix, solar generation improves the stability of capacity utilisations which in turn improves generation dependability. When developed alongside other renewable technologies, large-scale solar will help smooth out seasonal variations in total GB renewable electricity generation, more closely matching anticipated seasonal average levels of demand.
 - 10.1.17 As Associated Development to the main solar scheme, co-located storage will help the Scheme operate flexibly as an essential part of a zero-carbon electricity and energy system.
 - 10.1.18 The Scheme would connect to an existing grid connection point on an existing part of the NETS, efficiently optimising the use of an already existing national infrastructure asset.
 - 10.1.19 By being connected to the transmission system, large-scale solar generation can and will play an important role in the resilience of the GB electricity system from an adequacy and system operation perspective. This is because the transmission system is able efficiently to transfer bulk power from where it is in abundance to where it is needed. This connection means that it will be required to play its part in helping NGENSO manage the national electricity system.
 - 10.1.20 Large-scale solar generation also supports security of supply by helping reduce the national dependency on imported hydrocarbon source fuels. The

Scheme will therefore also help reduce the UK's exposure to volatile international energy prices.

- 10.1.21 The low marginal cost and low marginal carbon emissions energy generated at the Scheme can be confidently forecast and priced into future contracts for power delivery by all market participants, thus allowing all consumers to benefit from the market price reducing effect of solar generation.
- 10.1.22 The cost of solar generation is already highly competitive against the cost of other forms of conventional and low-carbon generation, both in GB and more widely.
- 10.1.23 Internationally, and importantly for GB in this regard, there is the ongoing trend of solar generation assets becoming larger and more affordable, each subsequent project providing a real-life demonstration that solar schemes of similar size and scale as the Scheme can and should be developed in GB. The development of such schemes will provide decarbonisation, energy security and commercial benefits to consumers.
- 10.1.24 If consented, the Scheme, along with other solar schemes, will make a critical contribution towards net zero. The government aims to triple solar capacity by 2030 and NGENO FES net zero pathways include 28 – 40GW of operational solar capacity in GB by 2030, alongside significant increases in the capacity of other technologies, representing an increase of between 12 and 24GW over the next 5 years.
- 10.1.25 However, the need for new clean power does not stop at 2030. The continued delivery of low-carbon generation facilities beyond 2030 is necessary to meet future electricity demand growth and achieve essential wider societal carbon savings. It is also important to continue to bring forward schemes in the event that 'Clean Power by 2030' is not achieved.
- 10.1.26 The meaningful and timely contributions offered by the Scheme to UK decarbonisation and security of supply, while helping lower bills for consumers throughout its operational life, will be critical on the path to net zero beyond delivery of the government's 'Clean Power by 2030' mission.
- 10.1.27 Without the Scheme, a significant and vital opportunity to develop a large-scale low-carbon generation scheme will have been passed over, increasing materially the risk that future Carbon Budgets and net zero 2050 will not be achieved.
- 10.1.28 The Scheme is a leading GB large-scale solar plus storage scheme. If consented, it would be an essential component of the UK's plan to deliver a future of efficient decarbonisation through the deployment of large-scale, technologically and geographically diverse low-carbon generation schemes and would also deliver flexibility to the UK electricity market.
- 10.1.29 The Scheme addresses all important and relevant aspects of existing and emerging government policy.

11. Author's Qualifications And Experience

11.1 Qualifications And Experience

- 11.1.1 This Statement of Need has been authored by Si Gillett, Director at Humbeat Ltd.
- 11.1.2 Humbeat is an independent electricity consultancy, established in 2016, to support participants in the UK's transition to a low-carbon electricity and energy system. The consultancy supports and advises private individuals and organisations with pre- and post-construction electricity developments by providing commercial and strategic advice in relation to those developments.
- 11.1.3 Humbeat specialises in assessing, describing, and quantifying the benefits specific technologies and individual developments bring to the overarching and urgent need for decarbonisation in the UK. Humbeat has been commissioned to provide electricity market expertise to over 12,000MW of development-phase renewable generation developments across the UK, including over 3,000MW of ground mount solar, ranging from 10MW sites to large-scale developments.
- 11.1.4 Mr Gillett authored Statements of Need for six NSIP solar schemes which received Development Consent between 2020 and 2024, including Cleve Hill Solar Park (May 2020), Longfield Solar Farm (June 2023), Sunnica Energy Farm (July 2024), Mallard Pass Solar Project (July 2024), Gate Burton Energy Park (July 2024) and Cottam Solar Project (August 2024).
- 11.1.5 Mr Gillett also developed evidence to support IROPI (Imperative Reasons of Overriding Public Interest) justifications for Hornsea 3 and Hornsea 4 Offshore Wind Farms. DCOs were granted in December 2020 and July 2023 respectively.
- 11.1.6 Humbeat is currently supporting approximately ten other nationally significant electricity generation infrastructure developments by providing electricity market and low-carbon transition expertise to their development teams, as well as multiple engagements on TCPA planning applications for solar and solar + storage developments.
- 11.1.7 Mr Gillett has 20 years of experience in energy sectors including petroleum and natural gas liquids, and conventional, nuclear, and renewable electricity – on both the generation and sale side. A wide range of energy experience provides a robust basis for a balanced assessment and analysis of the UK energy sector as a whole. This is especially important as the journey to net zero involves more integrated and system-level thinking than has ever previously been required in the electricity sector.
- 11.1.8 Mr Gillett holds Masters degrees in mathematics and nuclear regulation.

12. References

- Ref. 1 UK Government, Overarching National Policy Statement for Energy (EN-1), November 2023
- Ref. 2 UK Government, National Policy Statement for Renewable Energy Infrastructure (EN-3), November 2023
- Ref. 3 IPCC, Sixth Assessment Report, April 2022
- Ref. 4 IPCC, Press Release, Urgent climate action can secure a liveable future for all, 20 March 2023
- Ref. 5 World Meteorological Organisation, news report accompanying the Global Annual to Decadal Climate Update (2024-2028), 2024, accessed August 2024 from [Global temperature is likely to exceed 1.5°C above pre-industrial level temporarily in next 5 years](#)
- Ref. 6 UNFCCC, COP28 Outcomes, accessed January 2024 from ["We didn't turn the page on the fossil fuel era, but this outcome is the beginning of the end": UN Climate Change Executive Secretary at COP 28 Closing | UNFCCC](#)
- Ref. 7 Climate Change Act 2008 (2050 Target Amendment) Order 2019
- Ref. 8 Climate Change Committee, Annual Progress Reports to Parliament (2019 – 2024)
- Ref. 9 UK Government, Government energy use statistics at regional and local authority level, accessed August 2024 from <https://www.gov.uk/government/statistics/total-final-energy-consumption-at-regional-and-local-authority-level-2005-to-2020> <https://www.gov.uk/government/statistical-data-sets/regional-and-local-authority-electricity-consumption-statistics> and <https://www.gov.uk/government/statistics/regional-renewable-statistics> and <https://www.gov.uk/government/statistics/uk-local-authority-and-regional-greenhouse-gas-emissions-national-statistics-2005-to-2020>
- Ref. 10 UK Government, Energy White Paper: Powering our Net-Zero Future, 2020
- Ref. 11 UK Government, Net Zero Strategy, 2021
- Ref. 12 UK Government, British Energy Security Strategy, 2022
- Ref. 13 Rt Hon Chris Skidmore MP, Independent Review of Net Zero: Mission Zero, 2023
- Ref. 14 UK Government, Powering Up Britain, 2023, including:
- a. Joint Overview
 - b. Responding to Independent Review of Net Zero Recommendations
 - c. Responding to CCC Annual Progress Report Recommendations
 - d. Net Zero Growth Plan
 - e. Energy Security Plan
- Ref. 15 UK Government, New laws passed to bolster energy security and deliver net zero, October 2023

- Ref. 16 The Department for Energy Security and Net Zero and Ofgem, Connections Action Plan, November 2023
- Ref. 17 UK Government, National Policy Statement for Electricity Networks (EN-5), 2023
- Ref. 18 UK Government's press release of acceleration of carbon reduction to 2035, 2021
- Ref. 19 UK Government, Digest of UK Energy Statistics (DUKES): energy, accessed August 2024 from [DUKES 6.2.xlsx](#)
- Ref. 20 National Grid Electricity System Operator, Annual Future Energy Scenarios (2012 - 2024)
- Ref. 21 National Grid Electricity System Operator, Energy Background Document, 2024
- Ref. 22 UK Government, UK Energy in Brief, 2021
- Ref. 23 Climate Change Committee, Net Zero – The UK's contribution to stopping global warming, 2019
- Ref. 24 National Infrastructure Commission, Net Zero: Opportunities for the power sector, 2020
- Ref. 25 Energy Systems Catapult, Innovating to Net Zero, 2020
- Ref. 26 Climate Change Committee, The Sixth Carbon Budget: The UK's path to Net Zero, 2020
- Ref. 27 UK Government, Impact Assessment for the sixth carbon budget, 2020
- Ref. 28 HM Government. The Ten Point Plan for a Green Industrial Revolution, 2020
- Ref. 29 Guardian, Majority of new cars sold in UK will have to be fully electric by 2030 Government confirms, 2023, accessed from [Most new cars sold in UK will have to be fully electric by 2030, government confirms | Automotive industry | The Guardian](#)
- Ref. 30 Society of Motor Manufacturers and Traders, Vehicle Data / Car Registrations, accessed September 2024 from [UK new car registration data, UK car market - SMMT](#)
- Ref. 31 The Labour party, Change – Labour Party Manifesto 2024, accessed July 2024 from [Change-Labour-Party-Manifesto-2024-large-print.pdf](#)
- Ref. 32 UK Government, PM speech on Net Zero, 20 September 2023
- Ref. 33 UK Government, Taking charge: the Electric Vehicle Infrastructure Strategy, 2022
- Ref. 34 UK Government, Electric vehicle charging devices by local authority, accessed September 2024 from [Markdown map LocalAuthority publication template.knit](#)
- Ref. 35 Energy Live News, Boris Johnson promises to “*build build build*” to help UK recover from coronavirus crisis, 2020
- Ref. 36 Prime Minister's Office, A New Deal for Britain, 2020

- Ref. 37 BBC, Ban on new petrol and diesel cars in UK from 2030 under PM's green plan, 2020
- Ref. 38 National Grid ESO, TEC Register, accessed August 2024 from [Transmission Entry Capacity \(TEC\) register | National Energy System Operator](#)
- a. Enso Energy, Armthorpe Lane Solar Farm, accessed Sept 2024 from <https://ensoenergy.co.uk/projects/armthorpe-lane-solar-farm/>
 - b. Innova, Almholme Energy Hub, accessed September 2024 from <https://innova.co.uk/projects/almholme-energy-hub/>
- Ref. 39 UK Government, Renewable Energy Planning Database, accessed August 2024 from [Renewable Energy Planning Database: quarterly extract - GOV.UK](#)
- Ref. 40 Helm, D. Cost of energy review. BEIS, 2017
- Ref. 41 Low Carbon Contracts Company, CfD Register, accessed August 2024 from <https://cfd.lowcarboncontracts.uk/cfd-register/downloadfiles>
- Ref. 42 EMR Delivery Body, Capacity Market Registers, accessed August 2024 from <https://www.emrdeliverybody.com/CM/Registers.aspx>
- Ref. 43 National Grid ESO, ESO leads the way with major initiative to accelerate connections to the electricity transmission grid, February 2023
- Ref. 44 BBC, Norfolk Boreas: Work on offshore wind farm stops over soaring costs, July 2023
- Ref. 45 UK Government, National Planning Policy Framework, September 2023
- Ref. 46 Market regulatory notifications for the UK's existing nuclear fleet are available at www.remit.edfenergy.com, accessed August 2024
- Ref. 47 World Nuclear News, Heysham 2 and Torness end dates brought forward by EDF, 2022
- Ref. 48 The Guardian, Hinkley Point C could be delayed to 2031 and cost up to £35bn, says EDF, January 2024, accessed from <https://www.msn.com/en-gb/news/uknews/hinkley-point-c-could-be-delayed-to-2031-and-cost-up-to-35bn-says-edf/ar-BB1h8XD6>
- Ref. 49 UK Government, Sizewell C starts private investment process, September 2023
- Ref. 50 UK Government, Further steps to prepare Sizewell C for construction, accessed February 2024 from [Further steps to prepare Sizewell C for construction - GOV.UK](#)
- Ref. 51 UK Government, Great British Nuclear: Overview, July 2023
- Ref. 52 UK Government, Six companies through to next stage of nuclear technology competition, October 2023
- Ref. 53 UK Government, Towards Fusion Energy Strategy 2023 (update), 2023
- Ref. 54 National Infrastructure Commission, National Infrastructure Strategy, Fairer, Faster, Greener, 2020
- Ref. 55 UK Government, Industrial decarbonisation strategy, 2021

- Ref. 56 UK Government, UK Hydrogen Strategy, 2021
- Ref. 57 UK Government, Hydrogen Production Business Model, July 2023, accessed October 2023 from [Hydrogen Production Business Model / Net Zero Hydrogen Fund: successful projects - GOV.UK](#)
- Ref. 58 UK Government, Hydrogen Allocation Round 2: market engagement, May 2023, accessed October 2023 from [Hydrogen Allocation Round 2: market engagement - GOV.UK](#)
- Ref. 59 Hydrogen Energy Association, The UK's Hydrogen Project Map, accessed February 2024 from [The UK Hydrogen Project Map - Hydrogen Energy Association](#)
- Ref. 60 UK Government, Biomass Strategy, 2023
- Ref. 61 UK Government, Solar photovoltaics deployment, accessed August 2024 from [Solar photovoltaics deployment - GOV.UK](#)
- Ref. 62 Embedded Capacity Registers are published under the OpenData initiative for each of the six Distribution Network Operating companies
- Ref. 63 National Infrastructure Commission, Renewables, recovery, and reaching Net Zero, 2020
- Ref. 64 UK Government, Benefits of Long Duration Electricity Storage, BEIS Research Paper Number 2022/019, 2022
- Ref. 65 National Grid ESO, Network Options Assessment, 2022
- Ref. 66 Microgeneration Certification Scheme Data dashboard, accessed August 2024 from [The MCS Data Dashboard - MCS](#)
- Ref. 67 UK Government, Electricity generation costs, issued on three-year cycle, in 2013, 2016, 2020 and 2023
- Ref. 68 The World Bank: Global Solar Atlas 2.0, Solar resource data: Solargis
- Ref. 69 National Grid Electricity Transmission Research Tool accessed August 2024 from [ConnectNow | Research Assistant](#)
- Ref. 70 Ofgem, Open letter on future reform to the electricity connections process, May 2023
- Ref. 71 National Grid Electricity System Operator, 'Get on, get back or get out of the energy queue' – ESO announces urgent action to speed up electricity grid connections by up to 10 years, June 2023
- Ref. 72 Guardian, There are solutions to the food crisis. But ploughing up Britain isn't one of them, 2021.
- Ref. 73 Enevoldsen, P. and Jacobson, M.Z., Data investigation of installed and output power densities of onshore and offshore wind turbines worldwide, Energy for Sustainable Development, Elsevier, 2020 from [web.stanford.edu/group/efmh/jacobson/Articles/I/WindSpacing.pdf](#)
- Ref. 74 UK Government, Electricity fuel use, generation and supply, DUKES Table 5.6, accessed August 2024 from [DUKES 5.6.xlsx](#)
- Ref. 75 National Renewable Energy Laboratory, Best Research-Cell Efficiency Chart, accessed August 2024 from [Best Research-Cell Efficiency Chart | Photovoltaic Research | NREL](#)

- Ref. 76 National Grid Electricity System Operator, Electricity Ten Year Statement, 2022
- Ref. 77 National Grid Electricity System Operator, Network Options Assessment, July 2022
- Ref. 78 National Grid Electricity System Operator, System Operability Framework, 2014
- Ref. 79 National Infrastructure Commission, National Infrastructure Assessment Chapter 2: Low Cost, Low Carbon, 2018
- Ref. 80 EMR Delivery Body, Capacity Market Auction Guidelines, accessed August 2024 [EMR Portal - CMDocumentLibrary](#)
- Ref. 81 National Grid ESO Data Portal, accessed August 2024 from <https://www.nationalgrideso.com/data-portal>
- Ref. 82 Solar Power Portal, Solar PV costs fall 82% over the last decade, says IRENA, 2020
- Ref. 83 UK Government, Contracts for Difference for Low Carbon Electricity Generation - Consultation on proposed amendments to the scheme, 2020
- Ref. 84 UK Government, CfD Allocation Round 4 results are available from [Contracts for Difference \(CfD\) Allocation Round 4: results - GOV.UK](#) and Allocation Round 5 results are available from [Contracts for Difference \(CfD\) Allocation Round 5: results - GOV.UK](#)
- Ref. 85 Strbac, G., Aunedi, M. Whole-system cost of variable renewables in future GB electricity system, 2016
- Ref. 86 UK Government, Government reignites industrial heartlands 10 days out from the International Investment Summit, October 2024, available from [Government reignites industrial heartlands 10 days out from the International Investment Summit - GOV.UK](#)
- Ref. 87 UK Government, Energy Secretary convenes COP leaders past, present and future to offer UK support and leadership in responding to the climate crisis, accessed August 2024 from [Energy Secretary convenes COP leaders past, present and future to offer UK support and leadership in responding to the climate crisis - GOV.UK](#)
- Ref. 88 UK Government, Mission Control, accessed in July 2024 from [Chris Stark to lead Mission Control to deliver clean power by 2030 - GOV.UK](#)
- Ref. 89 UK Government, Sizewell C Development Expenditure (Devex) Subsidy Scheme, August 2024, accessed from [Sizewell C Development Expenditure \(Devex\) Subsidy Scheme - GOV.UK](#)

13. Abbreviations

Abbreviation/Term	Definition
AR4/5/6	Allocation Round 4/5/6 of the Contracts for Difference scheme
BECCS	Bioenergy with Carbon Capture and Storage
BESS	Battery Energy Storage System
BEV	Battery Electric Vehicle
CBDP	Carbon Budget Delivery Plan
CCC	The Climate Change Committee
CCGT	Combined Cycle Gas Turbine
CCUS	Carbon Capture Use and Storage
COP	Conference of the Parties to the United Nations Framework Convention on Climate Change (UNFCCC)
DCO	Development Consent Order
DESNZ	Department for Energy Security and Net Zero
DUKES	Government's Digest of UK Energy Statistics
ETYS	National Grid ESO's Electricity Ten Year Statement
EV	Electric Vehicle
E-W	East-West solar panel layout
FES	National Grid ESO's Future Energy Scenarios
FIT	Feed in Tariff
FSF	Fixed South Facing solar panel layout
GBN	Great British Nuclear
GDA	Generic Design Assessment
GHG	Greenhouse Gas
GSP	Grid Supply Point
GWh / GW	Gigawatt hour (energy) / gigawatt (power). 1GW = 1,000 MW
ha	Hectare
HAR	Government's Hydrogen Allocation Round
IPCC	Intergovernmental Panel on Climate Change
IRENA	International Renewable Energy Agency
kWh / kW	Kilowatt hour (energy) / kilowatt (power). 1MW = 1,000 kW
LCOE	Levelised Cost of Energy
LULUCF	Land Use, Land-use Change and Forestry

Abbreviation/Term	Definition
MCS	Government's Microgeneration Certification Scheme
MtCO ₂ / MtCO ₂ (e)	Million tonnes of carbon dioxide / Million tonnes of carbon dioxide equivalent
MWh / MW	Megawatt hour (energy) / megawatt (power)
NDC	Nationally Determined Contributions
NETS	National Electricity Transmission System
NGESO	National Grid Electricity System Operator
NGET	National Grid Electricity Transmission
NIC	National Infrastructure Commission
NOA	National Grid ESO's Network Options Assessment
NPPF	National Planning Policy Framework
NPS	National Policy Statement
NSIP	Nationally Significant Infrastructure Project
NZS	Government's Net Zero Strategy
ONR	Office for Nuclear Regulation
PV	Solar Photovoltaics
REPD	Government's Renewable Energy Planning Database
SAT	Single Axis Tracker solar panel layout
SMR	Small Modular (nuclear) Reactor
SP	Settlement Period (of the GB electricity market)
TEC	Transmission Entry Capacity
TWh / TW	Terawatt hour (energy) / terawatt (power). 1TW = 1,000 GW
WMO	World Meteorological Organisation
ZEV	Zero Emission Vehicle



BUILD | OWN | OPERATE | MAINTAIN

BOOM-POWER.CO.UK