
FENWICK SOLAR FARM

Fenwick Solar Farm
EN010152

Environmental Statement

Volume III Appendix 11-2: Acoustic Terminology

Document Reference: EN010152/APP/6.3

Regulation 5(2)(a)

Infrastructure Planning (Applications: Prescribed Forms and Procedure)
Regulations 2009

October 2024
Revision Number: 00

Revision History

Revision Number	Date	Details
00	October 2024	DCO application

Prepared for:
Fenwick Solar Project Limited

Prepared by:
AECOM Limited

© 2024 AECOM Limited. All Rights Reserved.

This document has been prepared by AECOM Limited (“AECOM”) for sole use of our client (the “Client”) in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between AECOM and the Client. Any information provided by third parties and referred to herein has not been checked or verified by AECOM, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of AECOM.

Table of Contents

1. Acoustic Terminology	1
-------------------------------	---

Tables

Table 1: Acoustic Terminology	1
-------------------------------------	---

1. Acoustic Terminology

1.1.1 Acoustic terminology used in the noise and vibration assessment are summarised in Table 1.

Table 1: Acoustic Terminology

Term	Description
Noise	Unwanted or unexpected sound.
Frequency (Hz)	The number of cycles per second (i.e., the number of vibrations that occur in one second); subjectively this is perceived as pitch.
Frequency Spectrum	The relative frequency contributions that make up a noise.
"A" Weighting (dB(A))	The human ear does not respond uniformly across the audible frequency range. The "A" weighting is commonly used to simulate the frequency response of the ear.
Decibel (dB)	The decibel is a logarithmic ratio of two values of a variable. The range of audible sound pressures is approximately 2×10^{-5} Pa to 200 Pa. Using decibel notation presents this range in a more manageable form, 0 dB to 140 dB.
Sound Pressure Level (Lp)	Equal to 20 times the logarithm to the base 10 of the ratio of the root mean squared (RMS) sound pressure to the reference sound pressure. In air the reference sound pressure is 2×10^{-5} Pa. Mathematically: $\text{Sound Pressure Level (dB)} = 20 \log_{10} \{p(t) / P_0\}$ Where $P_0 = 2 \times 10^{-5}$ Pa
Ambient Noise Level, $L_{Aeq,T}$	The equivalent continuous A-weighted sound pressure level of the totally encompassing sound in a given situation at a given time that is usually composed of sound from many sources near and far.
Background Noise Level $L_{A90,T}$	The A-weighted sound pressure level of the residual noise at the assessment position that is exceeded for 90% of a given time interval, T, measured using the fast time weighting, F, and quoted to the nearest whole number.
Reference Time Interval, T_r	The specified interval over which an equivalent continuous A-weighted sound pressure level is determined.

Term	Description
Specific Noise Level, $L_{Aeq,Tr}$	The equivalent continuous A-weighted sound pressure level at the assessment position produced by the specific noise source over a given reference time interval.
Rating Level, $L_{Ar,Tr}$	The specific noise level plus any adjustment for any characteristic features of the noise.
Level $L_{A10,T}$	The A-weighted sound pressure level exceeded for 10% of a given time interval, T, measured using the fast time weighting, F.
Peak Particle Velocity	The peak speed of particle movement in the ground due to vibration and used to assess impacts from construction activity induced vibration. The Peak Particle Velocity is defined as millimetres per second (mm/s).
LOAEL	Lowest Observed Adverse Effect Level
SOAEL	Significant Observed Adverse Effect Level



BOOM
POWER

BUILD | OWN | OPERATE | MAINTAIN

BOOM-POWER.CO.UK