Meridian Solar Farm

EN010169

Volume 8

Post-Submission Application Documents

8.12 Statement of Common Ground with Environment Agency (Rev 2) (Tracked)

APFP Regulation 5(2)(q)

Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009

October 2026

Contents

~~1. Introduction 3~~
~~1.1. Overview 3~~
~~2. Record of Engagement 6~~
~~2.1. Summary of Engagement Undertaken 6~~
~~3. Statement of Common Ground 8~~
~~3.1. Estates 8~~
~~3.2. Draft Development Consent Order 10~~
~~3.3. Flood Risk 12~~
~~3.4. Hydraulic Modelling 18~~
~~3.5. Groundwater and Contaminated Land 20~~
~~3.6. Ecology and Fisheries 23~~
~~3.7. Geomorphology 25~~
~~3.8. Water Resources 27~~
~~3.9. Water Quality 28~~
~~4. Signatures 32~~
1. Introduction 4
1.1. Overview 4
2. Record of Engagement 6
2.1. Summary of Engagement Undertaken 6
3. Statement of Common Ground 8
3.1. Estates 8
3.2. Draft Development Consent Order 10
3.3. Flood Risk 16
3.4. Hydraulic Modelling 24
3.5. Groundwater and Contaminated Land 29
3.6. Aquatic Ecology and Fish 32
3.7. Geomorphology 36
3.8. Water Resources 41
3.9. Water Quality 44
4. Signatures 51

Tables

~~Table 2-1: Record of Engagement ..... 6~~
~~Table 3-1 Estates ..... 8~~
~~Table 3-2 Draft Development Consent Order ..... 10~~
~~Table 3-3 Flood Risk ..... 12~~
~~Table 3-4 Hydraulic Modelling ..... 18~~
~~Table 3-5 Groundwater and Contaminated Land ..... 20~~

~~Table 3-6 Ecology and Fisheries ..... 23~~
~~Table 3-7 Geomorphology ..... 25~~
~~Table 3-8 Water Resources ..... 27~~
~~Table 3-9 Water Quality ..... 28~~
Table 2-1: Record of Engagement 6
Table 3-1 Estates 8
Table 3-2 Draft Development Consent Order 10
Table 3-3 Flood Risk 16
Table 3-4 Hydraulic Modelling 24
Table 3-5 Groundwater and Contaminated Land 29
Table 3-6 Aquatic Ecology and Fish 32
Table 3-7 Geomorphology 36
Table 3-8 Water Resources 41
Table 3-9 Water Quality 44

1. Introduction

1.1. Overview

1.1.1. This Statement of Common Ground (SoCG) has been prepared to support the examination process for the proposed Meridian Solar Farm. A DCO application has been made by Meridian Solar Farm Limited ('the Applicant') to the Secretary of State pursuant to Section 37 of the Planning Act 2008[1], which was accepted for examination by the Secretary of State pursuant to Section 55 of the Planning Act 2008 on 15 April 2026.

1.1.2. SoCGs are an established means in the planning process of allowing all parties to identify and focus on specific issues that may need to be considered during the examination. The purpose and possible content of SoCGs is detailed in the Ministry of Housing, Communities and Local Government's guidance entitled 'Planning Act 2008: Guidance on the examination stage of an application' (2026)[2], which states:

"*A SoCG is a written statement prepared jointly by the applicant and another interested party or parties but led and submitted by the applicant, setting out the factual matters about the application on which they agree, for example, on data or methodologies concerning the determination of any significant effects, but can just as helpfully record disagreement.*

…

SoCGs are expected to be concise and focused on the key issues, with the scope agreed between the parties from the outset of discussions on the application during the pre-application stage. SoCGs are often revised during the course of the examination as matters are agreed or disagreements clarified between the applicant and interested parties."

1.1.3. This document relates to matters between the Applicant and the Environment Agency (EA). It has been prepared jointly by the Applicant and the EA, and the EA has reviewed the Applicant's position as set out. It confirms to the Examining

[1] The Planning Act 2008. Available at: https://www.legislation.gov.uk/ukpga/2008/29/contents [Accessed 11 August 2026]
[2] MHCLG (2026) Guidance Planning Act 2008: Guidance on the examination stage of an application. Available at: https://www.gov.uk/guidance/planning-act-2008-guidance-on-the-examination-stage-of-an-application [Accessed 2 September 2026]

Authority where agreement has been reached between the parties, and where agreement has not (yet) been reached. This SoCG does not seek to replicate information that is available elsewhere, either within the DCO application and/or examination documents, referring out where appropriate.

1.1.4. The terminology used within the SoCG to reflect the status between the parties is either:

- "Agreed" to indicate where a matter has been resolved to the satisfaction of the parties.
- "Not Agreed" to indicate a final position where parties cannot agree.
- "Under Discussion" to indicate where matters are subject of on-going discussion with the aim to either resolve or refine the extent of disagreement between the parties.

1.1.5. Where matters would require the involvement of third parties in order to come to an agreement, these dependencies are noted.

2. Record of Engagement

2.1. Summary of Engagement Undertaken

2.1.1. Table 2-1 summarises the key meetings and correspondence between the parties subject to this SoCG.

Table 2-1: Record of Engagement

Date	Form of Engagement	Details
January 2024	Email	• The EA confirmed the existing fluvial defences reducing the risk of flooding to the Site consist of Crowland-Cowbit Washes and embankment. • The EA confirmed that the principal source of flooding to be considered is the River Welland, specifically breaching of the adjacent flood defence. • EA advised the 2017 SFRA breach locations are considered adequate for the Site. Further modelling analysis is not required, the 2017 SFRA hazard mapping can be used and is appropriate for this application. • EA advised that flood-sensitive infrastructure should be elevated above the 0.1% +climate change breach flood level.
19/12/2024	Online Meeting	Meeting with representatives from EA National Infrastructure Team to agree scope of hydraulic modelling analysis required to inform Scheme design and the Flood Risk Assessment (FRA).
24/04/2025	Online Meeting	Discussed approach to hydraulic modelling parameters and design requirements for mitigation approach.
28/07/2025	Online Meeting	• The Applicant provided an update of the hydraulic model results for the River Welland and Postland Pumped Catchment and discussed how these results are being used to assess flood risk in the FRA. • Discussed potential mitigation for the solar PV panels as a result of the modelling, and summarised volumetric loss calculations that were undertaken for the solar PV panel legs/poles.

Date	Form of Engagement	Details
20/01/2026	Online Meeting	• Discussed approach and results of the draft FRA. • Discussed the six solar stations located within Flood Zone 3b in Gotts Catchment, which have been raised on plinths to provide 600mm freeboard above the design flood level upon EA's request. • Discussed that the increase in flood depth caused by submerged panels (including mounting infrastructure) in a worst case scenario for the River Welland breach event scenario is approximately 9mm. EA noted no significant concerns.
04/02/2026	Email	Issued River Welland Breach Hydraulic Modelling Report to the EA, as requested at previous meeting.
23/06/2026	Email	Issued hydraulic model files to the EA, as requested via email.
15/07/2026	Online Meeting	Meeting to discuss flood risk comments from the EA's Relevant Representation.
20/08/2026	Online Meeting	Regular catch up call to discuss the preparation of the SoCG.
16/09/2026	Online Meeting	Meeting to discuss comments on the South Holland, River Welland and Postland hydraulic modeling, and Outline Flood Emergency Response Plan to be submitted by Deadline 2.
24/09/2026	Online Meeting	Meeting to discuss comments on the assessment of impacts on fish, set out within the EA's Relevant Representation.
28/09/2026	Online Meeting	Meeting to discuss water supply comments set out within the EA's and Anglian Water's Relevant ~~Representation~~Representations.
29/09/2026	Online Meeting	Regular catch up call to discuss the preparation of the SoCG.
13/10/2026	Online Meeting	Regular catch up call to discuss the preparation of the SoCG.
21/10/2026	Online Meeting	Meeting to discuss Postland Catchment Hydraulic Modelling Comments and the preparation of the SoCG.

3. Statement of Common Ground

3.1. Estates

Table 3-1 Estates

Ref	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
1.1	Compulsory Acquisition	The EA as landowner has contacted the applicant's solicitor regarding the proposed compulsory acquisition of Environment Agency land as part of the scheme. The current order limit boundary indicates that a small slither of in-land drainage ditch/bank has been included, which forms part of the adjacent statutory Flood Storage Reservoir (FSR). This land is managed in accordance with the requirements of the Reservoirs Act. It is not clear why compulsory acquisition of this parcel of land is required. The EA may require access rights across the Scheme for inspecting the FSR, as well as permanent clear access for maintenance and repairs to the reservoir banks. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1.	The Applicant has updated the **Land and Crown Land Plans – Section A Solar Development Area** [REP1-004], **Book of Reference** ~~[REP1-010],~~(Doc Ref. 4.3 Rev 3), **Land Rights Tracker** [REP1-012], **ES Figure 2-2** ~~[REP1-024]~~(Doc Ref. 6.2 Rev 2) and the **Outline Landscape and Ecology Management Plan (OLEMP)** ~~[REP1-070]~~(Doc Ref. 7.16 Rev 2) to exclude any works from the land within the ownership of the EA. In addition, the Applicant has updated **ES Figure 2-2** ~~[REP1-024]~~(Doc Ref. 6.2 Rev 2) and **Annex A Outline Landscape Masterplans** of the **OLEMP** ~~[REP1-070]~~(Doc Ref. 7.16 Rev 2) to show an 8m buffer from the EA land ownership boundary and to provide an access arrangement to the FSR. These requirements have also been included within the **Outline Construction Environmental Management Plan (OCEMP)** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **Outline Operational Environmental Management Plan (OOEMP)** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) and **Outline Decommissioning Environmental**	Under Discussion

Ref	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
		Deadline 2 Update No update at Deadline 2. **Deadline 3 Update** The EA are satisfied that the updated Land and Crown Land Plans [REP1-004] excludes any works from the land parcels A1-1 and A1-2 within the ownership of the EA, and that this is reflected in the Book of Reference [REP1-011] which removes any reference to the compulsory acquisition of EA land. The EA are satisfied that access across the Scheme, and permanent clear access to the reservoir banks, has been secured. The EA seek further clarification regarding EA rights relating to land parcels A1-3 and A1-9.	**Management Plan (ODEMP)** ~~[REP1-065]~~(Doc Ref. 7.12 Rev 2) submitted at Deadline 1. **Deadline 3 Update** The Applicant updated the **OCEMP** (Doc Ref. 7.10 Rev 3), **OOEMP** (Doc Ref. 7.11. Rev 2) and **ODEMP** (Doc Ref. 7.12 Rev 2) with regards to A1-1 and A1-2 to further clarify the wording with regards to the provision of access for the EA, as requested during the meeting held on 21 October 2026.	

3.2. Draft Development Consent Order

Table 3-2 Draft Development Consent Order

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
2.1	EA1 EA3 EA4	Draft DCO	The EA suggests alterations to the wording of the **Draft Development Consent Order** (DCO) (Doc Ref. 3.1 Rev 2) with regards to the implementation of environmental management plans for specified pre-commencement construction activities, the use of the phrase 'substantially in accordance with' and a request to be included as a named consultee on certain relevant Requirements. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** Regarding Requirement 12: Resolved: We are satisfied with the revised wording that will secure the environmental mitigation measures	The Applicant has amended Requirement 12 in the **Draft DCO** ~~[REP1-006]~~(Doc Ref. 3.1 Rev 3) submitted at Deadline 1, so that specified permitted preliminary works cannot commence until a CEMP has been approved. Certain low-risk permitted preliminary works remain excluded from the requirement where a CEMP is not considered necessary. The Applicant considers that the amended drafting appropriately secures the environmental mitigation measures contained within the CEMP. The Applicant considers that the phrase "substantially in accordance with" is appropriate and reflects established DCO drafting practice, providing flexibility for minor changes which may (for example) be required to reflect detailed design or the most up to date survey information at the	Under ~~Discussion~~discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			contained within the CEMP for relevant permitted preliminary works. Regarding 'substantially in accordance with': Unresolved. The EA maintains its position. Regarding EA as named consultee for Requirement 6 and 10: Resolved. **Deadline 3 update** EA1 & EA3 Resolved. EA4: The EA maintains its position regarding use of the phrase 'substantially in accordance with'.	time of construction whilst ensuring consistency with the certified outline documents. Similar drafting has been adopted by the Secretary of State for environmental management plans and other certified documents on recent solar NSIP projects, including One Earth Solar Farm Order 2026, Tillbridge Solar Order 2025 and Fenwick Solar Farm Order 2025. The Applicant understands that the Environment Agency wishes to be named as a consultee in respect of Requirements 6 (battery safety management plan) and 10 (surface and foul water drainage). The Applicant notes that the Environment Agency is already identified as a consultee for Requirement 6 of the **Draft DCO** [REP1-006]. In respect of Requirement 10, the Applicant has amended this in the **draft DCO** [REP1-006] submitted at Deadline 1 to include the Environment Agency as a consultee. **Deadline 3 update**	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				EA4: The Applicant maintains its position regarding use of the phase 'substantially in accordance with.'	
2.2	EA2 EA5	Protective Provisions for the disapplication of Environmental Permitting (England and Wales) Regulations 2016	The Applicant wishes to disapply the requirement for a Flood Risk Activity Permit under the Environmental Permitting (England and Wales) Regulations 2016. Protective Provisions to be included in the Draft DCO covering these requirements are yet to be agreed. **Deadline 2 Update** No update at Deadline 2. **Deadline 3 Update:** The EA are now satisfied that FRAPs will not be required for the development of this scheme. Specifically, all works are beyond the 8m fluvial or 16m tidal setback, and so would not be subject to an environmental permit under the Environmental Permitting Regulations.	The Applicant has provided Protective Provisions for EA's review and is in the process of engaging with the EA on these. The Applicant has included its preferred form of these protective provisions within the **draft DCO** ~~[REP1-006]~~(Doc Ref. 3.1 Rev 3) submitted at Deadline 1, noting that these are subject to change depending on ongoing negotiations between the parties~~]~~.. **Deadline 3 Update:** The Applicant has submitted a revised **Draft DCO** (Doc Ref. 3.1 Rev 3) at Deadline 3 with protective provisions for the EA removed.	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			This would remove the need for the inclusion of the Environment Agency Protective Provisions in the DCO. The EA await review of a revised dDCO with EA protective provisions removed to mark this point as resolved.		
2.3	EA6	Discharge of Requirements	There is insufficient time for a named consultee to review and respond to the discharge of requirements to request further information. The LPA must consult a named consultee within 5 working days of receipt of any application to discharge requirements. From the receipt of the consultation the LPA then has a total of 15 working days to request further information. Therefore, the named consultee has just 10 working days to review the consultation & determine if sufficient information has been provided. Risks to the water environment may not be adequately managed.	The Applicant considers that the discharge of requirements procedure in Schedule 14 provides an appropriate and proportionate process for consultation and the identification of any further information requirements. The drafting is consistent with that adopted by the Secretary of State in other recent solar NSIP DCOs, including the Tillbridge Solar Order 2025. In addition, Schedule 14 already provides flexibility for alternative timescales to be agreed in writing between the undertaker and the relevant planning authority where appropriate. The Applicant therefore does not consider	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			Amend wording to provide 15 working days for named consultees to review the consultation & determine if sufficient information has been provided. **Deadline 2 Update** No update at Deadline 2. **Deadline 3 Update:** The EA are satisfied with the intention to update the dDCO to extend the period for requesting further information from 15 working days to 20 working days. The EA await review of revised dDCO to resolve this issue.	that the proposed amendment is necessary. **Deadline 2 Update** The Applicant has agreed to amend paragraph 3(3) of Schedule 14 to the **Draft DCO** ~~[REP1-006]~~(Doc Ref. 3.1 Rev 3) at Deadline 3 to extend the period for requesting further information from 15 working days to 20 working days. This will provide requirement consultees with up to 15 working days to review consultation materials and determine whether further information is required. The Applicant considers that this amendment should address the Environment Agency's concern. The parties will review this point following submission of the updated **Draft DCO** ~~[REP1-006]~~(Doc Ref. 3.1 Rev 3) at Deadline 3. **Deadline 3 Update:**	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				The updated **Draft DCO** (Doc Ref. 3.1 Rev 3) has been submitted at Deadline 3.	

3.3. Flood Risk

Table 3-3 Flood Risk

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
3.1	EA7	Use of flood modelling to inform Site layout.	Detailed flood modelling is available but has not been consistently used to inform site layout. Instead, the FRA reverts to standard Flood Zone classifications to define site suitability and to demonstrate the application of a sequential approach to site layout. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** The Applicant's response is accepted. The issue previously raised arose from the use of Flood Zone terminology being used to describe modelled flood extents that include climate change allowance. Our original comments assumed the references related solely to Flood Zones shown in the Flood Map for Planning.	The Applicant discussed with the EA how detailed hydraulic modelling has been used to inform the Site layout during the meeting held on 15 July 2026. This included the use of detailed hydraulic modelling to define the extent of Work No. 1 on the **Works Plans** [APP-009], the relocation of an On-Site 132kV Substation, the exclusion of Solar Stations from Flood Zone 3a and 3b areas (with the exception of the Gotts catchment) and the specification of flood mitigation measures within the **Design Parameters** ~~[REP1-055].~~(Doc Ref. 7.4 Rev 3). A full response is provided in the **Relevant Representations Report** at Table 3.5 [REP1-074].	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The Applicant provided clarification on this at ISH1 and during EA/Applicant meeting on 16 September 2026.		
3.2	EA8 EA9	Consideration of flood defence assets and Crowland and Cowbit Washes Flood Storage Reservoir	There is insufficient consideration of EA flood defence assets. Inadequate recognition of the Crowland and Cowbit Washes as a designated large raised reservoir under the Reservoirs Act 1975. The operation of the Washes and their interaction with fluvial and tidal defences is not clearly represented. Inadequate consideration of key aspects such as proximity of development to the reservoir embankments, required standoff distances, and maintenance/access requirements. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update**	The Applicant has submitted an updated **FRA** [REP1-050] and **ES Chapter 11: Hydrology and Flood Risk** [REP1-020] at Deadline 1 to provide further detail on the EA flood defence assets and the Crowland and Cowbit Washes designated large raised reservoir located near the Scheme. As set out within Table 3-1 of this SoCG, the Applicant has made updates to the Application documents at Deadline 1 to provide an 8m buffer from the EA's land ownership boundary within Land Parcel A and to provide an access to the EA for the maintenance of the Flood Storage Reservoir. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The additional information and clarification provided by the Applicant is accepted.		
3.3	EA10	Consideration of tidal flood risk	There is inadequate understanding of tidal flood risk. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** The additional information and clarification provided by the Applicant is accepted.	The Applicant has revised the **FRA** [REP1-050] at Deadline 1 to provide further detail on the tidal flood risk to the Grid Connection Route. **ES Chapter 11: Hydrology and Flood Risk** [REP1-020] has also been updated accordingly. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed
3.4	EA11	Sensitivity testing for climate change.	Inconsistent approach to sensitivity testing for climate change. The H++ sea level rise scenario has been correctly used as a sensitivity test in accordance with guidance to consider a credible maximum scenario. However there is no equivalent assessment of a credible maximum scenario for peak river flows. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1.	The Applicant notes that the EA advised during pre-application engagement that the breach assessment for the River Welland should be undertaken using the 0.1% Annual Exceedance Probability (AEP) event with the Higher Central climate change allowance (28%) for the maximum flood event (effectively the Credible Maximum Scenario event). In addition, the **FRA** [REP1-050] considers the 0.1% AEP event plus	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			Deadline 2 Update We acknowledge the Applicant's explanation of the flood scenarios selected as the 'credible maximum' events. However, further justification is required to demonstrate why the chosen return interval and climate change scenarios for each catchment represent a suitably conservative approach to assessing the 'credible maximum', particularly where they differ from the methodology set out in the Government guidance, *Flood Risk Assessment: Climate Change Allowances*. **Deadline 3 Update:** The EA notes this is now agreed.	climate change for the South Holland Main Drain and Postland Catchment. In light of this requirement for the River Welland, and to ensure consistency in the assessment methodology, the Applicant considered it appropriate to apply the Higher Central climate change allowance to the South Holland Main Drain and the Postland Catchment assessments. This approach is consistent with the methodology agreed with the EA for the River Welland assessment. A full response is provided in the **Relevant Representations Report** [REP1-074].	
3.5	EA12 EA13	Development in Flood Zone 3b.	The proposal includes development within Flood Zone 3b (functional floodplain), which is contrary to national policy as set out in EN-1 National Policy Statement (NPS) paragraph 5.8.4. Further evidence should be provided to demonstrate the application of the Exception Test.	During previous pre-application engagement with the EA, it was indicated to the Applicant that the proposals for development in the Gotts catchment may be acceptable, if the Exception Test is met, demonstrating that the infrastructure cannot reasonably be located elsewhere,	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** Following the EA/Applicant meeting on 16 September 2026, the Applicant agreed to undertake additional assessment of flow conveyance routes within Flood Zone 3b. This work should demonstrate that the proposed solar panel support structures within Flood Zone 3b will not adversely affect flood flow routes or increase flood risk elsewhere. We await receipt and review of this information before this comment can be resolved. **Deadline 3 Update:** A 2D hydraulic model has now been developed by the Applicant. The assessment indicates that the solar stations proposed within Flood Zone 3b would not have an adverse impact on flood flow routes. However, it has now come to	600mm freeboard is provided for solar stations, floodplain function would not be impeded and overland flow velocities would not damage or cause debris blockage. The **FRA** [REP1-050] has been updated at Deadline 1 to more clearly set out why Flood Zone 3b cannot be avoided in the Gotts catchment. In summary, it has not possible to locate proposed infrastructure outside of Flood Zone 3b without either acquiring additional land (noting surrounding land north of South Holland Main Drain is also within Flood Zone 3b) or removing these land parcels from the Solar Development Area altogether, which would reduce the generating capacity of the Scheme. The proposed infrastructure within Flood Zone 3b has been designed to remain operational at times of flood, with 600mm freeboard provided for solar stations, and it does not materially increase flood risk or adversely affect	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			our attention that two construction compounds are also proposed within Flood Zone 3b associated with the Gotts Catchment. The Applicant should demonstrate why alternative locations at lower risk of flooding are not reasonably available. The assessment should clearly explain the justification for their location and the potential impacts on flood risk and flow routes within floodplain function. **EA13:** The applicant states that opportunities to reduce flood risk have been explored, but further evidence should be provided to demonstrate what alternatives were considered and why no additional flood risk reductions were achievable.	the operation or function of the functional floodplain. As such, the residual effect is considered to be acceptable and proportionate. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5. **Deadline 3 Update:** The Applicant will update the **FRA** [REP1-050] at Deadline 4 to include the further clarification requested by the EA.	
3.6	EA14	Bunding and flood storage provision.	A considerable amount of bunding is proposed around infrastructure located within the floodplain. The extent, layout, and function of these bunded areas are not clearly defined making it difficult to assess any cumulative impact. Limited consideration has been given regarding whether compensatory storage	The **FRA** [REP1-050] has been updated at Deadline 1 to clarify where bunding or a flood defence wall would be required to protect the Scheme's infrastructure, the worst-case flood event against which the flood protection requirements have been	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			or greater flood storage provision would be appropriate given the scale and number of bunded areas. Maintenance requirements and long-term performance of the bunds are not addressed. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** We are satisfied with the Applicant's response and the updated documents provided.	assessed, and the associated freeboard allowances. Bunding (or a flood defence wall) is proposed for On-Site Substations in Parcels A, B and C, the BESS compound, selected solar stations and the Cable Sealing End Compound (CSEC) South to manage residual flood risk associated with the assessed flood events. Hydraulic modelling completed for the Scheme considered bunding around the On-Site Substations and all Solar Stations for a worst-case assessment (see modelling assumptions in **FRA Annex B** [REP1-048]), using the maximum bund width. As such, the depth change volume assessment reported in the **FRA** [REP1-050] accounts for the possible worst-case bunding, whilst in practice some of the Solar Stations can also be raised on plinths instead. The flood depth change assessment demonstrates that the change is minimal and results in no	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				significant effects. The **FRA** [REP1-050] has been updated to provide additional discussion on the assessment of impacts on flood risk from the proposed bunds. Detailed design information of the bunds, including the height of bunds, inspection requirements and long-term maintenance arrangements, will be developed during the detailed design stage post-DCO consent. The commitment for inspection requirements and long-term maintenance arrangements to be set out has been included within the **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) at Deadline 1. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	

3.4. Hydraulic Modelling

Table 3-4 Hydraulic Modelling

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
4.1	EA15 EA16 EA17	Design event	Design event used for volume loss calculations is unclear. Design event scenario for bund wall heights in table 5-4 is not clear. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** The Applicant's response is accepted. The updated Flood Risk Assessment includes details of the specific design event scenarios used for the volume loss calculations and bund heights	The **FRA** [REP1-050] has been updated at Deadline 1 to clarify the design events used for volume loss calculations and the specification of flood mitigation parameters, including the height of bunds or flood defence walls. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed
4.2	EA18	Assessment of Solar PV Support Panels	It is not clear whether solar PV support panels are included in the assessment of volume losses for the Gotts Catchment.	The Applicant confirms the Scheme has assessed volume loss from solar PV panel legs across all four Parcels in the Solar Development Area, including the Gotts catchment. The **FRA** [REP1-050]	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
		in volume loss calculations.	The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Update Deadline 2** The Applicant's response is accepted. Further detail provided to clarify that the solar panel mounting infrastructure is included in the volume loss calculations for Gotts catchment	has been updated at Deadline 1 to clarify this. A full response is provided in the **Relevant Representations Report** at Table 3.5 [REP1-074].	
4.3	EA19	Confirmation of flood defence mitigation	Conflicting information with respect to flood defence standard of protection. Conflicting information with regards to mitigation. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update**	The **FRA** [REP1-050] has been reviewed and updated at Deadline 1 to ensure that the level of protection provided by the River Welland flood defences is described consistently throughout the report. In addition, the **FRA** [REP1-050] has been updated to clarify the flood mitigation measures embedded within the Scheme's design.	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The Applicant's response is accepted. An additional figure has been provided which includes a map showing the standard of protection of flood defences along the River Welland.	A full response is provided in the **Relevant Representations Report** [REP1- 074] at Table 3.5.	
4.4	EA20	Sensitivity test of the credible maximum tidal scenario (H++)	A sensitivity test for the credible maximum tidal scenario (H++) has not been undertaken in line with guidance. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** The Applicant's response is accepted. The additional information provided within Meridian Solar Farm Volume 6 Environmental Statement Appendix 11-3 Flood Risk Assessment Annex E is considered acceptable in terms of	The Applicant has prepared a new **FRA Annex E** [REP1-052] to set out the sensitivity test for the credible maximum tidal scenario (H++). A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			the assessment of a tidal H++ scenario and the implications for the development		
4.5	Additional Matter	Review of Hydraulic Modelling Files	Comments were received from the EA on the River Welland, South Holland and Postland Hydraulic Modelling files. **Deadline 2 Update** On-going. We raised several comments on the hydraulic modelling for the River Welland, Postland Catchment, and South Holland Main Drain. The Applicant has since submitted an updated technical note dated 29 September 2026 (River Welland Breach Modelling – Response to EA Comments), which addresses our comments relating to the River Welland modelling. We are now satisfied with the approach taken for the River Welland and have no further comments or concerns. With regards to the Postland Catchment and South Holland Main	The Applicant is in the process of reviewing these comments and preparing a response to the EA to provide a clarification in response to the comments received.	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			Drain, the Applicant is currently preparing responses to our comments, and we understand that updated reporting and further justification for the approaches adopted will be provided in due course. We do not expect our comments to result in changes to the modelled extents however, we are awaiting further detail on the impact on flood risk elsewhere with regards to development in Flood Zone 3b within the South Holland Main Drain Catchment. **Deadline 3 Update:** On-going. We have reviewed the Applicant's responses to our comments, and provided our comments at a meeting 21/10/2026. We await review of minor changes to the FRA at Deadline 4 to be able to close this issue.		

3.5. Groundwater and Contaminated Land

Table 3-5 Groundwater and Contaminated Land

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
5.1	EA21	Contaminated land assessment	The conclusions of ES Appendix 5-4: Contaminated Land Assessment [APP-174] and ES Appendix 5-5: Contaminated Land Assessment for Grid Corridor Extension [APP-175] have not been noted or referenced in ES Chapter 5: Agriculture and Soils [APP-056]. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** We are satisfied with the Applicant's response given that land contamination has been scoped out of the EIA. Adequate measures are in place for the management of unexpected contamination throughout the duration of the Scheme.	As explained within Table 5-1 of **ES Chapter 5: Agriculture and Soils** [REP1-014], an assessment of likely significant effects associated with contaminated land is scoped out of the EIA on the basis that the Preliminary Risk Assessments included within **ES Appendix 5-4: Contaminated Land Assessment** [APP-174] and **ES Appendix 5-5: Contaminated Land Assessment for Grid Corridor Extension** [APP-175] demonstrate that no significant effects are likely to occur with the implementation of standard industry practice measures. Standard industry practice measures to minimise risks associated with contaminated land have been incorporated within the **OCEMP** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **OOEMP** ~~[REP1-063],~~(Doc Ref. 7.11 Rev 2), and **ODEMP** ~~[REP1-065].~~(Doc Ref. 7.12 Rev 2). As such, no further assessment is presented within **ES Chapter 5: Agriculture and Soils** [REP1-014]. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
5.2	EA23	Unexpected contamination protocol	The unexpected contamination protocol does not include the need to contact the Local Authority and Environment Agency in the event contamination is identified. It does not mention the need to follow our Land Contamination Risk Management (LCRM) guidance. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** We are satisfied with the amendment made to the **OCEMP** [REP1-061], **OOEMP** [REP1-063] and **ODEMP** [REP1-065] and agree that this issue has been resolved.	The requirements to contact the Local Authority and Environment Agency and to follow Land Contamination Risk Management (LCRM) guidance in the event that contamination is identified has been included in the **OCEMP** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) and **ODEMP** ~~[REP1-065]~~(Doc Ref. 7.12 Rev 2) at Deadline 1. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed
5.3	EA22	Risks to groundwater.	The mitigation measures for trenchless crossings do not consider risks to groundwater. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1.	Table 3-7 of the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) has been updated at Deadline 1 to reference groundwater as a receptor for potential impacts from trenchless crossing construction. However, as summarised within Table 11-1 of **ES Chapter 11: Hydrology and Flood Risk** [REP1-020] and within **ES Appendix 1-2: EIA Scoping Opinion** [APP-167], Table 3.4 ID Ref 3.4.1, the Planning	Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			Deadline 2 Update We are satisfied with the amendment made to the **OCEMP** [REP1-061] and agree that this issue has been resolved.	Inspectorate agreed at scoping stage that groundwater aquifers were to be scoped out of further assessment in the ES due to the presence of unproductive superficial and bedrock strata. Trenchless crossing works will take place under the use of standard and good practice mitigation measures for minimising risk to controlled waters, which includes both surface waters and any groundwater. This is noted within Table 3-7 Hydrology and Flood Risk of the **OCEMP** ~~[REP1-061].~~(Doc Ref. 7.10 Rev 3). A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	

3.6. Aquatic Ecology and Fish

Table 3-6 Aquatic Ecology and Fish

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
6.1	EA24 EA25 EA26 EA27 EA28 EA29	Fish scope of assessment.	We are not satisfied that impacts to fish can be scoped out of the Environmental Statement and Water Framework Directive (WFD). The Salmon and Freshwater Fisheries Act 1975 and The Eels (England and Wales) Regulations 2009 have not been included in the list of legislation that is relevant to biodiversity. The Water Environment (Water Framework Directive) (England and Wales) Regulations 2017 has not been included. Fish are not mentioned as a potential receptor to impacts from fragmentation/ barriers to dispersal (e.g. from culverting and open-cut trenching of watercourses). There is the risk of any discharge pipes from swales to watercourses becoming an attractant for European eel, resulting in entrapment. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1.	**ES Appendix 11-2: WFD Report** [REP1-046] (Table 3-3) has been updated at Deadline 1. This now screens in the Grid Connection Route, and impacts to fish and aquatic ecology have also been assessed. **ES Chapter 9: Ecology and Biodiversity** [REP1-018] has been updated to include an assessment of impacts on fish for watercourse crossings across permanently wet watercourses on a precautionary basis. In addition, **ES Appendix 2-1: Watercourse Crossing Schedule** [REP1-026] has been updated to identify which watercourses subject to crossings are likely to be permanently wet or seasonally wet. The lack of fish surveys has been included within the limitations section of the updated **ES Chapter 9: Ecology and Biodiversity** [REP1-018] with an explanation as to the decision process for this. The absence of surveys	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			Deadline 2 Update We are satisfied with the explanations provided; and with the stated and proposed updates to various documents. We expect that, upon review of the stated updates, these issues can be resolved. **Deadline 3 Update:** The EA are satisfied with the overall approach taken, and await submission of updated documents to resolve these issues, as set out in our detailed response at Deadline 3. EA27: The updated oCEMP should reflect that any culverts in permanently wet waterbodies/ watercourses should be designed so as to preserve the natural bedform of the waterbody/watercourse, ensure fish passage is not impeded and where necessary provide fish easements within the culvert to enable fish passage.	however is not considered to affect the assessment findings. The majority of the drains/ ditches where watercourse crossings are proposed had only low or no levels of water present during surveys and as such, would be of limited value/use by fish. Where there is permanent water present, the timing of works (in order to avoid spawning periods) and construction methods will be considered for detailed design, as set out within the **OCEMP** ~~[REP1-061].~~(Doc Ref. 7.10 Rev 3). The **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) has also been updated at Deadline 1 to include a firmer commitment to the use of clear span structures for crossings across any permanently wet watercourses. Pipe connections from swales to watercourses have been minimised, with surface water from the Solar Development Area's swale -based drainage system draining into local receiving watercourses via a new open green ditch, where applicable, minimising the risk of eel	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				entrapment. This is secured within **ES Appendix 11-4 Outline Drainage Strategy** [APP-227]. In addition, **ES Appendix 9-1: Ecology Legislation, Policy and Guidance** [REP1-034] has been updated to include legislation relevant to the assessment of impacts on fish and the requirements of these legislation have been considered as part of the impact assessment presented within **ES Chapter 9: Ecology and Biodiversity** [REP1-018] and **ES Appendix 11-2: WFD Report** [REP1-046]. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5. **Deadline 3 Update:** The Applicant has updated the **OCEMP** (Doc Ref. 7.10 Rev 3) at Deadline 3 to include the requested clarifications for mitigation commitments.	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
6.2	EA30	Watercourse habitat mitigation	Further detail is required regarding the proposed mitigation for open-cut trenching of watercourse crossings. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** We are satisfied with revisions made to the **OLEMP** [REP1-070].	The design of the watercourse crossings will be confirmed at the detailed design stage, in accordance with the design principles and parameters secured through the **Design Parameters** ~~[REP1-055]~~(Doc Ref. 7.4 Rev 3) and the **OCEMP** ~~[REP1-061].~~(Doc Ref. 7.10 Rev 3). The wording within the **OLEMP** ~~[REP1-070]~~(Doc Ref. 7.16 Rev 2) has however been reviewed and updated at Deadline 1 to include details of the habitat creation commitments to all banksides where crossing points are required – specifically, 15m habitat creation either side of all crossing points, subject to agreement with the Internal Drainage Boards (IDBs). The mitigation for water voles has been discussed and agreed in principle with Natural England as part of consultation meetings, as can be evidenced from the **Statement of Common Ground with Natural England** ~~[REP1-084].~~(Doc Ref. 8.13 Rev 1). A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	Agreed

3.7. Geomorphology

Table 3-7 Geomorphology

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
7.1	EA31	Definition of 'temporary'.	The WFD impacts of 'temporary' watercourse crossings may be underestimated. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2. **Deadline 3 Update:** We are satisfied that REP1-021 Paragraph 11.7.16 ES Chapter 11: Hydrology and Flood Risk has been updated to provide a time frame for the temporary nature of the access crossing works - i.e. up to a maximum of four years. Informative: The applicant should be aware that a recent update in EA Works in Rivers guidance now considers the installation/ decommissioning of culverting to be a high	**ES Chapter 11: Hydrology and Flood Risk** [REP1-020] has been updated to state that temporary crossings will be in place for up to four years, the construction of which has been assessed in Section 11.8. Mitigation has been committed to on the design of culverts and on channel reinstatement, as set out within **ES Chapter 11: Hydrology and Flood Risk** [REP1-020] and secured through **OCEMP** (Table 3-7) ~~[REP1-061].~~(Doc Ref. 7.10 Rev 3). The WFD Assessment within **ES Appendix 11-2: WFD Report** [REP1-047] concludes that any impacts associated with temporary and permanent crossings will be localised, mostly on minor drainage channels within the WFD water body catchments, and not significant at the WFD water body scale. The Scheme would therefore not cause deterioration in the status of any WFD water body or prevent the water bodies achieving	~~Under Discussion~~ Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			risk activity, regardless of scale (i.e. temporal or spatial), and should be assessed as such. Therefore, the advice previously provided regarding 6-month "temporary" works in rivers has now been superseded.	target status, noting the embedded environmental mitigation. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	
7.2	EA32	Culvert design.	The use of pipe culverts should be restricted to those watercourses that are predominantly dry throughout the year. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** The EA have now reviewed the documents submitted at Deadline 1 and are satisfied with this response.	**ES Chapter 11: Hydrology and Flood Risk** [REP1-061] and the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) state that where possible existing accesses will be used unmodified or slightly modified as required. Where new temporary access crossings are needed the design of each crossing will be addressed on a 'case by case' basis at detailed design with flexibility retained for either clear span structures or culverts. Where culverts are proposed the design will ensure that they are sized to not impact on flow conveyance and ensure capacity for peak flow rates, among other factors to minimise environmental impact. An assessment for each water feature based on assumed reasonable worst-case parameters for a proposed structure is presented within Table 11-9 and Table 11-10	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				of **ES Chapter 11: Hydrology and Flood Risk** [REP1-020]. A pipe culvert was assumed given the desire to be able to easily remove the structure following completion of construction works. However, as mentioned above, flexibility is retained in the DCO for both clear-span or culvert structures, with the latter not necessarily a pipe. The majority of watercourses are low grade and mainly managed drains that are only seasonally wet and have very limited coarse sediment transport. As a result, there is limited potential for impacts on the water environment through throttling of flows and interference with sediment movement. Overall, the design of temporary access crossings will be agreed with the IDB, where required, depending upon ownership of the asset, as managed by protective provisions included within the **Draft DCO** ~~[REP1-006].~~(Doc Ref. 3.1 Rev 3). Furthermore, the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) has been updated at Deadline 1 to include a firmer commitment to the use of clear span structures for crossings across permanently	

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				wet watercourses, where practicable and safe to do so, except where the crossing forms part of a public highway access point (bellmouth access) or where an alternative crossing solution is justified through the detailed design process. In such cases, it must be demonstrated that there would be no significant adverse effects on fish. The Environment Agency would be consulted as part of the detailed design process, and suitable mitigation measures incorporated into the crossing design. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	
7.3	EA33	Watercourse crossing technique.	Further detail is required regarding the construction and reinstatement of open-cut watercourse crossings. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update**	For the intrusive crossings, Table 3-7 within the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) sets out the potential risks and mitigation measures for the construction of open cut watercourse crossings. Measures which are secured within the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) include a Pre-works Hydromorphological and Riparian Corridor Survey which will be undertaken to record channel features/habitats and provide the	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			No update at Deadline 2 **Deadline 3 Update:** The EA are now satisfied that re-instatement of open-cut trench watercourse crossings has been better defined in Table 3-7 of the OCEMP [REP1-061].	baseline, against which reinstatement will be designed. Reinstatement will seek to return the watercourse to a condition as found as a minimum whilst also considering opportunities for enhancement, which would be subject to agreement with the IDB. Furthermore, during reinstatement, any subsequent improvements to the watercourse that have occurred upstream or downstream by other initiatives can be taken into account, although as this is within the construction site any changes in baseline are unlikely. The **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) has been updated at Deadline 1 to clarify measures to be adopted for the construction and reinstatement of open cut watercourse crossings. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	

3.8. Water Resources

Table 3-8 Water Resources

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
8.1	n/a	Water Resources	The Applicant has indicated that water supply will not come from Anglian Water and will be tankered from 3rd parties. More detailed assessment of later usage will be required, and water tanker movements should be included in traffic assessments. This intended approach is outside the remit of the Environment Agency. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** A meeting to discuss water supply was held with the Applicant and Anglian Water 28/09/2026. Discussion is ongoing as a basic water supply strategy is undertaken. The meeting discussed water quantities and uses. Supply options need to be better defined to provide confidence that the typical and peak water demands can be met. A multiple source approach was recommended to provide contingency should any sources	The Scheme is not proposing connection to the mains water supply for construction or decommissioning. During operation, mains supply is only proposed for the operational water supply of site offices within the On-Site Substations, accommodating up to 10 site staff, subject to agreement with Anglian Water, or otherwise a third party commercial source will be used. All other construction, operational and decommissioning water supply is to be sourced from commercial suppliers and a connection to a mains supply or water abstraction does not form part of this DCO Application. Water tanker movements have been accounted for in the development traffic estimates assessed in **ES Chapter 15: Traffic and Access** ~~[APP-066].~~(Doc Ref. 6.1 Rev 1). The approach to the water supply is set out within the **OCEMP** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) and **ODEMP** ~~[REP1-065].~~(Doc Ref. 7.12 Rev 2).	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			become unviable. An application to Anglian Water Services should help to clarify the extent of quantities potentially available from them. The possibility of a de minimus groundwater abstraction (<20m3/day) was also raised. We can now confirm that further assessment of such an abstraction would not be required. This option may therefore be more viable to the Applicant as part of the supply options available. **Deadline 3 Update:** A Water Supply Strategy was submitted at Deadline 2. The EA are confident that operational water demands can be met. However, peak demands during construction phase require further contingency planning. Overall, the EA are satisfied that the Applicant has considered what opportunities and limitations there are for water supply in this region. There remain options not currently being considered which include de-minimus abstraction (outside of regulation); and licence trading which can be considered as part of a multi source supply approach.	A Water Supply Strategy will be prepared for Deadline 2, ahead of which a meeting is scheduled with the Environment Agency and Anglian Water to discuss the format and contents of the document. **Deadline 3 Update:** The Applicant submitted a **Water Supply Strategy** [REP2-019] at Deadline 2 and separately submitted a non-domestic water supply request application through the Anglian Water Services website. The Applicant is currently waiting for a response from Anglian Water Services on these submissions and will provide an update to the EA once received. **Water Supply Strategy** [REP2-019] references options for de-minimus abstraction and license trading. However, these options are not considered capable of delivering the required water for the Scheme on their own nor are they currently the preferred options for water supply.	

3.9. Water Quality

Table 3-9 Water Quality

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
9.1	EA34	Water quality monitoring	Water quality monitoring needs to be developed further to ensure risks to the environment are adequately managed. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** Further updates are required to the oCEMP and oOEMP to ensure WQ monitoring is adequately secured.	The **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) commits to the production of a detailed Water Management Plan (WMP), which has been agreed as a suitable approach on other similar NSIP schemes. The WMP (which will be produced post consent) will also include details of pre, during and post-construction water quality monitoring. A full response is provided in the **Relevant Representations Report** [REP1- 074] at Table 3.5. **Deadline 3 Update:** The Applicant awaits further comments from the EA on updates requested.	Under Discussion
9.2	EA35 and EA36	Watercourse receptor importance and water quality baseline.	When considering watercourse receptor importance, it is unclear how downstream watercourses have been included in assessment. Further baseline information should be presented.	**ES Chapter 11: Hydrology and Flood Risk** [REP1-020] paragraphs 11.4.1 to 11.4.7 outline the approach to the study area for the assessment. **ES Appendix 11-5: Hydrology and Flood Risk Baseline** [APP-233], Table	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** EA35 resolved – the EA are satisfied with the applicant's comments. EA36 – on-going.	1-3 and Table 1-8 provide further baseline information. The Water Management Plan (which will be produced post consent), as outlined in the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) will require pre, during and post-construction water quality monitoring. The monitoring as part of the pre-construction would include as a minimum pH, temperature, conductivity, dissolved oxygen and turbidity. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5. **Deadline 3 Update:** The Applicant awaits further comments from the EA on updates requested.	
9.3	EA37	Foul water strategy.	Foul water strategy for construction and decommissioning should be clarified.	The **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) and **ODEMP** ~~[REP1-065]~~(Doc Ref. 7.12 Rev 2) state that foul drainage during construction and decommissioning will be dealt with by	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** The EA are satisfied that the OCEMP (REP1-062) says "Scheme construction foul drainage is expected to be provided by self-contained cesspits (or similar sealed tank), regularly emptied by a waste management contractor" in Table 3.7. Words to the same effect are seen in section 2.3.2 in OOEMP (REP1-064) and Table 3.7 in ODEMP (REP1-066).	self-contained cesspits and will be regularly emptied by a waste management contractor. **ES Chapter 11: Hydrology and Flood Risk** [REP1-020] and **ES Appendix 11-2: WFD Report** [REP1-046] have been updated at Deadline 1 to refer to these arrangements for foul drainage during construction and decommissioning. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	
9.4	EA38 EA39 EA40	Request for further detail of mitigation measures.	Further detail is required in the accompanying outline management plans (oCEMP, oOEMP, oDEMP) regarding key pollution prevention measures. The EA will review and provide an update on their position following a	The Applicant has made updates to the **OCEMP** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) and **ODEMP** ~~[REP1-065]~~(Doc Ref. 7.12 Rev 2) at Deadline 1 to clarify mitigation measures in accordance with the EA's detailed	Under Discussion

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** Further minor detail is requested regarding fuel, chemical and oil storage.	comments raised in its relevant representation. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5. **Deadline 3 Update:** The Applicant awaits further comments from the EA on updates requested.	
9.5	EA41 EA42 EA43 EA44	Installation and Management of BESS and Substations.	Further detail is required regarding the installation and management of the BESS and substations. The EA will review and provide an update on their position following a review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** The EA are satisfied with the Applicant's response.	The Applicant has set out further details regarding the installation of, and management of fire risk at, the BESS and On-Site Substations within the **Relevant Representations Report** [REP1-074] at Table 3.5. Further details with regards to the management of firewater at the BESS Compound are set out within the **ES Appendix 11-4 Outline Drainage Strategy** [APP-227] and **the Outline Battery Safety Management Plan** [APP-284]. With regards to the On-Site Substations, modern substations are designed in accordance with relevant	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				UK standards and incorporate multiple layers of protection including electrical protection systems, fault detection, automatic isolation, fire separation distances, oil containment systems and routine inspection and maintenance. Table 3-8 of the **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) has been updated at Deadline 1 to clarify measures to be implemented with the detailed design and emergency planning procedures of on-site substations to prevent contaminated firewater runoff being released from the site during an incident. A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	
9.6	Points for consideration	Bunding (pollution) of electrical equipment.	Relevant guidance should be reflected in accompanying outline management plans (oCEMP, oOEMP, oDEMP) and WFD Report to support pollution prevention The EA will review and provide an update on their position following a	The Applicant has made updates to the **OCEMP** ~~[REP1-061],~~(Doc Ref. 7.10 Rev 3), **OOEMP** ~~[REP1-063],~~(Doc Ref. 7.11 Rev 2), **ODEMP** ~~[REP1-065]~~(Doc Ref. 7.12 Rev 2) and **ES Appendix 11-2: WFD Report** [REP1-046] at Deadline 1 to reflect compliance with	~~Under Discussion~~Agreed

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
			review of documents submitted by the Applicant at Deadline 1. **Deadline 2 Update** No update at Deadline 2 **Deadline 3 Update:** Agreed.	relevant guidance for pollution prevention. Where transformers and other electrical equipment are oil filled, these will comply with the Control of Pollution (Oil Storage) Regulations[3]. As such they will contain bunding to hold at least 110% of the maximum capacity of the transformer or other electrical equipment. Table 3-7 in the **OCEMP** ~~[REP1-061]~~(Doc Ref. 7.10 Rev 3) and Table 3-8 in the **OOEMP** ~~[REP1-063]~~(Doc Ref. 7.11 Rev 2) state that fuel and other potentially polluting chemicals will either be in self-bunded leak proof containers or stored in a secure impermeable and bunded area (minimum capacity of 110% of the capacity of the containers, which	

[3] HM Government (2001) The Control of Pollution (Oil Storage) (England) Regulations 2001. Available at: https://www.legislation.gov.uk/uksi/2001/2954/contents [Accessed 21/09/2026]

Ref	EA Ref.	Matter	Stakeholder Position	Meridian Solar Farm Position	Status
				constitutes 10% more capacity than is strictly needed). A full response is provided in the **Relevant Representations Report** [REP1-074] at Table 3.5.	

4. Signatures

4.1.1. This SoCG is agreed between the following:

Duly authorised for and on behalf of Meridian Solar Farm, the Applicant	Name Job Title Date Signature
Duly authorised for and on behalf of the Environment Agency	Name Job Title Date Signature