















Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



Ordnance Survey © Crown Copyright, 100018507

There are no assets within this map area



## Appendix D Proposed Drainage Information

- Greenfield Runoff Rates
- FEH22 Point Descriptors
- InfoDrainage schedule and results
- Stantec drawings:
  - 333101678/300.03/001 & 002 (BESS, National Grid & 400kV Substations BESS & 1B)
  - 333101678/300.03/004 & 005 (Project Substations 4B, 5A, 7F & 10C)
  - 333101678/300.03/003 & 006 to 023 (Concept Access Track Drainage Wider Order Limits)



FEH Catchment Descriptors - BESS, NG Substation, Project Substations 1 & 3

|                 |      |            |                  |      |
|-----------------|------|------------|------------------|------|
| FEH data export | Date | 13/10/2025 | FEHCDROM version | 2022 |
|-----------------|------|------------|------------------|------|

\\Cbh-vfil-001\cbh\Projects\333101211 Long Stratton (Hydro)\Incoming\FEH

| Descriptor  |        |
|-------------|--------|
| Catchment X | 617250 |
| Catchment Y | 288380 |
| Centroid X  |        |
| Centroid Y  |        |
| AREA        |        |
| ALTBAR      |        |
| ASPBAR      |        |
| ASPVAR      |        |
| BFIHOST     | 0.312  |
| BFIHOST19   | 0.333  |
| DPLBAR      |        |
| DPSBAR      |        |
| FARL        |        |
| FPEXT       |        |
| FPDBAR      |        |
| FPLOC       |        |
| LDP         |        |
| PROPWET     | 0.31   |
| RMED-1H     |        |
| RMED-1D     |        |
| RMED-2D     |        |
| SAAR        | 606    |
| SAAR4170    |        |
| SPRHOST     |        |
| URBCONC1990 |        |
| URBEXT1990  |        |
| URBLOC1990  |        |
| URBCONC2000 |        |
| URBEXT2000  |        |
| URBLOC2000  |        |
| C           |        |
| D1          |        |
| D2          |        |
| D3          |        |
| E           |        |
| F           |        |
| C(1 km)     |        |
| D1(1 km)    |        |
| D2(1 km)    |        |
| D3(1 km)    |        |
| E(1 km)     |        |
| F(1 km)     |        |

Descriptors provided by POINT export



# FEH Catchment Descriptors - Project Substation 132kV 4B

|                 |      |            |                  |      |
|-----------------|------|------------|------------------|------|
| FEH data export | Date | 08/09/2026 | FEHCDROM version | 2022 |
|-----------------|------|------------|------------------|------|

\\Cbh-vfil-001\cbh\Projects\333101211 Long Stratton (Hydro)\Incoming\FEH

| Descriptor  |        |
|-------------|--------|
| Catchment X | 620640 |
| Catchment Y | 294387 |
| Centroid X  |        |
| Centroid Y  |        |
| AREA        |        |
| ALTBAR      |        |
| ASPBAR      |        |
| ASPVAR      |        |
| BFIHOST     | 0.605  |
| BFIHOST19   | 0.6    |
| DPLBAR      |        |
| DPSBAR      |        |
| FARL        |        |
| FPEXT       |        |
| FPDBAR      |        |
| FPLOC       |        |
| LDP         |        |
| PROPWET     | 0.27   |
| RMED-1H     |        |
| RMED-1D     |        |
| RMED-2D     |        |
| SAAR        | 601    |
| SAAR4170    |        |
| SPRHOST     |        |
| URBCONC1990 |        |
| URBEXT1990  |        |
| URBLOC1990  |        |
| URBCONC2000 |        |
| URBEXT2000  |        |
| URBLOC2000  |        |
| C           |        |
| D1          |        |
| D2          |        |
| D3          |        |
| E           |        |
| F           |        |
| C(1 km)     |        |
| D1(1 km)    |        |
| D2(1 km)    |        |
| D3(1 km)    |        |
| E(1 km)     |        |
| F(1 km)     |        |

Descriptors provided by POINT export



# FEH Catchment Descriptors - Project Substation 2 400kV 5A

|                 |      |            |                  |      |
|-----------------|------|------------|------------------|------|
| FEH data export | Date | 08/09/2026 | FEHCDROM version | 2022 |
|-----------------|------|------------|------------------|------|

\\Cbh-vfil-001\cbh\Projects\333101211 Long Stratton (Hydro)\Incoming\FEH

| Descriptor  |        |
|-------------|--------|
| Catchment X | 622455 |
| Catchment Y | 293765 |
| Centroid X  |        |
| Centroid Y  |        |
| AREA        |        |
| ALTBAR      |        |
| ASPBAR      |        |
| ASPVAR      |        |
| BFIHOST     | 0.435  |
| BFIHOST19   | 0.437  |
| DPLBAR      |        |
| DPSBAR      |        |
| FARL        |        |
| FPEXT       |        |
| FPDBAR      |        |
| FPLOC       |        |
| LDP         |        |
| PROPWET     | 0.27   |
| RMED-1H     |        |
| RMED-1D     |        |
| RMED-2D     |        |
| SAAR        | 598    |
| SAAR4170    |        |
| SPRHOST     |        |
| URBCONC1990 |        |
| URBEXT1990  |        |
| URBLOC1990  |        |
| URBCONC2000 |        |
| URBEXT2000  |        |
| URBLOC2000  |        |
| C           |        |
| D1          |        |
| D2          |        |
| D3          |        |
| E           |        |
| F           |        |
| C(1 km)     |        |
| D1(1 km)    |        |
| D2(1 km)    |        |
| D3(1 km)    |        |
| E(1 km)     |        |
| F(1 km)     |        |

Descriptors provided by POINT export



# FEH Catchment Descriptors - Project Substation 132kV 7F

|                 |      |            |                  |      |
|-----------------|------|------------|------------------|------|
| FEH data export | Date | 08/09/2026 | FEHCDROM version | 2022 |
|-----------------|------|------------|------------------|------|

\\Cbh-vfil-001\cbh\Projects\333101211 Long Stratton (Hydro)\Incoming\FEH

| Descriptor  |        |
|-------------|--------|
| Catchment X | 624184 |
| Catchment Y | 295920 |
| Centroid X  |        |
| Centroid Y  |        |
| AREA        |        |
| ALTBAR      |        |
| ASPBAR      |        |
| ASPVAR      |        |
| BFIHOST     | 0.367  |
| BFIHOST19   | 0.385  |
| DPLBAR      |        |
| DPSBAR      |        |
| FARL        |        |
| FPEXT       |        |
| FPDBAR      |        |
| FPLOC       |        |
| LDP         |        |
| PROPWET     | 0.27   |
| RMED-1H     |        |
| RMED-1D     |        |
| RMED-2D     |        |
| SAAR        | 599    |
| SAAR4170    |        |
| SPRHOST     |        |
| URBCONC1990 |        |
| URBEXT1990  |        |
| URBLOC1990  |        |
| URBCONC2000 |        |
| URBEXT2000  |        |
| URBLOC2000  |        |
| C           |        |
| D1          |        |
| D2          |        |
| D3          |        |
| E           |        |
| F           |        |
| C(1 km)     |        |
| D1(1 km)    |        |
| D2(1 km)    |        |
| D3(1 km)    |        |
| E(1 km)     |        |
| F(1 km)     |        |

Descriptors provided by POINT export



# FEH Catchment Descriptors - Project Substation 132kV 10C

|                 |      |            |                  |      |
|-----------------|------|------------|------------------|------|
| FEH data export | Date | 08/09/2026 | FEHCDROM version | 2022 |
|-----------------|------|------------|------------------|------|

\\Cbh-vfil-001\cbh\Projects\333101211 Long Stratton (Hydro)\Incoming\FEH

| Descriptor  |        |
|-------------|--------|
| Catchment X | 629915 |
| Catchment Y | 295300 |
| Centroid X  |        |
| Centroid Y  |        |
| AREA        |        |
| ALTBAR      |        |
| ASPBAR      |        |
| ASPVAR      |        |
| BFIHOST     | 0.395  |
| BFIHOST19   | 0.412  |
| DPLBAR      |        |
| DPSBAR      |        |
| FARL        |        |
| FPEXT       |        |
| FPDBAR      |        |
| FPLOC       |        |
| LDP         |        |
| PROPWET     | 0.27   |
| RMED-1H     |        |
| RMED-1D     |        |
| RMED-2D     |        |
| SAAR        | 607    |
| SAAR4170    |        |
| SPRHOST     |        |
| URBCONC1990 |        |
| URBEXT1990  |        |
| URBLOC1990  |        |
| URBCONC2000 |        |
| URBEXT2000  |        |
| URBLOC2000  |        |
| C           |        |
| D1          |        |
| D2          |        |
| D3          |        |
| E           |        |
| F           |        |
| C(1 km)     |        |
| D1(1 km)    |        |
| D2(1 km)    |        |
| D3(1 km)    |        |
| E(1 km)     |        |
| F(1 km)     |        |

Descriptors provided by POINT export



|               |                                                                                                                |        |
|---------------|----------------------------------------------------------------------------------------------------------------|--------|
| Project Title | East Pye Solar DCO - Greenfield Runoff - BESS, National Grid Substation, and Project Substations 400kV 1 and 3 |        |
| Project No    | 333103270                                                                                                      | 100.06 |

Methodology as set out in SuDS Manual 24.3.2

[SUDS Manual Chapter 24](#)

1 Retrieve FEH Catchment Information

|                                  |         |       |            |
|----------------------------------|---------|-------|------------|
| Define BFIHOST definition source |         | FEH   | see note 1 |
| Catchment Descriptors            | BFIHOST | 0.333 |            |
|                                  | SAAR    | 606   | see note 1 |
|                                  | FARL    | 1.0   | see note 2 |

2 Derive QBAR (mean annual flood)

|                                                      |                        |      |     |            |
|------------------------------------------------------|------------------------|------|-----|------------|
| Define area                                          | Site Area              | 1.00 | ha  |            |
|                                                      | Applied Area           | 50.0 | ha  | see note 3 |
| FEH Index Flood (SuDS Manual Equation 24.2)          | QMED (Q <sub>2</sub> ) | 3.0  | l/s | see note 4 |
| Calculate QBAR by dividing QMED by 2yr growth factor | QBAR                   | 3.3  | l/s | see note 5 |

3 Select appropriate growth factors

|                           |                   |      |
|---------------------------|-------------------|------|
| FSR Hydrological Region   |                   | 5    |
| 100yr Growth Curve Factor | GQ <sub>100</sub> | 3.56 |
| 30yr Growth Curve Factor  | GQ <sub>30</sub>  | 2.55 |
| 10yr Growth Curve Factor  | GQ <sub>10</sub>  | 1.65 |
| 2yr Growth Curve Factor   | GQ <sub>2</sub>   | 0.89 |
| 1yr Growth Curve Factor   | GQ <sub>1</sub>   | 0.87 |

(refer to FSR Hydrological Region tab)



4 Derive Flood Frequency

Greenfield Runoff per 1ha

|                        |                  |      |        |
|------------------------|------------------|------|--------|
| 100yr Peak Runoff Rate | Q <sub>100</sub> | 11.9 | l/s/ha |
| 30yr Peak Runoff Rate  | Q <sub>30</sub>  | 8.5  | l/s/ha |
| 10yr Growth Curve Rate | Q <sub>10</sub>  | 5.5  | l/s/ha |
| QBAR Peak Runoff Rate  | QBAR             | 3.3  | l/s/ha |
| 2yr Peak Runoff Rate   | Q <sub>2</sub>   | 3.0  | l/s/ha |
| 1yr Peak Runoff Rate   | Q <sub>1</sub>   | 2.9  | l/s/ha |

DOCUMENT ISSUE RECORD

| Rev | Comments                          | Prepared | Date       | Checked   | Date       |
|-----|-----------------------------------|----------|------------|-----------|------------|
| -   | Original calculation              | E Edney  | 24/10/2025 | A Johnson | 03/12/2025 |
| A   | Re-issued with updated page title | E Edney  | 08/09/2026 | A Johnson | 08/09/2026 |
|     |                                   |          |            |           |            |



- Notes This spreadsheet has been created to allow derivation of greenfield runoff rates using the FEH statistical method applied in a manner consistent with the recommendations of the SuDS Manual. If you have recommendations to improve this spreadsheet please contact Alex Bearne.
- Note 1 FEH Web version 3 allows extraction of BFIHOST and SAAR values for each square kilometre grid Export point data from FEH Webs Service as .XML file and save in project folder and import in the FEH Point Data Import tab. If you do not think the BFIHOST value is representative of your site then it is possible to derive it manually. This should not normally be necessary. BFI can be derived manually using the methodology set out in the Flood Estimation Handbook (see Manual Derivation of BFIHOST tab) or can be defined from ground investigation information.  
As default the sheet references the imported FEH data
- Note 2 FARL value is a measure of attenuation from reservoirs and lakes for the majority of studies this should be set to 1 (representing no attenuation). If your site includes a large water body with an attenuating affect on runoff please consult a hydrologist.  
*FARL is a measurement of studies water bodies in the catchment so that their attenuation effects so this term becomes 1.0 and therefore drops out.* (see page 23 of the Preliminary rainfall runoff management for developments EA/Defra 2013)  
[Rainfall runoff management for developments.pdf](#)
- Note 3 If the site area is less than 50 hectare the spreadsheet will calculate QMED for 50ha and scale the results automatically to the defined Site Area
- Note 4 QMED is calculated using the statistical equation as revised by Kjeldsen in 2008

$$Q_{MED} = 8.3062AREA^{0.8510} \cdot 0.1536^{(1000/SAAR)} \cdot FARL^{3.4451} \cdot 0.0460^{BFIHOST^2}$$

[Rainfall runoff management for developments.pdf](#)

It is reproduced as Equation 24.2 in the SUDS Manual (pg 512)

- Note 5 QBAR is calculated by dividing QMED by the growth factor for the 2 year event, as per the methodology set out in paragraph 6.2.2 of 'Rainfall runoff management for developments' . QBAR is then used as the index flood for the basis of applying the growth factors.







|               |                                                                               |        |
|---------------|-------------------------------------------------------------------------------|--------|
| Project Title | East Pye Solar DCO - Greenfield Runoff - Project Substation 132kV Sub-Site 4B |        |
| Project No    | 333103270                                                                     | 100.06 |

Methodology as set out in SuDS Manual 24.3.2

[SU DS Manual Chapter 24](#)

1 Retrieve FEH Catchment Information

|                                  |         |       |            |
|----------------------------------|---------|-------|------------|
| Define BFIHOST definition source |         | FEH   | see note 1 |
| Catchment Descriptors            | BFIHOST | 0.600 |            |
|                                  | SAAR    | 601   | see note 1 |
|                                  | FARL    | 1.0   | see note 2 |

2 Derive QBAR (mean annual flood)

|                                                      |                        |      |     |            |
|------------------------------------------------------|------------------------|------|-----|------------|
| Define area                                          | Site Area              | 0.50 | ha  |            |
|                                                      | Applied Area           | 50.0 | ha  | see note 3 |
| FEH Index Flood (SuDS Manual Equation 24.2)          | QMED (Q <sub>2</sub> ) | 0.7  | l/s | see note 4 |
| Calculate QBAR by dividing QMED by 2yr growth factor | QBAR                   | 0.8  | l/s | see note 5 |

3 Select appropriate growth factors

|                           |                   |      |
|---------------------------|-------------------|------|
| FSR Hydrological Region   |                   | 5    |
| 100yr Growth Curve Factor | GQ <sub>100</sub> | 3.56 |
| 30yr Growth Curve Factor  | GQ <sub>30</sub>  | 2.55 |
| 10yr Growth Curve Factor  | GQ <sub>10</sub>  | 1.65 |
| 2yr Growth Curve Factor   | GQ <sub>2</sub>   | 0.89 |
| 1yr Growth Curve Factor   | GQ <sub>1</sub>   | 0.87 |

(refer to FSR Hydrological Region tab)



4 Derive Flood Frequency

Greenfield Runoff per 1ha

|                        |                  |     |    |
|------------------------|------------------|-----|----|
| 100yr Peak Runoff Rate | Q <sub>100</sub> | 2.7 | ha |
| 30yr Peak Runoff Rate  | Q <sub>30</sub>  | 1.9 | ha |
| 10yr Growth Curve Rate | Q <sub>10</sub>  | 1.2 | ha |
| QBAR Peak Runoff Rate  | QBAR             | 0.8 | ha |
| 2yr Peak Runoff Rate   | Q <sub>2</sub>   | 0.7 | ha |
| 1yr Peak Runoff Rate   | Q <sub>1</sub>   | 0.7 | ha |

DOCUMENT ISSUE RECORD

| Rev | Comments             | Prepared | Date       | Checked   | Date       |
|-----|----------------------|----------|------------|-----------|------------|
| -   | Original calculation | E Edney  | 08/09/2026 | A Johnson | 08/09/2026 |
|     |                      |          |            |           |            |
|     |                      |          |            |           |            |

- Notes This spreadsheet has been created to allow derivation of greenfield runoff rates using the FEH statistical method applied in a manner consistent with the recommendations of the SuDS Manual. If you have recommendations to improve this spreadsheet please contact Alex Bearne.
- Note 1 FEH Web version 3 allows extraction of BFIHOST and SAAR values for each square kilometre grid Export point data from FEH Webs Service as .XML file and save in project folder and import in the FEH Point Data Import tab. If you do not think the BFIHOST value is representative of your site then it is possible to derive it manually. This should not normally be necessary. BFI can be derived manually using the methodology set out in the Flood Estimation Handbook (see Manual Derivation of BFIHOST tab) or can be defined from ground investigation information.  
As default the sheet references the imported FEH data
- Note 2 FARL value is a measure of attenuation from reservoirs and lakes for the majority of studies this should be set to 1 (representing no attenuation). If your site includes a large water body with an attenuating affect on runoff please consult a hydrologist.  
*FARL is a measurement of studies water bodies in the catchment so that their attenuation effects so this term becomes 1.0 and therefore drops out.* (see page 23 of the Preliminary rainfall runoff management for developments EA/Defra 2013)  
[Rainfall runoff management for developments.pdf](#)
- Note 3 If the site area is less than 50 hectare the spreadsheet will calculate QMED for 50ha and scale the results automatically to the defined Site Area
- Note 4 QMED is calculated using the statistical equation as revised by Kjeldsen in 2008

$$Q_{MED} = 8.3062AREA^{0.8510} \cdot 0.1536^{(1000/SAAR)} \cdot FARL^{3.4451} \cdot 0.0460^{BFIHOST^2}$$

[Rainfall runoff management for developments.pdf](#)

It is reproduced as Equation 24.2 in the SUDS Manual (pg 512)

- Note 5 QBAR is calculated by dividing QMED by the growth factor for the 2 year event, as per the methodology set out in paragraph 6.2.2 of 'Rainfall runoff management for developments' . QBAR is then used as the index flood for the basis of applying the growth factors.





# FEH Greenfield Runoff

Using the 2008 Statistical Method QMED Equation



|               |                                                                               |        |
|---------------|-------------------------------------------------------------------------------|--------|
| Project Title | East Pye Solar DCO - Greenfield Runoff - Project Substation 400kV Sub-Site 5A |        |
| Project No    | 333103270                                                                     | 100.06 |

Methodology as set out in SuDS Manual 24.3.2

[SU DS Manual Chapter 24](#)

### 1 Retrieve FEH Catchment Information

|                                  |         |       |            |
|----------------------------------|---------|-------|------------|
| Define BFIHOST definition source |         | FEH   | see note 1 |
| Catchment Descriptors            | BFIHOST | 0.437 |            |
|                                  | SAAR    | 598   | see note 1 |
|                                  | FARL    | 1.0   | see note 2 |

### 2 Derive QBAR (mean annual flood)

|                                                      |                        |      |     |            |
|------------------------------------------------------|------------------------|------|-----|------------|
| Define area                                          | Site Area              | 3.50 | ha  |            |
|                                                      | Applied Area           | 50.0 | ha  | see note 3 |
| FEH Index Flood (SuDS Manual Equation 24.2)          | QMED (Q <sub>2</sub> ) | 7.8  | l/s | see note 4 |
| Calculate QBAR by dividing QMED by 2yr growth factor | QBAR                   | 8.8  | l/s | see note 5 |

### 3 Select appropriate growth factors

|                           |                   |      |
|---------------------------|-------------------|------|
| FSR Hydrological Region   |                   | 5    |
| 100yr Growth Curve Factor | GQ <sub>100</sub> | 3.56 |
| 30yr Growth Curve Factor  | GQ <sub>30</sub>  | 2.55 |
| 10yr Growth Curve Factor  | GQ <sub>10</sub>  | 1.65 |
| 2yr Growth Curve Factor   | GQ <sub>2</sub>   | 0.89 |
| 1yr Growth Curve Factor   | GQ <sub>1</sub>   | 0.87 |

(refer to FSR Hydrological Region tab)



### 4 Derive Flood Frequency

Greenfield Runoff per 1ha

|                        |                  |      |    |
|------------------------|------------------|------|----|
| 100yr Peak Runoff Rate | Q <sub>100</sub> | 31.2 | ha |
| 30yr Peak Runoff Rate  | Q <sub>30</sub>  | 22.4 | ha |
| 10yr Growth Curve Rate | Q <sub>10</sub>  | 14.5 | ha |
| QBAR Peak Runoff Rate  | QBAR             | 8.8  | ha |
| 2yr Peak Runoff Rate   | Q <sub>2</sub>   | 7.8  | ha |
| 1yr Peak Runoff Rate   | Q <sub>1</sub>   | 7.6  | ha |

### DOCUMENT ISSUE RECORD

| Rev | Comments             | Prepared | Date       | Checked   | Date       |
|-----|----------------------|----------|------------|-----------|------------|
| -   | Original calculation | E Edney  | 08/09/2026 | A Johnson | 08/09/2026 |
|     |                      |          |            |           |            |
|     |                      |          |            |           |            |



- Notes This spreadsheet has been created to allow derivation of greenfield runoff rates using the FEH statistical method applied in a manner consistent with the recommendations of the SuDS Manual. If you have recommendations to improve this spreadsheet please contact Alex Bearne.
- Note 1 FEH Web version 3 allows extraction of BFIHOST and SAAR values for each square kilometre grid Export point data from FEH Webs Service as .XML file and save in project folder and import in the FEH Point Data Import tab. If you do not think the BFIHOST value is representative of your site then it is possible to derive it manually. This should not normally be necessary. BFI can be derived manually using the methodology set out in the Flood Estimation Handbook (see Manual Derivation of BFIHOST tab) or can be defined from ground investigation information.  
As default the sheet references the imported FEH data
- Note 2 FARL value is a measure of attenuation from reservoirs and lakes for the majority of studies this should be set to 1 (representing no attenuation). If your site includes a large water body with an attenuating affect on runoff please consult a hydrologist.  
*FARL is a measurement of studies water bodies in the catchment so that their attenuation effects so this term becomes 1.0 and therefore drops out.* (see page 23 of the Preliminary rainfall runoff management for developments EA/Defra 2013)  
[Rainfall runoff management for developments.pdf](#)
- Note 3 If the site area is less than 50 hectare the spreadsheet will calculate QMED for 50ha and scale the results automatically to the defined Site Area
- Note 4 QMED is calculated using the statistical equation as revised by Kjeldsen in 2008

$$Q_{MED} = 8.3062AREA^{0.8510} \cdot 0.1536^{(1000/SAAR)} \cdot FARL^{3.4451} \cdot 0.0460^{BFIHOST^2}$$

[Rainfall runoff management for developments.pdf](#)

It is reproduced as Equation 24.2 in the SUDS Manual (pg 512)

- Note 5 QBAR is calculated by dividing QMED by the growth factor for the 2 year event, as per the methodology set out in paragraph 6.2.2 of 'Rainfall runoff management for developments' . QBAR is then used as the index flood for the basis of applying the growth factors.





# FEH Greenfield Runoff

Using the 2008 Statistical Method QMED Equation



|               |                                                                               |        |
|---------------|-------------------------------------------------------------------------------|--------|
| Project Title | East Pye Solar DCO - Greenfield Runoff - Project Substation 132kV Sub-Site 7F |        |
| Project No    | 333103270                                                                     | 100.06 |

Methodology as set out in SuDS Manual 24.3.2

[SU DS Manual Chapter 24](#)

### 1 Retrieve FEH Catchment Information

|                                  |         |       |            |
|----------------------------------|---------|-------|------------|
| Define BFIHOST definition source |         | FEH   | see note 1 |
| Catchment Descriptors            | BFIHOST | 0.385 |            |
|                                  | SAAR    | 599   | see note 1 |
|                                  | FARL    | 1.0   | see note 2 |

### 2 Derive QBAR (mean annual flood)

|                                                      |                        |      |     |            |
|------------------------------------------------------|------------------------|------|-----|------------|
| Define area                                          | Site Area              | 0.75 | ha  |            |
|                                                      | Applied Area           | 50.0 | ha  | see note 3 |
| FEH Index Flood (SuDS Manual Equation 24.2)          | QMED (Q <sub>2</sub> ) | 1.9  | l/s | see note 4 |
| Calculate QBAR by dividing QMED by 2yr growth factor | QBAR                   | 2.2  | l/s | see note 5 |

### 3 Select appropriate growth factors

|                           |                   |      |
|---------------------------|-------------------|------|
| FSR Hydrological Region   |                   | 5    |
| 100yr Growth Curve Factor | GQ <sub>100</sub> | 3.56 |
| 30yr Growth Curve Factor  | GQ <sub>30</sub>  | 2.55 |
| 10yr Growth Curve Factor  | GQ <sub>10</sub>  | 1.65 |
| 2yr Growth Curve Factor   | GQ <sub>2</sub>   | 0.89 |
| 1yr Growth Curve Factor   | GQ <sub>1</sub>   | 0.87 |

(refer to FSR Hydrological Region tab)



### 4 Derive Flood Frequency

Greenfield Runoff per 1ha

|                        |                  |     |    |
|------------------------|------------------|-----|----|
| 100yr Peak Runoff Rate | Q <sub>100</sub> | 7.7 | ha |
| 30yr Peak Runoff Rate  | Q <sub>30</sub>  | 5.5 | ha |
| 10yr Growth Curve Rate | Q <sub>10</sub>  | 3.6 | ha |
| QBAR Peak Runoff Rate  | QBAR             | 2.2 | ha |
| 2yr Peak Runoff Rate   | Q <sub>2</sub>   | 1.9 | ha |
| 1yr Peak Runoff Rate   | Q <sub>1</sub>   | 1.9 | ha |

### DOCUMENT ISSUE RECORD

| Rev | Comments             | Prepared | Date       | Checked   | Date       |
|-----|----------------------|----------|------------|-----------|------------|
| -   | Original calculation | E Edney  | 08/09/2026 | A Johnson | 08/09/2026 |
|     |                      |          |            |           |            |
|     |                      |          |            |           |            |

- Notes This spreadsheet has been created to allow derivation of greenfield runoff rates using the FEH statistical method applied in a manner consistent with the recommendations of the SuDS Manual. If you have recommendations to improve this spreadsheet please contact Alex Bearne.
- Note 1 FEH Web version 3 allows extraction of BFIHOST and SAAR values for each square kilometre grid Export point data from FEH Webs Service as .XML file and save in project folder and import in the FEH Point Data Import tab. If you do not think the BFIHOST value is representative of your site then it is possible to derive it manually. This should not normally be necessary. BFI can be derived manually using the methodology set out in the Flood Estimation Handbook (see Manual Derivation of BFIHOST tab) or can be defined from ground investigation information.  
As default the sheet references the imported FEH data
- Note 2 FARL value is a measure of attenuation from reservoirs and lakes for the majority of studies this should be set to 1 (representing no attenuation). If your site includes a large water body with an attenuating affect on runoff please consult a hydrologist.  
*FARL is a measurement of studies water bodies in the catchment so that their attenuation effects so this term becomes 1.0 and therefore drops out.* (see page 23 of the Preliminary rainfall runoff management for developments EA/Defra 2013)  
[Rainfall runoff management for developments.pdf](#)
- Note 3 If the site area is less than 50 hectare the spreadsheet will calculate QMED for 50ha and scale the results automatically to the defined Site Area
- Note 4 QMED is calculated using the statistical equation as revised by Kjeldsen in 2008

$$Q_{MED} = 8.3062AREA^{0.8510} \cdot 0.1536^{(1000/SAAR)} \cdot FARL^{3.4451} \cdot 0.0460^{BFIHOST^2}$$

[Rainfall runoff management for developments.pdf](#)

It is reproduced as Equation 24.2 in the SUDS Manual (pg 512)

- Note 5 QBAR is calculated by dividing QMED by the growth factor for the 2 year event, as per the methodology set out in paragraph 6.2.2 of 'Rainfall runoff management for developments' . QBAR is then used as the index flood for the basis of applying the growth factors.





|               |                                                                                |        |
|---------------|--------------------------------------------------------------------------------|--------|
| Project Title | East Pye Solar DCO - Greenfield Runoff - Project Substation 132kV Sub-Site 10C |        |
| Project No    | 333103270                                                                      | 100.06 |

Methodology as set out in SuDS Manual 24.3.2

[SUDS Manual Chapter 24](#)

1 Retrieve FEH Catchment Information

|                                  |         |       |            |
|----------------------------------|---------|-------|------------|
| Define BFIHOST definition source |         | FEH   | see note 1 |
| Catchment Descriptors            | BFIHOST | 0.412 |            |
|                                  | SAAR    | 607   | see note 1 |
|                                  | FARL    | 1.0   | see note 2 |

2 Derive QBAR (mean annual flood)

|                                                      |                        |      |     |            |
|------------------------------------------------------|------------------------|------|-----|------------|
| Define area                                          | Site Area              | 0.50 | ha  |            |
|                                                      | Applied Area           | 50.0 | ha  | see note 3 |
| FEH Index Flood (SuDS Manual Equation 24.2)          | QMED (Q <sub>2</sub> ) | 1.2  | l/s | see note 4 |
| Calculate QBAR by dividing QMED by 2yr growth factor | QBAR                   | 1.4  | l/s | see note 5 |

3 Select appropriate growth factors

|                           |                   |      |
|---------------------------|-------------------|------|
| FSR Hydrological Region   |                   | 5    |
| 100yr Growth Curve Factor | GQ <sub>100</sub> | 3.56 |
| 30yr Growth Curve Factor  | GQ <sub>30</sub>  | 2.55 |
| 10yr Growth Curve Factor  | GQ <sub>10</sub>  | 1.65 |
| 2yr Growth Curve Factor   | GQ <sub>2</sub>   | 0.89 |
| 1yr Growth Curve Factor   | GQ <sub>1</sub>   | 0.87 |

(refer to FSR Hydrological Region tab)



4 Derive Flood Frequency

Greenfield Runoff per 1ha

|                        |                  |     |    |
|------------------------|------------------|-----|----|
| 100yr Peak Runoff Rate | Q <sub>100</sub> | 5.0 | ha |
| 30yr Peak Runoff Rate  | Q <sub>30</sub>  | 3.6 | ha |
| 10yr Growth Curve Rate | Q <sub>10</sub>  | 2.3 | ha |
| QBAR Peak Runoff Rate  | QBAR             | 1.4 | ha |
| 2yr Peak Runoff Rate   | Q <sub>2</sub>   | 1.2 | ha |
| 1yr Peak Runoff Rate   | Q <sub>1</sub>   | 1.2 | ha |

DOCUMENT ISSUE RECORD

| Rev | Comments             | Prepared | Date       | Checked   | Date       |
|-----|----------------------|----------|------------|-----------|------------|
| -   | Original calculation | E Edney  | 08/09/2026 | A Johnson | 08/09/2026 |
|     |                      |          |            |           |            |
|     |                      |          |            |           |            |

- Notes This spreadsheet has been created to allow derivation of greenfield runoff rates using the FEH statistical method applied in a manner consistent with the recommendations of the SuDS Manual. If you have recommendations to improve this spreadsheet please contact Alex Bearne.
- Note 1 FEH Web version 3 allows extraction of BFIHOST and SAAR values for each square kilometre grid Export point data from FEH Webs Service as .XML file and save in project folder and import in the FEH Point Data Import tab. If you do not think the BFIHOST value is representative of your site then it is possible to derive it manually. This should not normally be necessary. BFI can be derived manually using the methodology set out in the Flood Estimation Handbook (see Manual Derivation of BFIHOST tab) or can be defined from ground investigation information.  
As default the sheet references the imported FEH data
- Note 2 FARL value is a measure of attenuation from reservoirs and lakes for the majority of studies this should be set to 1 (representing no attenuation). If your site includes a large water body with an attenuating affect on runoff please consult a hydrologist.  
*FARL is a measurement of studies water bodies in the catchment so that their attenuation effects so this term becomes 1.0 and therefore drops out.* (see page 23 of the Preliminary rainfall runoff management for developments EA/Defra 2013)  
[Rainfall runoff management for developments.pdf](#)
- Note 3 If the site area is less than 50 hectare the spreadsheet will calculate QMED for 50ha and scale the results automatically to the defined Site Area
- Note 4 QMED is calculated using the statistical equation as revised by Kjeldsen in 2008

$$Q_{MED} = 8.3062AREA^{0.8510} \cdot 0.1536^{(1000/SAAR)} \cdot FARL^{3.4451} \cdot 0.0460^{BFIHOST^2}$$

[Rainfall runoff management for developments.pdf](#)

It is reproduced as Equation 24.2 in the SUDS Manual (pg 512)

- Note 5 QBAR is calculated by dividing QMED by the growth factor for the 2 year event, as per the methodology set out in paragraph 6.2.2 of 'Rainfall runoff management for developments' . QBAR is then used as the index flood for the basis of applying the growth factors.



|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Inflows<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                                | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



### CA BESS

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 6.50 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



### CA National Grid Substation

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 6.00 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 0.750 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Inflows<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                                | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



### CA 400kV Project Substation Sub-Site 1B

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 1.10 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 0.750 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



### CA 400kV Project Substation BESS Site

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 3.00 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 0.750 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                                                            |  |                   |  |                                                                                 |  |  |                                                                                     |  |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|-------------------|--|---------------------------------------------------------------------------------|--|--|-------------------------------------------------------------------------------------|--|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  |                   |  | Date:<br>04/03/0026                                                             |  |  |  |  |
| Designed by:<br>EE                                                                                                                         |  | Checked by:<br>AJ |  | Approved By:<br>ID                                                              |  |  |                                                                                     |  |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  |                   |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |  |  |                                                                                     |  |

| Name             | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |      |
|------------------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|------|
| OF BESS          | Simple Junction | 617093.947  | 288726.490   |                 |           |                  |               |              |      |
| BESS FC          | Manhole         | 617121.538  | 288677.894   | 54.550          | 1.130     | 53.420           | Circular      | 3.000        | None |
| NG SS FC         | Manhole         | 616856.302  | 289205.618   | 55.700          | 0.870     | 54.830           | Circular      | 3.000        | None |
| OF NG            | Simple Junction | 616833.537  | 289117.073   |                 |           |                  |               |              |      |
| OF PSS1B         | Simple Junction | 617084.320  | 289206.805   |                 |           |                  |               |              |      |
| PSS1B FC         | Manhole         | 617101.754  | 289220.610   | 55.800          | 0.720     | 55.080           | Circular      | 1.200        | None |
| OF PSS BESS Site | Simple Junction | 617432.540  | 288303.347   |                 |           |                  |               |              |      |
| PSS BESS Site FC | Manhole         | 617386.046  | 288318.541   | 54.480          | 0.700     | 53.780           | Circular      | 3.000        | None |



|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                    | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



**BESS**

Type : Porous Paving

|                             |                           |
|-----------------------------|---------------------------|
| <b>Dimensions</b>           |                           |
| Exceedance Level (m)        | 54.550                    |
| Depth (m)                   | 0.650                     |
| Base Level (m)              | 53.900                    |
| Paving Layer Depth (mm)     | 80                        |
| Membrane Percolation (m/hr) | 32.4                      |
| Porosity (%)                | 30                        |
| Length (m)                  | 318.500                   |
| Long. Slope (1:X)           | 430.00                    |
| Width (m)                   | 204.058                   |
| Total Volume (m³)           | 11116.341                 |
| <b>Under Drain</b>          |                           |
| Height Above Base (m)       | 0.000                     |
| Diameter (mm)               | 150                       |
| No. of Barrels              | 1                         |
| Release Height (m)          | 0.000                     |
| Friction Scheme             | Colebrook-White Roughness |
| Roughness (mm)              | 0.6                       |
| <b>Inlets</b>               |                           |
| <b>Inlet</b>                |                           |
| Inlet Type                  | Lateral Inflow            |
| Incoming Item(s)            | CA BESS                   |
| Bypass Destination          | (None)                    |
| Capacity Type               | No Restriction            |

|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                    | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



## Outlets

### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 1.000          |
| Outlet Type         | Free Discharge |

## Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|



National Grid Substation

Type : Porous Paving

## Dimensions

|                             |           |
|-----------------------------|-----------|
| Exceedance Level (m)        | 55.700    |
| Depth (m)                   | 0.650     |
| Base Level (m)              | 55.050    |
| Paving Layer Depth (mm)     | 80        |
| Membrane Percolation (m/hr) | 34.2      |
| Porosity (%)                | 30        |
| Length (m)                  | 368.409   |
| Long. Slope (1:X)           | 470.00    |
| Width (m)                   | 162.869   |
| Total Volume (m³)           | 10263.272 |

## Under Drain

|                       |                           |
|-----------------------|---------------------------|
| Height Above Base (m) | 0.000                     |
| Diameter (mm)         | 150                       |
| No. of Barrels        | 1                         |
| Release Height (m)    | 0.000                     |
| Friction Scheme       | Colebrook-White Roughness |
| Roughness (mm)        | 0.6                       |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                    |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |

## Inlets

### Inlet

|                    |                             |
|--------------------|-----------------------------|
| Inlet Type         | Lateral Inflow              |
| Incoming Item(s)   | CA National Grid Substation |
| Bypass Destination | (None)                      |
| Capacity Type      | No Restriction              |

## Outlets

### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 3.000          |
| Outlet Type         | Free Discharge |

## Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|



**400kV Project Substation Sub-Site 1B**

Type : Porous Paving

## Dimensions

|                             |          |
|-----------------------------|----------|
| Exceedance Level (m)        | 55.800   |
| Depth (m)                   | 0.700    |
| Base Level (m)              | 55.100   |
| Paving Layer Depth (mm)     | 80       |
| Membrane Percolation (m/hr) | 34.2     |
| Porosity (%)                | 30       |
| Length (m)                  | 148.332  |
| Long. Slope (1:X)           | 600.00   |
| Width (m)                   | 74.154   |
| Total Volume (m³)           | 2047.728 |



|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                    | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



## Under Drain

|                       |                           |
|-----------------------|---------------------------|
| Height Above Base (m) | 0.000                     |
| Diameter (mm)         | 150                       |
| No. of Barrels        | 1                         |
| Release Height (m)    | 0.000                     |
| Friction Scheme       | Colebrook-White Roughness |
| Roughness (mm)        | 0.6                       |

## Inlets

### Inlet

|                    |                                            |
|--------------------|--------------------------------------------|
| Inlet Type         | Lateral Inflow                             |
| Incoming Item(s)   | CA 400kV Project Substation<br>Sub-Site 1B |
| Bypass Destination | (None)                                     |
| Capacity Type      | No Restriction                             |

## Outlets

### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 4.000          |
| Outlet Type         | Free Discharge |

## Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|



400kV Project Substation BESS Site

Type : Porous Paving

|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                    | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



### Dimensions

|                             |          |
|-----------------------------|----------|
| Exceedance Level (m)        | 54.480   |
| Depth (m)                   | 0.660    |
| Base Level (m)              | 53.820   |
| Paving Layer Depth (mm)     | 80       |
| Membrane Percolation (m/hr) | 34.2     |
| Porosity (%)                | 30       |
| Length (m)                  | 278.021  |
| Long. Slope (1:X)           | 480.00   |
| Width (m)                   | 107.892  |
| Total Volume (m³)           | 5222.353 |

### Under Drain

|                       |                           |
|-----------------------|---------------------------|
| Height Above Base (m) | 0.000                     |
| Diameter (mm)         | 150                       |
| No. of Barrels        | 1                         |
| Release Height (m)    | 0.000                     |
| Friction Scheme       | Colebrook-White Roughness |
| Roughness (mm)        | 0.6                       |

### Inlets

#### Inlet

|                    |                                          |
|--------------------|------------------------------------------|
| Inlet Type         | Lateral Inflow                           |
| Incoming Item(s)   | CA 400kV Project Substation<br>BESS Site |
| Bypass Destination | (None)                                   |
| Capacity Type      | No Restriction                           |

|                                                                                                                                            |                                                                                         |                   |                                                                                 |                                                                                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------|-------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                                     |                   |                                                                                 |  |
|                                                                                                                                            | Designed by:<br>EE                                                                      | Checked by:<br>AJ | Approved By:<br>ID                                                              |                                                                                     |
|                                                                                                                                            | Report Details:<br>Type: Stormwater Controls<br>Storm Phase: BESS and Sub-Site 1B_Mar26 |                   |                                                                                 |                                                                                     |
|                                                                                                                                            |                                                                                         |                   | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                                                                                     |

Outlets

|                     |                |
|---------------------|----------------|
| Outlet              |                |
| Outgoing Connection | 2.000          |
| Outlet Type         | Free Discharge |

Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
| Report Details:<br>Type: Connections<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
|                                                                                                                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |

| Name  | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Upstream Cover Level (m) | Upstream Invert Level (m) | Downstream Cover Level (m) | Downstream Invert Level (m) | Lock | Flow Restriction (L/s) |
|-------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|--------------------------|---------------------------|----------------------------|-----------------------------|------|------------------------|
| 1.000 | 37.035     | Pipe            | 77.156      |             | 0.6                            | 150                        | 54.550                   | 53.900                    | 54.550                     | 53.420                      | None |                        |
| 1.001 | 55.882     | Pipe            | 96.349      |             | 0.6                            | 150                        | 54.550                   | 53.420                    | 54.390                     | 52.840                      | None | 23.5                   |
| 3.000 | 16.459     | Pipe            | 74.813      |             | 0.6                            | 150                        | 55.700                   | 55.050                    | 55.700                     | 54.830                      | None |                        |
| 3.001 | 91.425     | Pipe            | 99.375      |             | 0.6                            | 150                        | 55.700                   | 54.830                    | 55.450                     | 53.910                      | None | 21.7                   |
| 4.000 | 1.880      | Pipe            | 93.999      |             | 0.6                            | 150                        | 55.800                   | 55.100                    | 55.800                     | 55.080                      | None |                        |
| 4.001 | 22.238     | Pipe            | 96.688      |             | 0.6                            | 150                        | 55.800                   | 55.080                    | 55.600                     | 54.850                      | None | 3.6                    |
| 2.000 | 5.439      | Pipe            | 135.977     |             | 0.6                            | 150                        | 54.480                   | 53.820                    | 54.480                     | 53.780                      | None |                        |
| 2.001 | 48.914     | Pipe            | 84.334      |             | 0.6                            | 150                        | 54.480                   | 53.780                    | 53.920                     | 53.200                      | None | 9.9                    |

| Name  | Culvert Type | Culvert Entrance |
|-------|--------------|------------------|
| 1.000 | (None)       | (None)           |
| 1.001 | (None)       | (None)           |
| 3.000 | (None)       | (None)           |
| 3.001 | (None)       | (None)           |
| 4.000 | (None)       | (None)           |
| 4.001 | (None)       | (None)           |
| 2.000 | (None)       | (None)           |
| 2.001 | (None)       | (None)           |



|                                                                                                                                            |                                                                                 |                          |                           |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|--------------------------|---------------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br><b>04/03/0026</b>                                                      |                          |                           |
|                                                                                                                                            | Designed by:<br><b>EE</b>                                                       | Checked by:<br><b>AJ</b> | Approved By:<br><b>ID</b> |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                          |                           |



**FEH: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction         | Storm Event                            | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|------------------|----------------------------------------|-----------------|------------------|----------------|----------------|--------------------|-----------------------------|------------|
| OF BESS          | FEH: 2 years: +0 %: 10080 mins: Summer |                 | 52.840           | 52.930         | 0.090          | 12.3               | 4010.159                    | OK         |
| BESS FC          | FEH: 2 years: +0 %: 10080 mins: Summer | 54.550          | 53.420           | 53.674         | 0.254          | 12.3               | 4010.182                    | Surcharged |
| NG SS FC         | FEH: 2 years: +0 %: 10080 mins: Summer | 55.700          | 54.830           | 55.072         | 0.242          | 11.1               | 3702.110                    | Surcharged |
| OF NG            | FEH: 2 years: +0 %: 10080 mins: Summer |                 | 53.910           | 53.995         | 0.085          | 11.1               | 3702.077                    | OK         |
| OF PSS1B         | FEH: 2 years: +0 %: 2160 mins: Summer  |                 | 54.850           | 54.892         | 0.042          | 3.1                | 381.312                     | OK         |
| PSS1B FC         | FEH: 2 years: +0 %: 2160 mins: Summer  | 55.800          | 55.080           | 55.263         | 0.183          | 3.1                | 381.330                     | Surcharged |
| OF PSS BESS Site | FEH: 2 years: +0 %: 10080 mins: Summer |                 | 53.200           | 53.262         | 0.062          | 6.9                | 1896.087                    | OK         |
| PSS BESS Site FC | FEH: 2 years: +0 %: 10080 mins: Summer | 54.480          | 53.780           | 53.991         | 0.211          | 6.9                | 1896.097                    | Surcharged |

|                                                                                                                                            |                                                                                 |                          |                           |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|--------------------------|---------------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br><b>04/03/0026</b>                                                      |                          |                           |
|                                                                                                                                            | Designed by:<br><b>EE</b>                                                       | Checked by:<br><b>AJ</b> | Approved By:<br><b>ID</b> |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                          |                           |



**FEH: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction         | Storm Event                            | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|------------------|----------------------------------------|-----------------|------------------|----------------|----------------|--------------------|-----------------------------|------------|
| OF BESS          | FEH: 30 years: +0 %: 720 mins: Winter  |                 | 52.840           | 52.950         | 0.110          | 16.3               | 1088.789                    | OK         |
| BESS FC          | FEH: 30 years: +0 %: 720 mins: Winter  | 54.550          | 53.420           | 53.742         | 0.322          | 16.3               | 1089.183                    | Surcharged |
| NG SS FC         | FEH: 30 years: +0 %: 960 mins: Winter  | 55.700          | 54.830           | 55.116         | 0.286          | 13.7               | 1204.881                    | Surcharged |
| OF NG            | FEH: 30 years: +0 %: 960 mins: Winter  |                 | 53.910           | 54.008         | 0.098          | 13.7               | 1204.350                    | OK         |
| OF PSS1B         | FEH: 30 years: +0 %: 2160 mins: Summer |                 | 54.850           | 54.895         | 0.045          | 3.6                | 550.775                     | OK         |
| PSS1B FC         | FEH: 30 years: +0 %: 4320 mins: Summer | 55.800          | 55.080           | 55.394         | 0.314          | 3.6                | 922.637                     | Surcharged |
| OF PSS BESS Site | FEH: 30 years: +0 %: 2880 mins: Winter |                 | 53.200           | 53.272         | 0.072          | 9.1                | 2091.947                    | OK         |
| PSS BESS Site FC | FEH: 30 years: +0 %: 2880 mins: Winter | 54.480          | 53.780           | 54.058         | 0.278          | 9.1                | 2092.047                    | Surcharged |

|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



**FEH: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction         | Storm Event                             | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|------------------|-----------------------------------------|-----------------|------------------|----------------|----------------|--------------------|-----------------------------|------------|
| OF BESS          | FEH: 30 years: +40 %: 960 mins: Winter  |                 | 52.840           | 52.957         | 0.117          | 17.4               | 1586.009                    | OK         |
| BESS FC          | FEH: 30 years: +40 %: 960 mins: Winter  | 54.550          | 53.420           | 53.766         | 0.346          | 17.4               | 1586.417                    | Surcharged |
| NG SS FC         | FEH: 30 years: +40 %: 960 mins: Winter  | 55.700          | 54.830           | 55.154         | 0.324          | 15.7               | 1389.905                    | Surcharged |
| OF NG            | FEH: 30 years: +40 %: 960 mins: Winter  |                 | 53.910           | 54.018         | 0.108          | 15.7               | 1389.322                    | OK         |
| OF PSS1B         | FEH: 30 years: +40 %: 4320 mins: Winter |                 | 54.850           | 54.895         | 0.045          | 3.6                | 1181.334                    | OK         |
| PSS1B FC         | FEH: 30 years: +40 %: 4320 mins: Winter | 55.800          | 55.080           | 55.480         | 0.400          | 3.6                | 1181.383                    | Surcharged |
| OF PSS BESS Site | FEH: 30 years: +40 %: 8640 mins: Winter |                 | 53.200           | 53.275         | 0.075          | 9.9                | 4179.151                    | OK         |
| PSS BESS Site FC | FEH: 30 years: +40 %: 8640 mins: Winter | 54.480          | 53.780           | 54.109         | 0.329          | 9.9                | 4179.161                    | Surcharged |

|                                                                                                                                            |                                                                                 |                   |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br>04/03/0026                                                             |                   |                    |
|                                                                                                                                            | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>ID |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



**FEH: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction         | Storm Event                             | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|------------------|-----------------------------------------|-----------------|------------------|----------------|----------------|--------------------|-----------------------------|------------|
| OF BESS          | FEH: 100 years: +0 %: 1440 mins: Summer |                 | 52.840           | 52.958         | 0.118          | 17.6               | 2373.259                    | OK         |
| BESS FC          | FEH: 100 years: +0 %: 1440 mins: Summer | 54.550          | 53.420           | 53.769         | 0.349          | 17.6               | 2373.662                    | Surcharged |
| NG SS FC         | FEH: 100 years: +0 %: 1440 mins: Winter | 55.700          | 54.830           | 55.158         | 0.328          | 15.9               | 2102.320                    | Surcharged |
| OF NG            | FEH: 100 years: +0 %: 1440 mins: Winter |                 | 53.910           | 54.019         | 0.109          | 15.9               | 2101.749                    | OK         |
| OF PSS1B         | FEH: 100 years: +0 %: 8640 mins: Winter |                 | 54.850           | 54.895         | 0.045          | 3.6                | 1458.062                    | OK         |
| PSS1B FC         | FEH: 100 years: +0 %: 7200 mins: Summer | 55.800          | 55.080           | 55.455         | 0.375          | 3.6                | 1427.609                    | Surcharged |
| OF PSS BESS Site | FEH: 100 years: +0 %: 7200 mins: Summer |                 | 53.200           | 53.275         | 0.075          | 9.9                | 3841.841                    | OK         |
| PSS BESS Site FC | FEH: 100 years: +0 %: 5760 mins: Winter | 54.480          | 53.780           | 54.199         | 0.419          | 9.9                | 3716.105                    | Surcharged |



|                                                                                                                                            |                                                                                 |                          |                           |
|--------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|--------------------------|---------------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B | Date:<br><b>04/03/0026</b>                                                      |                          |                           |
|                                                                                                                                            | Designed by:<br><b>EE</b>                                                       | Checked by:<br><b>AJ</b> | Approved By:<br><b>ID</b> |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                          |                           |



**FEH: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction         | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|------------------|------------------------------------------|-----------------|------------------|----------------|----------------|--------------------|-----------------------------|------------|
| OF BESS          | FEH: 100 years: +45 %: 480 mins: Summer  |                 | 52.840           | 52.990         | 0.150          | 19.0               | 858.439                     | OK         |
| BESS FC          | FEH: 100 years: +45 %: 1440 mins: Winter | 54.550          | 53.420           | 53.860         | 0.440          | 18.8               | 2675.186                    | Surcharged |
| NG SS FC         | FEH: 100 years: +45 %: 2160 mins: Winter | 55.700          | 54.830           | 55.228         | 0.398          | 18.7               | 3711.840                    | Surcharged |
| OF NG            | FEH: 100 years: +45 %: 1440 mins: Winter |                 | 53.910           | 54.060         | 0.150          | 18.7               | 2505.551                    | OK         |
| OF PSS1B         | FEH: 100 years: +45 %: 8640 mins: Winter |                 | 54.850           | 54.895         | 0.045          | 3.6                | 2110.042                    | OK         |
| PSS1B FC         | FEH: 100 years: +45 %: 7200 mins: Summer | 55.800          | 55.080           | 55.591         | 0.511          | 3.6                | 2030.394                    | Surcharged |
| OF PSS BESS Site | FEH: 100 years: +45 %: 8640 mins: Winter |                 | 53.200           | 53.275         | 0.075          | 9.9                | 5708.278                    | OK         |
| PSS BESS Site FC | FEH: 100 years: +45 %: 8640 mins: Winter | 54.480          | 53.780           | 54.321         | 0.541          | 9.9                | 5708.295                    | Surcharged |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control                   | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| BESS                                 | FEH: 2 years: +0 %:<br>10080 mins: Summer | 54.710            | 53.986            | 0.070             | 0.086             | 27.4              | 2084.842                  | 0.000                    | 12.3               | 4010.471                    |                             | OK     |
| National Grid Substation             | FEH: 2 years: +0 %:<br>10080 mins: Summer | 55.903            | 55.136            | 0.069             | 0.086             | 25.3              | 1913.580                  | 0.000                    | 11.1               | 3702.362                    |                             | OK     |
| 400kV Project Substation Sub-Site 1B | FEH: 2 years: +0 %:<br>720 mins: Winter   | 55.404            | 55.258            | 0.057             | 0.158             | 20.2              | 293.350                   | 0.000                    | 3.0                | 176.657                     |                             | OK     |
| 400kV Project Substation BESS Site   | FEH: 2 years: +0 %:<br>5760 mins: Summer  | 54.456            | 53.999            | 0.057             | 0.179             | 17.5              | 904.013                   | 0.000                    | 6.8                | 1450.413                    |                             | OK     |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control                   | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| BESS                                 | FEH: 30 years: +0 %:<br>1440 mins: Winter | 54.794            | 54.061            | 0.153             | 0.161             | 135.4             | 3819.094                  | 0.000                    | 16.2               | 2072.163                    |                             | OK     |
| National Grid Substation             | FEH: 30 years: +0 %:<br>1440 mins: Winter | 55.985            | 55.224            | 0.151             | 0.174             | 125.0             | 3585.837                  | 0.000                    | 13.7               | 1794.711                    |                             | OK     |
| 400kV Project Substation Sub-Site 1B | FEH: 30 years: +0 %:<br>1440 mins: Summer | 55.438            | 55.413            | 0.091             | 0.313             | 35.5              | 645.459                   | 0.000                    | 3.6                | 334.115                     |                             | OK     |
| 400kV Project Substation BESS Site   | FEH: 30 years: +0 %:<br>1440 mins: Winter | 54.513            | 54.068            | 0.114             | 0.248             | 62.5              | 1759.844                  | 0.000                    | 8.8                | 1122.941                    |                             | OK     |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control                   | Storm Event                             | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------------------------|-----------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| BESS                                 | FEH: 30 years: +40 %: 2160 mins: Winter | 54.860            | 54.130            | 0.220             | 0.230             | 135.6             | 5565.331                  | 0.000                    | 17.2               | 3496.316                    | 35                          | OK     |
| National Grid Substation             | FEH: 30 years: +40 %: 2160 mins: Winter | 56.051            | 55.293            | 0.217             | 0.243             | 125.2             | 5193.057                  | 0.000                    | 15.5               | 3034.743                    | 110                         | OK     |
| 400kV Project Substation Sub-Site 1B | FEH: 30 years: +40 %: 1440 mins: Summer | 55.514            | 55.502            | 0.167             | 0.402             | 49.7              | 943.245                   | 0.000                    | 3.6                | 372.708                     |                             | OK     |
| 400kV Project Substation BESS Site   | FEH: 30 years: +40 %: 1440 mins: Winter | 54.579            | 54.140            | 0.180             | 0.320             | 87.5              | 2519.858                  | 0.000                    | 9.9                | 1320.643                    |                             | OK     |



|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control                   | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| BESS                                 | FEH: 100 years: +0<br>%: 2160 mins: Winter | 54.876            | 54.145            | 0.235             | 0.245             | 142.8             | 5904.142                  | 0.000                    | 17.5               | 3560.770                    | 380                         | OK     |
| National Grid Substation             | FEH: 100 years: +0<br>%: 2160 mins: Winter | 56.066            | 55.306            | 0.232             | 0.256             | 131.8             | 5499.622                  | 0.000                    | 15.8               | 3105.770                    | 445                         | OK     |
| 400kV Project Substation Sub-Site 1B | FEH: 100 years: +0<br>%: 2160 mins: Winter | 55.530            | 55.518            | 0.183             | 0.418             | 24.2              | 997.223                   | 0.000                    | 3.6                | 575.599                     |                             | OK     |
| 400kV Project Substation BESS Site   | FEH: 100 years: +0<br>%: 2160 mins: Winter | 54.572            | 54.217            | 0.173             | 0.397             | 65.9              | 2726.646                  | 0.000                    | 9.9                | 1585.082                    | 310                         | OK     |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                    |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                    |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>ID |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control                   | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| BESS                                 | FEH: 100 years: +45 %: 2160 mins: Winter | 55.024            | 54.285            | 0.384             | 0.385             | 207.1             | 8982.433                  | 0.000                    | 18.8               | 3999.070                    |                             | OK     |
| National Grid Substation             | FEH: 100 years: +45 %: 2160 mins: Winter | 56.213            | 55.430            | 0.379             | 0.380             | 191.2             | 8256.295                  | 0.000                    | 18.7               | 3714.222                    |                             | OK     |
| 400kV Project Substation Sub-Site 1B | FEH: 100 years: +45 %: 2160 mins: Winter | 55.687            | 55.671            | 0.340             | 0.571             | 35.0              | 1511.414                  | 0.000                    | 3.6                | 679.821                     |                             | OK     |
| 400kV Project Substation BESS Site   | FEH: 100 years: +45 %: 2160 mins: Summer | 54.712            | 54.379            | 0.313             | 0.559             | 148.1             | 4187.852                  | 0.000                    | 10.0               | 1782.826                    |                             | OK     |


|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                     |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name             | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |      |
|------------------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|------|
| OF BESS          | Simple Junction | 617093.947  | 288726.490   |                 |           |                  |               |              |      |
| BESS FC          | Manhole         | 617121.538  | 288677.894   | 54.550          | 1.130     | 53.420           | Circular      | 3.000        | None |
| NG SS FC         | Manhole         | 616856.302  | 289205.618   | 55.700          | 0.870     | 54.830           | Circular      | 3.000        | None |
| OF NG            | Simple Junction | 616833.537  | 289117.073   |                 |           |                  |               |              |      |
| OF PSS1B         | Simple Junction | 617084.320  | 289206.805   |                 |           |                  |               |              |      |
| PSS1B FC         | Manhole         | 617101.754  | 289220.610   | 55.800          | 0.720     | 55.080           | Circular      | 1.200        | None |
| OF PSS BESS Site | Simple Junction | 617432.540  | 288303.347   |                 |           |                  |               |              |      |
| PSS BESS Site FC | Manhole         | 617386.046  | 288318.541   | 54.480          | 0.700     | 53.780           | Circular      | 3.000        | None |


Outlets

| Junction | Outlet Name | Outgoing Connection | Outlet Type  |
|----------|-------------|---------------------|--------------|
|          | Outlet      | 1.001               | Hydro-Brake® |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                     |
|                                                                                                                                            |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |


|         |                                                                                    |                                        |                     |             |
|---------|------------------------------------------------------------------------------------|----------------------------------------|---------------------|-------------|
| BESS FC | Junction                                                                           | Outlet Name                            | Outgoing Connection | Outlet Type |
|         | Invert Level (m)                                                                   | 53.420                                 |                     |             |
|         | Design Depth (m)                                                                   | 0.650                                  |                     |             |
|         | Design Flow (L/s)                                                                  | 21.5                                   |                     |             |
|         | Objective                                                                          | Minimise Upstream Storage Requirements |                     |             |
|         | Application                                                                        | Surface Water Only                     |                     |             |
|         | Sump Available                                                                     | <input type="checkbox"/>               |                     |             |
|         | Unit Reference                                                                     | CHE-0200-2150-0650-2150                |                     |             |
|         |  |                                        |                     |             |
|         | Outlet                                                                             | 3.001                                  | Hydro-Brake®        |             |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                     |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
|                                                                                                                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |


|          |                                                                                    |                                        |                     |             |
|----------|------------------------------------------------------------------------------------|----------------------------------------|---------------------|-------------|
| NG SS FC | Junction                                                                           | Outlet Name                            | Outgoing Connection | Outlet Type |
|          | Invert Level (m)                                                                   | 54.830                                 |                     |             |
|          | Design Depth (m)                                                                   | 0.650                                  |                     |             |
|          | Design Flow (L/s)                                                                  | 19.8                                   |                     |             |
|          | Objective                                                                          | Minimise Upstream Storage Requirements |                     |             |
|          | Application                                                                        | Surface Water Only                     |                     |             |
|          | Sump Available                                                                     | <input type="checkbox"/>               |                     |             |
|          | Unit Reference                                                                     | CHE-0195-1980-0650-1980                |                     |             |
|          |  |                                        |                     |             |
|          | Outlet                                                                             | 4.001                                  | Hydro-Brake®        |             |



|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                     |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
|                                                                                                                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| PSS1B FC | Junction                                                                           | Outlet Name                            | Outgoing Connection | Outlet Type |
|----------|------------------------------------------------------------------------------------|----------------------------------------|---------------------|-------------|
|          | Invert Level (m)                                                                   | 55.080                                 |                     |             |
|          | Design Depth (m)                                                                   | 0.700                                  |                     |             |
|          | Design Flow (L/s)                                                                  | 3.6                                    |                     |             |
|          | Objective                                                                          | Minimise Upstream Storage Requirements |                     |             |
|          | Application                                                                        | Surface Water Only                     |                     |             |
|          | Sump Available                                                                     | <input type="checkbox"/>               |                     |             |
|          | Unit Reference                                                                     | CHE-0091-3600-0700-3600                |                     |             |
|          |  |                                        |                     |             |
|          | Outlet                                                                             | 2.001                                  | Hydro-Brake®        |             |

|                                                                                                                                            |  |                                                                                 |                   |                                                                                     |                     |
|--------------------------------------------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar DCO:<br>Outline Surface Water Drainage<br>BESS, National Grid Substation &<br>Project Substations BESS Site and Sub-Site 1B |  | Date:<br>04/03/0026                                                             |                   |  |                     |
| Report Details:<br>Type: Junctions<br>Storm Phase: BESS and Sub-Site 1B_Mar26                                                              |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
|                                                                                                                                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



|                                                                                                           |                     |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                    |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                    |                                                                                     |



**132kV 4B**

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 0.50 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CASW1**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.036 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CASW2**

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 0.02 |
|-----------|------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |                     |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                    |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                    |                                                                                     |



**CASW3**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.023 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CASW4**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.039 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CASW5**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.042 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |                     |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                    |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                    |                                                                                     |



**CASW6**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.037 |
|-----------|-------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CA Inv1**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



**CA Inv2**

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



|                                                                                                           |                     |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                    |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                    |                                                                                     |



CA Inv3

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



CA Inv4

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



CA Inv5

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |                     |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                    |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                    |                                                                                     |



CA Inv6

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



CA Inv7

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |



CA Inv8

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing

| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 4B w inverters                          | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



CA Inv9

Type : Catchment Area

|           |       |
|-----------|-------|
| Area (ha) | 0.009 |
|-----------|-------|

#### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

#### Dynamic Sizing


|                              |                       |
|------------------------------|-----------------------|
| Runoff Method                | Time of Concentration |
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |  |  |                                                                                 |                   |                    |                                                                                     |  |
|-----------------------------------------------------------------------------------------------------------|--|--|---------------------------------------------------------------------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|--|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  |  | Date:<br>01/09/2026                                                             |                   |                    |  |  |
| Report Details:<br>Type: Junctions<br>Storm Phase: Project SS 132kV 4B w inverters                        |  |  | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |  |
|                                                                                                           |  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |                                                                                     |  |

| Name  | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |
|-------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|
| FC4B  | Manhole         | 620676.384  | 294425.240   | 33.700          | 0.800     | 32.900           | Circular      | 3.000        |
| OF4B  | Simple Junction | 620708.281  | 294450.291   |                 |           |                  |               |              |
| OFSW1 | Simple Junction | 620726.667  | 294597.392   |                 |           |                  |               |              |
| OFSW2 | Simple Junction | 620753.245  | 294711.379   |                 |           |                  |               |              |
| OFSW6 | Simple Junction | 620376.237  | 294596.073   |                 |           |                  |               |              |

| Name  | Lock |
|-------|------|
| FC4B  | None |
| OF4B  |      |
| OFSW1 |      |
| OFSW2 |      |
| OFSW6 |      |

### Outlets

| Junction | Outlet Name                                                                          | Outgoing Connection                    | Outlet Type  |
|----------|--------------------------------------------------------------------------------------|----------------------------------------|--------------|
| FC4B     | Outlet                                                                               | 5.001                                  | Hydro-Brake® |
|          | Invert Level (m)                                                                     | 32.900                                 |              |
|          | Design Depth (m)                                                                     | 0.750                                  |              |
|          | Design Flow (L/s)                                                                    | 1.0                                    |              |
|          | Objective                                                                            | Minimise Upstream Storage Requirements |              |
|          | Application                                                                          | Surface Water Only                     |              |
|          | Sump Available                                                                       | <input type="checkbox"/>               |              |
|          | Unit Reference                                                                       | CHE-0049-1000-0750-1000                |              |
|          |  |                                        |              |
|          |                                                                                      |                                        |              |

|                                                                                                           |                                                                                 |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |  |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |                                                                                     |



PP 132kV 4B

Type : Porous Paving

### Dimensions

|                             |         |
|-----------------------------|---------|
| Exceedance Level (m)        | 33.700  |
| Depth (m)                   | 0.680   |
| Base Level (m)              | 33.020  |
| Paving Layer Depth (mm)     | 80      |
| Membrane Percolation (m/hr) | 32.4    |
| Porosity (%)                | 30      |
| Length (m)                  | 100.000 |
| Long. Slope (1:X)           | 600.00  |
| Width (m)                   | 50.000  |
| Total Volume (m³)           | 900.549 |

### Under Drain

|                       |             |
|-----------------------|-------------|
| Height Above Base (m) | 0.000       |
| Diameter (mm)         | 100         |
| No. of Barrels        | 1           |
| Release Height (m)    | 0.000       |
| Friction Scheme       | Manning's n |
| n                     | 0.015       |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | 132kV 4B       |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 5.000          |
| Outlet Type         | Free Discharge |

### Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|



|                                                                                                           |                                                                                 |                   |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



SW1

Type : Swale

### Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 32.700      |
| Depth (m)              | 0.500       |
| Base Level (m)         | 32.200      |
| Top Width (m)          | 2.500       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 100.000     |
| Long. Slope (1:X)      | 350.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 75.000      |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW1          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv5        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | ND1     |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.027   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 32.200  |

### Advanced

#### Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                                                           |                                                                                 |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |  |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |                                                                                     |



SW3

Type : Swale

### Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 29.400      |
| Depth (m)              | 0.550       |
| Base Level (m)         | 28.850      |
| Top Width (m)          | 2.700       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 74.000      |
| Long. Slope (1:X)      | 480.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 65.120      |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | ND2            |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW3          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (2)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv7        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (3)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv6        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

|                                                                                                           |                     |                                                                                     |                   |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |  |                   |                    |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Designed by:<br>EE  |                                                                                     | Checked by:<br>AJ | Approved By:<br>RF |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                                                                                     |                   |                    |

Outlets

Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | 9.000   |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.028   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 28.850  |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                                                           |                                                                                 |                   |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



SW2

Type : Swale

### Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 31.000      |
| Depth (m)              | 0.500       |
| Base Level (m)         | 30.500      |
| Top Width (m)          | 2.500       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 64.500      |
| Long. Slope (1:X)      | 350.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 48.375      |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | ND1            |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW2          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | ND2     |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.027   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 30.500  |

### Advanced

#### Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                                                           |                                                                                 |                   |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



SW4

Type : Swale

### Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 29.400      |
| Depth (m)              | 0.500       |
| Base Level (m)         | 28.900      |
| Top Width (m)          | 2.500       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 130.000     |
| Long. Slope (1:X)      | 380.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 97.500      |

### Inlets

#### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW4          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv3        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

#### Inlet (2)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv4        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | ND3     |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.025   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 28.900  |

|                                                                                                           |                                                                                 |                   |                    |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |  |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |                                                                                     |

## Advanced

## Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|



SW5

Type : Swale

## Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 28.150      |
| Depth (m)              | 0.550       |
| Base Level (m)         | 27.600      |
| Top Width (m)          | 2.700       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 130.000     |
| Long. Slope (1:X)      | 500.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 114.400     |

## Inlets

### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW5          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Inlet (2)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | ND3            |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv9        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Inlet (3)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv8        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |



|                                                                                                           |                                                                                 |                   |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |



Outlets

Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | 10.000  |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.028   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 27.600  |

Advanced

Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|



SW6

Type : Swale

Swale

|                        |             |
|------------------------|-------------|
| Exceedance Level (m)   | 30.200      |
| Depth (m)              | 0.500       |
| Base Level (m)         | 29.700      |
| Top Width (m)          | 2.500       |
| Side Slope (1:X)       | 2.00        |
| Base Width (m)         | 0.500       |
| Freeboard (mm)         | 0           |
| Length (m)             | 122.000     |
| Long. Slope (1:X)      | 300.00      |
| Filtration Rate (m/hr) | 0.0         |
| Friction Scheme        | Manning's n |
| n                      | 0.03        |
| Total Volume (m³)      | 91.500      |

|                                                                                                           |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 4B w inverters              | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |

## Inlets

### Inlet (1)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | CASW6          |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv1        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

### Inlet (2)

|                    |                |
|--------------------|----------------|
| Inlet Type         | Point Inflow   |
| Incoming Item(s)   | CA Inv2        |
| Bypass Destination | (None)         |
| Inlet Destination  | Ponding Area   |
| Capacity Type      | No Restriction |

## Outlets

### Outlet

|                          |         |
|--------------------------|---------|
| Outgoing Connection      | 11.000  |
| Outlet Type              | Orifice |
| Diameter (m)             | 0.025   |
| Coefficient of Discharge | 0.600   |
| Invert Level (m)         | 29.700  |

## Advanced

### Swale

|              |     |
|--------------|-----|
| Porosity (%) | 100 |
|--------------|-----|

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
| Report Details:<br>Type: Connections<br>Storm Phase: Project SS 132kV 4B w inverters                      |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |

| Name   | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Height (mm) | Side Slope (1:X) |
|--------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|-------------|------------------|
| 5.000  | 2.914      | Pipe            | 24.285      |             | 0.6                            | 100                        |             |                  |
| 5.001  | 40.558     | Pipe            | 27.039      |             | 0.6                            | 100                        |             |                  |
| 9.000  | 20.586     | Pipe            | 58.816      |             | 0.6                            | 100                        |             |                  |
| ND1    | 1.154      | No Delay        |             |             |                                |                            |             |                  |
| ND2    | 1.038      | No Delay        |             |             |                                |                            |             |                  |
| 10.000 | 3.573      | Pipe            | 119.097     |             | 0.6                            | 150                        |             |                  |
| ND3    | 3.079      | No Delay        |             |             |                                |                            |             |                  |
| 11.000 | 73.996     | Pipe            | 60.653      |             | 0.6                            | 100                        |             |                  |

| Name   | Upstream Cover Level (m) | Upstream Invert Level (m) | Downstream Cover Level (m) | Downstream Invert Level (m) | Lock | Flow Restriction (L/s) | Culvert Type | Culvert Entrance |
|--------|--------------------------|---------------------------|----------------------------|-----------------------------|------|------------------------|--------------|------------------|
| 5.000  | 33.700                   | 33.020                    | 33.700                     | 32.900                      | None |                        | (None)       | (None)           |
| 5.001  | 33.700                   | 32.900                    | 32.000                     | 31.400                      | None | 1.03                   | (None)       | (None)           |
| 9.000  | 29.400                   | 28.850                    | 29.300                     | 28.500                      | None | 1.20                   | (None)       | (None)           |
| ND1    |                          |                           |                            |                             |      |                        |              |                  |
| ND2    |                          |                           |                            |                             |      |                        |              |                  |
| 10.000 | 28.100                   | 27.600                    | 28.070                     | 27.570                      | None | 1.20                   | (None)       | (None)           |
| ND3    |                          |                           |                            |                             |      |                        |              |                  |
| 11.000 | 30.607                   | 29.700                    | 29.080                     | 28.480                      | None | 0.91                   | (None)       | (None)           |

|                                                                                                           |  |  |  |                                                                                 |                   |                    |                                                                                     |  |
|-----------------------------------------------------------------------------------------------------------|--|--|--|---------------------------------------------------------------------------------|-------------------|--------------------|-------------------------------------------------------------------------------------|--|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  |  |  | Date:<br>01/09/2026                                                             |                   |                    |  |  |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Project SS 132kV 4B w inverters                   |  |  |  | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RF |                                                                                     |  |
|                                                                                                           |  |  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                    |                                                                                     |  |

| Inflow Label | Connected To | Flow (L/s) | Runoff Method         | Area (ha)    | Percentage Impervious (%) | Urban Creep (%) | Adjusted Percentage Impervious (%) | Area Analysed (ha) |
|--------------|--------------|------------|-----------------------|--------------|---------------------------|-----------------|------------------------------------|--------------------|
| 132kV 4B     | PP 132kV 4B  |            | Time of Concentration | 0.500        | 100                       | 0               | 100                                | 0.500              |
| CA Inv1      | SW6          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv2      | SW6          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv3      | SW4          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv4      | SW4          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv5      | SW1          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv6      | SW3          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv7      | SW3          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv8      | SW5          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CA Inv9      | SW5          |            | Time of Concentration | 0.009        | 100                       | 0               | 100                                | 0.009              |
| CASW1        | SW1          |            | Time of Concentration | 0.036        | 100                       | 0               | 100                                | 0.036              |
| CASW2        | SW2          |            | Time of Concentration | 0.020        | 100                       | 0               | 100                                | 0.020              |
| CASW3        | SW3          |            | Time of Concentration | 0.023        | 100                       | 0               | 100                                | 0.023              |
| CASW4        | SW4          |            | Time of Concentration | 0.039        | 100                       | 0               | 100                                | 0.039              |
| CASW5        | SW5          |            | Time of Concentration | 0.042        | 100                       | 0               | 100                                | 0.042              |
| CASW6        | SW6          |            | Time of Concentration | 0.037        | 100                       | 0               | 100                                | 0.037              |
| <b>TOTAL</b> |              | <b>0.0</b> |                       | <b>0.777</b> |                           |                 |                                    | <b>0.777</b>       |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 4B w inverters                |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                             | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-----------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC4B     | FEH4B: 2 years: +0 %: 7200 mins: Summer | 33.700          | 32.900           | 33.191         | 0.291          | 0.000                    | 0.8                | 280.480                     | Surcharged |
| OF4B     | FEH4B: 2 years: +0 %: 7200 mins: Summer |                 | 31.400           | 31.418         | 0.018          |                          | 0.8                | 280.477                     | OK         |
| OFSW1    | FEH4B: 2 years: +0 %: 360 mins: Winter  |                 | 28.500           | 28.521         | 0.021          |                          | 0.7                | 25.740                      | OK         |
| OFSW2    | FEH4B: 2 years: +0 %: 360 mins: Winter  |                 | 27.570           | 27.592         | 0.022          |                          | 0.8                | 26.558                      | OK         |
| OFSW6    | FEH4B: 2 years: +0 %: 240 mins: Summer  |                 | 28.480           | 28.499         | 0.019          |                          | 0.6                | 12.410                      | OK         |

|                                                                                                           |  |                                                                                 |             |              |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |             |              |  |
|                                                                                                           |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 4B w inverters                |  | EE                                                                              | AJ          | RF           |                                                                                     |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |



**FEH4B: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC4B     | FEH4B: 30 years: +0 %: 7200 mins: Winter | 33.700          | 32.900           | 33.294         | 0.394          | 0.000                    | 0.8                | 495.996                     | Surcharged |
| OF4B     | FEH4B: 30 years: +0 %: 7200 mins: Summer |                 | 31.400           | 31.418         | 0.018          |                          | 0.8                | 496.226                     | OK         |
| OFSW1    | FEH4B: 30 years: +0 %: 720 mins: Winter  |                 | 28.500           | 28.523         | 0.023          |                          | 0.9                | 64.295                      | OK         |
| OFSW2    | FEH4B: 30 years: +0 %: 600 mins: Winter  |                 | 27.570           | 27.594         | 0.024          |                          | 0.9                | 56.648                      | OK         |
| OFSW6    | FEH4B: 30 years: +0 %: 180 mins: Winter  |                 | 28.480           | 28.501         | 0.021          |                          | 0.8                | 13.286                      | OK         |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 4B w inverters                |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                               | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC4B     | FEH4B: 30 years: +40 %: 8640 mins: Winter | 33.700          | 32.900           | 33.394         | 0.494          | 0.000                    | 0.8                | 668.974                     | Surcharged |
| OF4B     | FEH4B: 30 years: +40 %: 8640 mins: Winter |                 | 31.400           | 31.418         | 0.018          |                          | 0.8                | 668.956                     | OK         |
| OFSW1    | FEH4B: 30 years: +40 %: 960 mins: Winter  |                 | 28.500           | 28.524         | 0.024          |                          | 1.0                | 95.908                      | OK         |
| OFSW2    | FEH4B: 30 years: +40 %: 960 mins: Winter  |                 | 27.570           | 27.596         | 0.026          |                          | 1.0                | 98.733                      | OK         |
| OFSW6    | FEH4B: 30 years: +40 %: 240 mins: Winter  |                 | 28.480           | 28.502         | 0.022          |                          | 0.8                | 19.768                      | OK         |

|                                                                                                           |  |                                                                                 |             |              |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |             |              |  |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 4B w inverters                |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |
|                                                                                                           |  | EE                                                                              | AJ          | RF           |                                                                                     |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |



**FEH4B: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                               | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC4B     | FEH4B: 100 years: +0 %: 2880 mins: Winter | 33.700          | 32.900           | 33.437         | 0.537          | 0.000                    | 0.8                | 247.790                     | Flood Risk |
| OF4B     | FEH4B: 100 years: +0 %: 2880 mins: Winter |                 | 31.400           | 31.418         | 0.018          |                          | 0.8                | 247.768                     | OK         |
| OFSW1    | FEH4B: 100 years: +0 %: 960 mins: Winter  |                 | 28.500           | 28.524         | 0.024          |                          | 1.0                | 96.885                      | OK         |
| OFSW2    | FEH4B: 100 years: +0 %: 960 mins: Winter  |                 | 27.570           | 27.596         | 0.026          |                          | 1.1                | 99.482                      | OK         |
| OFSW6    | FEH4B: 100 years: +0 %: 240 mins: Winter  |                 | 28.480           | 28.502         | 0.022          |                          | 0.8                | 19.244                      | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 4B w inverters                |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC4B     | FEH4B: 100 years: +45 %: 2880 mins: Winter | 33.700          | 32.900           | 33.610         | 0.710          | 0.000                    | 1.0                | 285.538                     | Flood Risk |
| OF4B     | FEH4B: 100 years: +45 %: 2880 mins: Winter |                 | 31.400           | 31.419         | 0.019          |                          | 1.0                | 285.514                     | OK         |
| OFSW1    | FEH4B: 100 years: +45 %: 1440 mins: Winter |                 | 28.500           | 28.526         | 0.026          |                          | 1.2                | 161.741                     | OK         |
| OFSW2    | FEH4B: 100 years: +45 %: 1440 mins: Winter |                 | 27.570           | 27.597         | 0.027          |                          | 1.2                | 166.782                     | OK         |
| OFSW6    | FEH4B: 100 years: +45 %: 720 mins: Summer  |                 | 28.480           | 28.503         | 0.023          |                          | 0.9                | 61.888                      | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 4B w inverters      |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Velocity (m/s) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|---------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 4B        | FEH4B: 2 years: +0 %: 10080 mins: Summer | 33.218            | 33.192            | 0.031             | 0.172             | 2.1               | 141.743                   | 0.000                    |                     | 0.9                | 328.034                     |                             | OK     |
| SW1                | FEH4B: 2 years: +0 %: 180 mins: Summer   | 32.505            | 32.395            | 0.019             | 0.195             | 3.4               | 6.153                     | 0.000                    | 0.1                 | 0.6                | 9.693                       |                             | OK     |
| SW3                | FEH4B: 2 years: +0 %: 360 mins: Winter   | 29.077            | 29.077            | 0.073             | 0.227             | 1.8               | 9.296                     | 0.000                    | 0.1                 | 0.7                | 25.762                      |                             | OK     |
| SW2                | FEH4B: 2 years: +0 %: 360 mins: Winter   | 30.698            | 30.690            | 0.014             | 0.190             | 1.2               | 4.992                     | 0.000                    | 0.1                 | 0.6                | 17.334                      |                             | OK     |
| SW4                | FEH4B: 2 years: +0 %: 240 mins: Summer   | 29.265            | 29.119            | 0.023             | 0.219             | 3.6               | 9.017                     | 0.000                    | 0.1                 | 0.6                | 12.581                      |                             | OK     |
| SW5                | FEH4B: 2 years: +0 %: 360 mins: Winter   | 27.882            | 27.846            | 0.022             | 0.246             | 2.4               | 13.582                    | 0.000                    | 0.1                 | 0.8                | 26.581                      |                             | OK     |
| SW6                | FEH4B: 2 years: +0 %: 240 mins: Summer   | 30.128            | 29.931            | 0.021             | 0.231             | 3.5               | 8.405                     | 0.000                    | 0.1                 | 0.6                | 12.439                      |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 4B w inverters      |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By:**  
**Max. Resident Volume**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Velocity (m/s) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|---------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 4B        | FEH4B: 30 years: +0 %: 2880 mins: Winter | 33.325            | 33.318            | 0.138             | 0.298             | 6.2               | 328.987                   | 0.000                    |                     | 0.9                | 218.457                     |                             | OK     |
| SW1                | FEH4B: 30 years: +0 %: 120 mins: Winter  | 32.514            | 32.504            | 0.028             | 0.304             | 6.6               | 15.314                    | 0.000                    | 0.1                 | 0.8                | 9.634                       |                             | OK     |
| SW3                | FEH4B: 30 years: +0 %: 720 mins: Winter  | 29.197            | 29.197            | 0.193             | 0.347             | 2.2               | 21.231                    | 0.000                    | 0.1                 | 0.9                | 64.317                      |                             | OK     |
| SW2                | FEH4B: 30 years: +0 %: 480 mins: Winter  | 30.784            | 30.784            | 0.100             | 0.284             | 1.7               | 11.486                    | 0.000                    | 0.1                 | 0.8                | 36.305                      |                             | OK     |
| SW4                | FEH4B: 30 years: +0 %: 180 mins: Winter  | 29.274            | 29.236            | 0.032             | 0.336             | 6.3               | 21.801                    | 0.000                    | 0.1                 | 0.7                | 13.149                      |                             | OK     |
| SW5                | FEH4B: 30 years: +0 %: 600 mins: Winter  | 27.961            | 27.961            | 0.101             | 0.361             | 3.2               | 31.152                    | 0.000                    | 0.1                 | 0.9                | 56.675                      |                             | OK     |
| SW6                | FEH4B: 30 years: +0 %: 180 mins: Winter  | 30.136            | 30.055            | 0.029             | 0.355             | 6.0               | 20.478                    | 0.000                    | 0.2                 | 0.8                | 13.332                      |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 4B w inverters      |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Velocity (m/s) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|---------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 4B        | FEH4B: 30 years: +40 %: 2880 mins: Winter | 33.430            | 33.421            | 0.243             | 0.401             | 8.7               | 485.302                   | 0.000                    |                     | 0.9                | 246.849                     | 765                         | OK     |
| SW1                | FEH4B: 30 years: +40 %: 180 mins: Winter  | 32.564            | 32.564            | 0.078             | 0.364             | 6.9               | 22.934                    | 0.000                    | 0.1                 | 0.9                | 16.127                      |                             | OK     |
| SW3                | FEH4B: 30 years: +40 %: 960 mins: Winter  | 29.277            | 29.277            | 0.273             | 0.427             | 2.4               | 31.430                    | 0.000                    | 0.1                 | 1.0                | 95.930                      |                             | OK     |
| SW2                | FEH4B: 30 years: +40 %: 720 mins: Winter  | 30.844            | 30.844            | 0.160             | 0.344             | 1.8               | 16.882                    | 0.000                    | 0.1                 | 0.9                | 57.197                      |                             | OK     |
| SW4                | FEH4B: 30 years: +40 %: 240 mins: Winter  | 29.301            | 29.301            | 0.059             | 0.401             | 7.1               | 32.432                    | 0.000                    | 0.1                 | 0.8                | 19.532                      |                             | OK     |
| SW5                | FEH4B: 30 years: +40 %: 960 mins: Winter  | 28.034            | 28.034            | 0.174             | 0.434             | 3.2               | 46.076                    | 0.000                    | 0.1                 | 1.0                | 98.760                      |                             | OK     |
| SW6                | FEH4B: 30 years: +40 %: 240 mins: Winter  | 30.138            | 30.125            | 0.032             | 0.425             | 6.8               | 30.477                    | 0.000                    | 0.2                 | 0.8                | 19.817                      |                             | OK     |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 4B w inverters      |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Velocity (m/s) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|---------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 4B        | FEH4B: 100 years: +0 %: 2880 mins: Winter | 33.447            | 33.438            | 0.260             | 0.418             | 9.1               | 510.707                   | 0.000                    |                     | 0.9                | 250.953                     | 1280                        | OK     |
| SW1                | FEH4B: 100 years: +0 %: 180 mins: Winter  | 32.547            | 32.548            | 0.062             | 0.348             | 6.3               | 20.686                    | 0.000                    | 0.1                 | 0.9                | 15.666                      |                             | OK     |
| SW3                | FEH4B: 100 years: +0 %: 960 mins: Winter  | 29.281            | 29.281            | 0.277             | 0.431             | 2.5               | 32.092                    | 0.000                    | 0.1                 | 1.0                | 96.909                      |                             | OK     |
| SW2                | FEH4B: 100 years: +0 %: 960 mins: Winter  | 30.844            | 30.844            | 0.160             | 0.344             | 1.6               | 16.838                    | 0.000                    | 0.1                 | 0.9                | 62.036                      |                             | OK     |
| SW4                | FEH4B: 100 years: +0 %: 240 mins: Winter  | 29.285            | 29.285            | 0.043             | 0.385             | 6.5               | 29.518                    | 0.000                    | 0.1                 | 0.8                | 19.041                      |                             | OK     |
| SW5                | FEH4B: 100 years: +0 %: 960 mins: Winter  | 28.039            | 28.039            | 0.179             | 0.439             | 3.3               | 47.046                    | 0.000                    | 0.1                 | 1.1                | 99.509                      |                             | OK     |
| SW6                | FEH4B: 100 years: +0 %: 240 mins: Winter  | 30.137            | 30.107            | 0.030             | 0.407             | 6.2               | 27.701                    | 0.000                    | 0.2                 | 0.8                | 19.293                      |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                    |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|--------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                    |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 4B w inverters      |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                    |



**FEH4B: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Velocity (m/s) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|---------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 4B        | FEH4B: 100 years: +45 %: 2880 mins: Winter | 33.623            | 33.611            | 0.436             | 0.591             | 13.2              | 773.578                   | 0.000                    |                     | 1.0                | 289.827                     |                             | OK     |
| SW1                | FEH4B: 100 years: +45 %: 240 mins: Winter  | 32.626            | 32.627            | 0.141             | 0.427             | 7.4               | 32.363                    | 0.000                    | 0.1                 | 1.0                | 23.521                      |                             | OK     |
| SW3                | FEH4B: 100 years: +45 %: 1440 mins: Winter | 29.398            | 29.398            | 0.394             | 0.548             | 2.7               | 50.684                    | 0.000                    | 0.1                 | 1.2                | 161.762                     | 875                         | OK     |
| SW2                | FEH4B: 100 years: +45 %: 960 mins: Winter  | 30.932            | 30.932            | 0.248             | 0.432             | 2.1               | 26.372                    | 0.000                    | 0.1                 | 1.0                | 89.313                      | 255                         | OK     |
| SW4                | FEH4B: 100 years: +45 %: 720 mins: Summer  | 29.373            | 29.373            | 0.131             | 0.473             | 6.7               | 47.114                    | 0.000                    | 0.1                 | 0.9                | 61.867                      |                             | OK     |
| SW5                | FEH4B: 100 years: +45 %: 1440 mins: Winter | 28.147            | 28.147            | 0.287             | 0.547             | 3.5               | 74.421                    | 0.000                    | 0.1                 | 1.2                | 166.810                     | 700                         | OK     |
| SW6                | FEH4B: 100 years: +45 %: 720 mins: Summer  | 30.196            | 30.197            | 0.090             | 0.497             | 6.4               | 43.928                    | 0.000                    | 0.1                 | 0.9                | 61.932                      |                             | OK     |

|                                                                                                           |                                                                                 |                   |                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                     |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RMF |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 400kV 5A                                      | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                     |



400kV 5A

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 3.50 |
|-----------|------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing


| Runoff Method                | Time of Concentration |
|------------------------------|-----------------------|
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions<br>Storm Phase: Project SS 400kV 5A                                    |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |
|------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|
| FC5A | Manhole         | 622363.002  | 293860.361   | 40.700          | 0.800     | 39.900           | Circular      | 3.000        |
| OF5A | Simple Junction | 622348.108  | 293859.755   |                 |           |                  |               |              |

| Name | Lock |
|------|------|
| FC5A | None |
| OF5A |      |

Outlets

| Junction | Outlet Name                                                                         | Outgoing Connection                    | Outlet Type  |
|----------|-------------------------------------------------------------------------------------|----------------------------------------|--------------|
| FC5A     | Outlet                                                                              | 6.001                                  | Hydro-Brake® |
|          | Invert Level (m)                                                                    | 39.900                                 |              |
|          | Design Depth (m)                                                                    | 0.800                                  |              |
|          | Design Flow (L/s)                                                                   | 8.8                                    |              |
|          | Objective                                                                           | Minimise Upstream Storage Requirements |              |
|          | Application                                                                         | Surface Water Only                     |              |
|          | Sump Available                                                                      | <input type="checkbox"/>               |              |
|          | Unit Reference                                                                      | CHE-0134-8800-0800-8800                |              |
|          |  |                                        |              |
|          |                                                                                     |                                        |              |

|                                                                                                           |                                                                                 |                   |                     |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|---------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                     |  |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RMF |                                                                                     |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 400kV 5A                          | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                     |                                                                                     |



PP SS 400kV 5A

Type : Porous Paving

### Dimensions

|                             |          |
|-----------------------------|----------|
| Exceedance Level (m)        | 40.700   |
| Depth (m)                   | 0.650    |
| Base Level (m)              | 40.050   |
| Paving Layer Depth (mm)     | 80       |
| Membrane Percolation (m/hr) | 32.4     |
| Porosity (%)                | 30       |
| Length (m)                  | 266.325  |
| Long. Slope (1:X)           | 650.00   |
| Width (m)                   | 132.571  |
| Total Volume (m³)           | 6040.794 |

### Under Drain

|                       |             |
|-----------------------|-------------|
| Height Above Base (m) | 0.000       |
| Diameter (mm)         | 150         |
| No. of Barrels        | 1           |
| Release Height (m)    | 0.000       |
| Friction Scheme       | Manning's n |
| n                     | 0.015       |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | 400kV 5A       |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 6.000          |
| Outlet Type         | Free Discharge |

### Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Connections<br>Storm Phase: Project SS 400kV 5A                                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name  | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Upstream Cover Level (m) | Upstream Invert Level (m) |
|-------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|--------------------------|---------------------------|
| 6.000 | 2.840      | Pipe            | 56.810      |             | 0.6                            | 150                        | 40.700                   | 40.050                    |
| 6.001 | 14.906     | Pipe            | 14.906      |             | 0.6                            | 150                        | 40.700                   | 39.900                    |

| Name  | Downstream Cover Level (m) | Downstream Invert Level (m) | Lock | Flow Restriction (L/s) | Culvert Type | Culvert Entrance |
|-------|----------------------------|-----------------------------|------|------------------------|--------------|------------------|
| 6.000 | 40.700                     | 40.000                      | All  |                        | (None)       | (None)           |
| 6.001 | 39.500                     | 38.900                      | None | 8.8                    | (None)       | (None)           |

|                                                                                                           |                                                                                 |                   |                     |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|---------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                     |  |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Project SS 400kV 5A                               | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RMF |                                                                                     |
|                                                                                                           | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                     |                                                                                     |

| Inflow Label | Connected To   | Flow (L/s) | Runoff Method         | Area (ha)   | Percentage Impervious (%) | Urban Creep (%) | Adjusted Percentage Impervious (%) | Area Analysed (ha) |
|--------------|----------------|------------|-----------------------|-------------|---------------------------|-----------------|------------------------------------|--------------------|
| 400kV 5A     | PP SS 400kV 5A |            | Time of Concentration | 3.50        | 100                       | 0               | 100                                | 3.50               |
| <b>TOTAL</b> |                | <b>0.0</b> |                       | <b>3.50</b> |                           |                 |                                    | <b>3.50</b>        |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 400kV 5A                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC5A     | FEH5A: 2 years: +0 %: 10080 mins: Summer | 40.700          | 39.900           | 40.121         | 0.221          | 0.000                    | 7.3                | 2183.104                    | Surcharged |
| OF5A     | FEH5A: 2 years: +0 %: 10080 mins: Summer |                 | 38.900           | 38.940         | 0.040          |                          | 7.3                | 2183.096                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 400kV 5A                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC5A     | FEH5A: 30 years: +0 %: 1440 mins: Summer | 40.700          | 39.900           | 40.217         | 0.317          | 0.000                    | 8.8                | 1189.018                    | Surcharged |
| OF5A     | FEH5A: 30 years: +0 %: 5760 mins: Summer |                 | 38.900           | 38.944         | 0.044          |                          | 8.8                | 3119.067                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 400kV 5A                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                      | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC5A     | FEH5A: 30 years:<br>+40 %: 8640 mins:<br>Winter  | 40.70<br>0      | 39.90<br>0       | 40.372         | 0.472          | 0.000                    | 8.8                | 4930.987                    | Surcharged |
| OF5A     | FEH5A: 30 years:<br>+40 %: 10080 mins:<br>Summer |                 | 38.90<br>0       | 38.944         | 0.044          |                          | 8.8                | 5176.133                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 400kV 5A                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                               | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC5A     | FEH5A: 100 years: +0 %: 8640 mins: Winter | 40.700          | 39.900           | 40.354         | 0.454          | 0.000                    | 8.8                | 4703.048                    | Surcharged |
| OF5A     | FEH5A: 100 years: +0 %: 8640 mins: Winter |                 | 38.900           | 38.944         | 0.044          |                          | 8.8                | 4703.036                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 400kV 5A                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                 | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|---------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC5A     | FEH5A: 100 years: +45 %: 10080 mins: Winter | 40.700          | 39.900           | 40.496         | 0.596          | 0.000                    | 8.8                | 6930.451                    | Flood Risk |
| OF5A     | FEH5A: 100 years: +45 %: 10080 mins: Winter |                 | 38.900           | 38.944         | 0.044          |                          | 8.8                | 6930.433                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 400kV 5A                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP SS 400kV 5A     | FEH5A: 2 years: +0 %: 10080 mins: Summer | 40.526            | 40.129            | 0.067             | 0.079             | 14.9              | 1073.365                  | 0.000                    | 7.3                | 2183.265                    |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 400kV 5A                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP SS 400kV 5A     | FEH5A: 30 years: +0 %: 2160 mins: Summer | 40.614            | 40.228            | 0.154             | 0.178             | 84.4              | 2122.439                  | 0.000                    | 8.8                | 1763.677                    |                             | OK     |



|                                                                                                           |  |                                                                                 |             |              |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |             |              |  |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 400kV 5A                  |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |
|                                                                                                           |  | EE                                                                              | AJ          | RMF          |                                                                                     |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |



**FEH5A: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By:  
Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP SS 400kV 5A     | FEH5A: 30 years: +40 %: 2880 mins: Summer | 40.690            | 40.386            | 0.230             | 0.336             | 93.6              | 3321.840                  | 0.000                    | 8.8                | 1905.095                    | 770                         | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 400kV 5A                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH5A: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP SS 400kV 5A     | FEH5A: 100 years: +0 %: 2880 mins: Summer | 40.704            | 40.402            | 0.245             | 0.352             | 97.8              | 3494.264                  | 0.000                    | 8.8                | 1936.272                    | 1195                        | OK     |

|                                                                                                           |                                                                                 |                                                                                     |                   |                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|-------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |  |                   |                     |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 400kV 5A                  | Designed by:<br>EE                                                              |                                                                                     | Checked by:<br>AJ | Approved By:<br>RMF |
|                                                                                                           | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                                                                                     |                   |                     |



**FEH5A: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP SS 400kV 5A     | FEH5A: 100 years: +45 %: 2880 mins: Winter | 40.867            | 40.563            | 0.407             | 0.513             | 91.5              | 5291.097                  | 0.000                    | 8.8                | 2261.409                    |                             | OK     |

|                                                                                                           |                     |                   |                     |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|---------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                     |  |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 132kV 7F                                      | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RMF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                     |                                                                                     |



132kV 7F

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 0.75 |
|-----------|------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing


|                              |                       |
|------------------------------|-----------------------|
| Runoff Method                | Time of Concentration |
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions<br>Storm Phase: Project SS 132kV 7F                                    |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |
|------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|
| FC7F | Manhole         | 624228.645  | 295874.378   | 42.250          | 0.750     | 41.500           | Circular      | 3.000        |
| OF7F | Simple Junction | 624232.431  | 295835.568   |                 |           |                  |               |              |

| Name | Lock |
|------|------|
| FC7F | None |
| OF7F |      |

Outlets

| Junction | Outlet Name                                                                         | Outgoing Connection                    | Outlet Type  |
|----------|-------------------------------------------------------------------------------------|----------------------------------------|--------------|
| FC7F     | Outlet                                                                              | 7.001                                  | Hydro-Brake® |
|          | Invert Level (m)                                                                    | 41.500                                 |              |
|          | Design Depth (m)                                                                    | 0.750                                  |              |
|          | Design Flow (L/s)                                                                   | 2.2                                    |              |
|          | Objective                                                                           | Minimise Upstream Storage Requirements |              |
|          | Application                                                                         | Surface Water Only                     |              |
|          | Sump Available                                                                      | <input type="checkbox"/>               |              |
|          | Unit Reference                                                                      | CHE-0072-2200-0750-2200                |              |
|          |  |                                        |              |
|          |                                                                                     |                                        |              |

|                                                                                                           |                                                                                 |                   |                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |                   |                     |
|                                                                                                           | Designed by:<br>EE                                                              | Checked by:<br>AJ | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 132kV 7F                          | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                     |



PP 132kV 7F

Type : Porous Paving

### Dimensions

|                             |          |
|-----------------------------|----------|
| Exceedance Level (m)        | 42.250   |
| Depth (m)                   | 0.680    |
| Base Level (m)              | 41.570   |
| Paving Layer Depth (mm)     | 80       |
| Membrane Percolation (m/hr) | 32.4     |
| Porosity (%)                | 30       |
| Length (m)                  | 122.474  |
| Long. Slope (1:X)           | 600.00   |
| Width (m)                   | 61.237   |
| Total Volume (m³)           | 1351.515 |

### Under Drain

|                       |             |
|-----------------------|-------------|
| Height Above Base (m) | 0.000       |
| Diameter (mm)         | 150         |
| No. of Barrels        | 1           |
| Release Height (m)    | 0.000       |
| Friction Scheme       | Manning's n |
| n                     | 0.015       |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | 132kV 7F       |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 7.000          |
| Outlet Type         | Free Discharge |

### Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Connections<br>Storm Phase: Project SS 132kV 7F                                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name  | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Upstream Cover Level (m) | Upstream Invert Level (m) |
|-------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|--------------------------|---------------------------|
| 7.000 | 2.871      | Pipe            | 41.010      |             | 0.6                            | 150                        | 42.250                   | 41.570                    |
| 7.001 | 38.994     | Pipe            | 111.411     |             | 0.6                            | 150                        | 42.250                   | 41.500                    |

| Name  | Downstream Cover Level (m) | Downstream Invert Level (m) | Lock | Flow Restriction (L/s) | Culvert Type | Culvert Entrance |
|-------|----------------------------|-----------------------------|------|------------------------|--------------|------------------|
| 7.000 | 42.250                     | 41.500                      | None |                        | (None)       | (None)           |
| 7.001 | 41.750                     | 41.150                      | None | 2.2                    | (None)       | (None)           |

|                                                                                                           |  |  |                                                                                 |             |              |                                                                                     |  |  |
|-----------------------------------------------------------------------------------------------------------|--|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|--|--|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  |  | Date:<br>01/09/2026                                                             |             |              |  |  |  |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Project SS 132kV 7F                               |  |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |  |  |
|                                                                                                           |  |  | EE                                                                              | AJ          | RMF          |                                                                                     |  |  |
|                                                                                                           |  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |  |  |

| Inflow Label | Connected To | Flow (L/s) | Runoff Method         | Area (ha)   | Percentage Impervious (%) | Urban Creep (%) | Adjusted Percentage Impervious (%) | Area Analysed (ha) |
|--------------|--------------|------------|-----------------------|-------------|---------------------------|-----------------|------------------------------------|--------------------|
| 132kV 7F     | PP 132kV 7F  |            | Time of Concentration | 0.75        | 100                       | 0               | 100                                | 0.75               |
| <b>TOTAL</b> |              | <b>0.0</b> |                       | <b>0.75</b> |                           |                 |                                    | <b>0.75</b>        |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 7F                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                             | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-----------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC7F     | FEH7F: 2 years: +0 %: 4320 mins: Summer | 42.250          | 41.500           | 41.707         | 0.207          | 0.000                    | 2.2                | 339.619                     | Surcharged |
| OF7F     | FEH7F: 2 years: +0 %: 2880 mins: Summer |                 | 41.150           | 41.186         | 0.036          |                          | 2.2                | 293.629                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 7F                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                              | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC7F     | FEH7F: 30 years: +0 %: 7200 mins: Summer | 42.250          | 41.500           | 41.836         | 0.336          | 0.000                    | 2.2                | 744.414                     | Surcharged |
| OF7F     | FEH7F: 30 years: +0 %: 7200 mins: Summer |                 | 41.150           | 41.186         | 0.036          |                          | 2.2                | 744.410                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 7F                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                      | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC7F     | FEH7F: 30 years:<br>+40 %: 7200 mins:<br>Summer  | 42.25<br>0      | 41.50<br>0       | 41.928         | 0.428          | 0.000                    | 2.2                | 1040.082                    | Surcharged |
| OF7F     | FEH7F: 30 years:<br>+40 %: 10080 mins:<br>Summer |                 | 41.15<br>0       | 41.186         | 0.036          |                          | 2.2                | 1138.177                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 7F                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC7F     | FEH7F: 100 years: +0 %: 2160 mins: Winter  | 42.250          | 41.500           | 41.981         | 0.481          | 0.000                    | 2.2                | 378.769                     | Flood Risk |
| OF7F     | FEH7F: 100 years: +0 %: 10080 mins: Summer |                 | 41.150           | 41.186         | 0.036          |                          | 2.2                | 1059.599                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 132kV 7F                            |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                 | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|---------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC7F     | FEH7F: 100 years: +45 %: 7200 mins: Winter  | 42.250          | 41.500           | 42.071         | 0.571          | 0.000                    | 2.2                | 1293.508                    | Flood Risk |
| OF7F     | FEH7F: 100 years: +45 %: 10080 mins: Winter |                 | 41.150           | 41.186         | 0.036          |                          | 2.2                | 1534.553                    | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 7F                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                            | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|----------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 7F        | FEH7F: 2 years: +0 %: 600 mins: Winter | 41.830            | 41.704            | 0.056             | 0.134             | 15.7              | 182.744                   | 0.000                    | 2.2                | 119.469                     |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 7F                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                              | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 7F        | FEH7F: 30 years: +0 %: 1440 mins: Summer | 41.873            | 41.869            | 0.099             | 0.299             | 24.9              | 449.390                   | 0.000                    | 2.3                | 221.742                     |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 7F                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 7F        | FEH7F: 30 years: +40 %: 2160 mins: Winter | 41.971            | 41.965            | 0.197             | 0.395             | 16.3              | 667.633                   | 0.000                    | 2.3                | 374.597                     |                             | OK     |



|                                                                                                           |  |                                                                                 |             |              |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |             |              |  |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 7F                  |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |
|                                                                                                           |  | EE                                                                              | AJ          | RMF          |                                                                                     |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |



**FEH7F: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 7F        | FEH7F: 100 years: +0 %: 2160 mins: Winter | 41.987            | 41.981            | 0.213             | 0.411             | 17.1              | 704.516                   | 0.000                    | 2.3                | 381.545                     | 315                         | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 132kV 7F                  |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH7F: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 7F        | FEH7F: 100 years: +45 %: 2880 mins: Winter | 42.152            | 42.144            | 0.378             | 0.574             | 19.5              | 1074.249                  | 0.000                    | 2.3                | 586.432                     |                             | OK     |

|                                                                                                           |                     |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |  |                     |
| Report Details:<br>Type: Inflows<br>Storm Phase: Project SS 133KV 10C                                     | Designed by:<br>EE  | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                                                                                     |                     |



132kV 10C

Type : Catchment Area

|           |      |
|-----------|------|
| Area (ha) | 0.50 |
|-----------|------|

### Preliminary Sizing

|                               |       |
|-------------------------------|-------|
| Volumetric Runoff Coefficient | 1.000 |
| Percentage Impervious (%)     | 100   |
| Time of Concentration (mins)  | 5     |

### Dynamic Sizing


|                              |                       |
|------------------------------|-----------------------|
| Runoff Method                | Time of Concentration |
| Summer Volumetric Runoff     | 1.000                 |
| Winter Volumetric Runoff     | 1.000                 |
| Time of Concentration (mins) | 5                     |
| Percentage Impervious (%)    | 100                   |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions<br>Storm Phase: Project SS 133KV 10C                                   |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name  | Junction Type   | Easting (m) | Northing (m) | Cover Level (m) | Depth (m) | Invert Level (m) | Chamber Shape | Diameter (m) |
|-------|-----------------|-------------|--------------|-----------------|-----------|------------------|---------------|--------------|
| FC10C | Manhole         | 629874.462  | 295265.207   | 33.440          | 0.690     | 32.750           | Circular      | 3.000        |
| OF10C | Simple Junction | 629816.694  | 295265.579   |                 |           |                  |               |              |

| Name  | Lock |
|-------|------|
| FC10C | None |
| OF10C |      |

## Outlets

| Junction | Outlet Name                                                                         | Outgoing Connection                    | Outlet Type  |
|----------|-------------------------------------------------------------------------------------|----------------------------------------|--------------|
| FC10C    | Outlet                                                                              | 8.001                                  | Hydro-Brake® |
|          | Invert Level (m)                                                                    | 32.750                                 |              |
|          | Design Depth (m)                                                                    | 0.690                                  |              |
|          | Design Flow (L/s)                                                                   | 1.4                                    |              |
|          | Objective                                                                           | Minimise Upstream Storage Requirements |              |
|          | Application                                                                         | Surface Water Only                     |              |
|          | Sump Available                                                                      | <input type="checkbox"/>               |              |
|          | Unit Reference                                                                      | CHE-0059-1400-0690-1400                |              |
|          |  |                                        |              |
|          |                                                                                     |                                        |              |

|                                                                                                           |                     |                   |                     |                                                                                     |
|-----------------------------------------------------------------------------------------------------------|---------------------|-------------------|---------------------|-------------------------------------------------------------------------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026 |                   |                     |  |
| Report Details:<br>Type: Stormwater Controls<br>Storm Phase: Project SS 133KV 10C                         | Designed by:<br>EE  | Checked by:<br>AJ | Approved By:<br>RMF |                                                                                     |
| Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN                           |                     |                   |                     |                                                                                     |



PP 132kV 10C

Type : Porous Paving

### Dimensions

|                             |         |
|-----------------------------|---------|
| Exceedance Level (m)        | 33.440  |
| Depth (m)                   | 0.640   |
| Base Level (m)              | 32.800  |
| Paving Layer Depth (mm)     | 80      |
| Membrane Percolation (m/hr) | 32.4    |
| Porosity (%)                | 30      |
| Length (m)                  | 99.000  |
| Long. Slope (1:X)           | 650.00  |
| Width (m)                   | 50.502  |
| Total Volume (m³)           | 841.177 |

### Under Drain

|                       |             |
|-----------------------|-------------|
| Height Above Base (m) | 0.000       |
| Diameter (mm)         | 150         |
| No. of Barrels        | 1           |
| Release Height (m)    | 0.000       |
| Friction Scheme       | Manning's n |
| n                     | 0.015       |

### Inlets

#### Inlet

|                    |                |
|--------------------|----------------|
| Inlet Type         | Lateral Inflow |
| Incoming Item(s)   | 132kV 10C      |
| Bypass Destination | (None)         |
| Capacity Type      | No Restriction |

### Outlets

#### Outlet

|                     |                |
|---------------------|----------------|
| Outgoing Connection | 8.000          |
| Outlet Type         | Free Discharge |

### Advanced

|                     |      |
|---------------------|------|
| Conductivity (m/hr) | 50.0 |
|---------------------|------|

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Connections<br>Storm Phase: Project SS 133KV 10C                                 |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |

| Name  | Length (m) | Connection Type | Slope (1:X) | Manning's n | Colebrook-White Roughness (mm) | Diameter / Base Width (mm) | Upstream Cover Level (m) | Upstream Invert Level (m) |
|-------|------------|-----------------|-------------|-------------|--------------------------------|----------------------------|--------------------------|---------------------------|
| 8.000 | 6.305      | Pipe            | 126.102     |             | 0.6                            | 150                        | 33.440                   | 32.800                    |
| 8.001 | 57.769     | Pipe            | 144.424     |             | 0.6                            | 150                        | 33.440                   | 32.750                    |

| Name  | Downstream Cover Level (m) | Downstream Invert Level (m) | Lock | Flow Restriction (L/s) | Culvert Type | Culvert Entrance |
|-------|----------------------------|-----------------------------|------|------------------------|--------------|------------------|
| 8.000 | 33.440                     | 32.750                      | None |                        | (None)       | (None)           |
| 8.001 | 32.900                     | 32.350                      | None | 1.4                    | (None)       | (None)           |

|                                                                                                           |  |                                                                                 |             |              |                                                                                     |  |  |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------|--------------|-------------------------------------------------------------------------------------|--|--|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |             |              |  |  |  |
| Report Details:<br>Type: Inflow Summary<br>Storm Phase: Project SS 133KV 10C                              |  | Designed by:                                                                    | Checked by: | Approved By: |                                                                                     |  |  |
|                                                                                                           |  | EE                                                                              | AJ          | RMF          |                                                                                     |  |  |
|                                                                                                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |             |              |                                                                                     |  |  |

| Inflow Label | Connected To | Flow (L/s) | Runoff Method         | Area (ha)   | Percentage Impervious (%) | Urban Creep (%) | Adjusted Percentage Impervious (%) | Area Analysed (ha) |
|--------------|--------------|------------|-----------------------|-------------|---------------------------|-----------------|------------------------------------|--------------------|
| 132kV 10C    | PP 132kV 10C |            | Time of Concentration | 0.50        | 100                       | 0               | 100                                | 0.50               |
| <b>TOTAL</b> |              | <b>0.0</b> |                       | <b>0.50</b> |                           |                 |                                    | <b>0.50</b>        |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 133KV 10C                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                             | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-----------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC10C    | FEH10C: 2 years: +0 %: 360 mins: Summer | 33.440          | 32.750           | 32.929         | 0.179          | 0.000                    | 1.3                | 43.392                      | Surcharged |
| OF10C    | FEH10C: 2 years: +0 %: 360 mins: Summer |                 | 32.350           | 32.380         | 0.030          |                          | 1.3                | 43.315                      | OK         |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 133KV 10C                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                               | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|-------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC10C    | FEH10C: 30 years: +0 %: 60 mins: Summer   | 33.440          | 32.750           | 32.959         | 0.209          | 0.000                    | 1.3                | 6.228                       | Surcharged |
| OF10C    | FEH10C: 30 years: +0 %: 1440 mins: Winter |                 | 32.350           | 32.380         | 0.030          |                          | 1.3                | 138.225                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 133KV 10C                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                      | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC10C    | FEH10C: 30 years:<br>+40 %: 30 mins:<br>Summer   | 33.44<br>0      | 32.75<br>0       | 32.960         | 0.210          | 0.000                    | 1.3                | 2.886                       | Surcharged |
| OF10C    | FEH10C: 30 years:<br>+40 %: 1440 mins:<br>Winter |                 | 32.35<br>0       | 32.380         | 0.030          |                          | 1.3                | 156.950                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 133KV 10C                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|--------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC10C    | FEH10C: 100 years: +0 %: 30 mins: Summer   | 33.440          | 32.750           | 32.947         | 0.197          | 0.000                    | 1.3                | 3.227                       | Surcharged |
| OF10C    | FEH10C: 100 years: +0 %: 1440 mins: Summer |                 | 32.350           | 32.380         | 0.030          |                          | 1.3                | 159.299                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Junctions Summary<br>Storm Phase: Project SS 133KV 10C                           |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Outflow**

| Junction | Storm Event                                 | Cover Level (m) | Invert Level (m) | Max. Level (m) | Max. Depth (m) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Status     |
|----------|---------------------------------------------|-----------------|------------------|----------------|----------------|--------------------------|--------------------|-----------------------------|------------|
| FC10C    | FEH10C: 100 years: +45 %: 15 mins: Summer   | 33.440          | 32.750           | 32.949         | 0.199          | 0.000                    | 1.3                | 1.440                       | Surcharged |
| OF10C    | FEH10C: 100 years: +45 %: 1440 mins: Summer |                 | 32.350           | 32.380         | 0.030          |                          | 1.3                | 186.436                     | OK         |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 133KV 10C                 |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 2 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                             | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-----------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 10C       | FEH10C: 2 years: +0 %: 720 mins: Winter | 33.001            | 32.945            | 0.048             | 0.145             | 9.0               | 122.221                   | 0.000                    | 1.4                | 87.114                      |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 133KV 10C                 |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 30 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                               | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|-------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 10C       | FEH10C: 30 years: +0 %: 2160 mins: Winter | 33.079            | 33.078            | 0.127             | 0.278             | 7.8               | 303.870                   | 0.000                    | 1.4                | 207.696                     |                             | OK     |

|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 133KV 10C                 |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 30 years: Increase Rainfall (%): +40: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 10C       | FEH10C: 30 years: +40 %: 2160 mins: Winter | 33.176            | 33.174            | 0.224             | 0.374             | 10.8              | 449.053                   | 0.000                    | 1.4                | 238.040                     | 485                         | OK     |

|                                                                                                           |                                                                                 |                                                                                     |                   |                     |
|-----------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|-------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B | Date:<br>01/09/2026                                                             |  |                   |                     |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 133KV 10C                 | Designed by:<br>EE                                                              |                                                                                     | Checked by:<br>AJ | Approved By:<br>RMF |
|                                                                                                           | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                                                                                     |                   |                     |



**FEH10C: 100 years: Increase Rainfall (%): +0: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|--------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 10C       | FEH10C: 100 years: +0 %: 2160 mins: Winter | 33.190            | 33.188            | 0.238             | 0.388             | 11.3              | 470.081                   | 0.000                    | 1.4                | 242.293                     | 810                         | OK     |



|                                                                                                           |  |                                                                                 |                   |                                                                                     |                     |
|-----------------------------------------------------------------------------------------------------------|--|---------------------------------------------------------------------------------|-------------------|-------------------------------------------------------------------------------------|---------------------|
| East Pye Solar:<br>East Pye Solar DCO<br>Substation Drainage 4B, 5A, 7F & 10C<br>Access Track Drainage 4B |  | Date:<br>01/09/2026                                                             |                   |  |                     |
|                                                                                                           |  | Designed by:<br>EE                                                              | Checked by:<br>AJ |                                                                                     | Approved By:<br>RMF |
| Report Details:<br>Type: Stormwater Controls Summary<br>Storm Phase: Project SS 133KV 10C                 |  | Stantec UK Ltd.:<br>Caversham Bridge House<br>Waterman Place<br>Reading RG1 8DN |                   |                                                                                     |                     |



**FEH10C: 100 years: Increase Rainfall (%): +45: Critical Storm Per Item: Rank By: Max. Resident Volume**

| Stormwater Control | Storm Event                                 | Max. US Level (m) | Max. DS Level (m) | Max. US Depth (m) | Max. DS Depth (m) | Max. Inflow (L/s) | Max. Resident Volume (m³) | Max. Flooded Volume (m³) | Max. Outflow (L/s) | Total Discharge Volume (m³) | Half Drain Down Time (mins) | Status |
|--------------------|---------------------------------------------|-------------------|-------------------|-------------------|-------------------|-------------------|---------------------------|--------------------------|--------------------|-----------------------------|-----------------------------|--------|
| PP 132kV 10C       | FEH10C: 100 years: +45 %: 2880 mins: Winter | 33.355            | 33.352            | 0.403             | 0.552             | 13.0              | 717.175                   | 0.000                    | 1.4                | 377.137                     |                             | OK     |





The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66803NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 20.04.10/04.
3. LAYOUT TAKEN FROM DRAWING DRAWING ESSE PYLE SOLAR FARM, BY ARUP AND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON APPROVED LAYOUT 11.11.2025
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.
5. SUB-STATION COMPOUNDS TO INCORPORATE BUNDS AT LOWEST POINTS TO CONTAIN SURFACE WATER RUNOFF AS REQUIRED.
6. ACCESS TRACKS WITHIN SUB-SITES AND THAT CONNECT ELEMENTS OF THE SCHEME (AND WHERE REQUIRED WITHIN BESS AND SUBSTATION COMPOUNDS) TO DRAIN TO SWALES OR FILTER DRAINS RUNNING PARALLEL WITH THE TRACKS.

|                                                                                     |                    |                                                                                     |                                              |
|-------------------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------------------|----------------------------------------------|
|  | ORDER LIMITS       |  | WORK 4 - NATIONAL GRID SUBSTATION            |
|  | EXISTING DITCH     |  | WORK 6 - 132kV AND 400kV PROJECT SUBSTATIONS |
|  | ACCESS TRACK       |  | PROPOSED SOLID SURFACE WATER PIPE            |
|  | AGGREGATE SUB-BASE |  | PROPOSED FLOW CONTROL CHAMBER                |
|  | PROPOSED SWALE     |  | PROPOSED HEADWALL                            |

|                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                  |      |       |            |
|------------------|------|-------|------------|
| P02 SWALES ADDED | EE   | -     | 2026.10.02 |
| P01 FIRST ISSUE  | EE   | -     | 2026.03.04 |
| Issued/Revision  | By   | Appd  | YYYY.MM.DD |
|                  | GD   | EE    | -          |
|                  | Dwn. | Dsgn. | Chkd.      |
|                  |      |       | 2026.03.04 |
|                  |      |       | YYYY.MM.DD |

S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.


Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title

CONCEPT SURFACE WATER DRAINAGE  
NATIONAL GRID AND 400KV PROJECT  
SUBSTATION SUB-SITE 1B

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P02</b>   | Drawing No.<br><b>333101678-300.03-001</b> |







Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAIVING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 11.01.2025, BESS LAYOUT BASED ON UPDATED LAYOUT 11.01.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE
5. BESS FACILITY (AND WHERE APPROPRIATE SUBSTATION COMPOUNDS) TO INCORPORATE BUNDS AT LOWEST POINTS OF COMPOUND TO CONTAIN SURFACE AND FIREWATER RUNOFF.
6. ACCESS TRACKS WITHIN SUB-SITES AND THAT CONNECT ELEMENTS OF THE SCHEME (AND WHERE REQUIRED WITHIN BESS AND SUBSTATION COMPOUNDS) TO DRIVE LORRIES OR FILTER DRAINS RUNNING PARALLEL WITH THE TRACKS.

KEY:

- |                                                                                     |                    |                                                                                     |                                              |
|-------------------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------------------|----------------------------------------------|
|  | ORDER LIMITS       |  | WORK 4 - NATIONAL GRID SUBSTATION            |
|  | EXISTING DITCH     |  | WORK 6 - 132kV AND 400kV PROJECT SUBSTATIONS |
|  | ACCESS TRACK       |  | PROPOSED SOLID SURFACE WATER PIPE            |
|  | AGGREGATE SUB-BASE |  | PROPOSED FLOW CONTROL CHAMBER                |
|  | PROPOSED SWALE     |  | PROPOSED HEADWALL                            |

UTILITIES KEY:

- |                                                                                     |                      |                                                                                     |                              |
|-------------------------------------------------------------------------------------|----------------------|-------------------------------------------------------------------------------------|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |                                                                                     |                              |

|                  |      |       |            |
|------------------|------|-------|------------|
| P02 SWALES ADDED | EE   | -     | 2026.10.02 |
| P01 FIRST ISSUE  | EE   | -     | 2026.03.04 |
| Issued/Revision  | By   | Appd  | YYYY.MM.DD |
|                  | GD   | -     | 2026.03.04 |
|                  | Dwn. | Dsgn. | Chkd.      |
|                  |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.


Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title

CONCEPT SURFACE WATER DRAINAGE  
BESS AND 400KV PROJECT SUBSTATION  
BESS SITE



|                          |                                           |
|--------------------------|-------------------------------------------|
| Project No.<br>333101678 | AI Scale<br>AS SHOWN                      |
| Revision<br><b>P02</b>   | Drawing No.<br><b>333101678-300.03-01</b> |



© Crown copyright and database rights 2024 . Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings  
Ordnance Survey AC0000849896

Dated: 02.10.2026 3:48:16 PM By: Raj, Shanthak  
 ORIGINAL SHEET - BOA I:\333101211 kina stration (metro)\card\dwars\333101678-370 03-072









Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66683NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PVE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2023. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENTION TO BE REFINED AT DETAILED DESIGN STAGE.
5. SUB-STATION COMPOUNDS TO INCORPORATE BUNDS AT LOWEST POINTS TO CONTAIN SURFACE WATER RUNOFF AS REQUIRED.
6. ACCESS TRACKS WITHIN SUB-SITES AND THAT CONNECT ELEMENTS OF THE SCHEME (AND WHERE REQUIRED WITHIN BESS AND SUBSTATION COMPOUNDS) TO DRAIN TO SWALES OR FILTER DRAINS RUNNING PARALLEL WITH THE TRACKS.

**KEY:**

- |                                                                                     |                    |                                                                                     |                                              |
|-------------------------------------------------------------------------------------|--------------------|-------------------------------------------------------------------------------------|----------------------------------------------|
|  | ORDER LIMITS       |  | WORK 6 - 132KV AND 400KV PROJECT SUBSTATIONS |
|  | EXISTING DITCH     |  | ORIFICE FLOW CONTROL                         |
|  | ACCESS TRACK       |  | PROPOSED SOLID SURFACE FLOW PIPE             |
|  | AGGREGATE SUB-BASE |  | PROPOSED FLOW CONTROL CHAMBER                |
|  | PROPOSED SWALE     |  | PROPOSED HEADWALL                            |
|  | FENCING            |                                                                                     |                                              |

UTILITIES KEY:

- |                                                                                     |                      |                                                                                     |                              |
|-------------------------------------------------------------------------------------|----------------------|-------------------------------------------------------------------------------------|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |                                                                                     |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.09.29 |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.


Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title

OUTLINE SURFACE WATER DRAINAGE  
400kV PROJECT SUBSTATION & ACCESS  
SUB-SITE 4B

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | AT Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-004</b> |





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.
- SUB-STATION COMPOUNDS TO INCORPORATE BUNDS AT LOWEST POINTS TO CONTAIN SURFACE WATER RUNOFF AS REQUIRED.
- ACCESS TRACKS WITHIN SUB-SITES AND THAT CONNECT ELEMENTS OF THE SCHEME (AND WHERE REQUIRED WITHIN BESS AND SUBSTATION COMPOUNDS) TO DRAIN TO SWALES OR FILTER DRAINS RUNNING PARALLEL WITH THE TRACKS.

KEY:

- ORDER LIMITS
- EXISTING DITCH
- ACCESS TRACK
- AGGREGATE SUB-BASE
- PROPOSED SWALE
- FENCING
- WORK 6 - 132KV AND 400KV PROJECT SUBSTATIONS
- ORIFICE FLOW CONTROL
- PROPOSED SOLID SURFACE WATER PIPE
- PROPOSED FLOW CONTROL CHAMBER
- PROPOSED HEADWALL

UTILITIES KEY:

- Ex Elec 011kV oh
- Ex Elec 400kV oh
- Ex Elec Lv oh
- Ex Elec Lv
- Ex Elec 011kV
- Ex Gas Low Pressure
- Ex Gas High Pressure
- Ex Comms BT Ducts
- Ex BT Overhead Lines
- Ex Water
- Abandoned
- Ex Comms Gigaclear
- Ex Gas Intermediate Pressure

|                 |      |       |            |
|-----------------|------|-------|------------|
| PO1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.09.29 |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | YYYY.MM.DD |

Issue Status

S2 - FOR INFORMATION





This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
OUTLINE SURFACE WATER DRAINAGE  
PROJECT SUBSTATIONS 5A, 7F & 10C

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-005 |








D


C

B

A



© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Ordnance Survey Licence No. 10000849896



01 SITE KEY PLAN  
006 NTS

02 PLAN  
006 1:1000



Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.
- BESS FACILITY (AND WHERE APPROPRIATE SUBSTATION COMPOUNDS) TO INCORPORATE BUNDS AT LOWEST POINTS OF COMPOUND TO CONTAIN SURFACE AND FIREWATER RUNOFF.
- ACCESS TRACKS WITHIN SUB-SITES AND THAT CONNECT ELEMENTS OF THE SCHEME (AND WHERE REQUIRED WITHIN BESS AND SUBSTATION COMPOUNDS) TO DRAIN TO SWALES OR FILTER DRAINS RUNNING PARALLEL WITH THE TRACKS.

KEY:

- |  |                    |  |                                              |
|--|--------------------|--|----------------------------------------------|
|  | ORDER LIMITS       |  | WORK 4 - NATIONAL GRID SUBSTATION            |
|  | EXISTING DITCH     |  | WORK 6 - 132KV AND 400KV PROJECT SUBSTATIONS |
|  | ACCESS TRACK       |  | PROPOSED SOLID SURFACE WATER PIPE            |
|  | AGGREGATE SUB-BASE |  | PROPOSED FLOW CONTROL CHAMBER                |
|  | PROPOSED SWALE     |  | PROPOSED HEADWALL                            |

UTILITIES KEY:

- |  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec LV oh        |  | Ex Water                     |
|  | Ex Elec LV           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.09.29 |
|                 | Dwn. | Dsgn. | Chkd.      |

Issue Status

S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.


Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT SURFACE WATER DRAINAGE  
SITES 1A AND 1B

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-006 |





The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operation.

- KEY:**
- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

|                                                                                     |                      |                                                                                     |                              |
|-------------------------------------------------------------------------------------|----------------------|-------------------------------------------------------------------------------------|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms GigaClear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |                                                                                     |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 2A

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-007</b> |




Printed: 05.10.2026 20:26.10.05 9:13:47 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 333101211 ] long stration (hydro)\cad\dwg\333101678-300-03-007-023

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Ordnance Survey AC0000849896

02 SITE 2A PLAN  
007 1:1500





1

2

3

4

5

D

C


B

A




2B

2C





© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896

02  
007  
SITE 2B/2C PLAN  
1:2000



01  
007  
SITE KEY PLANS  
NOT TO SCALE



# Stantec

Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

KEY:

- |                |                                   |
|----------------|-----------------------------------|
| ORDER LIMITS   | PROPOSED SOLID SURFACE WATER PIPE |
| EXISTING DITCH | PROPOSED FLOW CONTROL CHAMBER     |
| ACCESS TRACK   | PROPOSED HEADWALL                 |
| PROPOSED SWALE | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

Issue Status

## S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 2B/2C

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-008 |





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 668B3NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTEENMENT TO BE REFINED AT DETAILED DESIGN STAGE.

KEY:

- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.10.02 |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.



Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 4A/4B

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-009</b> |



Printed: 05.10.2026 20:26, 10.05.9:14:31 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 133310121 | lonastallon@indroil's card's dwart, 333101678-300 03-007-023





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

**Notes**

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

|                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
| <b>KEY:</b>                                                                         |                |                                                                                     |                                   |
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

|                                                                                     |                      |                                                                                     |                              |
|-------------------------------------------------------------------------------------|----------------------|-------------------------------------------------------------------------------------|------------------------------|
| <b>UTILITIES KEY:</b>                                                               |                      |                                                                                     |                              |
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |                                                                                     |                              |

|                 |      |       |                  |
|-----------------|------|-------|------------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02       |
| Issued/Revision | By   | Appd  | YYYY.MM.DD       |
|                 | GD   | EE    | 2026.10.02       |
|                 | Dwn. | Dsgn. | Chkd. YYYY.MM.DD |

Issue Status

**S2 - FOR INFORMATION**

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 5A/5B

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-010 |





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING EAST PYE ~~SOLAR FARM, BY ISLAND GREEN POWER UK DATED 19.11.2025.~~
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

**KEY:**

- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.



Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 3

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-011</b> |



Printed: 05.10.2026 20:26, 10:05 9:15:00 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 33310121 | lonastallon (vndro)'s card's dwst, 333101678-300 03-007-023





**01 SITE KEY PLANS**  
012 NOT TO SCALE



Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
www.stantec.com/uk

**Copyright Reserved**

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

**Notes**

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

**KEY:**

- |  |                |  |                                   |
|--|----------------|--|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

**UTILITIES KEY:**

- |  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.10.02 |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | YYYY.MM.DD |

Issue Status

**S2 - FOR INFORMATION**

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 7A

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-012 |

D

C

B



A

0 40 80 120 160 200m  
SCALE 1:2000

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896

**02 SITE 7A PLAN**  
012 1:2000





01  
013 SITE KEY PLANS  
NOT TO SCALE

Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

- Notes
- UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.
- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
  - TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
  - LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
  - FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

KEY:

|  |                |  |                                   |
|--|----------------|--|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

|  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec LV oh        |  | Ex Water                     |
|  | Ex Elec LV           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |                  |
|-----------------|------|-------|------------------|
| PD1 FIRST ISSUE | EE   | -     | 2024.10.02       |
| Issued/Revision | By   | Appd  | YYYY.MM.DD       |
|                 | GD   | EE    | 2024.10.02       |
|                 | Dwn. | Dsgn. | Chkd. YYYY.MM.DD |

Issue Status

**S2 - FOR INFORMATION**

This document is suitable only for the purpose noted above. Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.


Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 7B/7C

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-013 |

Project: 05.10.2024/2024.10.05 9:15:21 AM By: Ben. Shattuck  
Drawing: 333101678-300.03-013  
Drawing: 333101678-300.03-013

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896





Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel: +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

#### Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

#### KEY:

- |  |                |  |                                   |
|--|----------------|--|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

#### UTILITIES KEY:

- |  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

Issue Status

## S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 7D

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-014 |

## 01 SITE KEY PLANS

NOT TO SCALE

PRESENCE OF DITCH TO  
BE CONFIRMED THROUGH  
DETAILED DESIGN.

## 02 SITE 7D PLAN

1:1250

SCALE 1:2000

0 40 80 120 160 200m

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC000049896





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

**KEY:**

- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.



Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 7E/7F

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-015</b> |



Printed: 05.10.2026 20:26, 10.05.9:15:59 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 3333101211 long strallon (mvdrol\card)\dwars\333101678-300.03-007-023





Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel: +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved  
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes  
UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

| KEY: |                                   |
|------|-----------------------------------|
|      | ORDER LIMITS                      |
|      | EXISTING DITCH                    |
|      | ACCESS TRACK                      |
|      | PROPOSED SWALE                    |
|      | PROPOSED SOLID SURFACE WATER PIPE |
|      | PROPOSED FLOW CONTROL CHAMBER     |
|      | PROPOSED HEADWALL                 |
|      | FENCING                           |

| UTILITIES KEY: |                              |
|----------------|------------------------------|
|                | Ex Elec 011kV oh             |
|                | Ex Elec 400kV oh             |
|                | Ex Elec Lv oh                |
|                | Ex Elec Lv                   |
|                | Ex Elec 011kV                |
|                | Ex Gas Low Pressure          |
|                | Ex Gas High Pressure         |
|                | Ex Comms BT Ducts            |
|                | Ex BT Overhead Lines         |
|                | Ex Water                     |
|                | Abandoned                    |
|                | Ex Comms Gigaclear           |
|                | Ex Gas Intermediate Pressure |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2024.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |

Issue Status

## S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.



Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
7G/7H/7I

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-016 |





01 SITE KEY PLANS  
017 NOT TO SCALE

Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
[www.stantec.com/uk](http://www.stantec.com/uk)

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay. The Copyrights to all designs and drawings are the property of Stantec. Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

**KEY:**

- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

**UTILITIES KEY:**

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 7.1

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-017</b> |




Printed: 05.10.2026 20:26, 10.05.9:16:26 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 33310121 | long strallon (mvdra)\card\dwars\333101278-300.03-007-023

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896

02 SITE 7J PLAN  
017 1:2000





D

C


B

A



© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Ordnance Survey AC0000849896

02 018 SITE 7K/7L PLAN 1:2000



01 018 SITE KEY PLANS NOT TO SCALE



Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel. +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved  
The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes  
UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING EAST PYE 6633101678 BY ISLAND GREEN POWER UK, DATED 2024.10.02.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

- KEY:
- |                |                                   |
|----------------|-----------------------------------|
| ORDER LIMITS   | PROPOSED SOLID SURFACE WATER PIPE |
| EXISTING DITCH | PROPOSED FLOW CONTROL CHAMBER     |
| ACCESS TRACK   | PROPOSED HEADWALL                 |
| PROPOSED SWALE | FENCING                           |

- UTILITIES KEY:
- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2024.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |

Issue Status

## S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.



Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 7K/7L

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-018 |





Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel: +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

#### Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

#### KEY:

- |  |                |  |                                   |
|--|----------------|--|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

#### UTILITIES KEY:

- |  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.10.02 |
|                 | Dwn. | Dsgn. | Chkd.      |

Issue Status

## S2 - FOR INFORMATION

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo


Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 10A/10C

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-019 |

## 01 SITE KEY PLANS

019 NOT TO SCALE



10C

10A

PRESENCE OF DITCH TO  
BE CONFIRMED THROUGH  
DETAILED DESIGN.


## 02 SITE 10A/10C PLAN

019 1:2000

0 40 80 120 160 200m  
SCALE 1:2000

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896





01

020

SITE KEY PLANS

NOT TO SCALE

Stantec UK Limited  
Caversham Bridge House, Waterman Place  
Reading  
RG1 8DN  
Tel: +44 1189 500 761  
www.stantec.com/uk

Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

KEY:

|  |                |  |                                   |
|--|----------------|--|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

|  |                      |  |                              |
|--|----------------------|--|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |  |                              |

|                 |      |       |            |            |
|-----------------|------|-------|------------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2024.10.02 |            |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |            |
|                 | GD   | EE    | 2024.10.02 |            |
|                 | Dwn. | Dsgn. | Chkd.      | YYYY.MM.DD |

Issue Status

**S2 - FOR INFORMATION**

This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 10B/10D

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-020 |

Project: 333101678-300.03-020  
Drawing: 333101678-300.03-020  
Scale: 1:2000  
Date: 2024.10.02  
Author: [Name]  
Check: [Name]  
Approved: [Name]

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849696





The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

|                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

|                                                                                     |                      |                                                                                     |                              |
|-------------------------------------------------------------------------------------|----------------------|-------------------------------------------------------------------------------------|------------------------------|
|  | Ex Elec 011kV oh     |  | Ex Comms BT Ducts            |
|  | Ex Elec 400kV oh     |  | Ex BT Overhead Lines         |
|  | Ex Elec Lv oh        |  | Ex Water                     |
|  | Ex Elec Lv           |  | Abandoned                    |
|  | Ex Elec 011kV        |  | Ex Comms Gigaclear           |
|  | Ex Gas Low Pressure  |  | Ex Gas Intermediate Pressure |
|  | Ex Gas High Pressure |                                                                                     |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SUB-SITE 10E

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-021</b> |



Printed: 05.10.2026 20:26, 10.05.9:17:39 AM By: Raj, Shanthak  
ORIGINAL SHEET - ISCA [ 333301211 | lonastallon (vndro)'s card's dwst, 333301678-300 03-007-023

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings  
Ordnance Survey AC0000849896





Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing. Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

## Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

1. ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
2. TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
3. LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
4. FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

**KEY:**

- |                                                                                     |                |                                                                                     |                                   |
|-------------------------------------------------------------------------------------|----------------|-------------------------------------------------------------------------------------|-----------------------------------|
|  | ORDER LIMITS   |  | PROPOSED SOLID SURFACE WATER PIPE |
|  | EXISTING DITCH |  | PROPOSED FLOW CONTROL CHAMBER     |
|  | ACCESS TRACK   |  | PROPOSED HEADWALL                 |
|  | PROPOSED SWALE |  | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| P01 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | 2026.10.02 |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | YYYY.MM.DD |

### Issue Status

S2 - FOR INFORMATION


This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITES 8A/8B

|                          |                                            |
|--------------------------|--------------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                       |
| Revision<br><b>P01</b>   | Drawing No.<br><b>333101678-300.03-022</b> |



Printed: 05.10.2026 20:26, 10:05 9-17:49 AM By: Raj, Sharitak  
ORIGINAL SHEET - ISCA [ 3333012 ] | lonastallon@india'scad\dwst.333301678-300.03-007-023



Copyright Reserved

The Contractor shall verify and be responsible for all dimensions. DO NOT scale the drawing.  
Any errors or omissions shall be reported to Stantec without delay.  
The Copyrights to all designs and drawings are the property of Stantec.  
Reproduction or use for any purpose other than that authorised by Stantec is forbidden.

Notes

UTILITIES NOTE: The position of any existing public or private sewers, utility services, plant or apparatus shown on this drawing is believed to be correct, but no warranty to this is expressed or implied. Other such plant or apparatus may also be present but not shown. The Contractor is therefore advised to undertake their own investigation where the presence of any existing sewers, services, plant or apparatus may affect their operations.

- ALL DIMENSIONS ARE IN METRES UNLESS STATED OTHERWISE.
- TOPOGRAPHICAL SURVEY BASED ON DRAWING 66883NOLS-03 REV A, BY SURVEY SOLUTIONS, DATED 2024.10.04.
- LAYOUT TAKEN FROM DRAWING DRAWING EAST PYE SOLAR FARM, BY ISLAND GREEN POWER UK, DATED 19.11.2025. BESS LAYOUT BASED ON UPDATED LAYOUT 11.11.2025.
- FORM AND DEPTH OF ATTENUATION TO BE REFINED AT DETAILED DESIGN STAGE.

KEY:

- |                |                                   |
|----------------|-----------------------------------|
| ORDER LIMITS   | PROPOSED SOLID SURFACE WATER PIPE |
| EXISTING DITCH | PROPOSED FLOW CONTROL CHAMBER     |
| ACCESS TRACK   | PROPOSED HEADWALL                 |
| PROPOSED SWALE | FENCING                           |

UTILITIES KEY:

- |                      |                              |
|----------------------|------------------------------|
| Ex Elec 011kV oh     | Ex Comms BT Ducts            |
| Ex Elec 400kV oh     | Ex BT Overhead Lines         |
| Ex Elec Lv oh        | Ex Water                     |
| Ex Elec Lv           | Abandoned                    |
| Ex Elec 011kV        | Ex Comms Gigaclear           |
| Ex Gas Low Pressure  | Ex Gas Intermediate Pressure |
| Ex Gas High Pressure |                              |

|                 |      |       |            |
|-----------------|------|-------|------------|
| PD1 FIRST ISSUE | EE   | -     | 2026.10.02 |
| Issued/Revision | By   | Appd  | YYYY.MM.DD |
|                 | GD   | EE    | -          |
|                 | Dwn. | Dsgn. | Chkd.      |
|                 |      |       | 2026.10.02 |
|                 |      |       | YYYY.MM.DD |

Issue Status

S2 - FOR INFORMATION



This document is suitable only for the purpose noted above.  
Use of this document for any other purpose is not permitted.

Client/Project Logo

Client/Project  
EAST PYE SOLAR Ltd.

Title  
CONCEPT ACCESS TRACK DRAINAGE  
SITE 9

|                          |                                     |
|--------------------------|-------------------------------------|
| Project No.<br>333101678 | A1 Scale<br>AS SHOWN                |
| Revision<br>P01          | Drawing No.<br>333101678-300.03-023 |



01 SITE KEY PLANS  
023 NOT TO SCALE

02 SITE 9 PLAN  
023 1:1250

0 40 80 120 160 200m  
SCALE 1:2000

© Crown copyright and database rights 2024. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Ordnance Survey AC0000849896