



The Great Grid Upgrade

Sea Link

Sea Link

Volume 6: Environmental Information

Document Number 6.3.2.7.H

Part 2 Suffolk

Chapter 7

Appendix 2.7.H Preliminary Highway Impact Assessment

Planning Inspectorate Reference: EN020026

Version: B

February 2026

Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009 Regulation 5(2)(a)

nationalgrid

Page intentionally blank

Version History

Date	Issue	Status	Description / Changes
March 2025	A	Final	For DCO submission
February 2026	B	Final	Update to correct a few discrepancies in the table for S-RL1 and S-RJ1 (highlighted in blue)

2028 Future Baseline + Proposed Development (Worst-Case)

Ref	Receptor Type	Receptor	AM Development Peak (07:00-08:00)								AM Network Peak (08:00-09:00)							
			Baseline		Development		Total		% Increase		Baseline		Development		Total		% Increase	
			HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total
S-RL1	Road Link	A12 (south of A1094)	76	1,376	0	156	76	1,532	0.0%	11.3%	85	1,454	36	41	121	1,495	42.0%	2.8%
S-RL2	Road Link	A12 (between A1094 & B1121 Main Rd south junction)	69	976	0	123	69	1,099	0.0%	12.6%	80	1,118	21	25	101	1,143	26.3%	2.2%
S-RL3	Road Link	A12 (between B1121 Main Road junctions)	56	846	0	123	56	969	0.0%	14.5%	78	1,002	21	25	99	1,027	27.0%	2.5%
S-RL4	Road Link	A12 (north of B1121 Main Road northern junction)	62	866	0	123	62	989	0.0%	14.2%	71	1,031	21	25	92	1,056	29.4%	2.4%
S-RL5	Road Link	B1121 Main Road (east of A12)	8	232	0	107	8	339	0.0%	46.2%	13	350	20	21	33	371	157.4%	6.0%
S-RL6	Road Link	B1121 Main Road (south of B1119 Church Street)	10	215	0	15	10	230	0.0%	7.0%	13	427	1	3	14	430	7.4%	0.7%
S-RL7	Road Link	B1119 Church Street (east of B1121 Main Road)	6	200	0	15	6	215	0.0%	7.5%	6	272	1	3	7	275	16.1%	1.1%
S-RL8	Road Link	B1121 Aldeburgh Road (between A1094 and B1121 Saxmundham Road)	2	63	0	9	2	72	0.0%	14.2%	4	122	1	2	5	124	24.1%	1.6%
S-RL9	Road Link	B1121 Saxmundham Road (north of Grove Road)	1	41	0	9	1	50	0.0%	21.7%	4	118	1	2	5	120	24.1%	1.7%
S-RL10	Road Link	A1094 (between A12 and B1069 Snape Road)	23	697	0	139	23	836	0.0%	19.9%	21	737	22	29	43	766	106.2%	3.9%
S-RL11	Road Link	A1094 Aldeburgh Road (between B1069 Snape Road and B1122 Leiston Road)	8	225	0	41	8	266	0.0%	18.2%	11	347	12	17	23	364	105.3%	4.9%
S-RL12	Road Link	B1069 Snape Road (between A1094 Aldeburgh Road and Aldringham Lane)	19	527	0	139	19	666	0.0%	26.4%	18	516	22	29	40	545	124.9%	5.6%
S-RL13	Road Link	B1122 Leiston Road (between A1094 Aldeburgh Road and Aldringham Lane)	8	171	0	17	8	188	0.0%	9.9%	10	234	1	3	11	237	9.7%	1.3%
S-RJ1	Road Junction	A12/A1094 Junction	81	1,467	0	207	81	1,674	0.0%	14.1%	95	1,621	39	47	134	1,668	40.9%	2.9%
S-RJ2	Road Junction	A12/B1121 (South) Junction	70	1,004	0	177	70	1,180	0.0%	17.6%	81	1,186	31	36	112	1,221	38.4%	3.0%
S-RJ3	Road Junction	A12/B1119 Junction	57	1,077	0	123	57	1,200	0.0%	11.4%	82	1,312	21	25	103	1,337	25.7%	1.9%
S-RJ4	Road Junction	A12/B1121 (North) Junction	62	881	0	123	62	1,004	0.0%	14.0%	73	1,053	21	25	94	1,078	29.0%	2.4%
S-RJ5	Road Junction	A12/B1122 Junction	74	1,131	0	123	74	1,254	0.0%	10.9%	87	1,320	21	25	108	1,345	24.1%	1.9%
S-RJ6	Road Junction	B1121 Main Road/B1121 Church Hill Junction	12	251	0	107	12	358	0.0%	42.7%	13	472	20	21	33	493	148.5%	4.4%
S-RJ7	Road Junction	B1121 Main Road/B1119 Church St Signalised Junction	17	429	0	15	17	444	0.0%	3.5%	21	843	1	3	22	846	4.8%	0.4%
S-RJ8	Road Junction	B1121 Saxmundham Road/Grove Road/Mill Road Junction	2	49	0	9	2	58	0.0%	18.5%	4	133	1	2	5	135	24.1%	1.5%
S-RJ9	Road Junction	A1094 Aldeburgh Road/B1121 Aldeburgh Road Junction	24	747	0	139	24	886	0.0%	18.6%	25	840	22	29	47	869	88.5%	3.5%
S-RJ10	Road Junction	A1094 Aldeburgh Road/B1069 Snape Road Junction	25	737	0	139	25	876	0.0%	18.8%	28	843	22	29	50	872	78.7%	3.4%
S-RJ11	Road Junction	A1094/B1122 Leiston Road/Church Farm Road Roundabout	10	310	0	17	10	327	0.0%	5.5%	24	555	1	3	25	558	4.2%	0.5%
S-RJ12	Road Junction	B1122 Aldeburgh Road/B1353 Aldringham Lane Junction	15	378	0	0	15	378	0.0%	0.0%	19	715	0	0	19	715	0.0%	0.0%
S-RJ13	Road Junction	B1069 Leiston Road/B1353 Aldringham Lane Junction	20	581	0	0	20	581	0.0%	0.0%	17	696	0	0	17	696	0.0%	0.0%
S-RJ14	Road Junction	A1094/Sternfield Road/Church Road Junction	25	838	0	139	25	977	0.0%	16.6%	32	1,030	22	29	54	1,059	68.5%	2.8%

Values corrected from Version A. Note, the traffic and transport assessment remains unaffected, as this was originally based on these corrected figures.

Ref	Receptor Type	Receptor	PM Network Peak (17:00-18:00)								PM Development Peak (18:00-19:00)							
			Baseline		Development		Total		% Increase		Baseline		Development		Total		% Increase	
			HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total
S-RL1	Road Link	A12 (south of A1094)	25	1,322	17	21	42	1,343	68.4%	1.6%	9	755	0	155	9	910	0.0%	20.5%
S-RL2	Road Link	A12 (between A1094 & B1121 Main Rd south junction)	25	900	10	14	35	914	40.2%	1.5%	10	557	0	122	10	679	0.0%	21.9%
S-RL3	Road Link	A12 (between B1121 Main Road junctions)	25	719	10	14	35	732	40.2%	1.9%	9	415	0	122	9	537	0.0%	29.4%
S-RL4	Road Link	A12 (north of B1121 Main Road northern junction)	23	795	10	14	33	809	43.9%	1.7%	8	428	0	122	8	550	0.0%	28.5%
S-RL5	Road Link	B1121 Main Road (east of A12)	6	331	10	11	16	342	155.7%	3.3%	4	225	0	106	4	331	0.0%	47.2%
S-RL6	Road Link	B1121 Main Road (south of B1119 Church Street)	2	399	0	2	2	401	0.0%	0.5%	0	252	0	15	0	267	0.0%	6.0%
S-RL7	Road Link	B1119 Church Street (east of B1121 Main Road)	4	261	0	2	4	263	0.0%	0.8%	3	186	0	15	3	201	0.0%	8.1%
S-RL8	Road Link	B1121 Aldeburgh Road (between A1094 and B1121 Saxmundham Road)	3	89	0	1	3	90	0.0%	1.1%	0	87	0	8	0	95	0.0%	9.2%
S-RL9	Road Link	B1121 Saxmundham Road (north of Grove Road)	2	83	0	1	2	84	0.0%	1.2%	0	60	0	8	0	68	0.0%	13.3%
S-RL10	Road Link	A1094 (between A12 and B1069 Snape Road)	6	678	10	16	16	694	160.9%	2.4%	1	387	0	138	1	525	0.0%	35.6%
S-RL11	Road Link	A1094 Aldeburgh Road (between B1069 Snape Road and B1122 Leiston Road)	2	255	6	10	8	265	289.7%	3.9%	1	242	0	40	1	282	0.0%	16.5%
S-RL12	Road Link	B1069 Snape Road (between A1094 Aldeburgh Road and Aldringham Lane)	5	495	10	16	15	511	193.1%	3.2%	0	223	0	138	0	361	0.0%	62.0%
S-RL13	Road Link	B1122 Leiston Road (between A1094 Aldeburgh Road and Aldringham Lane)	6	217	1	3	7	220	16.8%	1.4%	3	127	0	17	3	144	0.0%	13.4%
S-RJ1	Road Junction	A12/A1094 Junction	26	1,438	19	25	44	1,463	71.5%	1.7%	9	809	0	205	9	1,014	0.0%	25.4%
S-RJ2	Road Junction	A12/B1121 (South) Junction	26	945	15	19	41	964	57.9%	2.0%	10	569	0	175	10	744	0.0%	30.8%
S-RJ3	Road Junction	A12/B1119 Junction	26	869	10	14	36	882	38.6%	1.6%	9	534	0	122	9	656	0.0%	22.8%
S-RJ4	Road Junction	A12/B1121 (North) Junction	25	822	10	14	35	836	40.2%	1.6%	8	442	0	122	8	564	0.0%	27.6%
S-RJ5	Road Junction	A12/B1122 Junction	22	1,032	10	14	32	1,045	46.0%	1.3%	16	571	0	122	16	693	0.0%	21.4%
S-RJ6	Road Junction	B1121 Main Road/B1121 Church Hill Junction	5	418	10	11	15	429	193.1%	2.6%	0	268	0	106	0	374	0.0%	39.5%
S-RJ7	Road Junction	B1121 Main Road/B1119 Church St Signalised Junction	6	861	0	2	6	863	0.0%	0.2%	2	598	0	15	2	613	0.0%	2.5%
S-RJ8	Road Junction	B1121 Saxmundham Road/Grove Road/Mill Road Junction	2	96	0	1	2	97	0.0%	1.0%	0	69	0	8	0	77	0.0%	11.5%
S-RJ9	Road Junction	A1094 Aldeburgh Road/B1121 Aldeburgh Road Junction	8	753	10	16	18	769	120.7%	2.1%	1	458	0	138	1	596	0.0%	30.1%
S-RJ10	Road Junction	A1094 Aldeburgh Road/B1069 Snape Road Junction	7	742	10	16	17	758	137.9%	2.2%	1	452	0	138	1	590	0.0%	30.6%
S-RJ11	Road Junction	A1094/B1122 Leiston Road/Church Farm Road Roundabout	5	448	1	3	6	451	19.3%	0.7%	4	323	0	17	4	340	0.0%	5.3%
S-RJ12	Road Junction	B1122 Aldeburgh Road/B1353 Aldringham Lane Junction	9	503	0	0	9	503	0.0%	0.0%	2	361	0	0	2	361	0.0%	0.0%
S-RJ13	Road Junction	B1069 Leiston Road/B1353 Aldringham Lane Junction	6	590	0	0	6	590	0.0%	0.0%	0	295	0	0	0	295	0.0%	0.0%
S-RJ14	Road Junction	A1094/Sternfield Road/Church Road Junction	10	880	10	16	20	896	96.6%	1.8%	1	498	0	138	1	636	0.0%	27.7%

Values corrected from Version A. Note, the traffic and transport assessment remains unaffected, as this was originally based on these corrected figures.

Ref	Receptor Type	Receptor	12 Hours (07:00-19:00)								24hr Daily							
			Baseline		Development		Total		% Increase		Baseline		Development		Total		% Increase	
			HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total
S-RL1	Road Link	A12 (south of A1094)	737	13,177	303	539	1,039	13,716	41.1%	4.1%	825	14,759	303	539	1,127	15,298	36.7%	3.6%
S-RL2	Road Link	A12 (between A1094 & B1121 Main Rd south junction)	654	9,774	178	364	832	10,138	27.2%	3.7%	732	10,947	178	364	910	11,311	24.3%	3.3%
S-RL3	Road Link	A12 (between B1121 Main Road junctions)	608	8,718	178	364	786	9,082	29.3%	4.2%	677	9,124	178	364	855	9,488	26.3%	4.0%
S-RL4	Road Link	A12 (north of B1121 Main Road northern junction)	582	9,063	178	364	760	9,427	30.6%	4.0%	651	10,171	178	364	829	10,535	27.3%	3.6%
S-RL5	Road Link	B1121 Main Road (east of A12)	123	4,023	176	310	299	4,333	143.3%	7.7%	108	4,247	176	310	284	4,557	162.5%	7.3%
S-RL6	Road Link	B1121 Main Road (south of B1119 Church Street)	99	3,905	4	50	103	3,955	4.1%	1.3%	87	4,126	4	50	91	4,176	4.6%	1.2%
S-RL7	Road Link	B1119 Church Street (east of B1121 Main Road)	78	2,756	4	50	82	2,806	5.1%	1.8%	71	2,979	4	50	75	3,029	5.6%	1.7%
S-RL8	Road Link	B1121 Aldeburgh Road (between A1094 and B1121 Saxmundham Road)	30	979	4	24	34	1,003	13.5%	2.5%	27	1,080	4	24	31	1,104	14.8%	2.2%
S-RL9	Road Link	B1121 Saxmundham Road (north of Grove Road)	22	885	4	24	26	909	17.8%	2.7%	18	891	4	24	22	915	22.2%	2.7%
S-RL10	Road Link	A1094 (between A12 and B1069 Snape Road)	218	6,402	180	418	398	6,820	82.7%	6.5%	200	7,062	180	418	380	7,480	90.2%	5.9%
S-RL11	Road Link	A1094 Aldeburgh Road (between B1069 Snape Road and B1122 Leiston Road)	86	3,528	96	218	182	3,746	111.9%	6.2%	95	4,034	96	218	191	4,252	100.7%	5.4%
S-RL12	Road Link	B1069 Snape Road (between A1094 Aldeburgh Road and Aldringham Lane)	156	5,245	180	418	336	5,663	115.4%	8.0%	173	5,997	180	418	353	6,415	103.8%	7.0%
S-RL13	Road Link	B1122 Leiston Road (between A1094 Aldeburgh Road and Aldringham Lane)	126	2,581	10	64	136	2,645	8.0%	2.5%	105	2,642	10	64	115	2,706	9.5%	2.4%
S-RJ1	Road Junction	A12/A1094 Junction	792	14,421	330	653	1,122	15,073	41.6%	4.5%	887	16,152	330	653	1,217	16,804	37.2%	4.0%
S-RJ2	Road Junction	A12/B1121 (South) Junction	670	10,204	266	519	936	10,723	39.7%	5.1%	750	11,428	266	519	1,016	11,947	35.5%	4.5%
S-RJ3	Road Junction	A12/B1119 Junction	627	11,317	178	364	805	11,681	28.4%	3.2%	695	11,370	178	364	873	11,734	25.6%	3.2%
S-RJ4	Road Junction	A12/B1121 (North) Junction	603	9,296	178	364	781	9,660	29.5%	3.9%	674	10,433	178	364	852	10,797	26.4%	3.5%
S-RJ5	Road Junction	A12/B1122 Junction	692	11,497	178	364	870	11,861	25.7%	3.2%	774	12,903	178	364	952	13,267	23.0%	2.8%
S-RJ6	Road Junction	B1121 Main Road/B1121 Church Hill Junction	118	4,244	176	310	294	4,554	149.1%	7.3%	104	4,482	176	310	280	4,792	169.1%	6.9%
S-RJ7	Road Junction	B1121 Main Road/B1119 Church St Signalised Junction	169	8,337	4	50	173	8,387	2.4%	0.6%	149	8,817	4	50	153	8,867	2.7%	0.6%
S-RJ8	Road Junction	B1121 Saxmundham Road/Grove Road/Mill Road Junction	25	1,022	4	24	29	1,046	16.2%	2.3%	20	1,028	4	24	24	1,052	20.2%	2.3%
S-RJ9	Road Junction	A1094 Aldeburgh Road/B1121 Aldeburgh Road Junction	242	7,210	180	418	422	7,628	74.5%	5.8%	222	7,953	180	418	402	8,371	81.2%	5.3%
S-RJ10	Road Junction	A1094 Aldeburgh Road/B1069 Snape Road Junction	234	8,600	180	418	414	9,018	76.9%	4.9%	260	9,832	180	418	440	10,250	69.2%	4.3%
S-RJ11	Road Junction	A1094/B1122 Leiston Road/Church Farm Road Roundabout	135	5,385	10	64	145	5,449	7.4%	1.2%	150	6,157	10	64	160	6,221	6.7%	1.0%
S-RJ12	Road Junction	B1122 Aldeburgh Road/B1353 Aldringham Lane Junction	172	5,719	0	0	172	5,719	0.0%	0.0%	144	5,875	0	0	144	5,875	0.0%	0.0%
S-RJ13	Road Junction	B1069 Leiston Road/B1353 Aldringham Lane Junction	152	4,966	0	0	152	4,966	0.0%	0.0%	135	5,139	0	0	135	5,139	0.0%	0.0%
S-RJ14	Road Junction	A1094/Sternfield Road/Church Road Junction	304	8,533	180	418	484	8,951	59.3%	4.9%	278	9,410	180	418	458	9,828	64.7%	4.4%

Values corrected from Version A. Note, the traffic and transport assessment remains unaffected, as this was originally based on these corrected figures.

Ref	Receptor Type	Receptor	Saturday (12:00-13:00)							
			Baseline		Development		Total		% Increase	
			HGVs	Total	HGVs	Total	HGVs	Total	HGVs	Total
S-RL1	Road Link	A12 (south of A1094)	13	1,376	37	43	51	1,419	277.2%	3.1%
S-RL2	Road Link	A12 (between A1094 & B1121 Main Rd south junction)	10	1,019	22	27	32	1,046	212.0%	2.6%
S-RL3	Road Link	A12 (between B1121 Main Road junctions)	9	847	22	27	31	873	235.6%	3.1%
S-RL4	Road Link	A12 (north of B1121 Main Road northern junction)	8	847	22	27	30	873	265.0%	3.1%
S-RL5	Road Link	B1121 Main Road (east of A12)	7	426	22	23	29	449	326.1%	5.4%
S-RL6	Road Link	B1121 Main Road (south of B1119 Church Street)	2	400	1	3	3	403	48.2%	0.8%
S-RL7	Road Link	B1119 Church Street (east of B1121 Main Road)	6	282	1	3	7	285	17.5%	1.1%
S-RL8	Road Link	B1121 Aldeburgh Road (between A1094 and B1121 Saxmundham Road)	1	76	1	2	2	78	96.4%	2.6%
S-RL9	Road Link	B1121 Saxmundham Road (north of Grove Road)	1	65	1	2	2	67	96.4%	3.1%
S-RL10	Road Link	A1094 (between A12 and B1069 Snape Road)	5	858	22	30	27	888	424.0%	3.5%
S-RL11	Road Link	A1094 Aldeburgh Road (between B1069 Snape Road and B1122 Leiston Road)	2	520	12	18	14	538	578.2%	3.5%
S-RL12	Road Link	B1069 Snape Road (between A1094 Aldeburgh Road and Aldringham Lane)	4	432	22	30	26	462	530.0%	6.9%
S-RL13	Road Link	B1122 Leiston Road (between A1094 Aldeburgh Road and Aldringham Lane)	7	239	2	5	9	244	29.6%	2.1%
S-RJ1	Road Junction	A12/A1094 Junction	15	1,566	41	49	55	1,615	280.1%	3.2%
S-RJ2	Road Junction	A12/B1121 (South) Junction	10	1,051	33	38	43	1,089	318.0%	3.6%
S-RJ3	Road Junction	A12/B1119 Junction	9	1,054	22	27	31	1,081	235.6%	2.5%
S-RJ4	Road Junction	A12/B1121 (North) Junction	8	883	22	27	30	910	265.0%	3.0%
S-RJ5	Road Junction	A12/B1122 Junction	7	1,133	22	27	29	1,160	302.9%	2.3%
S-RJ6	Road Junction	B1121 Main Road/B1121 Church Hill Junction	3	425	22	23	25	448	706.7%	5.4%
S-RJ7	Road Junction	B1121 Main Road/B1119 Church St Signalised Junction	4	910	1	3	5	913	24.1%	0.3%
S-RJ8	Road Junction	B1121 Saxmundham Road/Grove Road/Mill Road Junction	1	72	1	2	2	74	96.4%	2.8%
S-RJ9	Road Junction	A1094 Aldeburgh Road/B1121 Aldeburgh Road Junction	6	930	22	30	28	960	353.3%	3.2%
S-RJ10	Road Junction	A1094 Aldeburgh Road/B1069 Snape Road Junction	6	938	22	30	28	968	353.3%	3.2%
S-RJ11	Road Junction	A1094/B1122 Leiston Road/Church Farm Road Roundabout	3	703	2	5	5	708	64.2%	0.7%
S-RJ12	Road Junction	B1122 Aldeburgh Road/B1353 Aldringham Lane Junction	4	500	0	0	4	500	0.0%	0.0%
S-RJ13	Road Junction	B1069 Leiston Road/B1353 Aldringham Lane Junction	4	477	0	0	4	477	0.0%	0.0%
S-RJ14	Road Junction	A1094/Sternfield Road/Church Road Junction	6	1,091	22	30	28	1,121	353.3%	2.8%

Values corrected from Version A. Note, the traffic and transport assessment remains unaffected, as this was originally based on these corrected figures.

Page intentionally blank

National Grid plc
National Grid House,
Warwick Technology Park,
Gallows Hill, Warwick.
CV34 6DA United Kingdom

Registered in England and Wales
No. 4031152
nationalgrid.com