

AENC-NG-CNS-REP-0242

# Norwich to Tilbury

**Volume 8: Examination Documents**

**Document: 8.3.26 Signed Statement of Common Ground -  
Cadent Gas - Tracked Changes Version**

**Final Issue C**

**July 2026**

**Planning Inspectorate Reference: EN020027**

**nationalgrid**

# Revision History

| Version  | Date                | Submitted at      |
|----------|---------------------|-------------------|
| A        | 26 February 2026    | Deadline 1        |
| B        | 12 May 2026         | Deadline 4        |
| <u>C</u> | <u>21 July 2026</u> | <u>Deadline 7</u> |

# Cadent Gas

## ~~Draft~~ Statement of Common Ground

### 1. Purpose of the Statement of Common Ground

This Statement of Common Ground (SoCG) has been prepared to ~~outline the areas of~~confirm to the Examining Authority where agreement ~~and any remaining points of discussion~~has been reached and where agreement has not been reached between National Grid and Cadent Gas Limited (Cadent) regarding specific issues arising during construction and/or operation from the interface between the proposed Norwich to Tilbury Project and Cadent assets.

~~The aim is to clarify the shared understanding of any issues and facilitate an efficient resolution process.~~

This final signed version of the SoCG has been submitted at Examination Deadline 7.

### 2. Parties to the SoCG

This SoCG ~~is agreed between~~has been prepared by National Grid and Cadent Gas Limited.

### 3. Background

#### 3.1 Description of the Project/Development

National Grid Electricity Transmission plc ('National Grid') owns and maintains the national high voltage electricity transmission network throughout England and Wales. The transmission network connects the power from where it is generated to the regional Distribution Network Operators who then supply businesses and homes.

National Grid holds the Transmission Licence for England and Wales, and its statutory duty is to develop and maintain an efficient, coordinated and economical system of electricity transmission and to facilitate competition in the generation and supply of electricity, as set out in the Electricity Act 1989.

National Grid has developed plans for Norwich to Tilbury (referred to as the 'Project'). The Project would support the UK's net zero target through the connection of new low carbon energy generation in East Anglia and by reinforcing the transmission network.

The Project comprises reinforcement of the transmission network between the existing Norwich Main Substation in Norfolk and Tilbury Substation in Essex, via Bramford Substation, the new East Anglia Connection Node (EACN) Substation and the new Tilbury North Substation.

The reinforcement is needed because the existing transmission network, even with current upgrading, will not have sufficient capacity for the new renewable energy (a substantial proportion of which would be generated by offshore wind) that is expected to connect to the network over the next 10 years and beyond. Completion of the Project, together with other new reinforcements across the country, will meet this future energy transmission demand both in East Anglia and across the UK.

The Project is a Nationally Significant Infrastructure Project (NSIP), and National Grid is seeking development consent under statutory procedures set by government. NSIPs are projects of certain types, over a certain size, which are considered by the government to be of national importance, hence permission to build them needs to be given at a national level, by the relevant Secretary of State (in this case the Secretary of State for Energy Security and Net Zero). Instead of applying to the local authority for planning permission, the developer must apply to the Planning Inspectorate for a Development Consent Order (DCO) that would grant development consent.

National Grid has submitted an application for development consent to the Planning Inspectorate. The Examining Authority (consisting of five examining inspectors), after a period of public examination, will make their recommendation to the Secretary of State for Energy Security and Net Zero, who in turn will decide on whether development consent should be granted for the Project.

The Project is identified as critical to delivering a network which supports the clean power pathways for 2030 delivery.

The Planning Act 2008 places duties on National Grid as the DCO applicant to consult with prescribed or affected persons as well as to take account of responses to consultation and publicity. In accordance with these statutory requirements, National Grid has undertaken two non-statutory and one statutory consultation to inform its proposals, with further targeted consultations.

## **4. Stakeholder Interests**

Cadent has ~~legitimate~~legal interests that interact with the Norwich to Tilbury proposals. This has been identified as the network of Cadent underground assets.

National Grid is seeking to ensure that the interests of both parties and how they may be affected by the interaction are understood. From this position the aim is for the parties to agree actions to avoid or reduce the implications and for any remedial measures to be agreed. On this basis we seek the input from Cadent to demonstrate how their interests may be affected, how Cadent or National Grid and its contractors can collectively reduce those effects and input to agree the implementation of such measures.

National Grid and Cadent have identified approximately 175 physical interactions between Norwich to Tilbury and Cadent Assets. These interactions and ~~Cadent's~~Cadent's associated requests for mitigation are categorised below by the nature of the interaction. Any site-specific interaction requests are to be defined further to the below crossing categorisations through continued detailed design and engagement.

The chronology of National Grid's engagement with Cadent to date, and the evolution of the Project's design is summarised as follows:

- 2023
  - Introductory meeting to detail the proposed Norwich to Tilbury scheme and project team members
- 2024
  - Engagement on anticipated impacts to existing Cadent assets
  - Meeting to discuss and agree AC Interference study methodologies and provision of pipeline data
  - Cabling interactions focused meeting
  - Updates to the crossing interactions following Statutory Consultation
  - Initiation of Protective Provisions discussions
- 2025
  - Discussion following issuance of Norwich to Tilbury Scoping Document encompassing all project interactions.
  - Further discussion on studies outcome of AC Interference impacts to Cadent assets.
  - Further engagement on Protective Provision discussions
  - Initial development of items to be included within the Statement of Common Ground.
- 2026
  - Further engagement on Protective Provision discussions.
  - Further development of the draft Statement of Common Ground.

1-3 Strand  
London WC2N 5EH

T: +44 (0)20 7004 3000  
www.nationalgrid.com

## 5. Matters Agreed

| ID         | Issue                        | Agreement reached                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Date agreed                     | Relevant documentation                                  |
|------------|------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------|---------------------------------------------------------|
| 5.1        | <u>Asset Interactions</u>    | <p><u>All proposed Norwich to Tilbury interactions with existing Cadent Gas assets are subject to a Retained Apparatus Protection Clause as denoted within the agreed Protective Provisions submitted as part of the Draft Development Consent Order Schedule 16 Part 8 at Deadline 5. National Grid and Cadent Gas throughout the examination window have assessed and derisked the various site specific crossings including:</u></p> <ul style="list-style-type: none"> <li><u>• Bellmouth Junctions</u></li> <li><u>• Trackway</u></li> <li><u>• Haul Road</u></li> <li><u>• Stringing Position</u></li> <li><u>• Crossing Protection</u></li> <li><u>• Construction Laydown Areas</u></li> <li><u>• Overhead Line Areas</u></li> <li><u>• 400kV Underground Cable</u></li> <li><u>• Permanent Access</u></li> <li><u>• Pylon Working Area</u></li> <li><u>• Outfall Working Area</u></li> <li><u>• UKPN Works</u></li> </ul> | <u>7<sup>th</sup> July 2026</u> | <u>3.1 Draft DCO Revision F Tracked Changes Version</u> |
| <u>5.2</u> | <u>Protective Provisions</u> | <u>Protective Provisions have been agreed between both parties and submitted within the Draft Development Consent Order Schedule 16 Part 8 at Deadline 5.</u>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <u>7<sup>th</sup> July 2026</u> | <u>3.1 Draft DCO Revision F Tracked Changes Version</u> |

## 6. Matters Currently Under Discussion

| ID  | Issue              | Stakeholder position                                                                                                                                                  | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Relevant documentation |
|-----|--------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
| 6.1 | Bellmouth Junction | 17/02/26 – Cadent require RAMS to be provided prior to works start. Additionally the plant protection team may be required to attend on site during excavation works. | 28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG. RAMS will be provided prior to start of works. Reasonable notice period can be provided to Cadent so as to allow on-site supervision during excavation works.<br><br>The Bellmouth Junction Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation. |                        |
| 6.2 | Trackway           | 17/02/26 – Further engagement required to detail Cadents position towards Trackway interactions with Cadent assets.                                                   | 28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation                                                                                                                                                                                                                                                                                                            |                        |

1-3 Strand  
London WC2N 5EH

T: +44 (0)20 7004 3000  
www.nationalgrid.com



| ID  | Issue              | Stakeholder position                                                                                                                                                                                                                                                          | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Relevant documentation |
|-----|--------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
| 6.3 | Haul Road Crossing | 17/02/26 — Further engagement required to detail Cadent's position towards haul road crossing interactions with Cadent assets.                                                                                                                                                | 28/04/26 — National Grid's detailed design partners have engaged with Cadent to further define the site-specific crossing conditions with the intention of appending these site-specific conditions to the final SoCG.<br><br>The Haul Road Crossing Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation                                                                                                   |                        |
| 6.4 | Stringing Position | 17/02/26 — Demarcation of the pipeline within the stringing position is required and the earth protection zone must be built away from the pipe. No equipment or materials is to be stored atop the demarcated easement usually 3m either side of the pipeline but can be 6m. | 28/04/26 — National Grid's detailed design partners have engaged with Cadent to further define the site-specific crossing conditions with the intention of appending these site-specific conditions to the final SoCG.<br>National Grid commit to demarcating pipelines located within stringing positions where applicable.<br>The Stringing Position Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation |                        |
| 6.5 | Crossing           | 17/02/26 — National Grid should                                                                                                                                                                                                                                               | 28/04/26 — National Grid's detailed design partners have                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                        |

| ID  | Issue                | Stakeholder position                                                                                                                                                                                                                                                                                                                                                                                                            | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Relevant documentation |
|-----|----------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
|     | Protection           | <p>bridge over the pipeline with the scaffolding ensuring to avoid Cadents easement width.</p> <p>RAMS are to be submitted and supervision required for construction of scaffolding.</p> <p>For anchors, Cadent could consider reduced clearance if required.</p> <p>While not currently envisaged, the requirement for bearing calculations on the asset may be requested by Cadents Civil team subject to further review.</p> | <p>engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.</p> <p>RAMS will be provided prior to start of works.</p> <p>Reasonable notice period can be provided to Cadent so as to allow on-site supervision during excavation works.</p> <p>Where able National Grid will attempt to bridge over the scaffolding to avoid the Cadent easement for installation of screw anchors.</p> <p>The Crossing Protection Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.</p> <p>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation</p> |                        |
| 6.6 | Construction Laydown | <p>17/02/26 — National Grid are required to demarcate the pipe, fence off and avoid the easement.</p> <p>No storage is permitted atop Cadents assets.</p> <p>Where required by Cadent trackway crossing points are to be installed.</p> <p>RAMS are to be submitted to the local plant protection team in advance of works commencement.</p>                                                                                    | <p>28/04/26 — National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.</p> <p>National Grid commit to demarcating pipelines located where applicable.</p> <p>National Grid can commit to demarcating the pipeline within the laydown areas where applicable in addition to providing RAMS where required by Cadent.</p>                                                                                                                                                                                                                                                                                         |                        |

| ID  | Issue                            | Stakeholder position                                                                                                                                                                                                              | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Relevant documentation |
|-----|----------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
|     |                                  |                                                                                                                                                                                                                                   | <p>The Construction Laydown methodology has since been provided to Cadent to facilitate the review of proposed interactions.</p> <p>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation</p>                                                                                                                                                                                                                                                                                                                                              |                        |
| 6.7 | Overhead Line Crossing           | <p>17/02/26 – During stringing it is understood the bonds will be pulled out with a vehicle, e.g. ATV.</p> <p>Cadent require an agreed crossing point and adequate protection against rutting to avoid a reduced depth cover.</p> | <p>28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.</p> <p>National Grid will agree with Cadent a defined crossing point and adequate protection as required.</p> <p>The Overhead Line Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.</p> <p>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation</p> |                        |
| 6.8 | 400kV Underground Cable Crossing | <p>17/02/26 – Trial holes will need to be booked with Cadent for these works as the results will be required to feed into the design.</p> <p>A minimum of 600m separation is</p>                                                  | <p>28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.</p>                                                                                                                                                                                                                                                                                                                                                                          |                        |

| ID   | Issue            | Stakeholder position                                                                                                                                                                                                                                                                                                                                                                                       | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Relevant documentation |
|------|------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
|      |                  | <p>required between existing and proposed assets.</p> <p>On site supervision required and if a weld is exposed then Cadent will need to inspect the weld to monitor coating damage and stress state of the pipe when excavated.</p> <p>It is recommended for National Grid to start engaging at least 12 months in advance of these crossings as the local operations team will need to be planned in.</p> | <p>National Grid will continue to liaise with Cadent to arrange trial holes to determine asset locations.</p> <p>600mm separation requirement is noted, a National Grid position will be provided upon further consideration.</p> <p>Reasonable notice period can be provided to Cadent so as to allow on-site supervision during excavation works.</p> <p>National Grid note the timeframe requirements for engagement with Cadent local operations teams.</p> <p>The 400kV Underground Cable Crossing Construction Methodology has since been provided to Cadent to facilitate the review of proposed interactions.</p> <p>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation</p> |                        |
| 6.9  | Permanent Access | 17/02/26 – Further engagement required to detail Cadents position towards permanent access interactions with Cadent assets.                                                                                                                                                                                                                                                                                | <p>28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific crossing conditions with the intention of appending these site specific conditions to the final SoCG.</p> <p>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation</p>                                                                                                                                                                                                                                                                                                                                                                                              |                        |
| 6.10 | Pylon            | 17/02/26 – Further engagement required to detail Cadents position                                                                                                                                                                                                                                                                                                                                          | 28/04/26 – National Grids detailed design partners have engaged with Cadent to further define the site specific                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                        |

1-3 Strand  
London WC2N 5EH

T: +44 (0)20 7004 3000  
www.nationalgrid.com

| ID   | Issue                    | Stakeholder position                                                                                                                                                                                                                    | National Grid response                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | Relevant documentation |
|------|--------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
|      | Working Area             | towards pylon working areas-<br>interactions with Cadent assets.                                                                                                                                                                        | crossing conditions with the intention of appending these<br>site-specific conditions to the final SoCG.<br><br>The Pylon Working Area Construction Methodology has<br>since been provided to Cadent to facilitate the review of<br>proposed interactions.<br><br>Crossing of Cadent assets will be further governed by<br>clauses within the Protective Provisions under negotiation                                                                                                                                                                                                                                                                                                     |                        |
| 6.11 | Outfall-<br>Working Area | 17/02/26 – Trial holes will need to be<br>booked with Cadent for these works<br>as the results will be required to feed<br>into the design.<br><br>A minimum of 600m separation is<br>required between existing and<br>proposed assets. | 28/04/26 – National Grids detailed design partners have<br>engaged with Cadent to further define the site-specific<br>crossing conditions with the intention of appending these<br>site-specific conditions to the final SoCG.<br><br>The request for trial holes and 600mm separation distance<br>at outfall working areas is noted and National Grid will<br>provide a position upon further assessment.<br><br>The Outfall Working Area Construction Methodology has<br>since been provided to Cadent to facilitate the review of<br>proposed interactions.<br><br>Crossing of Cadent assets will be further governed by<br>clauses within the Protective Provisions under negotiation |                        |
| 6.12 | UKPN                     | 17/02/26 – Further engagement                                                                                                                                                                                                           | 28/04/26 – UKPN will engage directly with Cadent to agree                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |                        |

| ID   | Issue                                 | Stakeholder position                                                                                                                       | National Grid response                                                                                                                                                                                                                                                                              | Relevant documentation |
|------|---------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------|
|      | Overhead-Line Wood-Pole-Dismantling   | required to detail Cadents position towards UKPN overhead line wood pole dismantling interactions with Cadent assets.                      | crossing conditions in relation to the UKPN component of the Norwich to Tilbury DCO.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation.                                                                                       |                        |
| 6.13 | UKPN-Overhead-Tower-Dismantling       | 17/02/26 – Further engagement required to detail Cadents position towards UKPN overhead tower dismantling interactions with Cadent assets. | 28/04/26 – UKPN will engage directly with Cadent to agree crossing conditions in relation to the UKPN component of the Norwich to Tilbury DCO.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation.                             |                        |
| 6.14 | UKPN Cable Crossing                   | 17/02/26 – Further engagement required to detail Cadents position towards UKPN cable crossing interactions with Cadent assets.             | 28/04/26 – UKPN will engage directly with Cadent to agree crossing conditions in relation to the UKPN component of the Norwich to Tilbury DCO.<br><br>Crossing of Cadent assets will be further governed by clauses within the Protective Provisions under negotiation.                             |                        |
| 6.15 | Alternating Current (AC) Interference | 17/02/26 – Further engagement required to detail Cadents position towards AC Interference interactions with Cadent assets.                 | 17/02/26 – Methodology of the modelling has been agreed with Cadent in advance of undertaking the studies.<br>Engagement on the AC Interference impacts and subsequent mitigation requirements is ongoing.<br>A revised AC interference study has now been issued to Cadent for review and comment. |                        |

1-3 Strand  
London WC2N 5EH

T: +44 (0)20 7004 3000  
www.nationalgrid.com



| <b>ID</b> | <b>Issue</b>                                 | <b>Stakeholder position</b>                                                                                                       | <b>National Grid response</b>                                                                                                                                                                                                                                                                                                                                                                                                                                 | <b>Relevant documentation</b> |
|-----------|----------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------|
|           |                                              |                                                                                                                                   | National Grid are also progressing an outline mitigation design report to submit to Cadent detailing the extent of AC interference mitigations.                                                                                                                                                                                                                                                                                                               |                               |
| 6.16      | Protective Provisions                        |                                                                                                                                   | 20/04/26 – National Grid and Cadent Water have made substantial progress towards agreeing a set of bespoke protective provisions.<br>National Grid reiterates it's intent to include a set of agreed protective provisions within the draft DCO at the earliest opportunity to do so.                                                                                                                                                                         |                               |
| <u>ID</u> | <u>Issue</u>                                 | <u>Stakeholder position</u>                                                                                                       | <u>National Grid response</u>                                                                                                                                                                                                                                                                                                                                                                                                                                 | <u>Relevant documentation</u> |
| 6.1       | <u>Alternating Current (AC) Interference</u> | <u>17/02/26 - Further engagement required to detail Cadents position towards AC Interference interactions with Cadent assets.</u> | <u>Methodology of the modelling has been agreed with Cadent in advance of undertaking the studies. Engagement on the AC Interference impacts and subsequent mitigation requirements is ongoing.</u><br><u>A revised AC interference study has now been issued to Cadent for review and comment.</u><br><u>National Grid are also progressing an outline mitigation design report to submit to Cadent detailing the extent of AC interference mitigations.</u> |                               |


1-3 Strand  
London WC2N 5EH

T: +44 (0)20 7004 3000  
www.nationalgrid.com



7. Signatures


This Statement of Common Ground is agreed upon by the undersigned parties:

For National Grid 

Name: 

Position: Project Director

Date: 17/07/2026

For Cadent Gas Limited 

Name: 

Position: Senior Integrity Engineer

Date: 16/07/2026

National Grid plc  
National Grid House,  
Warwick Technology Park,  
Gallows Hill, Warwick.  
CV34 6DA United Kingdom

Registered in England and Wales  
No. 4031152  
[nationalgrid.com](http://nationalgrid.com)

|                                                                                                                                |           |
|--------------------------------------------------------------------------------------------------------------------------------|-----------|
| <b>Summary report:</b><br><b>Litera Compare for Word 11.16.0.74 Document comparison done on</b><br><b>7/15/2026 1:42:31 PM</b> |           |
| <b>Style name:</b> Default Style                                                                                               |           |
| <b>Intelligent Table Comparison:</b> Active                                                                                    |           |
| <b>Original filename:</b> 8.3.26 Draft Statement of Common Ground - Cadent Gas Revision B Clean Version.docx                   |           |
| <b>Modified filename:</b> 8.3.26 Signed Statement of Common Ground - Cadent Gas Revision C Clean Version.docx                  |           |
| <b>Changes:</b>                                                                                                                |           |
| <u>Add</u>                                                                                                                     | 34        |
| <del>Delete</del>                                                                                                              | 7         |
| <del>Move From</del>                                                                                                           | 0         |
| <u>Move To</u>                                                                                                                 | 0         |
| <u>Table Insert</u>                                                                                                            | 3         |
| <del>Table Delete</del>                                                                                                        | 1         |
| <u>Table moves to</u>                                                                                                          | 0         |
| <del>Table moves from</del>                                                                                                    | 0         |
| Embedded Graphics (Visio, ChemDraw, Images etc.)                                                                               | 0         |
| Embedded Excel                                                                                                                 | 0         |
| Format changes                                                                                                                 | 0         |
| <b>Total Changes:</b>                                                                                                          | <b>45</b> |