

AENC-NG-CNS-REP-0356

Norwich to Tilbury

Volume 8: Examination Documents

Document: 8.21 Detailed Written Scheme of Investigation:
Mitigation Areas 124, 136 (a & b), 137, 138, 141 & 142
- Tracked Changes Version

Final Issue B

July 2026

Planning Inspectorate Reference: EN020027

nationalgrid

Revision History

<u>Version</u>	<u>Date</u>	<u>Submitted at</u>
<u>A</u>	<u>10 June 2026</u>	<u>Deadline 5</u>
<u>B</u>	<u>21 July 2026</u>	<u>Deadline 7</u>

Contents

Executive summary	1
1. Introduction	2
1.1 Statement of Works Required	2
1.2 Site Description	2
1.3 Site Location	4
1.4 Standards and Guidance	4
1.5 Project Roles	5
2. Archaeological and Historical Background	7
2.1 Geology and Topography	7
2.2 Previous Investigations and Archaeological Background	7
3. Scope of Works	9
3.1 Introduction	9
3.2 Archaeological Detailed Excavation Areas	9
4. Aims and Objectives Overview	1013
4.1 Research Agenda	10 13
4.2 Mapping to East of England Regional Research Framework (EERRF)	11 14
5. Standards for Archaeological Work	1316
5.1 Standards for archaeological work	13 16
5.2 Detailed Excavation	14 17
5.3 Environmental Sampling and Scientific Dating	15 18
5.4 Finds Processing, Conservation and Human Remains	16 19
5.5 Communication, Monitoring, and Sign-Off	19 21
5.6 Post-Excavation, Reporting and Archiving	20 22
5.7 Public Outreach and Dissemination	20 23
6. Programme, staffing and attendance	2124
6.1 Initial timetable and staffing	21 24
7. Health, Safety, Security and Environment (HSSE)	2225

Table 3.1	The Rationale for each Mitigation Area.	10
Table 4.1	Alignment with Regional Research Agendas	11 14

Abbreviations	24 27
Glossary	25 28
Bibliography	26 29

Appendix A Figures

Figure 1: Location of Mitigation Areas 124, 136a&b, 137, 138, 141, 142

Figure 2a: Mitigation Area ~~136b, 141, and~~ 142 over Trial Trench Locations

Figure 2b: Mitigation Areas [141 and 136a over Trial Trench Locations](#)

[Figure 2c: Mitigation Area](#) 136a and 137 over Trial Trench Locations

Figure ~~2c~~[2d](#): Mitigation Area 138 over Trial Trench Locations

Figure ~~2d~~[2e](#): Mitigation Area 124 over Trial Trench Locations

Figure 3a: Mitigation Areas 136a&b, 137, 141, 142 over the Geophysical Interpretation

Figure 3b: Mitigation Areas 137 and 138 over the Geophysical Interpretation

Figure 3c: Mitigation Area 124 over the Geophysical Interpretation

Figure 4: Mitigation Areas 124, 136a&b, 137, 138, 141, 142 over Cropmark Data

Executive summary

This Detailed Written Scheme of Investigation (DWSI) sets out the archaeological mitigation requirements for mitigation areas 124, 136a, 136b, 137, 138, 141, and 142: Bramford Substation to East Anglia Connection Node (EACN) Substation - underground cable section, located on land between Docuras Farm Road and the A12, Colchester, Essex (**Figure 1**), as part of the Norwich to Tilbury Project. The scope of the archaeological mitigation works comprises ~~six~~seven areas of detailed archaeological excavation.

The Project involves reinforcement of the electricity transmission network to support the connection of new low-carbon energy generation. As construction has the potential to impact buried archaeological remains, which are a finite and non-renewable resource, a programme of archaeological mitigation is required in line with the Outline Archaeological Mitigation Strategy and Outline Written Scheme of Investigation (~~AMS~~OAMS-OWSI) (document reference 7.5).

The approach set out in this document has been informed by previous geophysical survey and trial trenching, which identified evidence for archaeological remains relating to various periods across the site. This includes foci of prehistoric, Roman and medieval remains.

The key objectives are to establish the character, extent and chronology of archaeological activity within the site, and to place the results within their wider local and regional context, including contributing to the East of England Research Framework.

All works will be undertaken in accordance with the ~~AMS~~OAMS-OWSI and relevant professional standards, including those set out by the Chartered Institute for Archaeologists, Historic England, ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council. Post-excavation assessment, reporting and archiving will ensure that the results are appropriately analysed and disseminated.

Health, safety and environmental considerations will be embedded throughout all stages of the archaeological works.

1. Introduction

1.1 Statement of Works Required

- 1.1.1 This document sets out the requirement for archaeological mitigation on land between Docuras Farm Road and the A12, Colchester, Essex. This comprises mitigation areas 124, 136a, 136b, 137, 138, 141, and 142: Bramford Substation to East Anglia Connection Node (EACN) - underground cable section. Hereafter, these archaeological mitigation areas will be collectively referred to as the site and individually as mitigation area 'ID number'. The scope of the archaeological mitigation works comprises ~~six~~seven areas of detailed archaeological excavation.
- 1.1.2 This document should be read in conjunction with the Outline Archaeological Mitigation Strategy and Outline Written Scheme of Investigation (~~AMS-OWSI~~OAMS-OWSI) (document reference 7.5) (Ref 2) for Norwich to Tilbury (the 'Project'), where generic standards for archaeological work are set out in **Section 5** (document reference 7.5) (Ref 2). This document details the types of and scope of archaeological mitigation proposed to reduce the effect of the Project on archaeological remains.
- 1.1.3 Appropriate and proportionate geophysical (magnetometer) survey and archaeological trial trenching has been undertaken to date by Headland Archaeology (Ref 18 and Ref 19), and these works have informed the scope and extent of the archaeological mitigation detailed here. These works are summarised in **Section 1.8** of the ~~AMS-OWSI~~OAMS-OWSI and detailed in the geophysics reports (document reference 6.11.A4) (Ref 18) and trial trenching reports (Ref 19, Ref 15, Ref 16, Ref 17, Ref 18).

1.2 Site Description

- 1.2.1 National Grid Electricity Transmission plc ('National Grid') owns and maintains the national high voltage electricity transmission network throughout England and Wales.
- 1.2.2 The transmission network connects the power from where it is generated to the regional Distribution Network Operators who then supply businesses and homes.
- 1.2.3 National Grid holds the Transmission Licence for England and Wales, and its statutory duty is to develop and maintain an efficient, coordinated and economical system of electricity transmission and to facilitate competition in the generation and supply of electricity, as set out in the Electricity Act 1989.
- 1.2.4 National Grid has developed plans for the Project. The Project would support the UK's net zero target through the connection of new low carbon energy generation in East Anglia and by reinforcing the transmission network.
- 1.2.5 The Project comprises reinforcement of the transmission network between the existing Norwich Main Substation in Norfolk and Tilbury Substation in Essex, via Bramford Substation, the new East Anglia Connection Node (EACN) Substation and the new Tilbury North Substation.

- 1.2.6 The reinforcement is needed because the existing transmission network, even with current upgrading, will not have sufficient capacity for the new renewable energy (a substantial proportion of which would be generated by offshore wind) that is expected to connect to the network over the next 10 years and beyond. Completion of the Project, together with other new reinforcements across the country, will meet this future energy transmission demand both in East Anglia and across the UK.
- 1.2.7 The Project comprises:
- A new 400 kilovolt (kV) electricity transmission connection of approximately 180 km overall length from Norwich Main Substation to Tilbury Substation via Bramford Substation, a new EACN Substation and a new Tilbury North Substation, including:
 - Approximately 159 km of new overhead line supported on approximately 509 pylons, either standard steel lattice pylons (approximately 50 m in height) or low height steel lattice pylons (approximately 40 m in height) and some of which would be gantries (typically up to 15 m in height) within proposed Cable Sealing End (CSE) compounds or existing or proposed substations.
 - Approximately 21 km of 400 kV underground cabling, some of which would be located through the Dedham Vale National Landscape (an Area of Outstanding Natural Beauty (AONB¹)).
 - Up to seven new CSE compounds (with permanent access) to connect the overhead lines to the underground cables.
 - Modification works to connect into the existing Norwich Main Substation and a substation extension at the existing Bramford Substation.
 - A new 400 kV substation on the Tendring Peninsula, referred to as the EACN Substation (with a new permanent access). This is proposed to be an Air Insulated Switchgear (AIS) substation.
 - A new 400 kV substation to the south of Orsett Golf Course in Essex, referred to as the Tilbury North Substation (with a new permanent access). This is proposed to be a Gas Insulated Switchgear (GIS) substation.
 - Modifications to the existing National Grid Electricity Transmission overhead lines to facilitate the connection of the existing network into the new Tilbury North Substation to provide connection to the Tilbury Substation.
 - Ancillary and/or temporary works associated with the construction of the Project.
- 1.2.8 In addition, third party utilities diversions and/or modifications would be required to facilitate the construction of the Project. There would also be land required for environmental mitigation and Biodiversity Net Gain (BNG).
- 1.2.9 As well as the permanent infrastructure, land would also be required temporarily for construction activities including, for example, working areas for construction equipment and machinery, site offices, welfare, storage and temporary construction access.

¹ National Landscape is the rebranded name of an AONB from 22 November 2023

- 1.2.10 The mitigation areas covered by this DWSI (Mitigation Areas 124, 136a, 136b, 137, 138, 141 and 142) form part of a wider agricultural landscape characterised by gently undulating to locally elevated topography and ongoing arable land use. The areas are situated within fields that have been subject to long-term cultivation, with evidence of historic land division reflected in field boundaries, drainage features and cropmark patterns. Variations in elevation, with higher ground to the north-west and broadly level ground across the remainder of the Site, contribute to the overall rural character of the landscape.
- 1.2.11 Archaeological investigations within these areas have identified evidence of multi-period activity, including limited prehistoric remains with a localised focus in mitigation area 138, Romano-British features indicative of agricultural land use and possible low-level or seasonal activity, and medieval features comprising boundary ditches and pits. More substantial post-medieval remains are present in places, including evidence of a building, well and associated features, alongside field systems and quarrying activity, with limited modern remains also recorded. The Site therefore lies within a landscape that demonstrates continuity of land use and activity from prehistory through to the modern period, contributing to its present agricultural character.

1.3 Site Location

- 1.3.1 The site is located approximately 1.6km northeast of Boxted Cross and is bounded by the A12 to the east, within the City of Colchester district of Essex, and in the parish of Langham. They are shown in **Figure 1**.
- 1.3.2 The site comprises a combined c. 15.97 hectares (ha) of arable land, split into seven distinct mitigation areas across seventeen fields.

1.4 Standards and Guidance

- 1.4.1 In line with **Section 5.1** of the ~~AMS-OWSI~~OAMS-OWSI (Ref 2) for the Norwich to Tilbury Project, this DWSI has been prepared in accordance with relevant professional standards and guidance, including the Guidelines on standards and practices for archaeological fieldwork for Colchester City Council (Ref 8), Place Services at Essex County Council Archaeological Advice for Planning Applications and Written Schemes of Investigation (Ref 21) ~~and The Client in~~advance of works commencing at the site.
- 1.4.2 This DWSI will set out how the ~~archaeological contractor~~Archaeological Contractor will apply the principles and objectives for archaeological mitigation (**Section 2**), construction activities requiring mitigation (**Section 4**) and the standards for archaeological work (**Section 5**) as presented in the ~~AMS~~OAMS-OWSI, and how the requirements of this DWSI will be followed. The document will also include details of staff, specialists, and project programmes.
- 1.4.3 The professional standards and guidance relevant in addressing the research agenda for the site, set out at **Section 4.1** below, include:
- *Chartered Institute for Archaeologists. 2020. Standard and Guidelines for the Collection, Documentation, Conservation and Research of Archaeological Materials. (Ref 4)*
 - *Chartered Institute for Archaeologists. 2022. Code of Conduct. (Ref 5)*

- *Chartered Institute for Archaeologists. 2023. Standard for Archaeological Excavation (Ref 6)*
- *Chartered Institute for Archaeologists. 2023. Universal Guidance for Archaeological Excavation. (Ref 7)*
- *Association of Local Government Archaeological Officers East of England and Historic England. 2021. East of England Regional Research Framework (EERRF) (online). (Ref 13)*
- *Gurney, D. 2003. Standards for Field Archaeology in the East of England. (Ref 14)*
- *Historic England. 2015. Geoarchaeology: Using Earth Sciences to Understand the Archaeological Record Ref 21)*
- *Historic England. 2018. The Role of the Human Osteologist in an Archaeological Fieldwork Project (Ref 22)*
- *Historic England. 2022. Radiocarbon Dating and Chronological Modelling: Guidelines and Best Practice (Ref 23)*
- *Historic England. 2025. Environmental Archaeology: A Guide to the Theory and Practice of Methods, from Sampling and Recovery to Post-excavation (third edition) (Ref 24)*
- *Colchester and Ipswich Museums (CIMS). 2008a. Guidelines on standards and practices for archaeological fieldwork in the Borough of Colchester (CBC) (Ref 8)*
- *CIMS. 2008b. Guidelines on the preparation and transfer of archaeological archives to Colchester and Ipswich Museums (CBC) (Ref 9)*
- *Place Services (Essex County Council). 2023. Archaeological Advice for Planning Applications and Written Schemes of Investigation (Ref 27)*
- *Museums Essex. 2022. Archaeological Archives in Essex: Guidelines for the Preparation and Deposition of Archives (Ref 28)*

1.5 Project Roles

- 1.5.1 National Grid will be responsible for instructing the works and providing necessary information on scope.
- 1.5.2 The 'Main Works Contractor' will be The Client's contractor in control of the Site and all contractors on it during the construction phase. The Main Works Contractor, when appointed, will oversee all stages of work with responsibility for health and safety, welfare and site security, and will ensure that appropriate temporary works required to facilitate the archaeological work are in place.
- 1.5.3 The Archaeological Clerk of Works (ACoW) team will be responsible for monitoring and assuring the work on behalf of the Client. An ACoW team will be on site for the duration of the works to oversee the archaeological works, monitor progress and assure the works. The team will liaise directly with the LPA Archaeological Advisor.

- 1.5.4 The 'Archaeological Contractor' is responsible for carrying out the excavation, reporting, deposition of the archive and dissemination. All reporting by the ~~archaeological contractor~~[Archaeological Contractor](#) will be via the ACoW team.
- 1.5.5 ~~The Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council are the LPA Archaeological Advisors, who provide the development control and planning advice and signs off the work when it is complete, in consultation with the Archaeological Clerk of Works team.
- 1.5.6 The 'project archive repository' is the organisation, a suitable museum in Essex, responsible for the long-term curation of the project archive, including the field notes, plans, photographs and archived finds. The ~~archaeological contractor~~[Archaeological Contractor](#) will establish the project archive repository prior to starting the work and will be assigned a unique project reference number ('site code').

2. Archaeological and Historical Background

2.1 Geology and Topography

- 2.1.1 The British Geological Survey (Ref 3) records the underlying bedrock geology of all the sites as Thames Group-Clay, silt and sand except for mitigation area 138 which is underlain by Red Crag Formation-Sand.
- 2.1.2 The overlying superficial geology across the sites is recorded as:
- Mitigation areas 124, 137, and 138: Lowestoft Formation-Sand and gravel
 - Mitigation area 136a and 136b: Kesgrave Catchment Subgroup-Sand and gravel, and Lowestoft Formation-Sand and gravel
 - Mitigation area 141: Head-Gravel, Kesgrave Catchment Subgroup-Sand and gravel
 - Mitigation area 142: Head-Diamicton
- 2.1.3 The soils across all of the sites are recorded as slightly acid loamy and clayey soils with impeded drainage, except for mitigation area 142 where soils are recorded as freely draining slightly acid loamy soils (Ref 25).
- 2.1.4 In the north-west, mitigation area 142 sits at 26m Above Ordnance Datum (AOD) and mitigation area 141 sits at 36m AOD. The ground then gently slopes upwards, and the topography is relatively flat across the rest of the sites with the other mitigation areas ranging between being 41 and 44m AOD (Ref 26).

2.2 Previous Investigations and Archaeological Background

- 2.2.1 Geophysical (magnetometer) survey (**Figures 3a-c**) (document reference 6.11.A4) (Ref 18) and archaeological trial trenching (**Figures 2a-d**) (document reference 6.11.A5) (Ref 15, Ref 16, Ref 17, Ref 19, and Ref 20) has been undertaken by Headland Archaeology across parts of the Project, including that which contains the mitigation areas referred to in this document. Historic England Aerial Investigation and Mapping data (formerly the National Mapping Programme) has also been reviewed (**Figure 4**).
- 2.2.2 The following section summarises results of the geophysical survey and trial trenching, where relevant to the mitigation areas. A detailed archaeological baseline for the wider project is presented within the Historic Environment Baseline Report (document reference 6.11.A1) (Ref 1).

Prehistoric Period (800,000 BC–AD 43)

- 2.2.3 Trial trenching identified limited prehistoric remains in the site, which was focussed in mitigation area 138. A subcircular enclosure ditch was recorded that contained a

prehistoric flint tool. Prehistoric pottery was also retrieved from linear features across the area, whilst various other undated linear and discrete features were present, which may have been contemporary. The ditches did not form a recognisable arrangement or pattern. Three unurned cremations were present in the east of mitigation area 138 as well as a charcoal-rich pit. A date for these was not available at the time of writing.

Roman Period (Roman (AD 43–410))

- 2.2.4 Roman remains have been identified at three of the mitigation areas. Sherds of Roman pottery were recorded in a possible boundary ditch and pits of unknown function in mitigation area 137. Unphased ditches, post-holes and pits were dispersed across the same area and may have been contemporary. Another small focus of Roman activity was identified in mitigation area 124 where a single pit contained Roman pottery, whilst a nearby medieval ditch contained residual Roman pottery. The relatively low quantities of finds recovered from the features in both mitigation areas 137 and 124 may suggest the features are related to agriculture or low-level/seasonal occupation.
- 2.2.5 A trackway and adjoining enclosure in mitigation area 142 which, although visible in geophysics and cropmarks, was heavily truncated by ploughing. Whilst its date is not certain, the character and layout of these features suggest a late Iron Age to Roman date is most likely.

Early medieval Period (AD 410–1066)

- 2.2.6 There were no early medieval archaeological remains identified during trial trenching.

Medieval Period (AD 1066–1540)

- 2.2.7 Medieval remains were recorded in mitigation areas 124 and 136a. A medieval boundary ditch and two pits containing medieval pottery were present within mitigation area 124 and likely represent a small activity focus associated with agricultural land use. Within mitigation area 136a a ditch that contained possible medieval pottery was recorded. The ditch appears to form the southern half of an enclosure.

Post-medieval Period (AD 1540–1900)

- 2.2.8 In mitigation area 136b, a 16th–18th century building, brick-lined well, associated pits (including one with ashy deposits and nails, and another with an intact vessel), and a possible brick surface were identified. Mitigation area 138 contained possible field boundaries and quarry pitting. In mitigation area 141, multiple ditches and a pit which correspond with cropmarks likely reflect post-medieval agricultural use predating nearby 19th-century cottages, although could potentially be earlier in date.

Modern Period (1901–present)

- 2.2.9 Modern activity was limited to a disused boundary ditch in mitigation area 142.

3. Scope of Works

3.1 Introduction

- 3.1.1 This section defines the scope of archaeological mitigation works to be undertaken within the mitigation areas identified in Section ~~4~~1.
- 3.1.2 In accordance with the ~~AMS-OWSI~~OAMS-OWSI, any additional archaeological works or alternative mitigation measures within the site in variance to this DWSI will be subject to further discussion and agreement with the ACoW team, The Client, ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council, and if appropriate Historic England. Additional archaeological work could include the extension of mitigation areas, changes to sampling strategy, or a methodology for preservation in situ.
- 3.1.3 Where significant archaeological remains extending beyond the limits of the defined mitigation areas are identified during mitigation works, and where these have the potential to contribute to national and/or regional research aims, mitigation areas may be extended, where necessary and practical, within the area of project impact or DCO Order Limits (whichever is smaller). Any such extension, and the extents of it, will be agreed with Place Services at Essex County Council, in consultation with the Client and Main Works Contractor, in advance of the additional works being undertaken.

3.2 Archaeological Detailed Excavation Areas

- 3.2.1 The archaeological mitigation will comprise of six detailed excavation areas (mitigation areas 124, 136a, 136b, 137, 138, 141, and 142), as defined in Appendix B of the ~~AMS-OWSI~~OAMS-OWSI. These are illustrated in **Figure 1**.
- 3.2.2 The individual mitigation areas comprise the following:
- Mitigation area 124 comprises c. 0.11 ha and will examine a small focus of Roman and medieval activity.
 - Mitigation area 136a comprises c. 0.33 ha and will examine a 16th - 18th century building, well and associated features.
 - Mitigation area 136b comprises c. 0.94 ha and will examine a possible medieval enclosure.
 - Mitigation area 137 comprises c. 5.07 ha and will examine Roman ditches and a pit, post-medieval field boundaries and widespread undated ditches.
 - Mitigation area 138 comprises c. 7.25 ha and will examine evidence of prehistoric activity and three undated cremations, as well as widespread undated features which may be contemporary.
 - Mitigation area 141 comprises c. 0.34 ha and will examine a small concentration of undated pits and ditches, within a cropmark complex, from which one sherd of undated pottery was recovered.

- Mitigation area 142 comprises c. 1.93 ha and will examine a trackway with an adjoined small enclosure which are possibly of Iron Age or Roman date and correspond with cropmarks.

3.2.3 An overview of the aims and objectives for the site can be found in Section [44](#). The details of the nature and specific aims of the detailed excavation area is set out in Section [55](#).

[3.2.4](#) [Table 3.1 outlines the trenching information that has informed the design of the mitigation areas.](#)

[Table 3.1](#) [The Rationale for each Mitigation Area.](#)

Mitigation Area	Headland Trenching Site and Area	Trench Numbers
124	Site 9 Area 25	TR09.226
136a	Site 9 Area 61	TR09.1085 TR09.1086 TR09.1087 TR09.1090
136b	Site 9 Area 61	TR09.1055 TR09.1057 TR09.1058 TR09.1060 TR09.1061 TR09.1062 TR09.1065 TR09.1066
137	Site 9 Area 62	TR09.909 TR09.910 TR09.911 TR09.912 TR09.913 TR09.914 TR09.915 TR09.916 TR09.917 TR09.918 TR09.919 TR09.920 TR09.921 TR09.922 TR09.923

[TR09.928](#)
[TR09.929](#)
[TR09.930](#)
[TR09.931](#)
[TR09.932](#)
[TR09.933](#)
[TR09.934](#)
[TR09.935](#)
[TR09.924](#)
[TR09.925](#)
[TR09.926](#)
[TR09.927](#)
[TR09.936](#)
[TR09.937](#)
[TR09.938](#)
[TR09.939](#)
[TR09.940](#)
[TR09.941](#)
[TR09.942](#)
[TR09.943](#)
[TR09.944](#)
[TR09.945](#)
[TR09.946](#)
[TR09.947](#)

[138](#)

[Site 9](#)
[Area 24N](#)

[TR09.624](#)
[TR09.625](#)
[TR09.626](#)
[TR09.627](#)
[TR09.628](#)
[TR09.629](#)
[TR09.630](#)
[TR09.871](#)
[TR09.872](#)
[TR09.874](#)
[TR09.875](#)
[TR09.883](#)
[TR09.889](#)
[TR09.891](#)
[TR09.902](#)
[TR09.904](#)
[TR09.878](#)
[TR09.890](#)

		<u>TR09.893</u> <u>TR09.894</u> <u>TR09.895</u> <u>TR09.899</u> <u>TR09.903</u>
<u>141</u>	<u>Site 9</u> <u>Area 60</u>	<u>TR09.608</u> <u>TR09.609</u> <u>TR09.610</u>
<u>142</u>	<u>Site 9</u> <u>Area 60</u>	<u>TR09.562</u> <u>TR09.563</u> <u>TR09.566</u> <u>TR09.567</u> <u>TR09.572a</u> <u>TR09.574a</u> <u>TR09.575a</u> <u>TR09.576a</u> <u>TR09.578a</u> <u>TR09.579a</u>

4. Aims and Objectives Overview

4.1 Research Agenda

- 4.1.1 The archaeological mitigation strategy for the site has been developed in accordance with the principles and objectives set out in the [AMS OAMS](#)-OWSI for the Norwich to Tilbury Project (document reference 7.5) (Ref 2). The research questions, aims and objectives will be subject to ongoing review during the mitigation works and may be refined as appropriate in response to emerging results, subject to agreement with ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client.
- 4.1.2 The [AMS OAMS](#)-OWSI establishes a research-led and proportionate approach to archaeological mitigation, ensuring that archaeological remains affected by the Project are appropriately investigated, recorded and analysed to advance understanding of the historic environment.
- 4.1.3 The approach adopted for the site therefore seeks to:
- Mitigate the impact of construction through appropriate investigation and recording.
 - Ensure that the results of archaeological works are placed within a wider local, regional and national context.
 - Contribute to established research frameworks, including the East of England Regional Research Framework (EERRF) (Ref 13).
 - Ensure that mitigation is proportionate to the significance, extent and character of the archaeological resource.

Aims

- 4.1.4 The principal research aims are to:
- Investigate the limited prehistoric activity, including the small cremation cemetery.
 - Investigate the extent and organisation of Roman agricultural activity and possible settlement activity.
 - Assess the nature, chronology and function of medieval enclosures and associated features.
 - Better understand the nature chronology and function of the extensive undated features.
 - Understand the impact of later activity on earlier landscapes, including continuity, reorganisation and truncation.

Objectives

4.1.5 The principal research objectives are to:

- Investigate and record archaeological remains to determine character and extent.
- Develop a site chronology; and
- Set the results of investigation into the context of the existing and emerging Regional Research Agendas. The current revision of the East of England Regional Research Framework (EERRF) (Ref 13) augments both the original version of the framework, published in two parts in 1997 and 2000, and a revised and updated version, published in 2011.

4.2 Mapping to East of England Regional Research Framework (EERRF)

4.2.1 The table below provides an overview of how the results of work may fit into the context of the existing East of England Regional Research Framework (EERRF), available online and updated in 2021 (Ref 13):

Table 4.1 Alignment with Regional Research Agendas

Anticipated Remains	Key Issues	Mapping to previous EERRF (2021)	Mapping to current EERRF (2026)
Later Prehistoric archaeological features potentially relating to settlement and burial	What is the nature and extent of the limited prehistoric activity identified within the site? Can the sub-circular enclosure represent settlement remains, and how does it relate to the wider landscape? How does this evidence contribute to understanding low-density prehistoric activity in the area? What is the nature and extent of the potential prehistoric cremations identified within the site? What can they tell us about funerary practice in the period?	Settlement types and distribution Regional variation in later prehistoric landscapes Relationship of neolithic and Bronze Age funerary landscapes to settlement	LBA-MIA 18: How can we improve the dating of Bronze Age cremations and inhumations? LBA-MIA 19: How can we improve our understanding of LBA to MIA burial practices? LBA-MIA 20: What can we say about the use of grave-goods during the LBA to MIA?
Roman agricultural features and possible settlement	What is the character and organisation of Roman activity within the	Rural settlement and farmsteads The agrarian economy	LIA-Rom 06: How can we increase our understanding of the

Anticipated Remains	Key Issues	Mapping to previous EERRF (2021)	Mapping to current EERRF (2026)
	site? Is there evidence for settlement associated with the agricultural field systems? How do the identified features relate to wider patterns of Roman rural land use? What evidence exists for continuity or reorganisation of activity across the landscape?	and landscape organisation Regional variation in Roman rural landscapes	Iron Age and Roman environment? LIA-Rom 13: How can we increase our understanding of Late Iron Age and Roman farmsteads?
Medieval enclosure systems and associated activity	What is the nature and relationship of the medieval enclosures and associated features? What do the features indicate about agricultural practices and land use? What evidence exists for change, development or abandonment? How does this evidence relate to medieval activity recorded elsewhere along the Project corridor?	Dispersed rural settlement patterns Agricultural practices and land management Settlement development, change and abandonment.	Med (Rural) 03: How can we improve our understanding of medieval agricultural practices? Med (Rural) 09: How can we characterise medieval rural settlement morphology and relationships?
Post-medieval remains relating to rural activity	What is the character and function of the post-medieval building and associated features? Do the identified features indicate domestic, agricultural or small-scale industrial activity?	Production and processing of food Production of material culture such as pottery and brick	P-Med 07: How can we increase our understanding of post-medieval bricks and brickwork in the region? P-Med 12: How should we approach the excavation of post-medieval deposits? P-Med 14: How can we characterise the post-medieval historic landscape and the factors which affected it?

5. Standards for Archaeological Work

5.1 Standards for archaeological work

- 5.1.1 All archaeological works will be undertaken in accordance with the [AMSOAMS](#)-OWSI for the Norwich to Tilbury Project (document reference 7.5) (Ref 2), which establishes the overarching principles, methodologies and standards for archaeological mitigation, and the detailed methodology set out within this DWSI.
- 5.1.2 Prior to the commencement of works, the appointed ~~archaeological contractor~~[Archaeological Contractor](#) will prepare a site-specific method statement for the archaeological mitigation areas set out within this DWSI. It will present a response to the standards set out within this DWSI, and will comply with the standards set out in the [AMSOAMS](#)-OWSI. The method statement will include a full programme for the archaeological work that would be referenced against key milestones and events in the overall design and construction programme. All work will comply with relevant standards and technical guidance (Chartered Institute for Archaeologists, 2023 (Ref 6 and Ref 7).
- 5.1.3 The archaeological method statement must include:
- A detailed programme of work that sets out the proposed sequence of tasks, anticipated timescales, staffing arrangements, and any other factors that may affect delivery.
 - A Data Management Plan which will describe the type of data that will be acquired and/or generated during the project, the way the data will be managed and stored, and the mechanisms to be employed to preserve and share the data.
 - The site-specific Health and Safety arrangements that outline the main risks associated with the works and control measures to mitigate these. Information on inductions, PPE, welfare, access, and emergencies will be included.
 - Confirmation of insurances that cover the planned works.
 - The number of staff and the relevant staff CVs.
 - The museum accession numbers and relevant archive repository.
 - The specific site codes that will be used during the project.
- 5.1.4 Areas defined for archaeological mitigation will be clearly demarcated on site. No plant or vehicles not directly involved in the archaeological works will be permitted within these areas until archaeological excavation has been completed and the area has been formally signed off by and released by ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council. All plant access within archaeological mitigation areas will be supervised and directed by a suitably qualified and experienced archaeologist.
- 5.1.5 To facilitate the construction phase of the Project, specific areas of the site may require completion and sign-off in advance of full excavation of the site, for example temporary haul roads. Any such process would be agreed with ~~the Archaeological~~

~~Advisor for Colchester City Council and~~ Place Services at Essex County Council and would include:

- full excavation of the specified area to the standards set out in this DWSI.
- sign-off by ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council before any construction works take place.
- demarcation and protection of the remainder of the site through appropriate fencing and signage.

5.2 Detailed Excavation

5.2.1 Detailed excavation will be undertaken in adherence to the methodologies for archaeological excavation and recording set out within **Section 5** of the ~~AMS~~OAMS-OWSI (Ref 2), including:

- Controlled machine stripping or hand excavation, where required in accordance with the methodology set out in **section 5.3** of the ~~AMS-OWSI~~OAMS-OWSI.
- Systematic recording of archaeological deposits, features and structures, in accordance with the methodology set out in **section 5.3** of the ~~AMS-OWSI~~OAMS-OWSI.
 - Data-capture for site plans will be by electronic distance measurement, PPGPS survey, measured survey or a combination of these measures; data-capture for site plans will as standard be capable of reproduction at a scale of 1:100; more complex features or areas of complex archaeological remains will be recorded at greater resolution.
- Implementation of appropriate and iterative sampling strategies, proportionate to the nature and significance of remains (**Section 5.3.67-5.3.82**5.3.72-5.3.75). These may be varied to suit the research value of the remains, subject to agreement with the ACoW team, ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and, if appropriate, Historic England. In terms of the hand excavation of archaeological features, these will include the following:
 - A minimum of 10% of the fills of linear features (ditches, etc) are to be excavated (**Section 5.3.74**5.3.72). The interventions must be representative of the available length of the feature and must consider any variations of size, depth, fills and any concentration of artefacts. For linear features 1.00m wide slots should be excavated across their width. Depending on the significance of the feature and whether research aims/objectives (see Section 44) can be answered, a higher percentage sample may be agreed, increasing in 10% (up to a maximum of 50%) increments through agreement with the ACoW team, ~~Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client.
 - For discrete features, such as pits, 50% of their fills will be excavated. In some instances, where significant archaeological remains have been identified or to address specific research questions, 100% will be excavated (**Section 5.3.72**5.3.73).
 - Features which are, or could be interpreted as, structural (such as drip gullies, post holes, internal or external surfaces, hearths, etc.) must be fully excavated

(~~Section 5.3.78-5.3.80~~5.3.79-5.3.81). Post-holes and pits must be examined in section and then fully excavated. Fabricated surfaces within the excavation area (e.g. yards and floors) must be fully exposed and cleaned. Any variation from this process can only be made by through agreement with the ~~Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client and must be confirmed in writing.

- Large or deep features may be excavated in opposing quadrants in the first instance, in agreement with ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client, or in other such gridded or systematic excavation as may be appropriate to the feature type.
- Provision should be made for hand excavation of any stratified layers (e.g. dark earth) in 2.50m or 1.00m systematic and gridded squares, to be agreed with the ACoW team, ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client on the basis of the complexity/extent of such layers. This should be accompanied by an appropriate finds recovery strategy which must include metal detector survey and on-site sieving to recover smaller artefacts/ecofacts.
- Provision should be made to fully investigate the depth of sequences and the depth of archaeological features. This may involve the use of stepping or shoring.
- Appropriate provision should be made for extracting water from sites and features.
- Hand auger or a power auger (where appropriate) is recommended to gain information from very deep features so a safe excavation strategy can be designed and implemented in discussion with ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client.
- Machine/mechanical assistance may only be used for very large/deep features, following agreement with ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client.
- Measures to ensure the preservation of archaeological evidence, where preservation in situ is feasible.
- Controlled metal detecting will be undertaken on all areas designated for archaeological mitigation prior to the excavation areas being opened. Detecting will also be completed after any surface clearance and prior to any hand excavation of archaeological features (~~section 5.3.27-5.3.32~~5.3.26-5.3.31). The location of any metalwork will be surveyed.

5.2.2 Fieldwork will be undertaken following best practice to ensure that archaeological remains are investigated to a level appropriate to their character, extent and significance, and that results can contribute to the agreed research objectives.

5.3 Environmental Sampling and Scientific Dating

5.3.1 The Archaeological Contractor will present a sampling strategy (based on the sampling requirements outlined in this DWSI, all available guidance and the specialist advice of their in-house or subcontracted palaeoenvironmental specialist)

to Place Services at Essex County Council and (if warranted) the Historic England Regional Advisor for Archaeological Science (RSA). Their in-house or subcontracted palaeoenvironmental specialist will take the role of co-ordinator for environmental archaeology for the Site, in accordance with the [AMSOAMS](#)-OWSI (Ref 2).

5.3.2 As set out in this section, site-specific environmental sampling strategy will include:

- Targeted sampling for charred plant remains, charcoal, and palaeoenvironmental material.
- Recovery of material suitable for palaeoenvironmental reconstruction and economic interpretation.
- Provision for specialist analysis where appropriate.

5.3.3 Specific sampling guidance should be followed, including:

- Bulk samples must be a minimum of 40 litres. If a feature is too small to produce this size of sample (e.g. a post hole) then 100% of the feature should be retained for processing.
- All samples will be retained until their potential has been assessed and until a retention strategy has been agreed with ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council. Where necessary, advice on the appropriateness of the proposed strategy should be sought from the Historic England Science Advisor (East of England).
- Samples of burnt flint or pottery retained for lipid analysis should not be washed.

5.3.4 Appropriate scientific dating techniques will be applied, where justified, to support the development of a robust chronological framework. These may include:

- Radiocarbon (C-14) dating which can be used to date any carbon-based organic materials, such as wood, bone, or plant remains. If remnant peat is found, reliable and high-resolution dating will be essential, and multiple methods will be employed unless otherwise justified.
- Archaeomagnetism dating for highly fired structures such as kilns or ovens and in situ burning.
- Luminescence dating (e.g. OSL or TL), where relevant.
- If preserved wood is present, for example, in waterlogged deposits then dendrochronology may be able to provide precise and accurate dates (suitable on-site provision to retain the wood in stable condition will be required).

5.4 Finds Processing, Conservation and Human Remains

5.4.1 Procedures for the recovery, treatment and storage of artefactual and ecofactual material will accord with:

- ClfA standards and guidance (Ref 7)
- Historic England best practice (Ref 23)

5.4.2 The recovery strategy for artefacts will be as follows:

- General principle: All artefacts from stratified contexts will be retained unless otherwise stated. Material from unstratified contexts will only be retained where of significance.
- Ceramic materials: All pottery, CBM and ceramic objects (e.g. loomweights, spindlewhorls) will be collected from stratified contexts. Unstratified material will only be retained where significant. In situ structural material will be recorded and sampled where appropriate.
- Stone materials: Building stone and portable objects will be retained from stratified contexts; unstratified material will only be collected where significant. Unworked stone will only be retained where it is clearly anthropogenic or functionally relevant.
- Metalwork and industrial residues: All metalwork and metalworking residues will be retained from stratified contexts. Obviously modern material from topsoil or unstratified contexts will not normally be retained.
- Flint and lithics: All worked flint will be retained. Burnt or unworked flint will be retained from stratified contexts.
- Ecofactual material: Animal bone, marine shell, and other ecofacts will be retained from stratified contexts. Where large assemblages occur, an appropriate sampling strategy will be adopted to characterise the assemblage.
- Glass and small finds: All glass, coins, worked bone, antler, leather, textile, and other small finds will be retained from stratified contexts. Unstratified material will only be retained where significant.
- Structural and in situ material: Structural elements (e.g. timbers, masonry, plaster, daub) will be recorded in situ, with sampling undertaken where appropriate for analysis, dating or identification.
- Bulk or modern material: Large assemblages of modern or post-medieval material (e.g. bottle dumps) will be recorded in situ and sampled where appropriate, rather than fully retained.
- Specialist analysis and retention: Retention, discard and sampling will be subject to specialist assessment and agreement with the ACoW team and the Archaeological Advisor for Colchester City Council and Place Services at Essex County Council.

5.4.3 In accordance with **Sections 5.3.108-5.3.119** of the ~~AMS-OWSI~~OAMS-OWSI, in the event that human remains are encountered:

- Works will stop in the affected area.
- The ACoW and The Client will be notified immediately. The ACoW will notify ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council as well as relevant authorities in order to agree an excavation strategy. Human remains will need to be fully excavated and recorded in accordance with Historic England (Ref 24) and ClfA (Ref 7) guidance. The treatment, excavation and removal of human remains will be undertaken in accordance with Article 23 of the draft Development Consent Order, which sets out the relevant provisions for the removal of human remains.

- Procedures will follow the requirements set out in Article 23 of the draft Development Consent Order, together with relevant Historic England guidance.
- Conservator and specialists should be on-site when excavation of burials begins to advise on conditions, potential and approaches. It may be possible to feedback results from the laboratory investigation of soil blocks to inform approaches on site.
- Human remains are to be treated at all stages with care and respect and are to be dealt with in accordance with the law. They must be recorded in situ and subsequently lifted, packed and marked to the standards compatible with those described in current guidance from ClfA, Historic England, Advisory Panel on the Archaeology of Burials in England (APABE) and the British Association of Biological Anthropology and Osteoarchaeology (BABAO). Where inhumations are encountered, the ~~archaeological contractor~~ Archaeological Contractor should make provision for the following:
 - Where human burials (inhumations and/or cremation), funerary monuments or other important funerary archaeological features are identified, detailed excavation is necessary to understand the context, dating and osteological features, in an effort to understand their significance. In accordance with **Section 5.3.99** of the ~~AMS-OWSI~~ OAMS-OWSI, excavation of human remains will not extend beyond the limits of the mitigation area; however, it may be followed under the baulk so that it may be lifted in its entirety, provided this will not result in disturbance of further burials, or extend beyond the Order Limits. Decisions on extensions to any mitigation areas will need to be made in consultation with ~~the Archaeological Advisor for Colchester City Council~~, Place Services at Essex County Council and The Client.
 - ~~The Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council should be consulted with regards to the most appropriate mitigation approach for sites where furnished burials are known, anticipated, or identified and amendments to the existing WSI may be necessary.
- The following sampling strategy should be followed:
 - Full excavation is necessary to understand the context, dating and osteological features, in an effort to understand their significance. Leaving human remains in situ should only be considered when excavation is not feasible, for example if the burial is only partially within the excavation area or the proposed development boundary, the decision to not excavate is with the osteologist, otherwise excavation is the standard procedure.
 - provision for retrieval of small bones in the head area (e.g. inner ear bones), torso/pelvic area (foetal remains, gall/bladder stones, hand bones depending on position), and the feet.
 - If grave goods are identified and are not subject to block lifting, additional specialist samples should be taken from the areas around the grave goods.
 - Cremation deposits should be subject to sampling and assessment for charcoal, charred plant remains, finds and the recovery of human bone.
 - Where un-urned cremations are suspected or identified, these will be subject to 100% sampling. Where large deposits of pyre debris are identified the human remains specialist will be contacted to devise an appropriate strategy

for excavation and sampling. The strategy will be developed at site consultation meeting(s) between the Archaeological Contractor(s), The Client, the relevant Historic England Regional Science Advisor and ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council.

- It may be beneficial to consider half sectioning the excavation of un-urned cremations to aid an understanding of the vertical distribution of the deposit; the deposit may then be excavated in spits.
- Block lift cremation urns to allow for X-radiography and excavation under laboratory conditions. The conservator or field staff experienced in lifting cremation urns will be present when lifting takes place. In the first instance, the conservator will be contacted for advice.

5.5 Communication, Monitoring, and Sign-Off

- 5.5.1 All archaeological works will be subject to monitoring and sign-off by ~~Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council, in accordance with the ~~AMS~~OAMS-OWSI (Ref 2):
- Archaeological areas will remain under archaeological control until formally agreed as completed.
 - Clear communication will be maintained between the ~~archaeological contractor~~Archaeological Contractor and construction teams via the ACoW team.
 - Areas will only be released once archaeological works have been signed off by ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council.
- 5.5.2 A unique site code will be obtained by the ~~archaeological contractor~~Archaeological Contractor from Essex Historic Environment Record (HER) and used for all recording, archiving and reporting.
- 5.5.3 The ~~archaeological contractor~~Archaeological Contractor will provide The Client, ACoW team and, if appropriate, ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council, with a weekly summary progress memo (1–2 pages). This will:
- Summarise the work undertaken during the week and the key findings.
 - Report on site attendance, where appropriate.
 - Confirm that the work will be completed to programme and identify any potential issues to programme.
 - Identify any health and safety issues (including near miss).
 - Post Excavation Programming, following fieldwork.
- 5.5.4 The ~~archaeological contractor~~Archaeological Contractor will provide all information reasonably practicable to the ACoW team to enable them to monitor compliance with this DWSI – e.g. site surveys, intervention plans, records and finds data etc.
- 5.5.5 As outlined in the ~~AMS-OWSI~~OAMS-OWSI sections 5.2.16-5.2.21, the formal sign off procedure will be as follows:

- Once the Archaeological Contractor(s) believes the fieldwork to be completed, a sign-off meeting would be held on site (unless alternative communication is agreed) between the ACoW, Client, ~~Archaeological Advisor for Colchester City Council~~ (and Historic England, if appropriate), Place Services at Essex County Council, the ~~archaeological contractor~~ Archaeological Contractor and the Main Works contractor.
- Sites that have been completed would be subject to a formal signing off procedure, in order to allow the mitigation areas (or parts thereof) to be released to the construction team. The ~~archaeological contractor~~ Archaeological Contractor would submit a completion statement to the ACoW. This statement will include a final site plan, showing locations of archaeological features and interventions (in both PDF and Shapefile format). The ACoW would submit the accepted completion statement to the Client and ~~Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council for confirmation (in consultation with Historic England, where required) that the relevant works have been completed in compliance with the relevant DWSIs.

5.6 Post-Excavation, Reporting and Archiving

5.6.1 Post-excavation works will be undertaken in accordance with the ~~AMS~~ OAMS-OWSI (Ref 2) and will include:

- An interim statement, to be submitted by the ~~archaeological contractor~~ Archaeological Contractor within six weeks of completing the fieldwork.
- Post-excavation assessment (PXA), to be submitted within ~~six months~~ one year of completion of the archaeological mitigation for relevant development stage, unless otherwise agreed in writing with the Client and ~~the Archaeological Advisor for Colchester City Council and~~ Place Services at Essex County Council.
- An updated project design (UPD), to be completed within one year of ~~completion~~ the approval of the PXAs. The UPD will provide details of timescales and costs for delivery of the archaeological ~~mitigation for the relevant development stage~~ project and detail full publication and archive deposition.
- Specialist analysis of finds and environmental material.
- Production of reports appropriate to the scale and significance of the remains.

5.6.2 All results will be:

- Integrated into the wider project framework.
- Assessed against the East of England Regional Research Framework (EERRF) (Ref 13).
- Made available through appropriate dissemination and reporting.

5.6.3 A complete archive (including digital data) will be prepared and deposited.

5.7 Public Outreach and Dissemination

5.7.1 A programme of dissemination and public engagement will be implemented in accordance with the ~~AMS~~ OAMS-OWSI (Ref 2) **Section 6.8**, proportionate to the

significance of the findings. These will fit within wider a Public Archaeology and Community Engagement Strategy (PACE), which will set out a Project-wide strategy for public engagement. This may include:

- Public summaries and outreach materials.
- Engagement with local stakeholders, schools and interest groups.
- Wider dissemination of significant results through appropriate channels.

6. Programme, staffing and attendance

6.1 Initial timetable and staffing

- 6.1.1 The archaeological ~~evaluation~~mitigation is anticipated to start in March 2027.
- 6.1.2 The ~~archaeological fieldwork subcontractor~~Archaeological Contractor will provide a detailed programme for the archaeological works within their method statement, which will also include estimated staff resources and CVs for key project team members.
- 6.1.3 A programme of archaeological works will be prepared and implemented in advance of construction, setting out the timing and sequence of investigative works. The programme will identify how archaeological activities interface with construction works and will be aligned with key project milestones, in accordance with the requirements of the ~~AMS-OWSI~~OAMS-OWSI (Section 5.1.4).
- 6.1.4 The programme will be agreed with the Archaeological Contractor, ACoW, and Main Works Contractor, and will allow for flexibility to accommodate site conditions, weather, and the nature and extent of archaeological remains encountered during the works.

7. Health, Safety, Security and Environment (HSSE)

- 7.1.1 Health and Safety will take priority over all other requirements. A conditional aspect of all archaeological work is both safe access to the area of work and a safe working environment. The project will be carried out in accordance with safe working practices.
- 7.1.2 The archaeological contractor's method statement shall include details of site-specific Health and Safety arrangements incorporating all elements of the archaeological works, including details on specific risks and mitigation requirements in relation to the programme of works. Should services be detected and work be required in proximity, the contractor will provide supplementary documentation detailing how work will be managed in a Mitigation Statement for Excavation.
- 7.1.3 The appointed archaeological contractor will also arrange appropriate security provisions with the Main Works Contractor at the site.
- 7.1.4 Currently known site-specific HSSE issues will need to be considered within the site-specific risk assessment prior to commencement of the fieldwork and copies sent to the representatives of The Client and their Main Works Contractor for approval.

Risk assessment and methodology statement (RAMS)

- 7.1.5 The archaeological contractor will produce a site-specific Risk Assessment and Methodology Statement (RAMS) to cover the onsite fieldwork and will supply a copy of the company's Health and Safety Policy. These will be reviewed by The Client to ensure that the policy and measures are appropriate.
- 7.1.6 The RAMS will have been read, understood, and signed by all staff attending the site before any fieldwork commences. Cross-disciplinary industry standards should be followed, considerations include:
 - Clear, concise, and site-specific. Bespoke to the site, and without generic text for hazards that do not apply or mitigation that is not applicable.
 - Tabulation of site-specific hazards, risk grading and mitigation measures.
 - Site manager contact details provided, along with a deputy.
 - Emergency action plan, with an address and route map to the closest Accident and Emergency.
 - Archaeological Contractor RAMS will be reviewed by an appropriately qualified and experienced member of staff (e.g. Project Manager), ideally with final approval by the H&S Manager/Senior Manager prior to review by The Client.

Personal protective equipment (PPE)

- 7.1.7 Staff present on site will be required to wear the appropriate Personal Protective Equipment (PPE), as identified in the RAMS. As a minimum this will be protective shoes, high-visibility vest, gloves, protective glasses and safety helmet. The requirement for any additional PPE will be identified in the RAMS.

Welfare

- 7.1.8 The Main Works Contractor will be responsible for providing and positioning suitable welfare facilities on site, including toilet and water for washing.

Abbreviations

Abbreviation	Full Reference
AIS	Air Insulated Switchgear
AONB	Area of Outstanding Natural Beauty
BNG	Biodiversity Net Gain
CPRSS	Corridor and Preliminary Routeing and Siting Study Report
CSE	Cable Sealing End
DCO	Development Consent Order
DNO	Distribution Network Operators
EACN	East Anglia Connection Node
EIA	Environmental Impact Assessment
ES	Environmental Statement
ESO	Electricity System Operator
GIS	Gas Insulated Switchgear
GW	Gigawatts
kV	Kilovolt
NSIP	Nationally Significant Infrastructure Project
NETS	National Electricity Transmission System
NETS SQSS	National Electricity Transmission System Security and Quality of Supply Standard
NGET	National Grid Electricity Transmission
Ofgem	Office of Gas and Electricity Markets
PEIR	Preliminary Environmental Information Report
SOBR	Strategic Options Backcheck and Review
SPA	Special Protection Area
SSSI	Site of Special Scientific Interest

Glossary

Term	Description
Alignment	The proposed overhead line and underground cable route.
Ancient woodland	Land that has been continually wooded since at least 1600 in England. Regarded as 'irreplaceable habitat' in national planning policy and guidance. Ancient woodland greater than 2 ha is recorded on the Natural England Ancient Woodland Inventory.
Archaeological Clerk of Works (ACoW)	A suitably qualified archaeologist or team appointed by National Grid to oversee and monitor archaeological works in accordance with the AMS OAMS OWSI and relevant DWSIs.
Biodiversity	The variability among living organisms from all sources including terrestrial, marine and other aquatic ecosystems and the ecological complexes of which they are part: this includes diversity within species, between species and of ecosystems.
Biodiversity Net Gain	An approach for developments to ensure habitats for wildlife are left in a measurably better state than they were before the development.
Cable	An insulated conductor designed for underground installation.
Cable Sealing End compound	Electrical infrastructure used as the transition point between overhead lines and underground cables. A compound on the ground acts as the principal transition point.
Conservation Area	An area of special architectural or historic interest, the character or appearance of which it is desirable to preserve or enhance as defined in s69(1)(a) in the Planning (Listed Building and Conservation Areas) Act 1990.
Development Consent Order	A statutory instrument which grants consents and other rights to build a Nationally Significant Infrastructure Project, as defined by the Planning Act 2008.
Distribution Network Operator	Companies that own and operate the power lines and infrastructure that connect the National Grid network to individual properties.
Substation	Substations are used to control the flow of power through the electricity system. They are also used to change (or transform) the voltage from a higher to lower voltage to allow it to be transmitted to local homes and businesses.

Bibliography

- Ref 1 Arcadis (2025). *Document: 6.11 Environmental Statement Chapter 11- Historic Environment - Clean Version*
- Ref 2 Arcadis (2025). Outline Archaeological Mitigation Strategy and Outline Written Scheme of Investigation.
- Ref 3 British Geological Survey. (2026). *Geology of Britain Map Viewer* [online] Available at: <http://mapapps.bgs.ac.uk/geologyofbritain/home.html> [accessed 01 May 2026]
- Ref 4 Chartered Institute for Archaeologists. (2020). Standard and Guidelines for the Collection, Documentation, Conservation and Research of Archaeological Materials.
- Ref 5 Chartered Institute for Archaeologists. (2022). Code of Conduct.
- Ref 6 Chartered Institute for Archaeologists. (2023). Standard for Archaeological Excavation.
- Ref 7 Chartered Institute for Archaeologists. (2023). Universal Guidance for Archaeological Excavation.
- Ref 8 Colchester and Ipswich Museums (CIMS). 2008a. Guidelines on standards and practices for archaeological fieldwork in the Borough of Colchester (CBC)
- Ref 9 CIMS. 2008b. Guidelines on the preparation and transfer of archaeological archives to Colchester and Ipswich Museums (CBC)
- Ref 10 EAA. (1997). Research and Archaeology: A Framework for the Eastern Counties, 1 Resource Assessment, East Anglian Archaeology Occasional Paper No. 3
- Ref 11 EAA. (2000). Research and Archaeology: A Framework for the Eastern Counties, 2 Research Agenda and Strategy, East Anglian Archaeology Occasional Paper No. 8
- Ref 12 EAA. (2011). Research and Archaeology Revisited: A Revised Framework for the East of England. East Anglian Archaeology Occasional Paper No. 24, ALGAO
- Ref 13 EERRF. (2021). *East of England Regional Research Framework* [online]. Available at: <https://researchframeworks.org/eoe/> [accessed May 2026]
- Ref 14 Gurney, D. (2003). Standards for Field Archaeology in the East of England.
- Ref 15 Headland (2025). Norwich to Tilbury, Site 9 Area 24N, Archaeological Evaluation Interim Report
- Ref 16 Headland (2025). Norwich to Tilbury, Site 9 Area 61, Archaeological Evaluation Interim Report
- Ref 17 Headland (2025). Norwich to Tilbury, Site 9 Area 62, Archaeological Evaluation Interim Report
- Ref 18 Headland (2026). Environmental Statement Appendix 11.4 Geophysical Survey (Priority Areas) Results Report - Clean Version- Part 1

- Ref 19 Headland (2026). Environmental Statement Appendix 11.5 - Trial Trenching Results Report - Tracked Changes Version
- Ref 20 Headland (2026). Norwich to Tilbury Site 009. Project Undergrounding Between The River Stour And The EACN Substation, Ardleigh – Part 1. Evaluation.
- Ref 21 Historic England. (2015). Geoarchaeology: Using Earth Sciences to Understand the Archaeological Record.
- Ref 22 Historic England. (2018). The Role of the Human Osteologist in an Archaeological Fieldwork Project. Swindon.
- Ref 23 Historic England. (2022). Radiocarbon Dating and Chronological Modelling: Guidelines and Best Practice
- Ref 24 Historic England. (2025). Environmental Archaeology: A Guide to the Theory and Practice of Methods, from Sampling and Recovery to Post-excavation (third edition)
- Ref 25 Soilsdapes, (2026). *Soilsdapes Viewer*. [Online] Available at: <https://www.landis.org.uk/soilsdapes/> [Accessed 01 May 2026].
- Ref 26 Topographic Map, (2026). *England topographic map*. [Online] Available at: <https://en-gb.topographic-map.com/map-kb57/England/?center=53.47451%2C-2.59194&zoom=15&popup=53.47749%2C-2.59483> [Accessed 28 04 2026].
- Ref 27 Place Services (Essex County Council). 2023. Archaeological Advice for Planning Applications and Written Schemes of Investigation
- Ref 28 Museums Essex. 2022. Archaeological Archives in Essex: Guidelines for the Preparation and Deposition of Archives

Appendix A.

Figures

Figure 1 - Location of Mitigation Areas 124, 136a&b, 137, 138, 141, 142

Figure 2a - Mitigation Area 142 over Trial Trench Locations




Figure 2b - Mitigation Areas 141 and 136b over Trial Trench Locations




Figure 2c - Mitigation Areas 136a and 137 over Trial Trench Locations

Doc Ref:



Legend

-  Order Limits
-  Mitigation Areas
-  Excavated
-  Archaeology
-  Spread or Layer
-  Trench Base
-  Trench Top




Figure 2d - Mitigation Area 138 over Trial Trench Locations


Doc Ref:



Legend

- Order Limits
- Mitigation Area
- Trench Top
- Trench Base
- Archaeology
- Excavated

Notes: © Crown copyright and database rights 2023 Ordnance Survey 0100031673, Contains public sector information licensed under the Open Government Licence v3.0, © National Grid UK



A	May 2026	DETAILED WORK FOR DETAILED EXCAVATION	MH	DA	OP
Rev	Date	Description	Drawn	Check	Approv

PROJECT:
Norwich to
Tilbury

Planning Inspectorate App Number: EN020027
Regulation 5(2)(a)

Title:

Figure 2d - Mitigation Area 138
over Trial Trench Locations

Designed		Date	25 May 2026
Drawn	M. Harshavardhan	Date	25 May 2026
Checked	D. Astbury	Date	25 May 2026
Approved	O. Prestidge	Date	25 May 2026
Scale:	1:2,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	A2	Project Number:	UK0035003.1497

Suitability Description:
Accepted as Concept Stage

Drawing Number:
10059280-ARC-EGN-ZZ-DR-ZZ-00291

Revision:
A




Figure 2e - Mitigation Area 124 over Trial Trench Locations




Figure 3a - Mitigation Areas 136a&b, 137, 141, 142 over the Geophysical Interpretation




Figure 3b - Mitigation Areas 137 and 138 over the Geophysical Interpretation







Figure 3c - Mitigation Area 124 over the Geophysical Interpretation



Doc Ref:

Legend

Order Limits

Mitigation Areas

Geophysical Interpretation (Points)

Spike

Geophysical Interpretation (Line)

Agriculture

Field Boundary

Field Drain

Natural

Geophysical Interpretation (Polygon)

Magnetic Disturbance (Above Ground)


Magnetic Disturbance (Below Ground)

Natural

Possible Archaeology

Uncertain

Notes: © Crown copyright and database rights 2023 Ordnance Survey 0100031673, Contains public sector information licensed under the Open Government Licence v3.0, © National Grid UK



A	May 2026	DETAILED WSs FOR DETAILED EXCAVATION	MH	DA	OP
Rev	Date	Description	Drawn	Check	Approv

nationalgrid

PROJECT:
Norwich to
Tilbury

Planning Inspectorate App Number: EN020027
Regulation 5(2)(a)

Title:

Figure 3c - Mitigation Area 124
over the Geophysical Interpretation


Designed		Date	25 May 2026
Drawn	M. Harshavardhan	Date	25 May 2026
Checked	D. Astbury	Date	25 May 2026
Approved	O. Prestidge	Date	25 May 2026
Scale:	1:4,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	A2	Project Number:	UK0035003.1497

Suitability Description:

Accepted as Concept Stage

Drawing Number:	Revision:
10059280-ARC-EGN-ZZ-DR-ZZ-00291	A

Figure 4 - Mitigation Areas 124, 136a&b, 137, 138, 141, 142 over Cropmark Data




Doc Ref:



- Legend
- Order Limits
 - Mitigation Areas
 - National Mapping Programme (Lines)
 - National Mapping Programme (Polygons)

Notes: © Crown copyright and database rights 2023 Ordnance Survey 0100031673, Contains public sector information licensed under the Open Government Licence v3.0, © National Grid UK



A	May 2026	DETAILED WSs FOR DETAILED EXCAVATION	MH	DA	OP
Rev	Date	Description	Drawn	Check	Approv

PROJECT:
nationalgrid Norwich to Tilbury

Planning Inspectorate App Number: EN020027
Regulation 5(2)(a)

Title:

Figure 4 - Mitigation Areas
124, 136a&b, 137, 138, 141,
142 over Cropmark Data

Designed		Date	25 May 2026
Drawn	M. Harshavardhan	Date	25 May 2026
Checked	D. Astbury	Date	25 May 2026
Approved	O. Prestidge	Date	25 May 2026
Scale:	1:7,000	Datum:	AOD
Original Size:	A3	Grid:	OS
Suitability Code:	A2	Project Number:	UK0035003.1497

Suitability Description:
Accepted as Concept Stage

Drawing Number:
10059280-ARC-EGN-ZZ-DR-ZZ-00291
Revision:
A

National Grid plc
National Grid House,
Warwick Technology Park,
Gallows Hill, Warwick.
CV34 6DA United Kingdom

Registered in England and Wales
No. 4031152
nationalgrid.com

Summary report: Litera Compare for Word 11.16.0.74 Document comparison done on 21/07/2026 14:03:00	
Style name: Default Style	
Intelligent Table Comparison: Active	
Original filename: 8.21 REVA.docx	
Modified filename: 8.21 Detailed Written Scheme of Investigation - Mitigation areas 124, 136 (a & b), 137, 138, 141 & 142_Revision B v2.3 - Clean Version.docx	
Changes:	
<u>Add</u>	100
Delete	107
Move From	0
<u>Move To</u>	0
<u>Table Insert</u>	2
Table Delete	0
<u>Table moves to</u>	0
Table moves from	0
Embedded Graphics (Visio, ChemDraw, Images etc.)	0
Embedded Excel	0
Format changes	0
Total Changes:	209