M5 Junction 10 Improvements Scheme

Environmental Statement (ES)

Appendix 10.6 Agricultural Land Survey Report -

Additional Areas

TR010063 - APP 6.15

Regulation 5 (2) (a)

Planning Act 2008

Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009



Volume 6
December 2023



Infrastructure Planning Planning Act 2008

The Infrastructure Planning (Applications: Prescribed Forms and Procedure) Regulations 2009

M5 Junction 10 Improvements Scheme

Development Consent Order 202[x]

6.15 Environmental Statement (ES)

Appendix 10.6 Agricultural Land Survey Report Additional Areas

Regulation Number:	Regulation 5(2)(a)
Planning Inspectorate Scheme Reference	TR010063
Application Document Reference	TR010063/APP/6.15
Author:	M5 Junction 10 Improvements Scheme Project Team

Version	Date	Status of Version
Rev 0	December 2023	DCO Application



Agricultural Land Classification:

J10 M5 Gloucestershire

Prepared for: **Atkins**

Prepared by:

Askew Land & Soil Limited

Date:

10th August 2022

Project Number: **C884**

Our interpretation of the site characteristics is based on available data made during our desktop study and soil survey. This desktop study and soil survey has assessed the characteristics of the site in relation to the assessment of its Agricultural Land Classification. It should not be relied on for alternative end-uses or for other schemes. This report has been prepared solely for the benefit of Atkins.

C884 Issue 1 i Askew Land & Soil Ltd

CONTENTS

1	INTRODUCTION	1
1.1	Background	1
1.2	Competency	1
1.3	Methodology	1
1.4	Structure of the Remainder of this Report	2
2	PLANNING POLICY FRAMEWORK	3
2.1	Background	3
2.2	National Planning Policy Statement (NPPF) July 2021	3
2.3	Best Practice Guidance	3
3	AGRICULTURAL LAND CLASSIFICATION	4
3.1	Background	4
3.2	Climate	4
3.3	Site	5
3.4	Soil	5
3.5	Interactive Limitations	7
3.6	ALC Grading at the Site	9
4	ALC AT THE SITE IN A WIDER GEOGRAPHICAL CONTEXT	10
4.1	Introduction	10
4.2	Pre-1988 ALC Information	10
4.3	Post-1988 ALC Information	11
5	SUMMARY AND CONCLUSIONS	12

APPENDICES

Appendix 1: Soil Profile Logs

Appendix 2: Soil Pit Description

Appendix 3: Topsoil Texture Analysis

1 INTRODUCTION

1.1 Background

1.1.1 This report was commissioned by Atkins to determine the quality of agricultural land proposed at Junction 10 of the M5, Cheltenham, Gloucestershire, GL51 0TH ('the Site'). The assessment was made in accordance with the Agricultural Land Classification (ALC) system for England and Wales (see 'Methodology' below). This ALC has involved a survey of approximately 7.8 hectare (ha) in three separates parcel (i.e., A to C), located north-west of Cheltenham, Gloucestershire, as shown on **Figure 1**. This is to complement an ALC survey of the wider J10/M5 scheme which is reported separately. The approximate centre of the current ALC Study Area is located at British National Grid (BNG) reference SO 90887 24782.

1.2 Competency

1.2.1 The work has been carried out by a Chartered Scientist (CSci), who is a Fellow (F.I. Soil Sci) of the British Society of Soil Science (BSSS). The soil surveyor meets the requirements of the BSSS Professional Competency Standard (PCS) scheme for ALC (see BSSS PCSS Document 2 'Agricultural Land Classification of England and Wales'¹. The BSSS PCS scheme is endorsed, amongst others, by the Department for Environment, Food and Rural Affairs (Defra), Natural England, the Science Council, and the Institute of Environmental Assessment and Management (IEMA).

1.3 Methodology

- 1.3.1 This assessment is based upon the findings of a study of published information on climate, geology and soil in combination with a soil investigation carried out in accordance with the Ministry of Agriculture, Fisheries and Food (MAFF)² 'Agricultural Land Classification of England and Wales: Revised Guidelines and Criteria for Grading the Quality of Agricultural Land', October, 1988 (henceforth referred to as the 'the ALC Guidelines').
- 1.3.2 The ALC system provides a framework for classifying land according to the extent to which its physical or chemical characteristics impose long-term limitations on agricultural use. The ALC system divides agricultural land into five grades (Grade 1 'Excellent' to Grade 5 'Very Poor'), with Grade 3 subdivided into Subgrade 3a 'Good' and Subgrade 3b 'Moderate'. Agricultural land classified as Grade 1, 2 and Subgrade 3a falls in the 'best and most versatile' category in Paragraphs 174 and 175 of the National Planning Policy Framework (NPPF) revised on 20th July

C884 Issue 1 1 Askew Land & Soil Ltd

-

¹ British Society of Soil Science. Professional Competency Scheme Document 2 'Agricultural Land Classification of England and Wales'.

² The Ministry of Agriculture, Fisheries and Food (MAFF) was incorporated within the Department for Environment, Food and Rural Affairs (Defra) in June 2001

- 2021. Further details of the ALC system and national planning policy implications are set out by Natural England in Technical Information Note 049³.
- 1.3.3 A detailed soil survey and ALC of the Site was carried out in May 2022. The ALC survey involved examination of the soil's physical properties at 8 auger-bore locations at a sampling density of approximately 1 auger bore per 1 ha. The soil profile was examined at each sample location to a maximum depth of approximately 1.2 m by hand with the use of a 5cm diameter Dutch (Edleman) soil auger. One soil pit, i.e., Pit 1 was excavated by hand with a spade in order to examine certain soil physical properties, such as stone content and the structural condition of the subsoil, more closely. The locations of the auger bores and the soil pit is shown on Figure 1.
- 1.3.4 The auger-bore locations were located using a hand-held Garmin E-Trec Geographic Information System (GIS) to enable the sample locations to be relocated for verification, if necessary. Where auger locations on a 100 m grid pattern fall on headland, tramlines, or within 3 m of a hedgerow or tree, they were relocated on agricultural land close by, i.e., to avoid compacted ground or land affected by tree roots, etc.
- 1.3.5 The soil profile at each sample location was described using the 'Soil Survey Field Handbook: Describing and Sampling Soil Profiles' (Ed. J.M. Hodgson, Cranfield University, 1997). Each soil profile was ascribed an Agricultural Land Classification (ALC) grade following the MAFF ALC Guidelines.
- 1.3.6 A sample of topsoil was collected at auger-bore locations 1 and 7, as shown on **Figure 1**. The samples were sent to an accredited laboratory for particle size analysis, i.e., the proportions of sand, silt and clay. This is to determine the definitive texture class of the topsoil, especially with regard to distinguishing between medium clay loams (i.e., <27% clay) and heavy clay loams (27% to 35% clay).

1.4 Structure of the Remainder of this Report

- 1.4.1 The remainder of this report is structured as follows:
 - Section 2 Planning Policy Framework
 - Section 3 Agricultural Land Classification;
 - Section 4 ALC at the Site in a Wider Geographical Context;
 - Section 5 Summary and Conclusions

C884 Issue 1 2 Askew Land & Soil Ltd

³ Natural England (December, 2012). 'Agricultural Land Classification: protecting the best and most versatile agricultural land (TIN049)'. Available online @ http://publications.naturalengland.org.uk/publication/35012 Last accessed August 2022

2 PLANNING POLICY FRAMEWORK

2.1 Background

2.1.1 This section of the report sets out the national and local planning framework in which to assess the opportunities and constraints to development at the Site in agricultural land quality terms.

2.2 National Planning Policy Statement (NPPF) July 2021

2.2.1 National planning policy guidance on development involving agricultural land is set out in National Planning Policy Framework (NPPF), which was revised on the 20th July 2021. The NPPF aims to provide a simplified planning framework which sets out the Government's economic, environmental and social planning policies for England. The NPPF includes policy guidance on 'Conserving and Enhancing the Natural Environment' (Section 15). Paragraph 174 (a and b) (page 50) are of relevance to this assessment of agricultural land quality and soil and states that:

'174...Planning policies and decisions should contribute to and enhance the natural and local environment by:

a) protecting and enhancing valued landscapes, sites of biodiversity or geological value and soils (in a manner commensurate with their statutory status or identified quality in the development plan);

b) recognising the intrinsic character and beauty of the countryside, and the wider benefits from natural capital and ecosystem services – including the economic and other benefits of the best and most versatile agricultural land, and of trees and woodland;...'

2.2.2 Paragraph 175 of the NPPF (2021) goes on to describe that:

'175. Plan should: distinguish between the hierarchy of international, national and locally designated sites; allocate land with the least environmental or amenity value, where consistent with other policies in this Framework 53 ...'

2.2.3 Footnote number 58 states that:

'Where significant development of agricultural land is demonstrated to be necessary, areas of poorer quality land should be preferred to those of a higher quality.'

2.3 Best Practice Guidance

2.3.1 The Department for Environment, Food and Rural Affairs (Defra) has published a 'Code of Practice for the Sustainable Use of Soils on Construction Sites'⁴.

C884 Issue 1 3 Askew Land & Soil Ltd

⁴ Department for Environment, Food and Rural Affairs (September, 2009) 'Code of Practice for the Sustainable Use of Soils on Construction Sites'. Available online @ https://www.gov.uk/government/publications/code-of-practice-for-the-sustainable-use-of-soils-on-construction-sites. Last accessed August 2022

3 AGRICULTURAL LAND CLASSIFICATION

3.1 Background

- 3.1.1 This section of the report sets out the findings of the Agricultural Land Classification (ALC). It is based on a desktop study of relevant published information on climate, topography, geology, and soil in conjunction with a soil survey.
- 3.1.2 As described in the ALC Guidelines, the main physical factors influencing agricultural land quality are:
 - climate;
 - site;
 - soil; and
 - interactive limitations.
- 3.1.3 These factors are considered in turn below.

3.2 Climate

3.2.1 Interpolated climate data relevant to the determination of the Agricultural Land Classification (ALC) grade of land within the current Study Area is given in Table 3.1 below.

Table 3.1: ALC Climate Data for J10 M5 Study Area				
Climate Parameter	Grid Ref: SO 909 249			
Average Altitude (m)	27			
Average Annual Rainfall (mm)	627			
Accumulated Temperature above 0°C (January – June)	1489			
Moisture Deficit (mm) Wheat	113			
Moisture Deficit (mm) Potatoes	107			
Field Capacity Days (FCD)	139			
Grade According to Climate	1			

3.2.2 With reference to Figure 1 'Grade according to climate' on page 6 of the ALC Guidelines, there is no climatic limitation to the quality of agricultural land at the Site. This means that agricultural land at the Site would be determined as Grade 1, without any additional limitations.

C884 Issue 1 4 Askew Land & Soil Ltd

3.2.3 Agricultural land at the Site is predicted to be at field capacity (i.e., the amount of soil moisture or water content held in soil after excess water has drained away and the rate of downward movement has materially decreased) for 139 Field Capacity Days (FCD) per year, mainly over the late autumn, winter and early spring. The combination of topsoil texture, drainage status (Wetness Class) of the profile, and number of FCD affects the degree to which agricultural land is limited by soil wetness.

3.3 Site

- 3.3.1 The approximately 7.8 ha ALC Study Area is located to the north-west of Cheltenham, Gloucestershire. The approximate centre Site parcel is located at British National Grid (BNG) reference SO 90887 24782. The location and boundaries of the Site are shown on **Figure 1**.
- 3.3.2 With regard to the ALC Guidelines, agricultural land quality can be limited by one or more of three main site factors as follows:
 - gradient;
 - micro-relief (i.e., complex change in slope angle over short distances); and
 - risk of flooding.

I. Gradient and Micro-Relief

3.3.3 The land within the Study Area is broadly level at an elevation of between 28 metres (m) Above Ordnance Datum (AOD) in the central region, to 23 mAOD at the lowest elevation in the north. The quality of agricultural land at the Site is not limited by gradient, as the gradient of the slope does not exceed 7° (see Table 1 of the ALC Guidelines, 1988). Likewise, the quality of agricultural land at the Site is not limited by micro-relief, i.e., complex changes in slope angle and direction over short distances.

II. Risk of Flooding

3.3.4 From the Government Flood Map for Planning website⁵, the Site is mainly located in Flood Zones 1 with a low risk of flooding, whilst the central parcel located in Flood Zone 2 and 3 with a higher risk of flooding. However, there are no records/data which show the quality of the agricultural land is limited by a risk of flooding in accordance with criteria for frequency and duration set out in Table 2 'Grade according to flood risk in summer' and/or Table 3 'Grade according to flood risk in winter' in the ALC Guidelines.

3.4 Soil

I. Geology/Soil Parent Material

C884 Issue 1 5 Askew Land & Soil Ltd

⁵ Government Flood Map for Planning. Available online @ https://flood-map-for-planning.service.gov.uk/confirm-location?easting=454700&northing=272400&nationalGridReference=SP547724 Last accessed August 2022

- 3.4.1 British Geological Survey (BGS) information available online⁶ has been utilised to identify the Bedrock underlying the Site and any Superficial (Drift) Deposits over the Bedrock. This information helps to determine the parent material⁷ from and within which a soil has formed. The BGS information (1:50,000) indicates the Study Area is underlain by mudstone in the Charmouth Mudstone Formation.
- 3.4.2 The BGS information (1:50,000) indicates the bedrock across most of the Study Area is not covered by any superficial deposits. However, there is some Alluvium (clay, silt, sand and gravel) in the central area (i.e., Parcel B), and Cheltenham Sand and Gravel in the north of the Site (i.e., Parcel A).

II. Published Information on Soil

- 3.4.3 The Soil Survey of England and Wales (SSEW) soil map of South West England (Sheet 5) at a scale of 1:250,000 and accompanying Bulletin No. 148 reports that agricultural land at the Site is mainly covered by soils in the Evesham 2 Association, with soil in the Badsey 2 Association in the north (i.e., Parcel A).
- 3.4.4 As described by the SSEW, the Evesham 2 Association are developed in Jurassic and Cretaceous clay shales and associated thin drifts in the clay vales of lowland England. These soils are clayey and have slowly permeable subsoils which are generally seasonally waterlogged (Wetness Class III).
- 3.4.5 The Badsey 2 Association comprise mainly of fine loamy soils over calcareous gravel. The soils are moderately to very porous over extremely porous gravelly subsoils and are largely well drained (Wetness Class I), in which winter rainwater is readily absorbed.

III. Soil Survey

3.4.6 The ALC/soil survey determined two types of soil, as described below.

Type 1

3.4.7 The first type of soil occurs in the north in Parcel A, which is covered by Cheltenham Sand and Gravels. Here the topsoil is slightly calcareous, dark greyish brown (2.5Y4/2), very slightly stony (6% hard gravel), sandy clay loam. The upper subsoil is a slightly calcareous (1-5% calcium carbonate), light olive brown (2.5Y5/4), slightly stony (8% hard gravel), sandy clay

 $\underline{\text{http://www.bgs.ac.uk/discoveringGeology/geologyOfBritain/viewer.html}}\ Last\ accessed\ August\ 2022$

C884 Issue 1 6 Askew Land & Soil Ltd

⁶ British Geological Survey 'Geology of Britain Viewer'. Available online @

⁷ British Geological Survey. A 'parent material' is a soil-science name for a weathered rock or deposit from and within which a soil has formed. In the UK, parent materials provide the basic foundations and building blocks of the soil, influencing their texture, structure, drainage and chemistry. Available online @ Soil Parent Material Model - British Geological Survey (bgs.ac.uk) Last accessed August 2022 ⁸ D.C. Findlay, G.J.N. Colborne, D.W. Cope, T.R. Harrod, D.V. Hogan, and S.J, Stains (1984) 'Soils and their use in Eastern England', Soil Survey of England and Wales Bulletin No.14, Harpenden

loam. These profiles do not have an SPL and are permeable (Wetness Class I). This type of soil fits SSEW's description of soils in the Badsey 2 Association.

Type 2

- 3.4.8 The second type of soil occurs in the central and southern parts of the Study Area, i.e., Parcel B and C. The soil hass very slightly calcareous (% calcium carbonate) and stoneless olive brown (2.5Y4/3) clay topsoil. The upper subsoil is a moderately calcareous (5-10% calcium carbonate), stoneless light olive brown (2.5Y5/3) clay. The lower subsoil is a moderately calcareous (1-5% calcium carbonate), stoneless olive (5Y5/3) clay. The top of a SPL was recorded at approximately 60cm and the profiles are placed in Wetness Class III.
- 3.4.9 A log of the soil profiles recorded on Site (see Figure 1) is given as **Appendix 1**. A description of one soil pit (soil Pit 1) is given as **Appendix 2**.

Topsoil Texture

3.4.10 The texture of the topsoil was determined on Site by hand-texturing, as described in Natural England's Technical Information Note 037 'Soil Texture'⁹. To substantiate topsoil texture determined during the ALC survey by hand-texturing, two sample of topsoil were collected over the Site (i.e., auger bore locations 1 and 7, **Figure 1**). The samples of topsoil were sent to an accredited laboratory for analysis of particle size distribution (PSD), based on the British Standard Institution particle size grades. The certificate of analysis is provided as **Appendix 3**. The findings of the PSD analysis are shown in Table 3.2 below:

Table 3.2: Topsoil To	Table 3.2: Topsoil Texture (re Table 10, ALC Guidelines)					
Topsoil Sample Location (See Fig. 1) % sand 0.063-2.0 mm % silt 0.002- 0.063 mm % clay <0.002 mm ALC Soil Texture Class						
AB1	13	32	55	Clay		
AB7	63	18	19	Sandy Clay Loam		

3.5 Interactive Limitations

3.5.1 From the published information above, together with the findings of the detailed soil survey, it has been determined that the quality of agricultural land at the Site is limited mainly by soil wetness during the autumn and winter, and by soil droughtiness during the growing season (spring and summer).

C884 Issue 1 7 Askew Land & Soil Ltd

⁹ Natural England's Technical Information Note 037 'Soil Texture'. Available online at http://publications.naturalengland.org.uk/publication/32016

I. Soil Wetness

3.5.2 From the ALC Guidelines, a soil wetness limitation exists where 'the soil water regime adversely affects plant growth or imposes restrictions on cultivations or grazing by livestock'.

Agricultural land quality at the Site is limited by soil wetness as per Table 3.3 below (based on Table 6 'Grade According to Soil Wetness – Mineral Soils' in the ALC Guidelines):

Wetness	Texture of the Top 25 cm	126 - 150
Class		Field Capacity Days
	Sandy Loam, Sandy Silt Loam	1
•	Medium Clay Loam*, Sandy Clay Loam	1
	Heavy Silty Clay Loam**, Heavy Clay Loam**	2
	Sandy Clay, Silty Clay, Clay	3a (2)
П	Sandy Loam, Sandy Silt Loam	1
	Medium Clay Loam*, Sandy Clay Loam	2
	Heavy Silty Clay Loam**, Heavy Clay Loam**	3a (2)
	Sandy Clay, Silty Clay, Clay	3b (3a)
III	Sandy Loam, Sandy Silt Loam	2
	Medium Clay Loam*, Sandy Clay Loam	3a (2)
	Heavy Silty Clay Loam**, Heavy Clay Loam**	3b (3a)
	Sandy Clay, Silty Clay, Clay	3b (3a)

^{* &}lt;27% clay; and ** >27% clay

3.5.3 In a climate area with 139 FCD, soil profiles in Wetness Class III with clay topsoil (i.e., Parcels B and C) are limited by soil wetness to Subgrade 3b.

II. Soil Droughtiness

3.5.4 From the ALC Guidelines, a soil droughtiness limitation exists 'in areas with relatively low rainfall or high evapotranspiration, or where the soil holds only small reserves of moisture available to plant roots.' The ALC grade according to soil droughtiness is shown in Table 3.4 below (based on Table 8 'Grade According to Droughtiness' in the ALC Guidelines). To be eligible for Grades 1 to 3b the moisture balances (MBs) must be equal to, or exceed, the stated minimum values for both wheat and potatoes. If the MB for either crop is less (i.e., more negative) than that shown for Subgrade 3b, the soil is Grade 4 on droughtiness):

Table 3.4: ALC Grade Acco	ording to Soil Droughtiness		
Grade/Subgrade	Moisture Balance (MB) Limits (mm)		
	Wheat	Potatoes	
1	+30	+10	
2	+5	-10	

^() bracket denote a grade uplift for naturally calcareous soils with more than 1% calcium carbonate and between 18% and 50% clay

3a	-20	-30
3b	-50	-55
4	<-50	<-55

3.5.5 As determined by MB calculations given in **Appendix 1**, the sandy clay loam soil profiles in the northern region of the Site (i.e., site parcel A) are limited by soil droughtiness to Subgrade 3a, i.e., a shortage of water in the soil for crops during the growing season.

3.6 ALC Grading at the Site

3.6.1 The area of land in each ALC grade has been measured from **Figure 2** and the area (ha) and proportion (% of Site) is given in Table 3.5.

Table 3.5: Agricultural Land Classification – Land Proposed for the J10 M5 Gloucestershire				
ALC Grade	Area (Ha)	Area (%)		
Grade 1 (Excellent)	0	0		
Grade 2 (Very Good)	0	0		
Subgrade 3a (Good)	1.8	23.1		
Subgrade 3b (Moderate)	6.0	76.9		
Grade 4 (Poor)	0	0		
Grade 5 (Very Poor)	0	0		
Other Land / Non-agricultural	0	0		
Total	7.8	100		

4 ALC AT THE SITE IN A WIDER GEOGRAPHICAL CONTEXT

4.1 Introduction

4.1.1 The aim of this section is to examine agricultural land quality at the Site in a national, regional, county and local context.

4.2 Pre-1988 ALC Information

4.2.1 During the 1960's and 1970's MAFF produced a series of maps to show the provisional ALC grade of agricultural land over the whole of England and Wales at a scale of 1:250,000. These provisional ALC maps are suitable for strategic land use planning only, i.e., they appropriate for land areas greater than 80 ha. The provisional MAFF ALC map of Eastern England (1:250,000, 1984) indicates that the quality of agricultural land at the Site is Grade 3 (not differentiated into Subgrade 3a or Subgrade 3a).

Table 4.1: Provisional ALC Grades as % of Total Land		Regional and Loca	l Context (Propor	tion of ALC
ALC Grade	England	South West Office	Gloucestershire County	Tewkesbury District
1 (excellent)	2.7	1.5	1.1	1.7
2 (very good)	14.2	7.6	5.4	5.4
3 (good to moderate)	48.2	58.9	70.2	69.9
4 (poor)	14.1	18.4	12.4	19.0
5 (very poor)	8.4	5.5	0.5	0.4
Non-Agricultural	5.0	4.6	6.6	1.1
Urban	7.3	3.6	3.8	2.5

3.4.8 Of note, the provisional (Pre 1988) ALC information shows that Tewkesbury District has a high proportion of agricultural land in Grade 3, i.e., 69.9% compared with 48.2% in England as a whole.

_


¹⁰ Ministry of Agriculture, Fisheries and Food, Land and Water Service, Technical Notes, Resource Planning (February 1983)

^{&#}x27;Agricultural Land Classification of England and Wales - The Distribution of the Grades' (TN/RP/01 TFS 846)

4.3 Post-1988 ALC Information

4.3.1 The former MAFF has not carried a Post-1988 ALC survey of agricultural land covering the Site.

An extract from the Post-1988 Agricultural Land Classification map online¹¹ surrounding the Site is given below.



4.3.2 As shown on the Post-1988 ALC survey above, MAFF has classified agricultural land close to the Site, to the west of the M5, as predominantly Subgrade 3b with pockets of Subgrade 3a. Therefore, the grading at the Site is consistent with MAFF Post 1988 ALC in the vicinity.

11

C884 Issue 1


¹¹ Multi Agency Geographic Information for the Countryside. Post 1988 Agricultural Land Classification. Available online @ www.MAGIC.gov.uk Last accessed August 2022

5 SUMMARY AND CONCLUSIONS

- 5.1.1 This report was commissioned by Atkins to determine the quality of agricultural land at Junction 10 of the M5, Cheltenham, Gloucestershire, GL51 0TH ('the Site'). The assessment was made in accordance with the Agricultural Land Classification (ALC) system for England and Wales. The approximately 7.8 hectare (ha) Study Area comprises of three parcels (i.e., Parcels A-C), located north-west of Cheltenham, Gloucestershire (see Figure 1). This is to complement an ALC survey of the wider J10/M5 scheme which is reported separately. The approximate centre of the Study Area is located at British National Grid (BNG) reference SO 90887 24782.
- 5.1.2 British Geological Survey (BGS) information (1:50,000) indicates that the Study Area is underlain by mudstone in the Charmouth Mudstone Formation. The bedrock across most of the Study Area is not covered by any superficial deposits, apart from Cheltenham Sand and Gravel in Parcel A and some Alluvium (Clay, Silt, Sand, And Gravel) in Parcel B.
- 5.1.3 The National Soil Map (1:250,000) shows the Study Area is covered by soils mainly in the Evesham 2 Association (i.e., Parcels B and C) with soil in the Badsey 2 Association in Parcel A. The Eversham 2 Association comprises clayey soils that and are slowly permeable (Wetness Class III), whilst the Badsey 2 Association comprises mainly of fine loamy soils over calcareous gravel which is well drained (Wetness Class I).
- 5.1.4 A detailed ALC/soil survey carried out in May 2022 determined two types of soil. The sand clay loam soils that are developed Cheltenham Sand and Gravels are limited by soil droughtiness to Subgrade 3a (i.e., 1.8ha or 23.1% of the Study Area) in the northern region (i.e., site parcel A). Whilst, the clay soils that are developed in Charmouth Mudstone and some Alluvium are limited by soil wetness to Subgrade 3b (i.e., 6ha or 76.9% of the Site) in the south of the Site (i.e. site parcel B and C).
- 5.1.5 MAFF has classified agricultural land close to the Site, to the west of the M5, as predominantly Subgrade 3b with pockets of Subgrade 3a. Therefore, the grading within the Study Area is consistent with MAFF Post 1988 ALC in the vicinity.

Figures





Appendix 1: Soil Profile Logs

Project Name Parcel				Parcel	
J10 M5 Additiona	l ALC 17May22				
Survey Type		Surveyor(s)	Cor	mpany	
Detailed ALC		RWA	Ask	Askew Land and Soil	
	Relief		Land use and v	regetation	
	Level				
		Postcode	Altitude	Area	
ce		GL510SW	27	10	
			T		
	Subgrade 3b t	o west	Flood Zones 2	and 3	
AT0	MDw	MDp	FCD	Climate grade	
1489	113	107	139	1	
		Superficial depo	sits		
· ·					
1:250 000		Deta	iled soil information		
		Date Revised			
		07/07/2022			
	Survey Type Detailed ALC ATO 1489	Survey Type Detailed ALC Relief Level MAFF detailed Subgrade 3b t ATO MDw 1489 113	Survey Type Detailed ALC Relief Level Postcode GL510SW MAFF detailed Subgrade 3b to west ATO MDw MDp 1489 113 107 Superficial deponder Formation Cheltenham Sar	Survey Type Surveyor(s) Cor Detailed ALC RWA Ask Relief Land use and value Level PGR (Permane Postcode Altitude GL510SW 27 MAFF detailed Flooding Subgrade 3b to west Flood Zones 2 ATO MDw MDp FCD 1489 113 107 139 Superficial deposits One Formation Cheltenham Sand And Gravel to NW of 1:250,000 Detailed soil information V2 to NW of J10 M5 Date Revised	

No.	LC
20	Limitation 3 Gr
8 120 72 SV5/3	3t
\$0.00474 24035 390474 224035 27 <7" N/A PGR	
So 909124885 390951 224885 28	
Not Applic Not	
SO 90414 24118 390414 224118 27	
So 2	
SO 90814 24118 39044 224118 27	3t
SO 90414 24118 390414 224118 27	
SO 90414 24118 390414 224118 27	
SO 90951 24885 390951 224885 28	
SO 90951 24885 390951 224885 28	
SO 90951 24885 390951 224885 28	
SO 90951 24885 390951 224885 28	31
SO 90951 24885 390951 224885 28	
18 28 10 5Y4/2 MD - N 7.5YR4/6	
18 28 10 5Y4/2 MD - h 7.5YR4/6 MD - h 2.5Y5/2 Yes C - Clay 0 SO 90936 24979 390936 224979 27 <7* N/A PGR 0 22 22 2.5Y4/4 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD - Cr.7.5YR4/6 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 Yes C - Clay 0 0 SO 91026 24998 391026 224998 27 Yes C - Clay 0 0 S	
18 28 10 5Y4/2 MD - N 7.5YR4/6	
18 28 10 5V4/2 MD - N 7.5VR4/6 MD - N 2.5VS/2 Ves C - Clay 0 SO 90936 24979 390936 224979 27 <7" N/A PGR 0 22 22 2.5V4/4 Ves C - Clay 0 Not Applic NON - No No 10 - 7 2 WC III 3b Wetness SO 91026 24998 391026 224998 27 <7" N/A PGR 0 22 22 2.5VS/3 CD - Cr.7.5VR4/6 Ves C - Clay 0 Not Applic NON - No No No 10 - 7 2 WC III 3b Wetness No C - Clay 0 Not Applic NON - No	
SO 90936 24979 390936 224979 27 <7* N/A PGR 0 22 22 2.5Y4/4	31
SO 90936 24979 390936 224979 27	
22 48 26 2.5Y5/3 CD-C/7.5YR4/6 Yes C-Clay 0 Poor NON-No Yes 48 120 72 2.5Y6/2 CD-C/7.5YR4/6 Yes C-Clay 0 NON-No Yes SO 91026 24998 391026 224998 27 <7* N/A PGR 0 22 22 2.5Y5/3 CD-C/7.5YR4/6 Yes C-Clay 0 Non-No No N	
22 48 26 2.5Y5/3 CD-C;7.5YR4/6 Yes C-Clay 0 Poor NON-No Yes 48 120 72 2.5Y6/2 CD-C;7.5YR4/6 Yes C-Clay 0 NON-No No N	
22 48 26 2.575/3 CD - C7.5784/6 Yes C - Clay 0 Poor NON - No Yes Yes C - Clay 0 Poor NON - No Yes SO 91026 24998 391026 224998 27 < 7* N/A PGR 0 22 22 2.575/3 CD - C7.5784/6 Yes C - Clay 0 No	
22 48 26 2.5Y5/3 CD-C7.5YR4/6 Yes C-Clay 0 Poor NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NNO	
22 48 26 2.5Y5/3 CD-C7.5YR4/6 Yes C-Clay 0 Poor NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NON-NNO Yes Yes C-Clay 0 Poor NON-NNO NNO	31-
SO 91026 24998 391026 224998 27 <7" N/A PGR 2 2 2 2 2.5Y5/3 CD - C7.5YR4/6 Yes C - Clay 0 Poor NON - No Ves SO 91026 24998 391026 224998 27 <7" N/A PGR 2 2 2 2.5Y5/3 CD - C7.5YR4/6 Yes C - Clay 0 Not Applic NON - No No 16 -1 2 WC III 3b Moderate NON - No No No 16 -1 2 WC III 3b Moderate NON - No	5.
22 44 22 2.5Y5/3 CD-Ci7.5YR4/6 Yes C-Clay 0 Moderate NON - No No No 44 84 40 2.5Y5/6 MP - N 7.5YR4/6 Yes C-Clay 0 Poor NON - NYes Yes	
22 44 22 2.5Y5/3 CD-Ci7.5YR4/6 Yes C-Clay 0 Moderate NON - No No No 44 84 40 2.5Y5/6 MP - N 7.5YR4/6 Yes C-Clay 0 Poor NON - NYes Yes	
22 44 22 2.5Y5/3 CD-C:7.5YR4/6 Yes C-Clay 0 Moderate NON - NNO NO 44 84 40 2.5Y5/6 MP-N7.5YR4/6 Yes C-Clay 0 Poor NON - NYes Yes	
22 44 22 2.5Y5/3 CD-Ci7.5YR4/6 Yes C-Clay 0 Moderate NON - No No No 44 84 40 2.5Y5/6 MP- \(\) \	
22 44 22 2.5Y5/3 CD-Ci7.5YR4/6 Yes C-Clay 0 Moderate NON - No No No 44 84 40 2.5Y5/6 MP- \(\) \	21-
44 84 40 2.5Y5/6 MP - N.7.5YR4/6 Yes C - Clay 0 Poor NON - NYes Yes	5.
SO 90622 25967 390622 25967 23 <7" N/A CER 0 24 24 2.5Y4/4 No SCL-San/6 2 0 GH-Gravel with non-porous (hard) stones Not Applic SC-Silg No No -20 -28 3a WCl 1 Droughtiness	2.
24 40 16 2.544/4 FF-Fe7.5YR4/6 No SCL-San 6 GH-Gravel with non-procus (hard) stones (Moderate SC-Slig No No	36
40 60 20 2.544/2 MD-h7.5784/6 No SC-Sand/70 GH-Gravel with non-porous (hard) stones Moderate ISC-Slig No No	
60 120 60 2.5Y6/6 MD - N - S.5Y8.4/6 No SC - Sand 70 GH - Gravel with non-porous (hard) stones Moderate SC - Slig No No	
SO 90702 25639 390702 25639 24 <7" N/A CER 0 30 30 2.5Y4/2 No SCL-San 6 4 0 GH-Gravel with non-porous (hard) stones Not Applic SC-Silg No No -11 -13 3a WCl 1 Droughtiness	2-
SU 9U/02 20039 39U/02 220039 24 < 7" N/A CER U 3U 3.5 25 2.5YE/4 NO SLC-3anlb 4 U 6H-Gravel with non-porous (lnard) stones Not ApplicibL-3legNo No -11 -13 3a WCL 1 Urougntiness 30 58 28 2.5YE/4 No SCC-3anlb 6 GH-Gravel with non-porous (lnard) stones Moderate (SC-5ligNo No	138
30 58 26 2-515/4 NO SCLT-Samp On - Gravel With non-porous (Inata) stones mouterate SC Singlyo NO SCLT-Samp On - Gravel With non-porous (Inata) stones Moderate SC Singlyo NO SCLT-Samp On Scit-Samp On Scit-Sam	
END END	

Mottle form

FF - Few Faint

FD - Few Distinct

FP - Few Prominent

CF - Common Faint

CD - Common Distinct

CP - Common Prominent

MF - Many Faint

MD - Many Distinct

MP - Many Prominent

VF - Very many Faint

VD - Very many Distinct

VP - Very many Prominent

Texture

C - Clay

CHK - Chalk

CS - Coarse Sand

CSL - Coarse sandy loam

CSZL - Coarse sandy silt loam

FP - Fibrous and semifibrous peats

FS - Fine Sand

FSL - Fine sandy loam

FSZL - Fine sandy silt loam

HCL - Clay loam (heavy)

HP - Humified peats

HZCL - Silty clay loam (heavy)

IMP - Impenetrable to roots

LCS - Loamy Coarse Sand

LFS - Loamy fine sand LMS - Loamy medium sand

LP - Loamy peats

MCL - Clay loam (medium)

MS - Medium Sand

MSL - Medium sandy loam

MSZL - Medium sandy silt loam

MZ - Marine Light Silts

MZCL - Silty clay loam (medium)

OC - Organic clays

OL - Organic loams

OS - Organic sands

PL - Peaty loams

PS - Peaty sands

SC - Sandy clay

SCL - Sandy clay loam

SP - Sandy peats

ZC - Silty clay

ZL - Silt loam

Stone Type

CH - Chalk or chalk stones

FSST - Soft fine grained sandstones

GH - Gravel with non-porous (hard) stones

GS - Gravel with porous stones (mainly soft stone types listed above)

HR - All hard rocks or stones (i.e. those which cannot be scratched with a finger nail)

MSST - Soft, medium or coarse grained sandstones

SI - Soft 'weathered' igneous or metamorphic rocks or stones

SLST - Soft oolitic or dolomitic limestones

ZR - Soft, argillaceous or silty rocks or stones

Ped. Shape

SG - Single grain GRA - Granular

SAB - Subangular Blocky

AB - Angular Blocky

PRIS - Prismatic PLAT - Platy

MASS - Massive

NA - N/A

Subsoil Structure Condition

Not Applicable

Good

Moderate

Poor

Soil or Ped. Strength

Loose

Very friable

Friable

Firm

Very firm

Extremely firm Extremely hard

N/A

Calcareousness

NON - Non-calcareous (<0.5% CaCO3)

VSC - Very slightly calcareous (0.5 - 1% CaCO3)

SC - Slightly calcareous (1 - 5% CaCO3)

MC - Moderately calcareous (5 - 10% CaCO3)

VC - Very calcareous (>10% CaCO3)

Ped. Size

VF - Very Fine

F - Fine

M - Medium

C - Coarse VC - Very Coarse

NA - N/A

Degree of Ped. Development

W - Weak

M - Moderate

S - Strong

NA - Not applicable

Wetness Class

WC I

WC II

WC III

WC V

WC VI

ALC Grades

L

2 3a

3b

4 5

Non-Ag

Gley

None Gley

N/A

Appendix 2: Soil Pit Description

Soil Survey							Surveyor	RWA
Easting (X)	390474	Northing (Y)	224035	Alt (m) 27			Grid Reference	SO 90474 24035
Land Use	PGR	Reference	2 (GR305280) Pit 1	Slope °	<7°		Date	17/05/2022
Bedrock		Superficial	None Recorded	Aspect	N/A		Date	17/05/2022
		T		1 2	1 4		1 6	
Lay	/er	Topsoil	2	3	4	5	6	7
Lower Depth (cm)		18	42	60	120			
Texture		•	C - Clay	C - Clay	C - Clay			
Matrix Colour		2.5Y4/3	2.5Y5/3	5Y4/3	5Y5/3			
Gley (Y/N)		No	Yes	Yes	Yes			
Ochreous Mottles	Form							
Octificous Mottics	Munsell Colour							
Grey Mottles	Form							
diey Mottles	Munsell Colour							
Manganese (Y/N)		No	No	Yes	Yes			
% Stones (type 1)		0	0	0	0			
Stones > 2cm								
Stones > 6cm								
Stone Type								
% Stones (type 2)								
Stones > 2cm								
Stones > 6cm								
Stone Type								
CaCO3		VSC - Very slight	SC - Slightly calcareous (1	SC - Slightly calc	MC - Moderately	calcareous	(5 - 10% CaCO3)	
Shape of Peds.			AB - Angular Blocky		PRIS - Prismatic		Ì	
Size of Peds.			C - Coarse	C - Coarse	C - Coarse			
Subsoil Structure			Moderate	Poor	Poor			
		Firm	Firm	Firm	Firm			
Degree of Ped. Dev		M - Moderate	M - Moderate	W - Weak	W - Weak			
Degree of rea. Development		moderate		can			ļ	

MDw	MDp	FCD
113	107	139

No

No

Slowly Permeable Layer (Y/N)

Wetness	Class (WC)	WC III
wethess	Grade (WE)	3b

Notes	
INOLES	

Yes

Yes

Appendix 3: Topsoil Texture Analysis



ISSUED BY SOIL PROPERTY TESTING LTD **DATE ISSUED: 10/06/2022**

Contrac	ontract J10 M5 Agricultural Land Classification							
Serial N	0.	40801_1						
Client:	Askew La	and and Soil Ltd		Soil Pro	perty T	esting Ltd		
	The Old Stables Upexe Exeter			15, 16, 18 Halcyon Court, St Margaret's Way, Stukeley Meadows, Huntingdon, Cambridgeshire, PE29 6DG				
	EX5 5ND			Tel: 01480 455579 Email: enquiries@soilpropertytesting.com Website: www.soilpropertytesting.com				
Samples	Submitte	=		Approved Signator	ies:			
	Askew La	and and Soil Ltd		☑ 1	.C. Garner B.Er	ng (Hons) FGS tor & Quality Manager		
Samples	Labelled:					, ,		
	J10 M5 A	Agricultural Land Clas	sification	□ W. Johnstone				
				Materials Lab Manager				
Date F	Received:	19/05/2022	Samples	Tested Between:	19/05/2022	and 10/06/2022		
Remarks: For the attention of Robert Askew Your Reference No: C884								
Notes:	1	All remaining samples o unless we are notified to			e disposed of afte	er 21 days from today,		
	2	2 Opinions and interpretations expressed herein are outside the scope of UKAS accreditation.						
	3 Tests marked "NOT UKAS ACCREDITED" in this test report are not included in the UKAS Accreditation Schedule for this testing laboratory.							
	4	This test report may not issuing laboratory.	t be reprodu	uced other than in full e	xcept with the prid	or written approval of the		
	5	The results within this report only relate to the items tested or sampled.						



ISSUED BY SOIL PROPERTY TESTING LTD DATE ISSUED: 10/06/2022



998

Contra	act		J10 M5	J10 M5 Agricultural Land Classification												
Serial	No.		40801_	1								Targ	get [Dat	е	16/06/2022
Sched	uled	Ву	Askew	Land a	nd So	oil Lto	d									
Schedi	ule R	emarks														
Bore Hole No.	Туре	Sample Ref.	Top Depth	23/11/2	site disti	ibution	\$51317									Sample Remarks
GR305280	Α	1	0.00	1												
5R429408	С	7	0.00	1												
	•	Totals		2												End of Schedule



ISSUED BY SOIL PROPERTY TESTING LTD DATE ISSUED: 10/06/2022




naag

Contract	J10 M5 Agricultural Land Classification
Serial No.	40801_1

DETERMINATION OF PARTICLE SIZE DISTRIBUTION Sample Borehole / Depth Description Remarks Pit No. Reference (m) Type 0.00 -Light olive brown slightly sandy silty CLAY with occasional olive yellow Material greater than 2mm removed GR305280 Α 1 mottling, decayed roots and rare gravel before test 0.25

Method of Test: Hydrometer + Pre-sieve Method of Pretreatment: Not required



CLAV	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLES	BOULDERS
CLAY	SILT			SAND			GRAVEL		COBBLES	POOLDEK3	

Н	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)
y d	0.0332	82	
r	0.0235	81	32
О	0.0168	78	
m	0.0088	72	Clay by
e	0.0063	66	Dry Mass
t e	0.0045	64	(%)
r	0.0029	58	
	0.0014	53	55

Sieve Size (mm)	Passing (%)	Sand By Dry Mass (%)
2.00	100	
1.18	100	
0.600	99	
0.425	98	13
0.300	95	13
0.212	91	
0.150	88	
0.063	87	

Fines By Dry Mas	ss (%)
<0.063mm	87

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		
125		
90		
63		
50		
37.5		0
28		U
20		
14		
10		
6.3		
5		

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5

Method of test: BS1377: Part 2: 1990: 9.2,9.5

Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter

Comments:



ISSUED BY SOIL PROPERTY TESTING LTD DATE ISSUED: 10/06/2022




าดดด

Contract	J10 M5 Agricultural Land Classification
----------	---

Serial No. 40801_1

DETERMINATION OF PARTICLE SIZE DISTRIBUTION Depth Sample Borehole / Description Remarks Pit No. Reference (m) Type Light olive brown slightly gravelly sandy silty CLAY with occasional 0.00 -Material greater than 2mm removed GR429408 С 7 yellowish brown mottling and decayed roots. Gravel is white, brown and before test 0.25 grey fine and medium subangular and subrounded

Method of Test: Hydrometer + Pre-sieve Method of Pretreatment: Not required



CLAV	Fine	Medium	Coarse	Fine	Medium	Coarse	Fine	Medium	Coarse	COBBLEC	BOULDERS
CLAY		SILT		SAND		GRAVEL		COBBLES	BOOLDEKS		

Н	Particle Size (mm)	Passing (%)	Silt by Dry Mass (%)
y d	0.0349	32	
r	0.0250	29	18
О	0.0178	28	
m	0.0094	23	Clay by
e	0.0067	22	Dry Mass
t e	0.0048	21	(%)
r	0.0031	20	
	0.0015	18	19

Sand By Dry Mass (%)	Passing (%)	Sieve Size (mm)
	100	2.00
	99	1.18
	97	0.600
63	92	0.425
03	74	0.300
	51	0.212
	42	0.150
	37	0.063

Fines By Dry Mass (%)				
<0.063mm	37			

Sieve Size (mm)	Passing (%)	2mm+ By Dry Mass (%)
300		
125		
90		
63		
50		
37.5		0
28		U
20		
14		
10		
6.3		
5		

Method of Preparation: BS1377: Part 1: 2016: 8.3 & 8.4.5
Method of test: BS1377: Part 2: 1990: 9.2,9.5

Type of Sample Key: U=Undisturbed, B=Bulk, D=Disturbed, J=Jar, W=Water, SPT=Split Spoon Sample, C=Core Cutter

Comments:



5th Floor, Block 5

Shire Hall Bearland Gloucester GL1 2TH

Tel: +44 (0) 8000 514 514