

Able Humber Ports Ltd

Rosper Road Loop

Feasibility Study



B90391-REP-TPL0001

Version P03

Final Issue

October 2013



	Authorisation Sheet	
Client:	Able UK Ltd on behalf of Able Humber Ports Ltd.	
Project Title:	B90391 Killingholme Port Rail Access	
Address:		
Prepared By:		
Name:	Vladimir Rangelov	
Signature:	Ph	
Position:	Senior Consultant and Transport Engineer	
Date:	14 th October 2013	
Checked By:		
Name:	Howard Pack	
Signature:	H. Pack	
Position:	Principal Consultant	
Date:	14 th October 2013	
Authorised By:		
Name:	John Barnard	
Signature:	Protot	
Position:	Associate Director	
Date:	14 th October 2013	

Notice:

It should be clearly understood that this document is intellectual property and copyright of Tata Steel UK Rail Consultancy Limited trading as Tata Steel Projects. It may not be used by any person for any other purpose other than that specified without the express written permission of Tata Steel Projects. Any liability arising out of use by a third party of this document for purposes not wholly connected with the above shall be the responsibility of that party who shall indemnify Tata Steel Projects against all claims, costs, damages and losses arising out of such use.

Docume	Document History										
Version No.	Approved by Date	Description	Prepared By	Reviewed By	Approved By						
P01	20/11/2012	Initial issue	HP	VR	HP						
P02	20/09/2013	Final issue	HP	VR	JB						
P03	14/10/2013	Report name amended, vertical profile, costs and comparison added.	VR	HP	JB						

Table of Contents

		Page No.
Execu	ıtive Summary	5
1.0	Scope of Works	7
2.0	Design Brief	8
2.1	Data Requirements	8
2.2	Methodology	8
2.2.1	Constraint Mapping	8
2.2.2	Site visit and workshop	8
3.0	Description of Route	8
3.1	Interfaces with other projects	9
3.2	Operating Assumptions	9
4.0	Findings	9
4.1	Rosper Road at Ground Level	10
4.2	Rosper Road Lifted	10
4.3	Rosper Road – Assessment of options	11
4.3.1	Rosper Road – road over railway bridge	11
4.3.2	Rosper Road – railway over road bridge	12
4.4	Earthworks	12
4.4.1	Geology	12
4.4.2	Geotechnical Constraints	13
4.4.3	Embankment Construction	13
4.4.4	Option 1a	14
4.4.5	Option 1b	14
4.4.6	Foundations	14
4.4.7	Ground Investigation	14
4.5	Underline Structures	15
4.5.1	Rosper Road	15
4.5.2	Option 1a	16
4.5.3	Option 1b	17
4.5.4	Combined Accommodation Track and Land Drain Bridge	17
4.5.5	Culverts	18
4.6	Signalling and Control	18
4.7	Operations	18
4.8	Environment	19
4.8.1	Statutory Order	19

4.8.2	Consents, Licences and Consultation	21
4.9	Cost Estimates	21
5.0	Conclusions	22
6.0	Recommendations	22

Appendices:

Appendix A: Drawings

Appendix D: Estimates

Appendix B: Risk Register
Appendix C: IDC Certificate

Executive Summary

Able Humber Ports Ltd (AHPL) wish to develop land in North Killingholme for Able Marine Energy Park (AMEP) and Able Logistics Park (ALP). The land is traversed by the existing Killingholme Branch Railway. As part of the development AHPL wish to have unimpeded access across the railway line for wind turbine assembly.

Network Rail has advised AHPL that it wishes to create a circular through route from the Ulceby to Barton line onto the Killingholme line and re-instate the disused part of the Killingholme Branch near Goxhill. This would result in an intensification of train services through the Marine Energy Park. The driver for these extra services is the Aire Valley Power Stations changing over to biomass consumption from coal to meet environmental requirements. Due to the reduced density of wood compared to coal, nearly twice as many trains are required to deliver the same calorific output.

AHPL wish to offer an alternative solution to Network Rail whereby a new shorter and cheaper Rosper Road Loop is constructed between new junctions at South Killingholme on the Immingham to Ulceby line (BRI2) and the Barton and Immingham Light Railway (KIL2). The new chord would form a triangular junction onto the Barton and Immingham Light Railway with one fork facing North towards the Able Marine Energy Park site and one fork facing South towards the Humber International Terminal (for coal and biomass) and Immingham Bulk Terminal (for coal and iron ore).

The operating and business logic is to provide a balloon shaped railway infrastructure for coal and biomass trains. Empty trains would use the new chord line and load at Humber International Terminal and Immingham Bulk Terminal and depart loaded via the existing railway.

This study is an early feasibility study into the constraints and options.

Of the options considered, only Option 1, the most Southerly option was considered viable by both client team and the study. This option has to interface with the existing Highways Authority scheme for an improvement of the A160's T-junction with Rosper Road. This presents issues over how the railway should cross Rosper Road. The conclusion of the study is that it should be by the railway crossing over the road, subject to a satisfactory gradient being achieved on the railway.

Two sub-options have been developed: -

- Option 1a has a shorter bridge over Rosper Road, but sharper curvature and it traverses poorer ground requiring more extensive engineered embankments;
- Option 1b has a longer viaduct over Rosper Road, but better curvature and it traverses better ground West of Rosper Road allowing normal embankments to be constructed there.

On initial costing Option 1b is the preferred option, but this will need to be confirmed by ground investigations and local survey. The length of the chord line is 1625 metres in the feasibility railway design. The costs of the new chord are preliminarily estimated at £38 million including contingency.

A comparison should be made with the original 2008 proposal to reinstate the closed KIL3 section of the Barton and Immingham Light Railway with a chord line at Goxhill, but without any upgrade to the section to Thornton Abbey of the Ulceby to Barton Line. The estimated costs, for the preferred Option C adjusted for inflation to Q4 2012 are £41m. It was considered at the time that any upgrade to the Ulceby to Thornton Abbey section could cost a further £15m, though no detailed work was undertaken on that.

The new shorter Rosper Road Loop will require the current Development Consent Order for the Able Marine Energy Park to be amended or a fresh Transport and Works Act Order under the 2013 regulations for railway works under 2 miles length to be procured.

The conclusion of the study is a new chord line is technically feasible, more readily constructible alternative to the Goxhill scheme and less controversial for the public.

It is a viable alternative to the previous proposal to provide a link to Immingham by re-instating the closed KIL3 section of the Barton and Immingham Light Railway with a chord line at Goxhill.


1.0 Scope of Works

The objective is to produce a feasibility study with budget costs, for a new railway linking the existing Killingholme Branch Line directly with the Immingham to Brocklesby Line to the South of the proposed Able Marine Energy Park.

Able Humber Ports Ltd.'s preferred route is Option 1 as shown on attached plan – AME – 06103A.

The study should indicate whether the railway should be carried by a bridge over Rosper Road, or whether Rosper Road should be lifted on a bridge over the new railway.

The study will ignore issues regarding land ownership and any costs associated therein.



Plan 1 – Extract from Drawing AME – 06103A

2.0 Design Brief

2.1 Data Requirements

Able Humber Ports Ltd is progressing a Development Consent Order Application for the Able Marine Energy Park and has supplied Tata Steel Projects with the available data from this project.

Tata Steel Projects has supplemented this information with available GIS data, additional LIDAR data and previous survey data.

2.2 Methodology

2.2.1 Constraint Mapping

Tata Steel Projects has built a GIS based constraints map of the proposed route. This includes all known environmental features, land use and geological information. This has been supplemented by a site walk through by our engineering team. A preliminary alignment was then produced.

2.2.2 Site visit and workshop

A site visit was undertaken to verify the constraints map and examine the suitability of the preliminary alignment. Then feasible alignments were drawn up. An interdisciplinary workshop was then held to define the environmental and engineering issues and risks.

3.0 Description of Route

The route commences with a junction off the existing Humber Commercial Railway from Brocklesby to Immingham (Engineer's Line Reference BRI2) at approximately 103¾ miles at South Killingholme. It curves in an Easterly direction towards Rosper Road over derelict land, crosses Rosper Road and traverses grazing land attached to Hazel Deane Farm, running parallel to a North Lincolnshire Council Site of Importance to Nature Conservation. It then forks in a northerly direction to join the Barton and Immingham Light Railway (Engineer's Line Reference KIL2). A southern fork is also possible forming a triangle towards the Barton and Immingham Light Railway (Engineer's Line Reference KIL2) and ABP's Humber International Terminal.

The route crosses a buried gas pipeline near its commencement point, an elevated disused gas pipeline near Rosper Road, a buried gas pipeline adjacent to Rosper Road and an elevated gas pipeline near the junction with the Killingholme Branch.

Between the Humber Commercial Railway and Rosper Road the route crosses land susceptible to surface water flooding with little apparent land drainage. Between Rosper Road and the Killingholme Branch there are land drains and the ground is less susceptible to surface water flooding. The nearest habitation is Hazel Deane Farm. The route will reduce the farm's available grazing land.

3.1 Interfaces with other projects

The route will need to interface with the existing Network Rail and Associated British Ports (ABP) project to provide additional capacity at Humber International Terminal for imported coal and biomass traffic.

The Highways Agency are currently developing a scheme for the A160 Humber Road and Rosper Road Junction. This may be completed before the construction of the new railway.

Network Rail are also undertaking a signalling re-control project on the Immingham to Brocklesbury line. The interface with this project and the timescales will need to be understood.

It will also need to interface with AHPL's projects at AMEP and ALG and the C.Ro and C.Gen projects.

3.2 Operating Assumptions

For the purposes of this study we have assumed that the new railway will be a single bi-directional track able to hold a 775m long train clear of the Immingham to Brocklesbury line and the Killingholme Branch. The line-speed is assumed to be 30 mph; this could be increased to 40mph, except that the speed on the Humber Commercial Railway is limited to 30mph at this point.

The curve and junction onto the Killingholme Branch (KIL2) is limited to 25 mph.

The gradients on the new line need to be adequate for the normal operation of 2,500 tonne trains hauled by a Class 66 locomotive.

A 30/40 mph trailing crossover may need to be provided on the Immingham to Brocklesbury line adjacent to the new connection. This should replace the existing 10mph trailing crossover.

The Northern facing fork onto the Killingholme Branch needs to access the existing Killingholme Branch.

The Southern facing fork needs to access the Humber International Terminal and possibly any repositioned facility at Immingham Bulk Terminal.

The new railway, for the purposes of this study is assumed to be operated as part of the national network, controlled by Network Rail, though it could be operated by another company regulated or exempted by the ORR.

4.0 Findings

Options 2 and 3 have been discarded at an early stage due to the impracticality of making a junction with the existing Humber Commercial Railway. At the proposed junction point there is an extensive network of gas pipelines for the Conoco Oil Refinery and an existing junction for the Total UK refinery.

Option 1 allowed the junction to be placed immediately East of the pipelines at the Conoco Oil Refinery and the existing junctions. However Option 1 will cross the proposed A160 Humber Road and Rosper Road new traffic gyratory junction. The initial optioneering thus is concentrated on the practicality of crossing Rosper Road at this location. Two possibilities are considered: Rosper Road remaining at ground level and Rosper Road lifted over a Railway at or near to ground level.

As the project developed the difficulty of lifting Rosper Road over the new Railway became apparent and the Option 1 progressed with the Railway on a bridge over Rosper Road instead. Two sub-options for the railway route were developed in response to geo-technical issues. These two sub-options were costed and this favoured Option 1b where the railway kept to the better ground.

4.1 Rosper Road at Ground Level

The rail over-bridge would need to be made wider than the current highway width to allow any future dualling of Rosper Road and also for the Highways Agency's scheme for a gyratory link road at the A160 Humber Road and Rosper Road Junction.

The proposed bridge would also have to be made wider on the west side to accommodate the visibility splay of the new gyratory link road and the safety fencing protecting the structure.

The carriageway cannot be lowered due to the heavy congestion of services beneath the carriageway and adjacent verges, including a high pressure gas main.

The proposed large embankment adjacent to the wetlands area may push up levels within the wetland and thus dry out the area. The embankment may also prevent the existing horizontal water egress, possibly requiring several culverts beneath it. These significant issues will need to be consulted on with the Environment Agency and the Internal Drainage Board.

4.2 Rosper Road Lifted

Rosper Road can be lifted above the proposed railway assuming the following: -

- The rail level at the existing road is 4.0m AOD maximum: -
- The length available to lift the road is 240m;
- The required headroom is 5.45m;
- The depth from the road centreline to bridge soffit is 1.5m maximum.

To achieve this the geometry will need to be as follows: -

- South of the bridge the road will start to rise from it's existing level on a 2000m radius 'absolute minimum' sag curve;
- The sag will be followed by a 4.5% gradient;
- Between the gradient and the bridge will be a 1700m radius '1 step relaxation' crest curve;
- The crest curve will result in a '1 step relaxation' in stopping sight distance of 90m, the combination of that and the crest curve resulting in a 'departure from standard' (the departure is to avoid excessive land take, but a full standard curve could be used if needed);

- The alignment will have to come off-line to avoid effecting the existing wetlands and associated ditch, although this will make traffic phasing easier;
- The proposed new link and abnormal load route would become unviable due to height differences, meaning that the existing Humber Road railway bridge would have to be widened to accommodate a dual carriageway, including the changing the Rosper Road/Humber Road junction;
- The abnormal load route may be disrupted;
- The fire station entrance would have to be modified.
- The embankment may prevent the existing horizontal water egress, possibly requiring many culverts beneath it. This option will also require a road drainage system separate from ditches draining the surrounding embankments. This will probably require a balancing pond with oil interceptor and penstock to prevent spillages contaminating the surrounding water bodies. These significant issues will need to be consulted on with the Environment Agency and the Internal Drainage Board.
- Adjacent to the new link the proposed rail bridge will have to be set back enough to allow the 120m sightline and parapet/safety fencing in front of the abutment/wing-wall.

Three large culverts will be required under the proposed embankment to link the ditches beneath, at least one needing to have a diameter larger than 1.8 m and thus a structure. Also, the Environment Agency may insist on multiple additional smaller culverts to allow water and wildlife egress, plus new ditches at the bottom of one or both sides of the embankment.

The site access may need traffic lighting and a 3m wide haul road is sufficient.

4.3 Rosper Road – Assessment of options

All options will require the Highways Agency, Environment Agency and Internal Drainage Board to be consulted. The Highways Agency will require any subsequent change to their design to be done by their chosen consultant subject to their procedures and timescales. This will then be charged to Able Humber Ports Ltd. Pell Frischmann (the initial consultant on the proposed A160T highways scheme) identified water voles and amphibian habitat in the surrounding ditches and fields.

4.3.1 Rosper Road – road over railway bridge

The practicality of lifting Rosper Road over the railway is subject not only to the engineering issues for the interface between road and railway, but to the progress of the wider highway scheme. It would need a change in the concept of the scheme to one where the existing Humber Road railway over-bridge is widened to a accommodate a dual carriageway with an improved junction between Humber Road and Rosper Road. It would also affect local access to the fire station. The drainage issues would be similar to those for the other option. In addition altering the proposed Rosper Road layout would render the railway scheme liable for the costs of the highway scheme under a Highways Act 1980 Section 278 agreement.

4.3.2 Rosper Road – railway over road bridge

The option with the railway crossing the road is also not without difficulties. Besides the engineering construction issues, the gradients on the new railway are critical. For a heavy freight railway the desirable maximum gradient is 1 in 150. This cannot be achieved.

A satisfactory gradient of 1 in 127, compensated for curvature is achievable with a soffit height of 5.7. This height is recommended to mitigate the risk of bridge strikes.

This will require the hog (or crest) vertical curve for the railway to be on the bridge over Rosper Road. The railway will climb from a new junction near the Conoco Oil Refinery to the road intersection and then drop to the junction with the existing Killingholme Branch line. The gradients are severely affected by the required road to soffit heights.

If Rosper Road is required to convey high loads, then a road to soffit height of 6.45m is required. This is likely to worsen the railway gradients and train performance to the extent that the freight train loads could be reduced for existing traffic or severely constrained for new traffic. At this point the option to lift Rosper Road over the railway should be considered.

The engineering construction issues relate to the difficulty and extent of earthworks required to lift the new railway over Rosper Road. These are discussed below.

However the railway bridge over Rosper Road option effectively avoids complications with the highway layout, de-risking the project. This would be the preferred option, unless the Highways Agency is willing to amend their scheme at nil or low cost to Able Humber Port Ltd.

4.4 Earthworks

Following our visit to the Killingholme chord line site on the 8th November 2012, the geotechnical setting have been reviewed to identify constraints that are anticipated to be relevant to the site. This review has been based around the scheme alignment as discussed on site as illustrated on the drawing B90391-DRG-PWY0001 P05, B90391-DRG-PWY0002 P01 and GIS data sources.

4.4.1 Geology

An assessment of the geological setting has been undertaken based on information publically available, in the form, of the geological map and historic logs held by the British Geological Survey in the general location. In addition, the Client has provided a Ground Investigation report associated with a proposed development on a site adjacent to the proposed route (Biomass Power Station proposal).

The likely ground conditions are summarised below:

- MADE GROUND: Made Ground may be present in localized areas along the route associated with past activities on the site. However, any Made Ground present is likely to be limited in its vertical extent.
- TIDAL FLAT DEPOSITS: Present from Ground Level to in the region of between 3m (north) and 8m (South). Tidal flat deposits are considered likely to be present along the majority of the route, and will likely comprise of a sandy SILT overlain by a firm clay crust,

characteristic of these deposits. Evidence from borehole logs indicates that organic and peat material may be present. Commonly contain a high moisture content.

- GLACIAL TILL: Likely present across the site beneath the Tidal Flat Deposits and above the Bedrock.
- CHALK: Bedrock geology likely present in the region of 12 to 26m below ground level (shallower towards the south)

4.4.2 Geotechnical Constraints

The following geotechnical constraints have been recognized:

- Highly compressible ground (Tidal Flat Deposits)
- Additional loading on the existing earthworks
- Differential settlement at the transition zone (transfer deck) between bridging structures and the embankment, and between the existing earthworks and the new embankment earthworks
- Washout channels at the top of the till creating a greater thickness of the compressible deposits
- Glacial Erratic's present within the Glacial Till could offer obstructions to piling works
- Other geological features which may impact on the design including meta-stable soils in sink holes and the presence of wind blown sands.

4.4.3 Embankment Construction

Settlement associated with the additional load associated with the creation of an embankment on the compressible deposits (Tidal Flat Deposits) could be minimised through the use of: -

- Replacement of soil with lighter alternative products to construct the embankment, including the use of expanded polystyrene (EPS) blocks
- The placement of an engineered Geogrid at the base of the embankment to spread the load and to provide the required stiffness.
- The use of piles or stone columns beneath the embankment to support the embankment and to provide a narrower embankment, due to the potential of peat deposits a grouted stone column solution may be required.

The UIC Code 719R recommends for highly compressible soils with organic content: -

"Grouted stone columns, premixed and concrete columns: In very soft soil or soil with organic layers columns can be formed by injecting binder into the stone or gravel column. Alternatively pre-mixed materials can be used. To have a proper load distribution among the columns a cap layer with re-inforcement (for example Geogrids) above the columns may be necessary. "

"Lightweight fill materials: When it is necessary either to construct a new line or restore an existing line with a peat subgrade, it is necessary to limit additional loads. This can be achieved by using lightweight material (expanded clay, expanded polystyrene) which is confined by a geotextile and protected by a layer of gravel beneath the ballast layer."

Consideration is required for the placement of an embankment parallel to any drainage ditches, and a stability assessment would be required to assess the impact on the ditch from the addition surcharge associated with the embankment. A structure solution may be more suitable at the interface with the drainage ditch forming part of the Nature Reserve.

4.4.4 Option 1a

Option 1a is built entirely over the Tidal Flat Deposits and will require extensive engineered embankments throughout. It has the advantage of a shorter bridge over Rosper Road. See drawing B90391-DRG-PWY0002 P01 for details.

4.4.5 Option 1b

Where practicable he railway should be constructed on the areas where Glacial Till can provide load bearing and a normal embankment constructed. Glacial Till has good load bearing capabilities. These locations are shown on the British Geological Survey GIS data and the site visit noted a correlation between the GIS data and locations of dense vegetation where Glacial Till was likely to be present near the surface and other locations supporting grasses that may indicate the presence of Tidal Flat Deposits. This will need to be confirmed by borehole data and soil tests.

See drawings B90391-DRG-PWY0001 P05 and B90391-DRG-PWY0005 P01 for details.

Option 1b has been developed to site the railway West of Rosper Road directly on the Glacial Till deposits, thereby allowing normal embankments to be constructed. This is at the expense of a longer viaduct over Rosper Road. East of Rosper Road the route is constructed on Tidal Flat Deposits and follows a similar route to Option 1a.

4.4.6 Foundations

The bridge structures would need to utilise a piled solution as the Tidal Flat Deposits would not provide adequate bearing capacity for shallow foundations. The underlying Glacial Till would be a suitable bearing stratum for the piles. The presence of Glacial Till at a shallow depth than presumed near Rosper Road could remove the need for piles.

4.4.7 Ground Investigation

A ground investigation is required along the proposed route to ascertain the ground conditions at the site. The ground investigation should be designed to prove the thickness of the Tidal Flat Deposits as well as the bearing capacity of the underlying Glacial Till. This should be done early in the design to fully identify the design constraints.

4.5 Underline Structures

4.5.1 Rosper Road

To accommodate the proposed chord linking the Killingholme Branch Lline (KIL2) to the Immingham to Brocklesbury Line a new structure is required to bridge over Rosper Road (OS Ref: TA 171 169).

Rosper Road is a busy carriageway providing access to various oil refinery facilities in the Killingholme area.

Two track alignments have been considered; Option 1a requires a 50 to 55m long under-bridge and Option 1b requires an approximately 150m long viaduct structure.

The normal road to soffit headroom is 5.3m. This would provide a gradient of 1 in 142 on the Western side and 1 in 130 on the Eastern side. However this could be susceptible to bridge strikes. The deck strength would need to be assessed and sacrificial beams may be required over the carriageway.

The new bridge should provide 5.7 metre clear headroom to be deemed unsusceptible to road vehicle impact ("Bridge Strike"). This would avoid the possible need for sacrificial beams. However the compensated gradients would worsen to 1 in 127 on the Western side and 1 in 121 on the Eastern side. These gradients are on the limit of being operable with heavy freight trains. See drawing B90391-DRG-PWY0005 P01 for details.

There is a risk that Rosper Road could be designated a High Load route in which case a 6.45m headroom would be required. There is route indicated by the Highways Agency (HiR22) in the Immingham area and clarification of requirements will need to be undertaken at the next stage of development. This would worsen the gradients still further to 1 in 102 on the Western side and 1 in 98 on the Eastern side. At this point the option to take the road over the railway should be considered.

The gradient of the railway either side of the structure is steep to enable the new track to tie back into the existing railway formation at either end. The 'construction depth' is the vertical dimension between the tops of the rails and the bridge soffit and should be kept to minimum to maintain lowest possible track gradients.

Ground conditions throughout the site are variable. The available information shows at the proposed structure location the ground is formed from a thick band of Tidal Flat Deposits overlaying a band of Glacial Till further overlaying chalk. A primary aquifer is contained within the chalk. The Tidal Flat Deposits are structurally weak and therefore the substructure of the bridge will have to be formed on pile foundations socketed in the Glacial Till strata.

It is known that there are numerous services running adjacent to the west side of Rosper Road between the carriageway and the ditch. It is assumed that the cost of diverting these services far outweighs the cost of bridging over them, which is why only a single span option has been considered for Option 1.

4.5.2 Option 1a

To minimise construction depth a transversely spanning composite deck is proposed supported by outer longitudinal main girders. The composite deck is formed from transversely spanning universal columns at 1.5 m centres encased in concrete. The concrete slab is launched between cross girders down to bottom flange level to reduce the deck self-weight. The main girders are formed from steel plate girders – See figure 1.




Figure 1: D-type Bridge

The construction depth of this deck will be approximately:

Deck slab = 500mm

Bottom Flange thickness = 100mm

Ballast depth = 300mm (potentially reduced to 200mm)

Typical concrete sleeper and rail = 367mm

Construction Depth = 1267mm (1167 with reduced ballast depth)

The bridge is located in an aggressive atmosphere, in close proximity to the sea and near numerous oil refinery facilities; consideration should be given to using weathering steels to reduce long term maintenance costs.

The bridge could be constructed alongside/near to the existing structure and installed by launching or transporter method. Transporter method is the most cost effective providing an overnight road closure is available.

The abutments of the bridge will be formed from a monolithic 1.2 metre thick cast in-situ reinforced concrete walls, supported off contiguous piled substructure consisting 900mm diameter

piles at 1200mm centres. Cast in-situ reinforced concrete wing-walls will extend from abutments, returning at 45 degrees to retain the earth embankments.

4.5.3 Option 1b

A three span viaduct would be proposed to bridge the approximately 150 metre long void created by Option 1b. A similar deck construction would be utilised as Option 1a, especially over the highway spans where construction depth is critical. Construction depth is not critical over the Eastern span therefore a less onerous cross girder spacing would be adopted in the deck to reduce cost. Accurate and detailed design need to be produced at a later stage.

The piers would be formed from a monolithic 1.2 metre thick cast in-situ reinforced concrete walls, supported off contiguous piled substructure consisting 900mm diameter piles at 1200mm centres.

4.5.4 Combined Accommodation Track and Land Drain Bridge

The proposed works isolate the area of land to the south of the new chord at the east end. An under-bridge is proposed to enable access into this area of land. The bridge is to be combined to carry the new chord over the adjacent land drain as well.

The proposed bridge is to be formed from precast reinforced concrete portal frames. The portals will be supported by contiguous piled walls with a reinforced concrete capping beam. The portal frames will be keyed into the capping beam.




Figure 2: Combined Accommodation Track and Land Drain Bridge

4.5.5 Culverts

East of Rosper Road there are three other drains that will need culverting.

Two drains adjacent to the Nature Conservation site will need concrete pipes or similar to a diameter of 1.8 metres. It may be possible after a hydrological survey to reduce the pipe diameter to 900mm.

The third drain affected is at the junction of the new railway with the Killingholme Branch. The existing 900mm culvert should be extended.

If the chord line facing South is constructed two further drains will need culverting with 1.8m concrete pipes or similar.

4.6 Signalling and Control

At this stage no evaluation of signalling requirements has been undertaken.

However the scheme should provide for an entry and exit signal with overlaps in each direction.

The line should be worked under the Track Circuit Block regulations and controlled from the new Signalling Centre for the North Lincolnshire re-control project.

4.7 Operations

The new line is required to support an alternative access route to the Killingholme Branch. The current Network Rail proposal is to re-instate the Killingholme to Goxhill line with a new Southern chord onto the Ulceby to Barton line.

The rationale for this is that it will allow an approach to Killingholme from the North allowing an empty coal or biomass train to load at Humber International Terminal without the locomotive having to run round its train before or after loading. This is thought to provide a substantial increase in train paths.

The new line proposed by Able Humber Ports Ltd has as its rationale a lower cost alternative to the Goxhill scheme that delivers substantially the same benefits. The route is considerably shorter and lower cost. It avoids the congested area around Immingham East and West Junctions.

The Southern fork off the new line offers the possibility of a direct link into the Humber International Terminal (HIT) for coal trains.

This could fulfil a substantial role as part of a balloon loop for coal and biomass Merry-Go-Round (MGR) traffic. This would require the existing train load-out facility at Humber International Terminal to be connected onto the new line. Empty trains would arrive via the new line, load and depart via the existing line. Terminal times would be substantially reduced and capacity increased.

Similarly there may be productivity improvements to be gained at Immingham Bulk Terminal for Tata Steel if the load-out facility was aligned with the current Killingholme Branch past the terminal.

This would require a more substantial study to prove the concept.

The construction of the new railway would permit the existing KIL2 section of the Barton and Immingham Light Railway to remain as a Light Railway as it would no longer be required for a future enhancement as a through freight route.

4.8 Environment

4.8.1 Statutory Order

The new railway will require the current Development Consent Order for the Able Marine Energy Park to be amended or a fresh Transport and Works Act Order under the 2013 regulations for railway works under 2 miles length to be procured.

If the current Development Consent Order is amended then the extent to which the supporting Environmental Statement may need to be amended will have to be determined.

If a new Transport and Workss Act Order is procured, then the size and extent of the scheme, as determined by the Town and Country Planning (Environmental Impact Assessment) Regulations (2011), S.I. No. 1824, will likely require an Environmental Impact Assessment (EIA), and subsequent Environmental Statement (ES), as the scheme is over the threshold for railway developments requiring an EIA (development of >1 hectare), stated within Schedule 2, 10(d). This will likely form an integral part of submission of a planning application for the scheme.

It is recommended that in order to determine both the requirement for an EIA, and the scope of what environmental aspects would be required to be included within the assessment, the Local Authority (North Lincolnshire Council) Planning department should be contacted at the earliest stage possible and the Planning Inspectorate consulted.

This would entail requesting both an advisory Screening Decision and an advisory Scoping Opinion for the scheme from North Lincolnshire Council and final decision from the Planning Inspectorate.

It is anticipated that given the location of the scheme, and the surrounding environmental receptors, the aspects that will likely require impact assessment will include, but not necessarily be limited to;

• Ecology and Biodiversity— Impact on surrounding statutory and non statutory nature reserves, impact on legally protected species and associated habitats identified within the local area (Water Voles, Great Crested Newts, wintering birds), impact on biodiversity in the surrounding landscape. The scheme will likely require mitigation measures, translocation/exclusion schemes with seasonal, programming, design and cost implications. Additionally, the direct and indirect impacts upon the adjacent Local Wildlife Site (Rosper Road Pools) will need to be considered and a management plan will likely be required to be implemented both during and after construction.

- Water Resources— The proposed alignment bisects several drainage ditches, is located within an area at risk of flooding and is located directly adjacent to an aquatic nature reserve (see above). As a result, flood risk assessments, drainage impact assessments, design issues, cost implications and impacts on ecology will all require consideration.
- Hydrogeology the site is underlain by a principle bedrock aquifer and is located in a
 coastal region, and as such hydrological linkage to the sea may require assessment. This
 will likely require specific design solutions with agreement from the Environment Agency
 (with the associated cost implications).
- Archaeology local archaeological resources are currently unknown but may require assessment. Issues to be considered will be dependent on the design solution and may have programming, design and cost implications.
- Air/Land Pollution ground conditions within, and adjacent to the proposed scheme will likely need to be assessed, and monitored to ensure no pollution pathways will be affected/created by the scheme. These issues will likely present cost implications to the scheme.
- Transport the impact of the construction and operation of the scheme on both the rail
 and road network will likely require assessing to determine the extent of the impact of the
 scheme on the local transport resources. This will likely require specific design solutions
 with agreement from the North Lincolnshire Council Highways Department, Highways
 Authority and Health and Safety Executive (with the associated cost and programming
 implications).
- Visual The potential to impact on the surrounding landscape the extensive proposed structure will be sited within a flat receiving environment which will be visible from a potentially significant distance. A Landscape impact assessment may be required.
- Climate Change the impact of both the design and the construction of the scheme will require assessment.
- Sustainability A scheme of this magnitude has the potential to impact on material use and transportation issues through design. Construction impacts should also be considered during the design phases.

These aspects will need to be assessed with respect to the environmental impact of both the construction and the operation of the proposed scheme.

It is probable that, following the screening process, the development will require an Environmental Statement. The Environmental Impact Assessment of the scoped environmental aspects (most notably ecology, water resources, hydrogeology and Transport) will likely require a significant volume of baseline survey work to inform the assessment. This survey work will likely have seasonal requirements, and may be required to be programmed over a calendar year, or longer, imposing significant programming issues with regard to securing planning permission prior to the construction of the scheme.

As such, it is critical for the progression of this scheme that a screening decision is obtained and the environmental aspects are scoped by the local planning authority at the earliest stage possible.

4.8.2 Consents, Licences and Consultation

Outside of the likely requirement for an EIA as part of securing the Development Consent Order for the scheme, it is anticipated that several consents and licences will be required from the statutory authorities for the scheme to proceed. As part of these consents and licences requirements, additional survey and assessment work may also be required.

Consents and licences that would likely be required include: -

- Protected species licences (e.g. European Protected Species (EPS) mitigation licences for Great Crested Newts, Water Vole exclusion/translocation licences) from Natural England
- Environment Agency/ Internal Drainage Board consents with respect to alterations to the local drainage ditch network
- Consent from the Environment Agency with respect to development within an area at risk of flooding/ over a Principle Aquifer
- North Lincolnshire Council Highways Department/ Highways Agency will require being consulted/involved for the proposed alterations to the local road network.
- English Heritage/ North Lincolnshire Council Archaeology Department should be consulted to determine the extent of archaeological resources

As previously discussed, the survey works for these consents/licences will likely have specific seasonal requirements which would likely impact upon the design/construction programme for the scheme.

On initial costing Option 1b is the preferred option, but this will need to be confirmed by ground investigations and local survey. The length of the chord line is 1625 metres in the feasibility railway design. The costs of the new chord are preliminarily estimated at £38 million including contingency.

A comparison should be made with the original 2008 proposal to reinstate the closed KIL3 section of the Barton and Immingham Light Railway with a chord line at Goxhill, but without any upgrade to the section to Thornton Abbey of the Ulceby to Barton Line. The estimated costs, for the preferred Option C adjusted for inflation to Q4 2012 are £41m. It was considered at the time that any upgrade to the Ulceby to Thornton Abbey section could cost a further £15m, though no detailed work was undertaken on that.

The new shorter Rosper Road Loop will require the current Development Consent Order for the Able Marine Energy Park to be amended or a fresh Transport and Works Act Order under the 2013 regulations for railway works under 2 miles length to be procured.

4.9 Cost Estimates

On initial costing Option 1b is the preferred option, but this will need to be confirmed by ground investigations, bridges design and local survey. The length of the chord line is 1625 metres in the feasibility railway design. The costs of the new chord are preliminarily estimated at £38.3 million including contingency.

Option 1a is estimated to cost £44.7 million due to traversing poor ground.

A comparison should be made with the original 2008 proposal to reinstate the closed KIL3 section of the Barton and Immingham Light Railway with a chord line at Goxhill, but without any upgrade to the section to Thornton Abbey of the Ulceby to Barton Line. The estimated costs, including contingency, adjusted for inflation are £35 million for the short option A, £41 million for the longer (preferred) option C, £42.5 million for the longest option B, £56 million for the looping option D. Note that the figures above are high-level estimates.

It was considered at the time that any upgrade to the Ulceby to Thornton Abbey section could cost a further £15m, though no detailed work was undertaken on that.

5.0 Conclusions

The new Rosper Road Loop (in the parish of South Killingholme), can be engineered and constructed. Option 1b is the most cost-effective solution.

The crossing of Rosper Road can be undertaken by lifting the new railway over the road. The alternative of raising Rosper Road and the consequent alterations to the A160 highway scheme should only be considered if Rosper Road is required for High Loads with the consequent raising of the soffit level and worsening of the railway gradients.

The key risks to the scheme arise from the poor ground conditions making earthworks more complex.

The operating benefits of the scheme are in providing a direct access to the Humber International Terminal for coal and biomass trains, thereby nullifying any strategic requirement for the KIL3 line from Killingholme to Goxhill.

6.0 Recommendations


The development of the interface between the new railway and the HIT terminal should be investigated further with Network Rail and ABP. Similarly the provision of facilities at Immingham Bulk Terminal may need to be considered.

The Rosper Road Loop scheme should be supported on the basis that it offers a more readily constructible alternative to the Goxhill scheme and the strategic benefit of diverting future railway growth away from the AMEP site.

Appendix A: Drawings


Option 1a and 1b.






PROPOSED ROSPER ROAD LOOP - ASSUMED ROAD LEVELS





PROPOSED ROSPER ROAD LOOP - ASSUMED ROAD LEVELS

CONSTANT COMPENSATED GRADIENTS OF 1:142 FOR THE SOUTH CHORD



YORK OFFICE FOR AUDIT PURPOSES.

ASSOCIATED DRAWINGS / REPORTS:-

P01 14 10 PRELIMINARY ISSUE. FOR DISCUSSION VR GKW GKW

Rev. Date Descriptions of revision Des. Chkd. Appr.

V.RANGELOV G.WARREN

Approved G.WARREN

Approved H. Marken Marken

Appendix B: Risk Register





CONSTRUCTION (DESIGN & MANAGEMENT) REGULATIONS 2007

Designer's Health & Safety Risk Review

Document Referen	ce Number:	B90391-RAS-PEN00	001		Version	P01			
Project Number:	B90391		A	applicable from Sta	age:	Design			
Project Title:	Rosper Rail Loop								
Client:	ABLE UK Ltd								
CDM Co-ordinator	(Organisation & Co	ntact Name)	ABLE UK; to be confirmed						
Designer (Organisa	ation & Contact Nan	ne)	Tata Steel Projects, Dave White						
Is the Structure to	be used as a workp	lace?:	No						
(if yes, the design to	take into account pr	ovisions of Workplac	e (Health, Safety and \	Welfare) Regulation	ıs 1992 ar	d the 2002 amendments			

I have reviewed the attached list of residual risks and identified those which are significant and included them in the Designer's Risk Log/Pre-Construction Information. These risks cannot be reasonably designed out.

The following Disciplines/Designers pro-actively contributed to the risk elimination, reduction and control on this project:										
Discipline	Assessment Number	Discipline	Assessment Number							
Bridges & Infrastructure	no. 1 - no. 5									
Environmental	no. 6 - no. 9									
Track & Transport Planning	no. 10 - no. 19									
Geotechnical	no. 20 - no. 21									

Reference Number: PF-05-03
Page 1 of 4 Revision Number: 8

Revision Date: 22/06/12 Tata Steel Projects

DESIGNERS RIS	K LOG	B90391 Rosper Rail Loop									_			
Hazard Ref No.	Category	Risk Description	Frequency	Severity	Significance H, M, L	Design Control Action	Frequency	Severity	Significance H, M, L	Progress	Information Transmission Route	Residual Risk Action Owner	Comments	Risk Type
Overall Risks Options 1A and 1B														
1	Construction	Potential Bridge strike.	5	4	Ι	Lower existing highway/increase railway elevation.	2	1	١	Open		Contractor		CDM H&S
2		Differential settlement of bridge against embankment.	4	4	Н	Ensure design has sufficient transition between the two structures	2	2	L	Open		Contractor		CDM H&S
3	Maintenance	Very costly relocation.	3	3	М	Ensure close liaison between asset owners is maintained.	2	1	L	Open		Contractor		Project
4	Maintenance	Very costly relocation.	4	3	Н	Ensure close liaison between asset owners is maintained. Can pipe be relocated during a maintenance period?	2	1	L	Open		Maintainer		Project
5	Construction	Incur additional costs and delays	3	4	Η	Conduct utilities/services search and mapping.	1	2	_	Open		Contractor		CDM H&S
6	Construction	Higher water table/instability of embankment and localised flooding and ecological impacts and associated mitigation. Project/Programme Delay and high additional costs.	3	5	Н	Ensure embankment design and loading does not have any impact on existing drainage and wet land habitats.	2	5	M	Open		Client		Project
7	Construction	Project/Programme Delay and high additional costs	3	5	Η	Environmental assessment and determination of appropriate mitigation measures to be undertaken prior to design/construction works	3	3	M	Open		Client		Project
8	Construction	Approval of scheme by Local Planning Authorities. Significant programming and cost implications	4	5	Н	Liase with Planning authorities at earliest stage possible to understand planning requirements	2	4	M	Open		Client		Project
9		Approval of scheme by Statutory Authorities. Project/Programme Delay , high additional costs and Public Inquiry	3	5	Н	Liaise with Statutory authorities at earliest stage possible to understand scheme constraints/limitations and requirements. Consultation strategy to be developed	2	5	M	Open		Client		Project
10		Stop, delay or incur additional costs to the project	3	5	Ξ	Obtain early agreement between all stakeholders	2	4	M	Open		Client		Project

11	Operations	Axle-loads heavier than 25.5 tonnes can be introduced in future on this line. That will put extra stress on the rails.	3	3	M	Design using CEN60 rail (60 kg/m) and S&C. Provide dense sleeper spacing.	3	1	L	Open	Client	Project
12	Construction	Incur unexpected costs and possible delays	2	3	L	Conduct a survey and ground investigation prior to final design	1	2	L	Open	Contractor	Project
13	Construction	Project/Programme Delay and high additional costs	2	4	M	Obtain agreement between all parties	1	4	L	Open	Client	Project
14	Operations	Additional costs, possible delays	1	3	L	Start planning in advance	1	1	L	Open	Operator	Project
15	Construction	Will require additional cost and railway possessions	2	3	L	Establish if faster crossover is necessary	1	2	L	Open	Client	Project
16	Operations	Weigh-bridge will limit gradients, may be the capacity of the new railway	3	3	M	Negotiations on connections, requirements and design	3	3	M	Open	Client	Project
17	Operations	Increased clearance will degrade the railway's maximum trailing load and achievable speed. Limit the number of trains	3	4	Н	Build gentle railway gradients, lower the road level, vertical curve over the bridge and wide horizontal curves	1	3	L	Open	Operator	Project
18	Construction	Project/Programme Delay and additional costs	2	3	L	Establish requirements before design	1	2	L	Open	Contractor	Project
19	Construction	Project/Programme Delay and additional costs	2	3	L	Assess the existing signalling	1	1	L	Open	Contractor	Project
Additional Risks for Option 1B B90391-DRG- PWY0001 P04												
20	Construction	Further encroachment onto Wet land and existing drainage. Localised flooding	3	3	M	Ensure a detail Ground Investigation is carried out prior to design works to ensure correct solution is provided.	1	2	L	Open	Client	Project
21	Construction	Incorrect solution for embankment designed	3	3	M	Ensure Detailed G.I. is carried out prior to design to ensure correct solution is provided	1	3	L	Open	Contractor	Project
				\vdash								
				f								

RISK MATRIX

Page: 4 of 4

Risk Assessment process requires an examination of the workplace to establish what could cause harm to people. The Risk Matrix is designed to help the assessor to weigh up whether enough precautions have been taken or if more needs to be done to control the risks.

It should be noted that this method of rating risks is very subjective, based on a broad judgement of the values attached to frequency and severity. However, it does provide a practicable method of prioritising or rating risks and give an overall score.

Fred	quency of an Accident Occurring	Severity of Consequences						
1,	highly improbably	1.	minor injury, no time off					
2.	remotely possible but know to occur	2.	injury resulting in up to 3 days off					
3.	infrequent	3.	injury resulting in 3 or more days off					
4.	occasional	4.	major disability (eg loss of limb, eye, etc)					
5.	frequent and regular	5.	fatality					

Ove	erall	Risk	Ratin	g								
			S	everi	ty		RISK (HAZARD RATING) = FREQUENCY x SEVERITY					
		5	4	3	2	1	This gives a matrix of possible rating values as	s follows:-				
77	5	25	20	15	10	15	The rating values can then be grouped into thr	ee broad				
ē	4	20	18	12	8	4	classes of risk:-					
Frequency	3	15	12	9	6	3	Critical Risks	15-25				
nc	2	10	8	8	4	2	Significant Risks	8-12				
~	1	- 5	4	3	2	1	Minor Risks	1-6				

Reference Number: PF-05-03

Revision Date: 22/06/12

Tata Steel Projects

Appendix C: IDC Certificate

TATA STEEL



Inter-Disciplinary Check Certificate

Certificate Number:		B90391-IDC-PEN0001								
The documents listed be the undersigned checking					sign Check (IDC) by					
Client:	LE UK Lt	d	Client Project Ref:	B90391						
Project Title:	Kil	lingholm	gholme Port Rail Access							
Document No.	Re	v No.	Document Title:							
B90391-DRG-PWY0001	P0	4	CONSTRAINTS	DRAWING , OPTION	1B					
B90391-DRG-PWY0002	P0	1	CONSTRAINTS	DRAWING , OPTION	1A					
B90391-EST-COM0001	P0	3	Two Options Cos	t Estimate						
B90391-RAS-PEN0001	P0	1	RISK REGISTER	R - MULTI-DISCIPLIN	E					

Checking Discipline	Checking Organisation	Name of CRE	Signature of CRE	Date
Track	Tata Steel Projects	Dave White	139-	05/12/12
Geotechnical	Tata Steel Projects	Matthew Bickley	un	05/12/12
Transport Planning	Tata Steel Projects	Vladimir Rangelov	12/10	<u>0</u> 5/12/12
Highways	Tata Steel Projects	Liam Bradley	Theoly	05/12/12
Civils / Bridges (Ancillary/Drainage)	Tata Steel Projects	Peter Mullen	PHO	05/12/12
Environmental	Tata Steel Projects	Richard Seabrook	1860	9 5/12/12
We confirm	that we have satisfactorily	completed IDC on the	above documen	ts

Preparing Discipline:	Preparing Organisations Name:	Name:	Signature:	Date:
Track	Tata Steel Projects	Dave White	00	06/12/12
	he IDC process on the above	Name:	Signature:	Date:
documents is of Procedure	complete in line with the IDC	D.W176	The	06/12/12

2

Appendix D: Estimates

Project Title Rosper Rail Loop
Job Description Two Options
Tata Estimate Nr. B90391-EST-COM0001

Tata Estimate Nr. B90391-EST-COM0001 Revision P03 Estimate Stage
Estimate Date 03-Dec-12 Costed at 4Q2012 Confidence +/-50%

Entimata Prockdown		Ontion 1P	Ontion 1A	Ontion 2	Ontion 4	Ontion 5
Estimate Breakdown		Option 1B	Option 1A	Option 3	Option 4	Option 5
Contractor's direct costs -		1 077 100	1 077 400			
Signalling		1,677,400	1,677,400			
AV/DC Electrification		0.417.000	2 200 200			
Permanent Way		2,417,800	2,398,806			
Telecoms		81,000	81,000			
Operational Property						
Structures		6,900,000	2,710,000			
General Civils		8,760,480	16,272,980			
Utilities		100,000	100,000			
Level Crossings		-	-			
Other		-	-			
Contractor's Base Construction Cost inc	OH&P: Sub-Total A	19,936,680	23,240,186	_	_	_
Network Rail's "direct costs"	JIIMI . Jub-Tolai A	19,930,000	23,240,100	_	-	-
NDS - Materials		incl. in rates				
NDS - Fleet		incl. in rates				
- Engineering trains		incl. in rates				
- Engineering trains - Tampers		incl. in rates				
·	tion Management					
NDS - Possession / Isola	lion ivianagement	inci. in rates	incl. in rates	incl. in rates	incl. in rates	incl. in rates
	Sub - Total B			_	-	_
Total Base Construction Cost inc OH&P: Sub-T		19,936,680	23,240,186	-	-	-
Contractor's indirect costs	otal C (A+D)	13,330,000	20,240,100	_	_	_
Preliminaries	(Note 1)	4,247,996	4,908,697	_	_	_
Design	(Note 1)	2,252,748	2,733,348	_	_	_
Testing & Commissioning	(Note 1)	332,244	331,674	_	_	_
Training	(Note 1)	332,244	331,074			
Spares						
Other						
Other						
	Sub - Total D	6,832,988	7,973,720	-	-	-
Total Constructi		26,769,668	31,213,906	-	-	-
Network Rail's indirect & other costs						
Allowance for Network rail charges	2.0%	535,393	624,278	-	-	-
Project Management, (remaining costs)	(Note 1)	-	-	-	-	-
Compensation charges (TOC & FOC)	0.3%	80,309	93,642	-	-	-
TWA Charges		-	-	-	-	-
Land / Property Costs & compensation		-	-	-	-	-
Sponsor	(Note 1)	-	-	-	-	-
	<u> </u>					
	Sub - Total F	615,702	717,920	-	-	-
Point Estimate - Su	o - Total G (E+F)	27,385,370	31,931,826	-	-	-
Uplift for Risk and Contingency						
To Mean	£	07.005.05	04.004.005			
Project Budget (Point Estimate		27,385,370	31,931,826	-	-	-
QRA Value - at P50	£					
QRA Value - at P80 - incremental on P50	£					
Adjustment for residual factors %	400/	10.054.440	10 770 700			
or Contingency allowance	40%	10,954,148	12,772,730	-	-	-
Project Anticipated F	inal Cost (AFC)	38,339,518	44,704,556	_	_	_
Other Costs to the Customer	003t (Al 0)	00,000,010	44,704,000			
Allowance for Escalation		_	_	_	_	_
Allowance for Network Rail Fee Fund		_	_	_		
Allowance for Industry Risk Fund						
Allowance for Industry Risk Fund Allowance for Insurance Top-up						
mowanice for insurance rop-up						
	ost to Customer	38,339,518	44,704,556	_	_	_
	Jor to Gastoniel	00,000,010	77,707,000			_

Notes:-

Note 1: refer to assuptions and comments sheets for values used in the claculation of Contractors and Network Rail's Indirect Costs.

ASSUMPTIONS AND COMMENTS

Project Title / Location Rosper Rail Loop

Corus Estimate No.B90391-EST-COM0001RevisionP03Estimate Date 03-Dec-12Costed at 4Q2012

CALCULATION OF INDIRECT COSTS

The following values have been used for calculation of Contractors and Network Rail's Indirect Costs:

Asset	Preliminaries	Design	Test &	Network Rail	Sponsor
			Commission	Management	
Signalling	35%	15%	15%		
AV/DC Electrification	20%	10%	15%		
Permanent Way	20%	10%	3%		
Telecoms	25%	10%	10%		
Operational Property	15%	8%	0%		
Structures	20%	10%	0%		
General Civils	20%	12%	0%		
Utilities	25%	10%	0%		
Level Crossings	25%	12%	10%		
Other	25%	10%	10%		

User note: Any values entered above will be carried to the estimate summary.

GENERAL

The estimates are based on information contained in:

Drawing / report ref.	Version	Title
B90391-DRG-PWY0001	P04	Constraints Drawing Option 1B
B90391-DRG-PWY0002	P01	Constraints Drawing Option 1A

ASSUMPTIONS

A1 Currently no investigation into the signalling requirements, therefore the signalling costs are provisional at this stage allowing for 4nr (3 aspect) coloured light signals. Allowances for the following have also been made:

Upgrading the existing power supplies - £100K

Modifying interlockings - £100K (assumed not SSI)

Panel alterations - £50K

A2 Provisional allowances have been made for the following signalling equipment based on the following assumptions.

Track circuits 2nr per signal plus 1 per point end.

SPT 1nr per controlled signal.

Location case 1 per signal plus two per point end.

AWS 1nr per controlled signal.

TPWS 1nr per controlled signal.

- A3 Assumes no work required to private level crossing at northern end of the site.
- A4 An allowance has been made for works to existing embankments at the western connection points to avoid differential settlement. Further investigation will be required to determine the extent of the works, however an allowance of £204K has been made at this stage.

- A5 An allowance of £100K has been made for the lowering of an existing gas pipe under the new railway embankment.
- A6 An allowance has been made for Network rail charges based on the project being undertaken as a 3rd party scheme.
- A7 Option 1B new embankments will be required to the new chord connection. These have been split into two types, as follows:
 - Conventional Embankments these are located to the western side of the 150m bridge on the assumption that sufficient ground bearing capacity is available from the existing glacial till. This type of embankment will be formed using selected subsoil layers.
 - Engineered Embankments these are located to the eastern side of the 150m bridge on the assumption that insufficient ground bearing capacity is available from the existing tidal flats, which are built up of highly compressible soils. This type of embankment will be supported on stone columns and formed using a geogrid base layer and lighter embankment fill (i.e. expanded clay)
- A8 All new embankments to Option 1A to the eastern and western side of the bridge (over Rosper Road) will be engineered embankments as detailed above.
- A9 Option 1A allows for a 50m underbridge crossing Rosper Road.
- A10 All embankments are have been broken down into average heights and are approximate at this stage.
- A11 Replacement DV crossover is excluded from the estimate, but has been included as a risk item (see Project Risks sheet).

EXCLUSIONS

- E1 TWA Charges
- E2 Land / Property Costs & compensation
- E3 Sponsor costs
- E4 Allowance for Escalation
- E5 Allowance for Network Rail Fee Fund
- E6 Allowance for Industry Risk Fund
- E7 Allowance for Insurance Top-up
- E8 Road bridge over closed Level Crossing
- E9

Project Title / Location Rosper Rail Loop
Tata Estimate No. B90391-EST-COM0001
GRIP Stage

Revision P03

Estimating Risk Register

The estimating risk register identifes any risks to the project and/or estimate identified in preparing the estimate; this is to inform the QRA process only and any potential cost impacts will not impact on the estimate total.

Any assessment of the level of cost impact (by percentage/ H/M/L assessment / cost value or range) is a subjective assessment only.

onal embankment to west of Rosper Road needs to med, as further investigation is required to glacial till for Rosper Road to be designated a high load route greater headroom to the underside of the railway	50%	
greater headroom to the underside of the railway		
onsequently the required railway gradients may not vable.	50%	
nent of existing trailing crossover - Ulceby Line	30%	
	vable.	vable.

CONFIDENCE LEVEL MATRIX

Asset	Asset Scope confidence Pri					
Signalling	Low	Poor				
E&P	NA	NA				
Track	Low	Poor				
Telecoms	Low Poor					
OP Property	NA	NA NA				
Structures	S Low Po					
General Civils	Low	Poor				
Utilities	Poor					
Remarks		·				
Notes:						
Scope Confidence: High = g scope may grow significantly	good confidence scope will not change significantly; Me #	edium = Limited scope growth	predicted; Low =			
Price confidence: Good = w	ve have good cost knowledge; Poor = poor cost knowle	edge and/or price certainty				

Project Risks Page 5 of 8

		OPTION S	SUMMARY		
-	itle / Location Rosper Rail Lo	•			
Option	B90391-EST-C	OM0001	D avidatan DO	20	
Estimate	timate No. 03-Dec-12 Date		Revision Po Costed at 4Q		
section	item	quant unit	rate	total	Comments
Signalling					
Priced on	<u>SEU</u> Signalling Equivalent Units	nr			inc T&C & design
	Comprising: Xnr signals, Xnr point ents, X		PWS, Xnr IBJ's/TC	-	inc rac a design
Elemental	pricina				exc T&C & design
	Recoveries	%		-	· ·
	Modify route interlocking VDU / Panel modifications	1 Sum 1 Sum	100,000.00 50,000.00		Allowance Only Allowance Only
	Signals: 3 Aspect; controlled.	4 nr	49,000.00	196,000	Allowance Only
	Signals: Banner repeater	nr 2 pr	12 000 00	26,000	
	Signals: Subsidiary on same post Signals: Route indicator	2 nr 4 nr	13,000.00 12,000.00	48,000	
	R/A Off Indicator (incl. plunger)	nr	·		
	Switch heating - point end equip Switch heating - control cabinet	5 nr 4 nr	7,600.00 13,000.00	38,000 52,000	
	Switch heating - power supplies	2 nr	11,000.00	22,000	
	Switch heating - transformer	6 nr	2,200.00	13,200	
	Track Circuit Alts to track circuit lengths	10 nr nr	13,000.00 4,900.00	130,000	
	TPWS	6 nr	18,000.00	108,000	
	AWS - magnet	nr	05.000.00	-	
	AWS (bi directional) complete Location Case & Base	6 nr 16 nr	25,000.00 13,000.00	150,000 208,000	Allow 1 per signal & 2 per point end
	Lineside trough; C/1/9	2000 m	76.00	152,000	7 mow 1 por digital a 2 por point ona
	Lineside trough; C/1/43	m O mr	17 500 00	- 25 000	10 Em lana
	UTX (2 track inc 2nr TC) Cable: Power	2 nr 3000 m	17,500.00 20.00	60,000	10.5m long
	Cable : 48c multicore	3000 m	50.00	150,000	
	Sign: Speed signs (reflective) Telephones: PZT	16 nr nr	700.00	11,200	3nr per T/O & 4 per X/O
	Telephones: SPT inc drivers walkway	4 nr	7,000.00	28,000	
	Upgrade to existing power supplies	1 sum	100,000.00	100,000	Allowance Only
	othersplease state	Х		-	1,677,400
Electrifica					
_	Not Applicable			-	-
P-way Removals	Removal of plain line	200 m	38.00	7,600	
11011101410	Removal of S&C units - Crossover	1 nr	10,000.00	10,000	
	Removal of bufferstops	nr		-	
01 /110 /					
Slew / lift /	<u>lower</u>	shift		_	
	Slew n.e. 25mm	m		-	check is not less that min shift
	Slew n.e. 50mm Slew n.e. 100mm	m 150 m	82.00	12 200	check is not less that min shift check is not less that min shift
	Slew n.e. 200mm	m	02.00	12,300	check is not less that min shift
	Take-up and relay	158 m	310.00	48,980	
	Additional ballast for slews Take up & relay S&C	m3 nr		-	
	lift	Sum		-	use elemest sheet
	lower	Sum		-	use elemest sheet
	othersplease state	Х		-	
New		m		-	
	Plain line (CEN56; 200mm) Plain line (CEN56; 200mm)	160 m 1800 m	810.00 567.00	-,	On NR infrastructure On 'Greenfield' land
	E/O for Geotech & Sand blanket	1960 m	82.00	160,720	On Greenield land
	Track drainage	m O ===		-	inc catch pits at 25m centres
	S&C turnouts CV9.25 S&C turnouts EV	2 nr 1 nr	240,000.00 380,000.00		On NR infrastructure. Incl. point motors. On NR infrastructure. Incl. point motors.
	S&C turnouts CV9.25	1 nr	168,000.00		On 'Greenfield' land. Incl. point motors.
	S&C crossover	nr		-	
	Bufferstop fixed Bufferstop sliding	nr nr		-	
	Saving for re-use of materials	m		-	0.447.055
	othersplease state	Х		-	2,417,800
Telecoms					
	CIS screens speakers	sum sum		-	includes control equipment includes control equipment
	CCTV cameras	sum		-	includes control equipment
	Cable: Telecoms 30 pair	3000 m	17.00	51,000	• •
	Cable: Fibre Optic 24 core Lineside trough; C/1/9	m m		-	In Signalling
	UTX (2 track inc 2nr TC)	sum		-	- g
	Control cabinet	nr		-	

			OPTIOI	NSUMMARY		
roject T Option	itle / Location	Rosper Rail Loo B90391-EST-COI	-			
	stimate No.	03-Dec-12		Revision		
stimate	Date			Costed at	4Q2012	
ection	item Upgrade to concentr	ators	quant unit 1 sum	rate 30,000.00	total 30,000	Comments Allowance Only 81,000
peration	nal Property Not Applicable					
Bridges						
	Under Bridge - 150m Under Bridge - 6m (s		1 sum 1 sum	6,330,000.00 570,000.00		Single track. Incl. piling allowance Single track. Incl. piling allowance
					-	
					-	6,900,000
ivils	Site Clearance - Ger	oral	34190 m2	0.80	27 252	Small bushes and shrubs
	E/O Shrub clearance		34190 m2 6838 m2	0.80 0.83	,	standard price based on large area
	E/O Tree clearance	, ,	1710 m2	2.90		standard price based on large area
	New Conventional E	· ,	335 m	4,300.00		8.3m High
	Engineered Embank		210 m	8,900.00		6.0m High
	Engineered Embank		180 m	6,500.00		5.0m High
	Engineered Embank		76 m	3,750.00		3.5m High
	Engineered Embank		453 m	2,275.00		2.5m High
	Engineered Embank		80 m	1,675.00	, ,	2.0m High
	Engineered Embank		306 m	720.00	,	1.0m High
	Stone Columns		3026 nr	600.00		450dia x average 5m deep
	Existing embankmer	nts - Geotech work	1 sum	204,000.00		Allowance only - 150m at each connection
	Drainage Ditch		2449 m	90.00		1m depth.
	Stone Haulage Road	l - 3m wide	1312 m	135.00		500mm thick stone road
	Boundary Fence		1742 m	35.00		Post & Wire Fence 1.4m high
	Culvert - 32m x 1.8m	ı dia	2 nr	43,000.00	86,000	· ·
	Culvert - 10m x 0.9m	n dia extend	1 nr	9,000.00	9,000	8,760,480
Itilities						
	Gas Pipe Diversion		1 sum	100,000.00	100,000	Allowance Only 100,000
evel Cro	-					
	Recoveries		%		-	
	Bomac crossing dec		m2		-	
	Cattle/trespass guar	aing	m2		-	
	Crossing barriers	aundara	nr		-	Pood Troffic Lights / Wig Wags
	Warning lights, inc s Local control unit	ounders	sum		-	Road Traffic Lights / Wig Wags
	Telephones		nr nr		-	
	New REB - building		nr			
	REB - interlocking /	signalling	nr			
	UTX (12m long inc 2		nr		_	
	URX (12m long inc 2		nr		_	
	minor modifications	,	sum		-	minimum shift cost
			sum		-	No barriers, including fencing alts
			sum		-	-
Other	othersplease state		- x		-	-
	Summary		Signallir	na	1,677,400	
	y			lectrification	1,077,400	Not Applicable
			Permane		2,417,800	• •
			Telecom	•	81,000	
				nal Property	-	-
			Structur		6,900,000	
			General		8,760,480	
			Utilities		100,000	
			Lovel Cr	ossings	•	
				ossings	-	
			Other	ossings	<u> </u>	_

	•	Rail Loop 1A	OF HU	NSUMMARY		
Option Corus Es Estimate	stimate No. 03-Dec-1	EST-COM0001 2		Revision P		
ection	item	quant	unit	rate	total	Comments
gnalling]					
ced on	SEU Signalling Equivalent Units		nr		_	inc T&C & design
	Comprising: Xnr signals, Xnr point			r TPWS, Xnr IBJ's/TC		mo rao a accign
emental	pricina					exc T&C & design
omontai	Recoveries		%		-	oxo rao a dosign
	Modify route interlocking VDU / Panel modifications		Sum Sum	100,000.00		Allowance Only Allowance Only
	Signals: 3 Aspect; controlled.	4		50,000.00 49,000.00	196,000	Allowance Only
	Signals: Banner repeater		nr		-	
	Signals: Subsidiary on same post Signals: Route indicator	2		13,000.00 12,000.00	26,000 48,000	
	R/A Off Indicator (incl. plunger)		nr	12,000.00	40,000	
	Switch heating - point end equip	5		7,600.00	38,000	
	Switch heating - control cabinet Switch heating - power supplies	4 2		13,000.00	52,000 22,000	
	Switch heating - power supplies Switch heating - transformer	6		11,000.00 2,200.00	13,200	
	Track Circuit	10	nr	13,000.00	130,000	
	Alts to track circuit lengths		nr nr	4,900.00	100 000	
	TPWS AWS - magnet	6	nr nr	18,000.00	108,000	
	AWS (bi directional) complete	6	nr	25,000.00	150,000	
	Location Case & Base	16		13,000.00		Allow 1 per signal & 2 per point end
	Lineside trough; C/1/9 Lineside trough; C/1/43	2000	m m	76.00	152,000	
	UTX (2 track inc 2nr TC)	2		17,500.00	35,000	10.5m long
	Cable: Power	3000		20.00	60,000	
	Cable: 48c multicore Sign: Speed signs (reflective)	3000 16		50.00 700.00	150,000 11 200	3nr per T/O & 4 per X/O
	Telephones: PZT		nr	700.00	-	on por 176 a 1 por 300
	Telephones: SPT inc drivers walky	•	nr	7,000.00	28,000	
	Upgrade to existing power supplies othersplease state		sum x	100,000.00	100,000	Allowance Only 1,677,400
-way	Not Applicable				-	-
<u>emovals</u>	Removal of plain line Removal of S&C units - Crossover	200 1		38.00 10,000.00	7,600 10,000	
	Removal of bufferstops		nr	10,000.00	-	
					-	
ew / lift /	lower				-	
	Slew n.e. 25mm		m		-	check is not less that min shift
	Slew n.e. 50mm Slew n.e. 100mm	150	m m	82.00	- 12 300	check is not less that min shift check is not less that min shift
	Slew n.e 200mm		m	02.00	-	check is not less that min shift
	Take-up and relay	158		310.00	48,980	
	Additional ballast for slews Take up & relay S&C		m3 nr		-	
	lift		Sum		-	use elemest sheet
	lower		Sum		-	use elemest sheet
	othersplease state		X		-	
<u>ew</u>			m		-	
	Plain line (CEN56; 200mm)	160 1894		810.00		On NR infrastructure On 'Greenfield' land
	Plain line (CEN56; 200mm) E/O for Geotech & Sand blanket	2054		567.00 82.00	1,073,898	On Greenlieid land
	Track drainage		m	02.00	-	inc catch pits at 25m centres
	S&C turnouts CV9.25	2		240,000.00		On NR infrastructure. Incl. point motors
	S&C turnouts DV	1	nr nr	300,000.00 168,000.00		On NR infrastructure. Incl. point motor On 'Greenfield' land. Incl. point motors
	S&C turnouts CV			100,000.00	-	c.coioid idiid. moi. point motors
	S&C turnouts CV S&C crossover		nr			
	S&C crossover Bufferstop fixed		nr		-	
	S&C crossover Bufferstop fixed Bufferstop sliding				- - -	
	S&C crossover Bufferstop fixed		nr nr		- - -	2,398,806
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state		nr nr m x		- - -	
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state CISscreens		nr nr m x		:	includes control equipment
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state		nr nr m x		-	
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state CIS screens PA speakers CCTV cameras Cable: Telecoms 3	0 pair 3000	nr nr m x sum sum sum	17.00		includes control equipment includes control equipment
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state CIS screens PA speakers CCTV cameras Cable: Telecoms 3 Cable: Fibre Optic 24	0 pair 3000 4 core	nr nr m x sum sum sum m	17.00	-	includes control equipment includes control equipment includes control equipment
elecoms	S&C crossover Bufferstop fixed Bufferstop sliding Saving for re-use of materials othersplease state CIS screens PA speakers CCTV cameras Cable: Telecoms 3	0 pair 3000 4 core	nr nr m x sum sum sum m	17.00	-	includes control equipment includes control equipment

			OFTION	NSUMMARY		
Project T Option	itle / Location	Rosper Rail Loo B90391-EST-COI	-			
Corus Es Estimate	stimate No. Date	03-Dec-12		Revision F Costed at 4		
ection	item Upgrade to concent	rators	quant unit 1 sum	rate 30,000.00	total 30,000	Comments Allowance Only
	. •				-	81,000
peration	al Property Not Applicable					
Bridges						a
	Under Bridge - 50m Under Bridge - 6m (1 sum 1 sum	2,140,000.00 570,000.00		Single track. Incl. piling allowance Single track. Incl. piling allowance
					-	2,710,000
Civils						
	Site Clearance - Ge E/O Shrub clearance		34190 m2	0.80	,	Small bushes and shrubs
	E/O Shrub clearance	` '	6838 m2 1710 m2	0.83 2.90		standard price based on large area standard price based on large area
	Engineered Embani	· ,	404 m	15,500.00		8.3m High
	Engineered Embank		60 m	11,500.00	, ,	7.0m High
	Engineered Embank	ment	270 m	8,900.00	2,403,000	6.0m High
	Engineered Embank		180 m	6,500.00		5.0m High
	Engineered Embank		76 m	3,750.00		3.5m High
	Engineered Embank		453 m	2,275.00		2.5m High
	Engineered Embank Engineered Embank		80 m 306 m	1,675.00 720.00		2.0m High 1.0m High
	Stone Columns	anent	5301 nr	600.00		450dia x average 5m deep
	Existing embankme	nts - Geotech work	1 sum	306,000.00		Allowance only - 150m at each connection
	Drainage Ditch		2449 m	90.00		1m depth.
	Stone Haulage Road	d - 3m wide	1312 m	135.00	177,120	500mm thick stone road
	Boundary Fence		1742 m	35.00		Post & Wire Fence 1.4m high
	Culvert - 32m x 1.8n Culvert - 10m x 0.9n		2 nr 1 nr	43,000.00 9,000.00	86,000 9,000	
Jtilities	Gas Pipe Diversion		1 sum	100,000.00	100 000	Allowance Only
	ado i ipo Bivoroion		i dani	100,000.00	-	100,000
evel Cro			0/			
	Recoveries	alz.	% m2		-	
	Bomac crossing dec Cattle/trespass guar		m2		-	
	Crossing barriers	ang	nr		_	
	Warning lights, inc s	ounders	sum		-	Road Traffic Lights / Wig Wags
	Local control unit		nr		-	0 0 0
	Telephones		nr		-	
	New REB - building		nr		-	
	REB - interlocking /	0 0	nr		-	
	UTX (12m long inc 2 URX (12m long inc 2		nr nr		-	
	minor modifications		sum		-	minimum shift cost
			sum		-	
Other			sum		-	-
	othersplease state		- x		-	<u> </u>
	Summary		Signallin		1,677,400	
			Permane	•	2,398,806	Not Applicable
			Telecom		81,000	
			•	nal Property	2 710 000	-
			Structure General		2,710,000 16,272,980	
			Utilities	J. 1113	100,000	
			Level Cr	ossings	-	
			Other	.	-	
			Other			



Tata Steel Projects, York (Head Office)

Meridian House, The Crescent, York, YO24 1AW, UK T: +44 (0) 1904 454 600, F: +44 (0) 1904 454 601

Tata Steel Projects, Birmingham

Alpha Tower, Crowne Plaza Suffolk Street, Birmingham, B1 1TT, UK T: +44 (0) 121 242 1240, F: +44 (0) 121 246 4664

Tata Steel Projects, Manchester

1st Floor, Fairbairn House, 70-72 Sackville Street, Manchester, M1 3NJ, UK T: + 44 (0) 161 242 2990, F: +44 (0) 161 242 2999

Tata Steel Projects, Workington

Curwen Road, Derwent Howe, Workington, Cumbria, CA14 3YX, UK T: +44 (0)1900 68000, F: +44 (0)1900 601111.

Tata Steel Projects, Reading

Office 2.14, Dukesbridge House, 23 Dukes Street Reading, Berkshire, RG1 4SA, UK Tel: +44(0) 843 4878776

Tata Steel UK

30, Millbank, London, SW1P 4WY, UK T: +44 (0) 20 7717 4444, F: +44 (0) 20 7717 4455